Open Document Format for Office Applications (OpenDocument) Version 1.2

Part 1: OpenDocument Schema

Committee Specification Draft 06

2 December 2010

Specification URIs:

This Version:

http://docs.oasis-open.org/office/v1.2/csd06/OpenDocument-v1.2-csd06-part1.odt
(Authoritative)
http://docs.oasis-open.org/office/v1.2/csd06/OpenDocument-v1.2-csd06-part1.pdf
http://docs.oasis-open.org/office/v1.2/csd06/OpenDocument-v1.2-csd06-part1.html

Previous Version:

http://docs.oasis-open.org/office/v1.2/cd05/OpenDocument-v1.2-cd05-part1.odt
(Authoritative)
http://docs.oasis-open.org/office/v1.2/cd05/OpenDocument-v1.2-cd05-part1.pdf
http://docs.oasis-open.org/office/v1.2/cd05/OpenDocument-v1.2-cd05-part1.html

Latest Version:

http://docs.oasis-open.org/office/v1.2/OpenDocument-v1.2-part1.odt
http://docs.oasis-open.org/office/v1.2/OpenDocument-v1.2-part1.pdf
http://docs.oasis-open.org/office/v1.2/OpenDocument-v1.2-part1.html

Technical Committee:

OASIS Open Document Format for Office Applications (OpenDocument) TC

Chairs:

Rob Weir, IBM
Michael Brauer, Oracle Corporation

Editors:

Patrick Durusau <patrick@durusau.net>
Michael Brauer, Oracle Corporation <michael.brauer@sun.com>

Related Work:

This document is part of the OASIS Open Document Format for Office Applications (OpenDocument) Version 1.2 specification.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The OpenDocument v1.2 specification has these parts:

OpenDocument v1.2 part 1 (this part); OpenDocument Schema
OpenDocument v1.2 part 2: Recalculated Formula (OpenFormula) Format
OpenDocument v1.2 part 3: Packages

OpenDocument v1.2 part 1 defines these schemas and ontologies:

OpenDocument v1.2 Relax NG Schema
OpenDocument v1.2 Metadata Manifest Ontology

Declared XML Namespaces:

urn:oasis:names:tc:opendocument:xmlns:animation:1.0
urn:oasis:names:tc:opendocument:xmlns:chart:1.0
urn:oasis:names:tc:opendocument:xmlns:config:1.0
urn:oasis:names:tc:opendocument:xmlns:database:1.0
urn:oasis:names:tc:opendocument:xmlns:dr3d:1.0
urn:oasis:names:tc:opendocument:xmlns:drawing:1.0
urn:oasis:names:tc:opendocument:xmlns:form:1.0
urn:oasis:names:tc:opendocument:xmlns:manifest:1.0
urn:oasis:names:tc:opendocument:xmlns:meta:1.0
urn:oasis:names:tc:opendocument:xmlns:data style:1.0
urn:oasis:names:tc:opendocument:xmlns:office:1.0
urn:oasis:names:tc:opendocument:xmlns:presentation:1.0
urn:oasis:names:tc:opendocument:xmlns:script:1.0
urn:oasis:names:tc:opendocument:xmlns:table:1.0
urn:oasis:names:tc:opendocument:xmlns:text:1.0
urn:oasis:names:tc:opendocument:xmlns:style:1.0
urn:oasis:names:tc:opendocument:xmlns:xsl-fo-compatible:1.0
urn:oasis:names:tc:opendocument:xmlns:svg-compatible:1.0
urn:oasis:names:tc:opendocument:xmlns:smil-compatible:1.0
urn:oasis:names:tc:opendocument:xmlns:of:1.2
http://docs.oasis-open.org/ns/office/1.2/meta/odf#

Abstract:

This document is part of the Open Document Format for Office Applications (OpenDocument) Version 1.2 specification.

It defines an XML schema for office applications and its semantics. The schema is suitable for office documents, including text documents, spreadsheets, charts and graphical documents like drawings or presentations, but is not restricted to these kinds of documents.

Status:

This document was last revised or approved by the OASIS Open Document Format for Office Applications (OpenDocument) Technical Committee on the above date. The level of approval is also listed above. Check the current location noted above for possible later revisions of this document. This document is updated periodically on no particular schedule.

Technical Committee members should send comments on this specification to the Technical Committee's email list. Others should send comments to the Technical Committee by using the "Send A Comment" button on the Technical Committee's web page at www.oasis-open.org/committees/office.

For information on whether any patents have been disclosed that may be essential to implementing this specification, and any offers of patent licensing terms, please refer to the Intellectual Property Rights section of the Technical Committee web page (www.oasis-open.org/committees/office/ipr.php.)

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Notices

Copyright © OASIS® 2002–2010. All Rights Reserved.

All capitalized terms in the following text have the meanings assigned to them in the OASIS Intellectual Property Rights Policy (the "OASIS IPR Policy"). The full Policy may be found at the OASIS website.

This document and translations of it may be copied and furnished to others, and derivative works that comment on or otherwise explain it or assist in its implementation may be prepared, copied, published, and distributed, in whole or in part, without restriction of any kind, provided that the above copyright notice and this section are included on all such copies and derivative works. However, this document itself may not be modified in any way, including by removing the copyright notice or references to OASIS, except as needed for the purpose of developing any document or deliverable produced by an OASIS Technical Committee (in which case the rules applicable to copyrights, as set forth in the OASIS IPR Policy, must be followed) or as required to translate it into languages other than English.

The limited permissions granted above are perpetual and will not be revoked by OASIS or its successors or assigns.

This document and the information contained herein is provided on an "AS IS" basis and OASIS DISCLAIMS ALL WARRANTIES, EXPRESS OR IMPLIED, INCLUDING BUT NOT LIMITED TO ANY WARRANTY THAT THE USE OF THE INFORMATION HEREIN WILL NOT INFRINGE ANY OWNERSHIP RIGHTS OR ANY IMPLIED WARRANTIES OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE.

OASIS requests that any OASIS Party or any other party that believes it has patent claims that would necessarily be infringed by implementations of this OASIS Committee Specification or OASIS Standard, to notify OASIS TC Administrator and provide an indication of its willingness to grant patent licenses to such patent claims in a manner consistent with the IPR Mode of the OASIS Technical Committee that produced this specification.

OASIS invites any party to contact the OASIS TC Administrator if it is aware of a claim of ownership of any patent claims that would necessarily be infringed by implementations of this specification by a patent holder that is not willing to provide a license to such patent claims in a manner consistent with the IPR Mode of the OASIS Technical Committee that produced this specification. OASIS may include such claims on its website, but disclaims any obligation to do so.

OASIS takes no position regarding the validity or scope of any intellectual property or other rights that might be claimed to pertain to the implementation or use of the technology described in this document or the extent to which any license under such rights might or might not be available; neither does it represent that it has made any effort to identify any such rights. Information on OASIS' procedures with respect to rights in any document or deliverable produced by an OASIS Technical Committee can be found on the OASIS website. Copies of claims of rights made available for publication and any assurances of licenses to be made available, or the result of an attempt made to obtain a general license or permission for the use of such proprietary rights by implementers or users of this OASIS Committee Specification or OASIS Standard, can be obtained from the OASIS TC Administrator. OASIS makes no representation that any information or list of intellectual property rights will at any time be complete, or that any claims in such list are, in fact, Essential Claims.

The names "OASIS", “OpenDocument”, “Open Document Format” and “ODF” are trademarks of OASIS, the owner and developer of this specification, and should be used only to refer to the organization and its official outputs. OASIS welcomes reference to, and implementation and use

of, specifications, while reserving the right to enforce its marks against misleading uses. Please see http://www.oasis-open.org/who/trademark.php for above guidance.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Table of Contents

1 Introduction 79
1.1 Introduction 79
1.2 Terminology 79
1.3 Normative References 79
1.4 Non Normative References 82
1.5 Namespaces 82
2 OpenDocument Documents, Consumers and Producers 85
2.1 Introduction 85
2.2 Documents 85
2.2.1 OpenDocument Document 85
2.2.2 OpenDocument Extended Document 86
2.2.3 OpenDocument Text Document 86
2.2.4 OpenDocument Spreadsheet Document 87
2.2.5 OpenDocument Drawing Document 87
2.2.6 OpenDocument Presentation Document 87
2.2.7 OpenDocument Chart Document 87
2.2.8 OpenDocument Image Document 88
2.2.9 OpenDocument Formula Document 88
2.2.10 OpenDocument Database Front End Document 88
2.3 Producers 88
2.3.1 OpenDocument Producer 88
2.3.2 OpenDocument Extended Producer 89
2.4 Consumer 89
3 Document Structure 90
3.1 Document Representation 90
3.1.1 General 90
3.1.2 <office:document>(Single OpenDocument XML Files) 90
3.1.3 Package OpenDocument Files 90
3.1.3.1 General 90
3.1.3.2 <office:document-content> 90
3.1.3.3 <office:document-styles> 91
3.1.3.4 <office:document-meta> 91
3.1.3.5 <office:document-settings> 91
3.1.4 Summary of Document Representation 91
3.2 <office:meta> 92

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

3.3 <office:body>..... 92
3.4 <office:text>..... 93
3.5 <office:drawing>..... 93
3.6 <office:presentation>..... 93
3.7 <office:spreadsheet>..... 94
3.8 <office:chart>..... 94
3.9 <office:image>..... 94
3.10 <office:settings>..... 95
3.10.1 General..... 95
3.10.2 <config:config-item-set>..... 95
3.10.3 <config:config-item>..... 95
3.10.4 <config:config-item-map-indexed>..... 96
3.10.5 <config:config-item-map-entry>..... 96
3.10.6 <config:config-item-map-named>..... 96
3.11 Cursor Position Setting..... 96
3.12 <office:scripts>..... 97
3.13 <office:script>..... 97
3.14 <office:font-face-decls>..... 97
3.15 Styles..... 97
3.15.1 General..... 97
3.15.2 <office:styles>..... 98
3.15.3 <office:automatic-styles>..... 98
3.15.4 <office:master-styles>..... 98
3.16 Document Signatures..... 99
3.17 Foreign Elements and Attributes..... 99
3.18 White Space Processing and EOL Handling..... 100
3.19 MIME Types and File Name Extensions..... 100
4 Metadata..... 101
4.1 General..... 101
4.2 RDF Metadata..... 101
4.2.1 In Content Metadata (RDFa)..... 101
4.2.2 manifest.rdf..... 101
4.2.2.1 General..... 101
4.2.2.2 odf:ContentFile..... 101
4.2.2.3 odf:StylesFile..... 102
4.2.2.4 odf:Element..... 102
4.2.2.5 odf:prefix..... 102
4.2.2.6 odf:suffix..... 102

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

4.3 Non-RDF Metadata ... 102
4.3.1 General ... 102
4.3.2 Pre-Defined Metadata Elements ... 103
4.3.2.1 <meta:generator> ... 103
4.3.2.2 <dc:title> ... 103
4.3.2.3 <dc:description> ... 103
4.3.2.4 <dc:subject> ... 104
4.3.2.5 <meta:keyword> ... 104
4.3.2.6 <meta:initial-creator> ... 104
4.3.2.7 <dc:creator> ... 104
4.3.2.8 <meta:printed-by> ... 104
4.3.2.9 <meta:creation-date> ... 105
4.3.2.10 <dc:date> ... 105
4.3.2.11 <meta:print-date> ... 105
4.3.2.12 <meta:template> ... 105
4.3.2.13 <meta:auto-reload> ... 106
4.3.2.14 <meta:hyperlink-behaviour> ... 106
4.3.2.15 <dc:language> ... 106
4.3.2.16 <meta:editing-cycles> ... 106
4.3.2.17 <meta:editing-duration> ... 107
4.3.2.18 <meta:document-statistic> ... 107
4.3.3 <meta:user-defined> ... 107
5 Text Content ... 108
5.1 Headings, Paragraphs and Basic Text Structure ... 108
5.1.1 General ... 108
5.1.2 <text:h> ... 108
5.1.3 <text:p> ... 109
5.2 <text:page-sequence> ... 111
5.2.1 General ... 111
5.2.2 <text:page> ... 111
5.3 Lists ... 111
5.3.1 <text:list> ... 111
5.3.2 Default List Style ... 112
5.3.3 <text:list-header> ... 112
5.3.4 <text:list-item> ... 112
5.3.5 List Item Style Rules ... 113
5.3.6 <text:numbered-paragraph> ... 113
5.3.7 Numbered Paragraph Style Rules ... 113
5.4 <text:section> ... 114

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

5.4.1 General ... 114
5.4.2 <text:section-source> ... 115
5.5 Change Tracking ... 115
5.5.1 <text:tracked-changes> ... 115
5.5.2 <text:changed-region> ... 115
5.5.3 <text:insertion> ... 116
5.5.4 <text:deletion> ... 116
5.5.5 <text:format-change> ... 117
5.5.6 <office:change-info> ... 117
5.5.7 Change Marks ... 117
5.5.7.1 General ... 117
5.5.7.2 <text:change-start> ... 118
5.5.7.3 <text:change-end> ... 118
5.5.7.4 <text:change> ... 118
5.6 <text:soft-page-break> ... 118
5.7 Document Declarations ... 119
6 Paragraph Elements Content ... 120
6.1 Basic Text Content ... 120
6.1.1 General ... 120
6.1.2 White Space Characters ... 120
6.1.3 <text:s> ... 121
6.1.4 <text:tab> ... 121
6.1.5 <text:line-break> ... 121
6.1.6 Soft Hyphens, Hyphens, and Non-breaking Spaces ... 121
6.1.7 <text:span> ... 122
6.1.8 <text:a> ... 123
6.1.9 <text:meta> ... 124
6.1.10 <text:number> ... 125
6.2 Bookmarks and References ... 126
6.2.1 Bookmarks ... 126
6.2.1.1 General ... 126
6.2.1.2 <text:bookmark> ... 126
6.2.1.3 <text:bookmark-start> ... 126
6.2.1.4 <text:bookmark-end> ... 126
6.2.2 References ... 127
6.2.2.1 General ... 127
6.2.2.2 <text:reference-mark> ... 127
6.2.2.3 <text:reference-mark-start> ... 127

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

6.2.2.4 <text:reference-mark-end> 128
6.3 Notes 128
6.3.1 General 128
6.3.2 <text:note> 128
6.3.3 <text:note-citation> 128
6.3.4 <text:note-body> 128
6.4 <text:ruby> 129
6.4.1 General 129
6.4.2 <text:ruby-base> 129
6.4.3 <text:ruby-text> 130
7 Text Fields 132
7.1 General 132
7.2 Common Characteristics of Field Elements 132
7.3 Document Fields 132
7.3.1 General 132
7.3.2 <text:date> 132
7.3.3 <text:time> 133
7.3.4 <text:page-number> 133
7.3.5 <text:page-continuation> 133
7.3.6 Subsequent Author Fields 134
7.3.6.1 General 134
7.3.6.2 <text:sender-firstname> 134
7.3.6.3 <text:sender-lastname> 134
7.3.6.4 <text:sender-initials> 134
7.3.6.5 <text:sender-title> 135
7.3.6.6 <text:sender-position> 135
7.3.6.7 <text:sender-email> 135
7.3.6.8 <text:sender-phone-private> 135
7.3.6.9 <text:sender-fax> 136
7.3.6.10 <text:sender-company> 136
7.3.6.11 <text:sender-phone-work> 136
7.3.6.12 <text:sender-street> 136
7.3.6.13 <text:sender-city> 137
7.3.6.14 <text:sender-postal-code> 137
7.3.6.15 <text:sender-country> 137
7.3.6.16 <text:sender-state-or-province> 137
7.3.7 Author Fields 138
7.3.7.1 <text:author-name> 138
7.3.7.2 <text:author-initials> 138

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.3.8 <text:chapter>..... 138
7.3.9 <text:file-name>..... 139
7.3.10 <text:template-name>..... 139
7.3.11 <text:sheet-name>..... 139
7.4 Variable Fields..... 140
7.4.1 General..... 140
7.4.2 <text:variable-decls>..... 140
7.4.3 <text:variable-decl>..... 141
7.4.4 <text:variable-set>..... 141
7.4.5 <text:variable-get>..... 141
7.4.6 <text:variable-input>..... 141
7.4.7 <text:user-field-decls>..... 142
7.4.8 <text:user-field-decl>..... 142
7.4.9 <text:user-field-get>..... 142
7.4.10 <text:user-field-input>..... 143
7.4.11 <text:sequence-decls>..... 143
7.4.12 <text:sequence-decl>..... 143
7.4.13 <text:sequence>..... 144
7.4.14 <text:expression>..... 144
7.4.15 <text:text-input>..... 144
7.5 Metadata Fields..... 145
7.5.1 General..... 145
7.5.2 <text:initial-creator>..... 145
7.5.3 <text:creation-date>..... 145
7.5.4 <text:creation-time>..... 145
7.5.5 <text:description>..... 146
7.5.6 <text:user-defined>..... 146
7.5.7 <text:print-time>..... 146
7.5.8 <text:print-date>..... 146
7.5.9 <text:printed-by>..... 147
7.5.10 <text:title>..... 147
7.5.11 <text:subject>..... 147
7.5.12 <text:keywords>..... 148
7.5.13 <text:editing-cycles>..... 148
7.5.14 <text:editing-duration>..... 148
7.5.15 <text:modification-time>..... 148
7.5.16 <text:modification-date>..... 149

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.5.17 <text:creator>..... 149
7.5.18 Document Statistics Fields..... 149
7.5.18.1 General..... 149
7.5.18.2 <text:page-count>..... 149
7.5.18.3 <text:paragraph-count>..... 150
7.5.18.4 <text:word-count>..... 150
7.5.18.5 <text:character-count>..... 150
7.5.18.6 <text:table-count>..... 151
7.5.18.7 <text:image-count>..... 151
7.5.18.8 <text:object-count>..... 151
7.5.19 <text:meta-field>..... 151
7.6 Database Fields..... 153
7.6.1 General..... 153
7.6.2 <form:connection-resource>..... 153
7.6.3 <text:database-display>..... 153
7.6.4 <text:database-next>..... 154
7.6.5 <text:database-row-select>..... 154
7.6.6 <text:database-row-number>..... 154
7.6.7 <text:database-name>..... 155
7.7 More Fields..... 155
7.7.1 Page Variable Fields..... 155
7.7.1.1 General..... 155
7.7.1.2 <text:page-variable-set>..... 155
7.7.1.3 <text:page-variable-get>..... 156
7.7.2 <text:placeholder>..... 156
7.7.3 <text:conditional-text>..... 156
7.7.4 <text:hidden-text>..... 157
7.7.5 <text:reference-ref> 157
7.7.6 <text:bookmark-ref>..... 157
7.7.7 <text:note-ref>..... 157
7.7.8 <text:sequence-ref>..... 158
7.7.9 <text:script>..... 158
7.7.10 <text:execute-macro>..... 159
7.7.11 <text:hidden-paragraph>..... 159
7.7.12 <text:dde-connection>..... 159
7.7.13 <text:measure>..... 160
7.7.14 <text:table-formula> (deprecated)..... 160
8 Text Indexes..... 161

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

8.1 Index Marks 161
8.1.1 General 161
8.1.2 <text:toc-mark-start> 161
8.1.3 <text:toc-mark-end> 161
8.1.4 <text:toc-mark> 162
8.1.5 <text:user-index-mark-start> 162
8.1.6 <text:user-index-mark-end> 162
8.1.7 <text:user-index-mark> 162
8.1.8 <text:alphabetical-index-mark-start> 163
8.1.9 <text:alphabetical-index-mark-end> 163
8.1.10 <text:alphabetical-index-mark> 163
8.1.11 <text:bibliography-mark> 164
8.2 Index Structure 164
8.2.1 General 164
8.2.2 <text:index-body> 164
8.2.3 <text:index-title> 165
8.3 <text:table-of-content> 165
8.3.1 General 165
8.3.2 <text:table-of-content-source> 166
8.3.3 <text:table-of-content-entry-template> 166
8.4 <text:illustration-index> 166
8.4.1 General 166
8.4.2 <text:illustration-index-source> 167
8.4.3 <text:illustration-index-entry-template> 167
8.5 <text:table-index> 167
8.5.1 General 167
8.5.2 <text:table-index-source> 168
8.5.3 <text:table-index-entry-template> 168
8.6 <text:object-index> 168
8.6.1 General 168
8.6.2 <text:object-index-source> 169
8.6.3 <text:object-index-entry-template> 169
8.7 <text:user-index> 169
8.7.1 General 169
8.7.2 <text:user-index-source> 170
8.7.3 <text:user-index-entry-template> 170
8.8 <text:alphabetical-index> 170

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

8.8.1 General 170
8.8.2 <text:alphabetical-index-source> 171
8.8.3 <text:alphabetical-index-auto-mark-file> 171
8.8.4 <text:alphabetical-index-entry-template> 172
8.9 <text:bibliography> 172
8.9.1 General 172
8.9.2 <text:bibliography-source> 172
8.9.3 <text:bibliography-entry-template> 172
8.10 <text:index-source-styles> 173
8.11 <text:index-source-style> 173
8.12 <text:index-title-template> 173
8.13 Index Template Entries 174
8.13.1 <text:index-entry-chapter> 174
8.13.2 <text:index-entry-text> 174
8.13.3 <text:index-entry-page-number> 174
8.13.4 <text:index-entry-span> 175
8.13.5 <text:index-entry-bibliography> 175
8.13.6 <text:index-entry-tab-stop> 175
8.13.7 <text:index-entry-link-start> 175
8.13.8 <text:index-entry-link-end> 176
9 Tables 177
9.1 Basic Tables 177
9.1.1 General 177
9.1.2 <table:table> 177
9.1.3 <table:table-row> 178
9.1.4 <table:table-cell> 178
9.1.5 <table:covered-table-cell> 178
9.1.6 <table:table-column> 179
9.1.7 <table:table-header-rows> 179
9.1.8 <table:table-rows> 180
9.1.9 <table:table-row-group> 180
9.1.10 <table:table-column-group> 180
9.1.11 <table:table-header-columns> 181
9.1.12 <table:table-columns> 181
9.1.13 <table:title> 181
9.1.14 <table:desc> 182
9.2 Advanced Tables 182

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9.2.1 Referencing Table Cells 182
9.2.2 Absolute and relative cell addressing 183
9.2.3 Cell Range Address 183
9.2.4 Column and Row Range Addresses 183
9.2.5 Cell Range Address List 183
9.2.6 <table:table-source> 183
9.2.7 <table:scenario> 184
9.2.8 <table:shapes> 184
9.3 Advanced Table Cells 185
9.3.1 <table:cell-range-source> 185
9.3.2 <table:detective> 185
9.3.3 <table:operation> 185
9.3.4 <table:highlighted-range> 185
9.4 Spreadsheet Document Content 186
9.4.1 <table:calculation-settings> 186
9.4.2 <table:null-date> 186
9.4.3 <table:iteration> 186
9.4.4 <table:content-validations> 187
9.4.5 <table:content-validation> 187
9.4.6 <table:help-message> 187
9.4.7 <table:error-message> 188
9.4.8 <table:error-macro> 188
9.4.9 <table:label-range> 188
9.4.10 <table:label-ranges> 189
9.4.11 <table:named-expressions> 189
9.4.12 <table:named-range> 189
9.4.13 <table:named-expression> 189
9.4.14 <table:database-ranges> 190
9.4.15 <table:database-range> 190
9.4.16 <table:database-source-sql> 190
9.4.17 <table:database-source-table> 191
9.4.18 <table:database-source-query> 191
9.4.19 <table:sort> 191
9.4.20 <table:sort-by> 191
9.4.21 <table:subtotal-rules> 192
9.4.22 <table:sort-groups> 192
9.4.23 <table:subtotal-rule> 192

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9.4.24 <table:subtotal-field>..... 192
9.5 Filters..... 193
9.5.1 General..... 193
9.5.2 <table:filter>..... 193
9.5.3 <table:filter-and>..... 193
9.5.4 <table:filter-or>..... 193
9.5.5 <table:filter-condition>..... 193
9.5.6 <table:filter-set-item>..... 194
9.6 Data Pilot Tables..... 194
9.6.1 General..... 194
9.6.2 <table:data-pilot-tables>..... 195
9.6.3 <table:data-pilot-table>..... 195
9.6.4 Data Pilot Table Source..... 195
9.6.5 <table:source-cell-range>..... 195
9.6.6 <table:source-service>..... 196
9.6.7 <table:data-pilot-field>..... 196
9.6.8 <table:data-pilot-level>..... 196
9.6.9 <table:data-pilot-subtotals>..... 197
9.6.10 <table:data-pilot-subtotal>..... 197
9.6.11 <table:data-pilot-members>..... 197
9.6.12 <table:data-pilot-member>..... 197
9.6.13 <table:data-pilot-display-info>..... 198
9.6.14 <table:data-pilot-sort-info>..... 198
9.6.15 <table:data-pilot-layout-info>..... 198
9.6.16 <table:data-pilot-field-reference>..... 198
9.6.17 <table:data-pilot-groups>..... 199
9.6.18 <table:data-pilot-group>..... 199
9.6.19 <table:data-pilot-group-member>..... 199
9.7 <table:consolidation>..... 199
9.8 <table:dde-links>..... 200
9.9 Change Tracking in Spreadsheets..... 200
9.9.1 General..... 200
9.9.2 <table:tracked-changes>..... 200
9.9.3 <table:insertion>..... 200
9.9.4 <table:dependencies>..... 201
9.9.5 <table:dependency>..... 201
9.9.6 <table:deletions>..... 201

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9.9.7 <table:cell-content-deletion>..... 201
9.9.8 <table:change-deletion>..... 202
9.9.9 <table:deletion>..... 202
9.9.10 <table:cut-offs>..... 202
9.9.11 <table:insertion-cut-off>..... 202
9.9.12 <table:movement-cut-off>..... 203
9.9.13 <table:movement>..... 203
9.9.14 <table:source-range-address>..... 203
9.9.15 <table:target-range-address>..... 203
9.9.16 <table:change-track-table-cell>..... 204
9.9.17 <table:cell-content-change>..... 204
9.9.18 <table:cell-address>..... 204
9.9.19 <table:previous>..... 205
10 Graphic Content..... 206
10.1 General..... 206
10.2 Enhanced Page Features for Graphical Applications..... 206
10.2.1 <style:handout-master>..... 206
10.2.2 <draw:layer-set>..... 206
10.2.3 <draw:layer>..... 207
10.2.4 <draw:page>..... 207
10.2.5 <draw:equation>..... 208
10.3 Drawing Shapes..... 208
10.3.1 General..... 208
10.3.2 <draw:rect>..... 208
10.3.3 <draw:line>..... 208
10.3.4 <draw:polyline>..... 209
10.3.5 <draw:polygon>..... 209
10.3.6 <draw:regular-polygon>..... 210
10.3.7 <draw:path>..... 211
10.3.8 <draw:circle>..... 211
10.3.9 <draw:ellipse>..... 212
10.3.10 <draw:connector>..... 212
10.3.11 <draw:caption>..... 213
10.3.12 <draw:measure>..... 213
10.3.13 <draw:control>..... 214
10.3.14 <draw:page-thumbnail>..... 215
10.3.15 <draw:g>..... 215

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.3.16 <draw:glue-point>.... 216
10.3.17 <svg:title>.... 216
10.3.18 <svg:desc>.... 217
10.3.19 <office:event-listeners>.... 217
10.4 Frames.... 217
10.4.1 General.... 217
10.4.2 <draw:frame>.... 218
10.4.3 <draw:text-box>.... 218
10.4.4 <draw:image>.... 219
10.4.5 <office:binary-data>.... 219
10.4.6 Objects.... 220
10.4.6.1 General.... 220
10.4.6.2 <draw:object>.... 220
10.4.6.3 <draw:object-ole>.... 220
10.4.7 <draw:applet>.... 221
10.4.8 <draw:plugin>.... 221
10.4.9 <draw:param>.... 221
10.4.10 <draw:floating-frame>.... 222
10.4.11 Contours.... 222
10.4.11.1 General.... 222
10.4.11.2 <draw:contour-polygon>.... 222
10.4.11.3 <draw:contour-path>.... 222
10.4.12 <draw:a>.... 223
10.4.13 Client Side Image Maps.... 223
10.4.13.1 General.... 223
10.4.13.2 <draw:image-map>.... 223
10.4.13.3 <draw:area-rectangle>.... 223
10.4.13.4 <draw:area-circle>.... 224
10.4.13.5 <draw:area-polygon>.... 224
10.5 3D Shapes.... 225
10.5.1 General.... 225
10.5.2 <dr3d:scene>.... 225
10.5.3 <dr3d:light>.... 225
10.5.4 <dr3d:cube>.... 226
10.5.5 <dr3d:sphere>.... 226
10.5.6 <dr3d:extrude>.... 226
10.5.7 <dr3d:rotate>.... 226
10.6 Custom Shape.... 227

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.6.1 <draw:custom-shape> 227
10.6.2 <draw:enhanced-geometry> 227
10.6.3 <draw:handle> 228
10.7 Presentation Shapes 228
10.8 Presentation Animations 229
10.8.1 <presentation:animations> 229
10.8.2 <presentation:sound> 229
10.8.3 <presentation:show-shape> 229
10.8.4 <presentation:show-text> 230
10.8.5 <presentation:hide-shape> 230
10.8.6 <presentation:hide-text> 230
10.8.7 <presentation:dim> 230
10.8.8 <presentation:play> 231
10.8.9 <presentation:animation-group> 231
10.9 SMIL Presentation Animations 231
10.9.1 General 231
10.9.2 <presentation:event-listener> 232
10.9.3 Presentation Document Content 232
10.9.3.1 <presentation:header> 232
10.9.3.2 <presentation:header-decl> 232
10.9.3.3 <presentation:footer> 232
10.9.3.4 <presentation:footer-decl> 233
10.9.3.5 <presentation:date-time> 233
10.9.3.6 <presentation:date-time-decl> 233
10.9.3.7 <presentation:settings> 234
10.9.3.8 <presentation:show> 234
11 Chart Content 235
11.1 <chart:chart> 235
11.2 Title, Subtitle and Footer 235
11.2.1 <chart:title> 235
11.2.2 <chart:subtitle> 235
11.2.3 <chart:footer> 236
11.3 <chart:legend> 236
11.4 <chart:plot-area> 237
11.5 3D Plot Area 237
11.6 <chart:wall> 237
11.7 <chart:floor> 237
11.8 <chart:axis> 238

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

11.9 <chart:categories>..... 238
11.10 <chart:grid>..... 238
11.11 <chart:series>..... 238
11.12 <chart:domain>..... 239
11.13 <chart:data-point>..... 239
11.14 <chart:data-label>..... 239
11.15 <chart:mean-value>..... 240
11.16 <chart:error-indicator>..... 240
11.17 <chart:regression-curve>..... 240
11.18 <chart:equation>..... 240
11.19 <chart:stock-gain-marker>..... 241
11.20 <chart:stock-loss-marker>..... 241
11.21 <chart:stock-range-line>..... 241
12 Database Front-end Document Content..... 242
12.1 <office:database>..... 242
12.2 <db:data-source>..... 242
12.3 <db:connection-data>..... 242
12.4 <db:database-description>..... 242
12.5 <db:file-based-database>..... 243
12.6 <db:server-database>..... 243
12.7 <db:connection-resource>..... 243
12.8 <db:login>..... 243
12.9 <db:driver-settings>..... 244
12.10 <db:auto-increment>..... 244
12.11 <db:delimiter>..... 244
12.12 <db:character-set>..... 244
12.13 <db:table-settings>..... 245
12.14 <db:table-setting>..... 245
12.15 <db:application-connection-settings>..... 245
12.16 <db:table-filter>..... 245
12.17 <db:table-include-filter>..... 246
12.18 <db:table-exclude-filter>..... 246
12.19 <db:table-filter-pattern>..... 246
12.20 <db:table-type-filter>..... 246
12.21 <db:table-type>..... 247
12.22 <db:data-source-settings>..... 247
12.23 <db:data-source-setting>..... 247

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

12.24 <db:data-source-setting-value>..... 247
12.25 Forms and Reports..... 248
12.25.1 General..... 248
12.25.2 <db:forms>..... 248
12.25.3 <db:reports>..... 248
12.25.4 <db:component-collection>..... 248
12.25.5 <db:component>..... 249
12.26 <db:queries>..... 249
12.27 <db:query-collection>..... 249
12.28 <db:query>..... 249
12.29 <db:order-statement>..... 250
12.30 <db:filter-statement>..... 250
12.31 <db:update-table>..... 250
12.32 <db:table-representations>..... 250
12.33 <db:table-representation>..... 251
12.34 <db:columns>..... 251
12.35 <db:column>..... 251
12.36 <db:schema-definition>..... 251
12.37 <db:table-definitions>..... 252
12.38 <db:table-definition>..... 252
12.39 <db:column-definitions>..... 252
12.40 <db:column-definition>..... 252
12.41 <db:keys>..... 253
12.42 <db:key>..... 253
12.43 <db:key-columns>..... 253
12.44 <db:key-column>..... 253
12.45 <db:indices>..... 253
12.46 <db:index>..... 254
12.47 <db:index-columns>..... 254
12.48 <db:index-column>..... 254
13 Form Content..... 255
13.1 General..... 255
13.2 <office:forms>..... 255
13.3 <form:form>..... 255
13.4 <xforms:model>..... 256
13.5 Controls..... 256
13.5.1 General..... 256

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

13.5.2 <form:text>..... 256
13.5.3 <form:textarea>..... 257
13.5.4 <form:password>..... 257
13.5.5 <form:file>..... 257
13.5.6 <form:formatted-text>..... 258
13.5.7 <form:number>..... 258
13.5.8 <form:date>..... 259
13.5.9 <form:time>..... 259
13.5.10 <form:fixed-text>..... 259
13.5.11 <form:combobox>..... 260
13.5.12 <form:item>..... 260
13.5.13 <form:listbox>..... 260
13.5.14 <form:option>..... 260
13.5.15 <form:button>..... 261
13.5.16 <form:image>..... 261
13.5.17 <form:checkbox>..... 261
13.5.18 <form:radio>..... 262
13.5.19 <form:frame>..... 262
13.5.20 <form:image-frame>..... 262
13.5.21 <form:hidden>..... 263
13.5.22 <form:grid>..... 263
13.5.23 <form:column>..... 263
13.5.24 <form:value-range>..... 264
13.5.25 <form:generic-control>..... 264
13.6 Event Listeners..... 264
13.7 <form:properties>..... 266
13.8 <form:property>..... 266
13.9 <form:list-property>..... 266
13.10 <form:list-value>..... 267
14 Common Content..... 268
14.1 <office:annotation>..... 268
14.2 <office:annotation-end>..... 268
14.3 <meta:date-string>..... 268
14.4 Event Listener Tables..... 269
14.4.1 General..... 269
14.4.2 <script:event-listener>..... 269
14.4.3 Event Types..... 269

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

14.4.4 Macro Name and Location 269
14.5 <math:math> 270
14.6 DDE Connections 270
14.6.1 General 270
14.6.2 <text:dde-connection-decls> 270
14.6.3 <text:dde-connection-decl> 270
14.6.4 <table:dde-link> 271
14.6.5 <office:dde-source> 271
15 SMIL Animations 272
15.1 General 272
15.2 Basic Animation Elements 272
15.2.1 General 272
15.2.2 <anim:animate> 272
15.2.3 <anim:animateTransform> 272
15.2.4 <anim:set> 273
15.2.5 <anim:animateMotion> 273
15.2.6 <anim:animateColor> 273
15.2.7 <anim:transitionFilter> 274
15.3 Animation Model Attributes 274
15.3.1 General 274
15.3.2 Simple Animation Functions 274
15.4 Animation Timing 274
15.4.1 General 274
15.4.2 <anim:par> 274
15.4.3 <anim:seq> 275
15.4.4 <anim:iterate> 275
15.5 <anim:audio> 276
15.6 Animation Command Elements 276
15.6.1 <anim:command> 276
15.6.2 <anim:param> 277
16 Styles 278
16.1 General 278
16.2 <style:style> 278
16.3 <style:map> 279
16.4 <style:default-style> 280
16.5 <style:page-layout> 280
16.6 <style:header-style> 280

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.7 <style:footer-style>..... 280
16.8 <style:default-page-layout>..... 281
16.9 <style:master-page>..... 281
16.10 <style:header>..... 282
16.11 <style:footer>..... 282
16.12 <style:header-left>..... 283
16.13 <style:footer-left>..... 283
16.14 <style:region-left>..... 283
16.15 <style:region-center>..... 284
16.16 <style:region-right>..... 284
16.17 <presentation:notes>..... 284
16.18 <table:table-template>..... 285
16.19 Cell Styles..... 285
16.19.1 General..... 285
16.19.2 <table:first-row>..... 285
16.19.3 <table:last-row>..... 286
16.19.4 <table:first-column>..... 286
16.19.5 <table:last-column>..... 286
16.19.6 <table:body>..... 286
16.19.7 <table:even-rows>..... 287
16.19.8 <table:odd-rows>..... 287
16.19.9 <table:even-columns>..... 287
16.19.10 <table:odd-columns>..... 287
16.20 <table:background>..... 287
16.21 <style:font-face>..... 288
16.22 <svg:font-face-src>..... 288
16.23 <svg:font-face-name>..... 289
16.24 <svg:font-face-uri>..... 289
16.25 <svg:definition-src>..... 289
16.26 <svg:font-face-format>..... 289
16.27 Data Styles..... 290
16.27.1 General..... 290
16.27.2 <number:number-style>..... 290
16.27.3 <number:number>..... 290
16.27.4 <number:embedded-text>..... 290
16.27.5 <number:scientific-number>..... 291
16.27.6 <number:fraction>..... 291

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.27.7 <number:currency-style>..... 291
16.27.8 <number:currency-symbol>..... 291
16.27.9 <number:percentage-style>..... 292
16.27.10 <number:date-style>..... 292
16.27.11 <number:day>..... 293
16.27.12 <number:month>..... 293
16.27.13 <number:year>..... 293
16.27.14 <number:era>..... 293
16.27.15 <number:day-of-week>..... 294
16.27.16 <number:week-of-year>..... 294
16.27.17 <number:quarter>..... 294
16.27.18 <number:time-style>..... 294
16.27.19 <number:hours>..... 295
16.27.20 <number:minutes>..... 295
16.27.21 <number:seconds>..... 295
16.27.22 <number:am-pm>..... 295
16.27.23 <number:boolean-style>..... 296
16.27.24 <number:boolean>..... 296
16.27.25 <number:text-style>..... 296
16.27.26 <number:text>..... 296
16.27.27 <number:text-content>..... 297
16.27.28 <style:text-properties>..... 297
16.28 Text Style Families..... 298
16.28.1 Text Styles..... 298
16.28.2 Paragraph Styles..... 298
16.28.3 Section Styles..... 298
16.28.4 Ruby Styles..... 298
16.29 Enhanced Text Styles..... 298
16.29.1 <text:linenumbering-configuration>..... 298
16.29.2 <text:linenumbering-separator>..... 299
16.29.3 <text:notes-configuration>..... 299
16.29.4 <text:note-continuation-notice-forward>..... 299
16.29.5 <text:note-continuation-notice-backward>..... 300
16.29.6 <text:bibliography-configuration>..... 300
16.29.7 <text:sort-key>..... 300
16.30 <text:list-style>..... 300
16.31 <text:list-level-style-bullet>..... 301

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.32 <text:list-level-style-number>..... 301
16.33 <text:list-level-style-image>..... 302
16.34 <text:outline-style>..... 302
16.35 <text:outline-level-style>..... 302
16.36 Table Styles..... 303
16.36.1 Table Styles..... 303
16.36.2 Table Column Styles..... 303
16.36.3 Table Row Styles..... 303
16.36.4 Table Cell Styles..... 303
16.37 Graphic Styles..... 303
16.38 Presentation Styles..... 303
16.39 Drawing Page Style..... 303
16.40 Enhanced Graphic Style Elements..... 304
16.40.1 <draw:gradient>..... 304
16.40.2 <svg:linearGradient>..... 304
16.40.3 <svg:radialGradient>..... 304
16.40.4 <svg:stop>..... 305
16.40.5 <draw:hatch>..... 305
16.40.6 <draw:fill-image>..... 305
16.40.7 <draw:opacity>..... 306
16.40.8 <draw:marker>..... 306
16.40.9 <draw:stroke-dash>..... 307
16.41 <style:presentation-page-layout>..... 307
16.42 <presentation:placeholder>..... 307
16.43 Chart Styles..... 307
17 Formatting Elements..... 309
17.1 General..... 309
17.2 <style:page-layout-properties>..... 309
17.3 <style:background-image>..... 309
17.4 <style:footnote-sep>..... 310
17.5 <style:header-footer-properties>..... 310
17.6 <style:paragraph-properties>..... 311
17.7 <style:tab-stops>..... 311
17.8 <style:tab-stop>..... 311
17.9 <style:drop-cap>..... 312
17.10 <style:ruby-properties>..... 312
17.11 <style:section-properties>..... 312

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

17.12 <style:columns>.....312
17.13 <style:column>.....313
17.14 <style:column-sep>.....313
17.15 <style:table-properties>.....313
17.16 <style:table-column-properties>.....314
17.17 <style:table-row-properties>.....314
17.18 <style:table-cell-properties>.....314
17.19 <style:list-level-properties>.....315
17.20 <style:list-level-label-alignment>.....315
17.21 <style:graphic-properties>.....315
17.22 <style:chart-properties>.....317
17.23 <chart:symbol-image>.....318
17.24 <chart:label-separator>.....318
17.25 <style:drawing-page-properties>.....318
18 Datatypes.....320
18.1 Introduction.....320
18.2 W3C Schema Datatypes.....320
18.3 Other Datatypes.....321
18.3.1 angle.....321
18.3.2 anyIRI.....321
18.3.3 boolean.....321
18.3.4 cellAddress.....321
18.3.5 cellRangeAddress.....321
18.3.6 cellRangeAddressList.....321
18.3.7 character.....321
18.3.8 clipShape.....321
18.3.9 color.....321
18.3.10 coordinate.....321
18.3.11 countryCode.....322
18.3.12 CURIE.....322
18.3.13 CURIEs.....322
18.3.14 dateOrDateTime.....322
18.3.15 distance.....322
18.3.16 language.....322
18.3.17 languageCode.....322
18.3.18 length.....322
18.3.19 namespacedToken.....322

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

18.3.20 nonNegativeLength..... 323
18.3.21 nonNegativePixelLength..... 323
18.3.22 pathData..... 323
18.3.23 percent..... 323
18.3.24 point3D..... 323
18.3.25 points..... 323
18.3.26 positiveLength..... 323
18.3.27 relativeLength..... 323
18.3.28 safeCURIE..... 323
18.3.29 scriptCode..... 323
18.3.30 signedZeroToHundredPercent..... 323
18.3.31 styleName..... 324
18.3.32 styleNameRef..... 324
18.3.33 styleNameRefs..... 324
18.3.34 targetFrameName..... 324
18.3.35 textEncoding..... 324
18.3.36 timeOrDateTime..... 324
18.3.37 URIorSafeCURIE..... 324
18.3.38 valueType..... 324
18.3.39 variableName..... 324
18.3.40 vector3D..... 324
18.3.41 zeroToHundredPercent..... 324
19 General Attributes..... 325
19.1 General..... 325
19.2 anim:color-interpolation..... 325
19.3 anim:color-interpolation-direction..... 325
19.4 anim:audio-level..... 325
19.5 anim:command..... 326
19.6 anim:formula..... 326
19.7 anim:id (deprecated)..... 327
19.8 anim:iterate-interval..... 328
19.9 anim:iterate-type..... 328
19.10 anim:name..... 328
19.11 anim:sub-item..... 328
19.12 anim:value..... 329
19.13 chart:attached-axis..... 329
19.14 chart:automatic-content..... 329

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.15 chart:class 330
19.15.1 <chart:chart>, <chart:series> 330
19.15.2 <chart:grid> 336
19.16 chart:column-mapping (deprecated) 337
19.17 chart:data-source-has-labels (deprecated) 337
19.18 chart:dimension 337
19.19 chart:display-equation 338
19.20 chart:display-r-square 338
19.21 chart:label-cell-address 338
19.22 chart:legend-align 339
19.23 chart:legend-position 339
19.24 chart:name 340
19.25 chart:repeated 340
19.26 chart:row-mapping (deprecated) 340
19.27 chart:style-name 340
19.28 chart:values-cell-range-address 341
19.29 config:name 341
19.30 config:type 341
19.31 db:additional-column-statement 342
19.32 db:append-table-alias-name 342
19.33 db:apply-command 342
19.34 db:as-template 342
19.35 db:base-dn 343
19.36 db:boolean-comparison-mode 343
19.37 db:catalog-name 343
19.38 db:command 343
19.39 db:data-source-setting-is-list 344
19.40 db:data-source-setting-name 344
19.41 db:data-source-setting-type 344
19.42 db:data-type 345
19.43 db:database-name 345
19.44 db:decimal 345
19.45 db:default-cell-style-name 345
19.46 db:default-row-style-name 345
19.47 db:delete-rule 346
19.48 db:description 346
19.49 db:enable-sql92-check 346

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.50 db:encoding 347
19.51 db:escape-processing 347
19.52 db:extension 347
19.53 db:field 347
19.54 db:hostname 347
19.55 db:ignore-driver-privileges 348
19.56 db:is-ascending 348
19.57 db:is-autoincrement 348
19.58 db:is-clustered 348
19.59 db:is-empty-allowed 349
19.60 db:is-first-row-header-line 349
19.61 db:login-timeout 349
19.62 db:is-nullable 349
19.63 db:is-password-required 350
19.64 db:is-unique 350
19.65 db:precision 350
19.66 db:is-table-name-length-limited 350
19.67 db:local-socket 351
19.68 db:max-row-count 351
19.69 db:media-type 351
19.70 db:name 351
19.70.1 General 351
19.70.2 <db:column> 351
19.70.3 <db:column-definition> 352
19.70.4 <db:component> 352
19.70.5 <db:component-collection> 352
19.70.6 <db:index> 352
19.70.7 <db:index-column> 352
19.70.8 <db:key> 352
19.70.9 <db:key-column> 353
19.70.10 <db:query> 353
19.70.11 <db:query-collection> 353
19.70.12 <db:table-definition> 353
19.70.13 <db:table-representation> 353
19.70.14 <db:update-table> 353
19.71 db:parameter-name-substitution 354
19.72 db:port 354

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.73 db:referenced-table-name....354
19.74 db:related-column-name....354
19.75 db:row-retrieving-statement....354
19.76 db:scale....355
19.77 db:schema-name....355
19.78 db:show-deleted....355
19.79 db:string....355
19.80 db:style-name....355
19.80.1 General....355
19.80.2 <db:column>....356
19.80.3 <db:query>....356
19.80.4 <db:table-representation>....356
19.81 db:suppress-version-columns....356
19.82 db:system-driver-settings....356
19.83 db:thousand....357
19.84 db:title....357
19.85 db:type....357
19.85.1 General....357
19.85.2 <db:key>....357
19.85.3 <db:server-database>....357
19.85.4 <db:table-definition>....358
19.86 db:type-name....358
19.87 db:update-rule....358
19.88 db:use-catalog....359
19.89 db:use-system-user....359
19.90 db:user-name....359
19.91 db:visible....359
19.92 dr3d:ambient-color....360
19.93 dr3d:center....360
19.94 dr3d:diffuse-color....360
19.95 dr3d:direction....360
19.96 dr3d:distance....360
19.97 dr3d:enabled....361
19.98 dr3d:focal-length....361
19.99 dr3d:lighting-mode....361
19.99.1 General....361
19.99.2 <chart:plot-area>....361

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.99.3 <dr3d:scene>....361
19.100 dr3d:max-edge....362
19.101 dr3d:min-edge....362
19.102 dr3d:projection....362
19.103 dr3d:shade-mode....362
19.104 dr3d:shadow-slant....363
19.105 dr3d:size....363
19.106 dr3d:specular....363
19.107 dr3d:transform....363
19.108 dr3d:vpn....364
19.109 dr3d:vrp....364
19.110 dr3d:vup....364
19.111 draw:align....364
19.112 draw:angle....365
19.113 draw:archive....365
19.114 draw:border....365
19.115 draw:caption-id....366
19.116 draw:caption-point-x....366
19.117 draw:caption-point-y....366
19.118 draw:chain-next-name....366
19.119 draw:class-id....366
19.120 draw:class-names....367
19.121 draw:code....367
19.122 draw:color....367
19.122.1 General....367
19.122.2 <draw:hatch>....367
19.122.3 <presentation:dim>....367
19.123 draw:concave....368
19.124 draw:concentric-gradient-fill-allowed....368
19.125 draw:control....368
19.126 draw:copy-of....368
19.127 draw:corner-radius....369
19.128 draw:corners....369
19.129 draw:cx....369
19.130 draw:cy....369
19.131 draw:data....370
19.132 draw:display....370

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.133 draw:display-name 370
19.133.1 General 370
19.133.2 <draw:fill-image> 370
19.133.3 <draw:gradient> 370
19.133.4 <draw:hatch> 371
19.133.5 <draw:marker> 371
19.133.6 <draw:opacity> 371
19.133.7 <draw:stroke-dash> 371
19.133.8 <svg:linearGradient> 371
19.133.9 <svg:radialGradient> 371
19.134 draw:distance 372
19.134.1 General 372
19.134.2 <draw:hatch> 372
19.134.3 <draw:stroke-dash> 372
19.135 draw:dots1 372
19.136 draw:dots1-length 372
19.137 draw:dots2 373
19.138 draw:dots2-length 373
19.139 draw:end 373
19.140 draw:end-angle 373
19.141 draw:end-color 373
19.142 draw:end-glue-point 374
19.143 draw:end-intensity 374
19.144 draw:end-shape 374
19.145 draw:enhanced-path 374
19.146 draw:engine 376
19.147 draw:escape-direction 377
19.148 draw:extrusion 377
19.149 draw:extrusion-allowed 377
19.150 draw:extrusion-brightness 378
19.151 draw:extrusion-color 378
19.152 draw:extrusion-depth 378
19.153 draw:extrusion-diffusion 378
19.154 draw:extrusion-first-light-direction 379
19.155 draw:extrusion-first-light-harsh 379
19.156 draw:extrusion-first-light-level 379
19.157 draw:extrusion-light-face 379

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.158 draw:extrusion-metal....380
19.159 draw:extrusion-number-of-line-segments....380
19.160 draw:extrusion-origin....380
19.161 draw:extrusion-rotation-angle....381
19.162 draw:extrusion-rotation-center....381
19.163 draw:extrusion-second-light-direction....381
19.164 draw:extrusion-second-light-harsh....382
19.165 draw:extrusion-second-light-level....382
19.166 draw:extrusion-shininess....382
19.167 draw:extrusion-skew....382
19.168 draw:extrusion-specularity....383
19.169 draw:extrusion-viewpoint....383
19.170 draw:filter-name....383
19.171 draw:formula....383
19.172 draw:frame-name....385
19.173 draw:glue-point-leaving-directions....385
19.174 draw:glue-point-type....386
19.175 draw:glue-points....386
19.176 draw:handle-mirror-horizontal....387
19.177 draw:handle-mirror-vertical....387
19.178 draw:handle-polar....387
19.179 draw:handle-position....388
19.180 draw:handle-radius-range-maximum....389
19.181 draw:handle-radius-range-minimum....389
19.182 draw:handle-range-x-maximum....390
19.183 draw:handle-range-x-minimum....390
19.184 draw:handle-range-y-maximum....390
19.185 draw:handle-range-y-minimum....390
19.186 draw:handle-switched....390
19.187 draw:id....391
19.187.1 General....391
19.187.2 <draw:glue-point>....391
19.187.3 <dr3d:cube>, <dr3d:extrude>, <dr3d:rotate>, <dr3d:scene>, <dr3d:sphere>, <draw:caption>, <draw:circle>, <draw:connector>, <draw:control>, <draw:custom-shape>, <draw:ellipse>, <draw:frame>, <draw:g>, <draw:line>, <draw:measure>, <draw:page>, <draw:page-thumbnail>, <draw:path>, <draw:polygon>, <draw:polyline>, <draw:rect>, <draw:regular-polygon> and <office:annotation>....391
19.188 draw:kind....392
19.189 draw:layer....392

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.190 draw:line-skew ... 392
19.191 draw:mime-type ... 393
19.192 draw:mirror-horizontal ... 393
19.193 draw:mirror-vertical ... 393
19.194 draw:master-page-name ... 394
19.195 draw:may-script ... 394
19.196 draw:modifiers ... 394
19.197 draw:name ... 394
19.197.1 General ... 394
19.197.2 <draw:caption> ... 395
19.197.3 <draw:circle> ... 395
19.197.4 <draw:connector> ... 395
19.197.5 <draw:control> ... 395
19.197.6 <draw:custom-shape> ... 395
19.197.7 <draw:ellipse> ... 395
19.197.8 <draw:equation> ... 396
19.197.9 <draw:fill-image> ... 396
19.197.10 <draw:frame> ... 396
19.197.11 <draw:g> ... 396
19.197.12 <draw:gradient> ... 396
19.197.13 <draw:hatch> ... 396
19.197.14 <draw:layer> ... 396
19.197.15 <draw:line> ... 397
19.197.16 <draw:marker> ... 397
19.197.17 <draw:measure> ... 397
19.197.18 <draw:opacity> ... 397
19.197.19 <draw:page> ... 397
19.197.20 <draw:page-thumbnail> ... 397
19.197.21 <draw:param> ... 398
19.197.22 <draw:path> ... 398
19.197.23 <draw:polygon> ... 398
19.197.24 <draw:polyline> ... 398
19.197.25 <draw:rect> ... 398
19.197.26 <draw:regular-polygon> ... 398
19.197.27 <draw:stroke-dash> ... 399
19.197.28 <office:annotation> (deprecated) ... 399
19.197.29 <svg:linearGradient> ... 399

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.197.30 <svg:radialGradient>..... 399
19.198 draw:nav-order..... 400
19.199 draw:nohref..... 400
19.200 draw:notify-on-update-of-ranges..... 400
19.201 draw:object..... 400
19.202 draw:opacity..... 401
19.203 draw:page-number..... 401
19.204 draw:path-stretchpoint-x..... 401
19.205 draw:path-stretchpoint-y..... 401
19.206 draw:points..... 402
19.207 draw:protected..... 402
19.208 draw:recreate-on-edit..... 402
19.209 draw:rotation..... 403
19.210 draw:shape-id..... 403
19.211 draw:sharpness..... 403
19.212 draw:start..... 403
19.213 draw:start-angle..... 403
19.214 draw:start-color..... 404
19.215 draw:start-glue-point..... 404
19.216 draw:start-intensity..... 404
19.217 draw:start-shape..... 404
19.218 draw:style..... 404
19.218.1 General..... 404
19.218.2 <draw:gradient>..... 405
19.218.3 <draw:hatch>..... 405
19.218.4 <draw:opacity>..... 406
19.218.5 <draw:stroke-dash>..... 406
19.219 draw:style-name..... 406
19.219.1 General..... 406
19.219.2 <dr3d:cube>..... 406
19.219.3 <dr3d:extrude>..... 407
19.219.4 <dr3d:rotate>..... 407
19.219.5 <dr3d:scene>..... 407
19.219.6 <dr3d:sphere>..... 407
19.219.7 <draw:caption>..... 407
19.219.8 <draw:circle>..... 407
19.219.9 <draw:connector>..... 408

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.219.10 <draw:control>..... 408
19.219.11 <draw:custom-shape>..... 408
19.219.12 <draw:ellipse>..... 408
19.219.13 <draw:frame>..... 408
19.219.14 <draw:g>..... 408
19.219.15 <draw:line>..... 409
19.219.16 <draw:measure>..... 409
19.219.17 <draw:page>..... 409
19.219.18 <draw:page-thumbnail>..... 409
19.219.19 <draw:path>..... 409
19.219.20 <draw:polygon>..... 409
19.219.21 <draw:polyline>..... 410
19.219.22 <draw:rect>..... 410
19.219.23 <draw:regular-polygon>..... 410
19.219.24 <office:annotation>..... 410
19.219.25 <presentation:notes>..... 410
19.219.26 <style:handout-master>..... 411
19.219.27 <style:master-page>..... 411
19.220 draw:text-areas..... 411
19.221 draw:text-path..... 412
19.222 draw:text-path-allowed..... 412
19.223 draw:text-path-mode..... 413
19.224 draw:text-path-same-letter-heights..... 413
19.225 draw:text-path-scale..... 413
19.226 draw:text-rotate-angle..... 414
19.227 draw:text-style-name..... 414
19.228 draw:transform..... 414
19.229 draw:type..... 415
19.229.1 General..... 415
19.229.2 <draw:connector>..... 415
19.229.3 <draw:enhanced-geometry>..... 415
19.230 draw:value..... 416
19.231 draw:z-index..... 416
19.232 fo:column-count..... 416
19.233 fo:column-gap..... 416
19.234 fo:country..... 417
19.234.1 <text:alphabetical-index-source>..... 417

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.234.2 <text:bibliography-configuration>....417
19.235 fo:end-indent....417
19.236 fo:language....417
19.236.1 General....417
19.236.2 <text:alphabetical-index-source>....418
19.236.3 <text:bibliography-configuration>....418
19.237 fo:margin-left....418
19.238 fo:max-height....418
19.239 fo:max-width....419
19.240 fo:min-height....419
19.241 fo:min-width....419
19.242 fo:script....420
19.242.1 General....420
19.242.2 <text:alphabetical-index-source>....420
19.242.3 <text:bibliography-configuration>....420
19.243 fo:space-after....420
19.244 fo:space-before....420
19.245 fo:start-indent....421
19.246 fo:text-indent....421
19.247 form:allow-deletes....421
19.248 form:allow-inserts....421
19.249 form:allow-updates....422
19.250 form:apply-design-mode....422
19.251 form:apply-filter....422
19.252 form:auto-complete....423
19.253 form:automatic-focus....423
19.254 form:bound-column....423
19.255 form:button-type....424
19.256 form:command....424
19.257 form:command-type....424
19.258 form:control-implementation....425
19.259 form:convert-empty-to-null....425
19.260 form:current-selected....425
19.261 form:current-state....426
19.262 form:current-value....426
19.263 form:data-field....426
19.264 form:datasource....427

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.265 form:default-button....427
19.266 form:delay-for-repeat....428
19.267 form:detail-fields....428
19.268 form:disabled....428
19.269 form:dropdown....428
19.270 form:echo-char....429
19.271 form:enctype....429
19.272 form:escape-processing....429
19.273 form:filter....430
19.274 form:focus-on-click....430
19.275 form:for....430
19.276 form:id....430
19.277 form:ignore-result....431
19.278 form:image-align....431
19.279 form:image-data....431
19.280 form:image-position....432
19.281 form:is-tristate....432
19.282 form:label....432
19.283 form:linked-cell....433
19.284 form:list-linkage-type....433
19.285 form:list-source....433
19.286 form:list-source-type....434
19.287 form:master-fields....435
19.288 form:max-length....435
19.289 form:max-value....435
19.289.1 General....435
19.289.2 <form:date>....435
19.289.3 <form:formatted-text>....436
19.289.4 <form:number> and <form:value-range>....436
19.289.5 <form:time>....436
19.290 form:min-value....436
19.290.1 General....436
19.290.2 <form:date>....436
19.290.3 <form:formatted-text>....436
19.290.4 <form:number> and <form:value-range>....436
19.290.5 <form:time>....437
19.291 form:method....437

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.292 form:multi-line ... 437
19.293 form:multiple ... 437
19.294 form:name ... 438
19.295 form:navigation-mode ... 438
19.296 form:order ... 438
19.297 form:orientation ... 439
19.298 form:page-step-size ... 439
19.299 form:printable ... 439
19.300 form:property-name ... 439
19.301 form:readonly ... 440
19.302 form:repeat ... 440
19.303 form:selected ... 440
19.304 form:size ... 441
19.305 form:source-cell-range ... 441
19.306 form:spin-button ... 441
19.307 form:state ... 442
19.308 form:step-size ... 442
19.309 form:tab-cycle ... 442
19.310 form:tab-index ... 443
19.311 form:tab-stop ... 443
19.312 form:text-style-name ... 444
19.313 form:title ... 444
19.314 form:toggle ... 444
19.315 form:validation ... 444
19.316 form:value ... 445
19.316.1 General ... 445
19.316.2 <form:button> ... 445
19.316.3 <form:date> ... 445
19.316.4 <form:number> and <form:value-range> ... 445
19.316.5 <form:checkbox>, <form:combobox>, <form:file>, <form:formatted-text>, <form:hidden>, <form:image>, <form:option>, <form:password>, <form:radio>, <form:text>, <form:textarea> ... 445
19.316.6 <form:time> ... 446
19.317 form:visual-effect ... 446
19.318 form:xforms-list-source ... 446
19.319 form:xforms-submission ... 446
19.320 grddl:transformation ... 446
19.321 meta:cell-count ... 447

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.322 meta:character-count 447
19.323 meta:date 447
19.324 meta:delay 447
19.325 meta:draw-count 448
19.326 meta:frame-count 448
19.327 meta:image-count 448
19.328 meta:name 448
19.329 meta:non-whitespace-character-count 448
19.330 meta:object-count 449
19.331 meta:ole-object-count 449
19.332 meta:page-count 449
19.333 meta:paragraph-count 449
19.334 meta:row-count 449
19.335 meta:sentence-count 450
19.336 meta:syllable-count 450
19.337 meta:table-count 450
19.338 meta:value-type 450
19.339 meta:word-count 451
19.340 number:automatic-order 451
19.341 number:calendar 451
19.342 number:country 452
19.343 number:decimal-places 452
19.343.1 General 452
19.343.2 <number:number> 452
19.343.3 <number:seconds> 453
19.343.4 <number:scientific-number> 453
19.344 number:decimal-replacement 453
19.345 number:denominator-value 453
19.346 number:display-factor 454
19.347 number:format-source 454
19.348 number:grouping 454
19.349 number:language 455
19.350 number:min-denominator-digits 455
19.351 number:min-exponent-digits 455
19.352 number:min-integer-digits 455
19.353 number:min-numerator-digits 455
19.354 number:position 456

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.355 number:possessive-form....456
19.356 number:rfc-language-tag....456
19.357 number:script....457
19.358 number:style....457
19.358.1 General....457
19.358.2 <number:day>....457
19.358.3 <number:day-of-week>....457
19.358.4 <number:era>....458
19.358.5 <number:hours>....458
19.358.6 <number:minutes>....458
19.358.7 <number:month>....458
19.358.8 <number:quarter>....459
19.358.9 <number:seconds>....459
19.358.10 <number:year>....459
19.359 number:textual....459
19.360 number:title....460
19.361 number:transliteration-country....460
19.362 number:transliteration-format....460
19.363 number:transliteration-language....460
19.364 number:transliteration-style....461
19.365 number:truncate-on-overflow....461
19.366 office:automatic-update....461
19.367 office:boolean-value....462
19.368 office:conversion-mode....462
19.369 office:currency....463
19.370 office:date-value....463
19.371 office:dde-application....463
19.372 office:dde-item....463
19.373 office:dde-topic....464
19.374 office:display....464
19.375 office:mimetype....464
19.376 office:name....464
19.376.1 General....464
19.376.2 <draw:a>....464
19.376.3 <draw:area-circle>....465
19.376.4 <draw:area-rectangle>....465
19.376.5 <draw:area-polygon>....465

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.376.6 <office:annotation> 465
19.376.7 <office:annotation-end> 465
19.376.8 <office:dde-source> 466
19.376.9 <text:a> 466
19.376.10 <text:dde-connection-decl> 466
19.377 office:process-content (deprecated) 466
19.378 office:server-map 466
19.379 office:string-value 467
19.380 office:target-frame 467
19.381 office:target-frame-name 467
19.382 office:time-value 468
19.383 office:title 468
19.384 office:value 468
19.385 office:value-type 469
19.386 office:version 470
19.387 presentation:action 471
19.388 presentation:animations 472
19.389 presentation:class 472
19.390 presentation:class-names 473
19.391 presentation:delay 473
19.392 presentation:direction 473
19.393 presentation:endless 475
19.394 presentation:effect 475
19.395 presentation:force-manual 476
19.396 presentation:full-screen 476
19.397 presentation:group-id 477
19.398 presentation:master-element 477
19.399 presentation:mouse-as-pen 477
19.400 presentation:mouse-visible 477
19.401 presentation:name 478
19.402 presentation:node-type 478
19.403 presentation:object 479
19.404 presentation:pages 479
19.405 presentation:path-id 479
19.406 presentation:pause 479
19.407 presentation:placeholder 480
19.408 presentation:play-full 480

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.409 presentation:presentation-page-layout-name 480
19.410 presentation:preset-class 480
19.411 presentation:preset-id 481
19.412 presentation:preset-sub-type 481
19.413 presentation:show 481
19.414 presentation:show-end-of-presentation-slide 481
19.415 presentation:show-logo 482
19.416 presentation:source 482
19.417 presentation:speed 482
19.418 presentation:start-scale 483
19.419 presentation:start-page 483
19.420 presentation:start-with-navigator 483
19.421 presentation:stay-on-top 483
19.422 presentation:style-name 484
19.423 presentation:transition-on-click 484
19.424 presentation:use-date-time-name 484
19.425 presentation:use-footer-name 485
19.426 presentation:use-header-name 485
19.427 presentation:user-transformed 485
19.428 presentation:verb 485
19.429 script:event-name 486
19.430 script:language 487
19.431 script:macro-name 487
19.432 smil:accelerate 487
19.433 smil:accumulate 487
19.434 smil:additive 487
19.435 smil:attributeName 488
19.436 smil:autoReverse 489
19.437 smil:begin 489
19.438 smil:by 489
19.439 smil:calcMode 489
19.440 smil:decelerate 490
19.441 smil:direction 490
19.442 smil:dur 490
19.443 smil:end 490
19.444 smil:endsync 490
19.445 smil:fadeColor 491

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.446 smil:fill ... 491
19.447 smil:fillDefault ... 491
19.448 smil:from ... 491
19.449 smil:keySplines ... 492
19.450 smil:keyTimes ... 492
19.451 smil:mode ... 492
19.452 smil:repeatCount ... 492
19.453 smil:repeatDur ... 492
19.454 smil:restart ... 493
19.455 smil:restartDefault ... 493
19.456 smil:subtype ... 493
19.457 smil:targetElement ... 493
19.458 smil:to ... 494
19.459 smil:type ... 494
19.460 smil:values ... 494
19.461 style:adjustment ... 494
19.462 style:apply-style-name ... 495
19.463 style:auto-update ... 495
19.464 style:base-cell-address ... 495
19.465 style:char ... 495
19.466 style:class ... 496
19.467 style:color ... 496
19.468 style:condition ... 496
19.469 style:data-style-name ... 497
19.469.1 General ... 497
19.469.2 <presentation:date-time-decl> ... 497
19.469.3 <style:style> ... 498
19.469.4 <text:creation-date> ... 498
19.469.5 <text:creation-time> ... 498
19.469.6 <text:database-display> ... 498
19.469.7 <text:date> ... 498
19.469.8 <text:editing-duration> ... 499
19.469.9 <text:expression> ... 499
19.469.10 <text:meta-field> ... 499
19.469.11 <text:modification-date> ... 499
19.469.12 <text:modification-time> ... 499
19.469.13 <text:print-date> ... 499

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.469.14 <text:print-time>.... 500
19.469.15 <text:table-formula>.... 500
19.469.16 <text:time>.... 500
19.469.17 <text:user-defined>.... 500
19.469.18 <text:user-field-get>.... 500
19.469.19 <text:user-field-input>.... 501
19.469.20 <text:variable-get>.... 501
19.469.21 <text:variable-input>.... 501
19.469.22 <text:variable-set>.... 501
19.470 style:default-outline-level.... 501
19.471 style:display.... 502
19.472 style:display-name.... 502
19.473 style:distance.... 502
19.474 style:distance-before-sep.... 503
19.475 style:distance-after-sep.... 503
19.476 style:family.... 503
19.477 style:filter-name.... 504
19.478 style:font-adornments.... 504
19.479 style:font-charset.... 504
19.480 style:font-family-generic.... 504
19.481 style:font-pitch.... 505
19.482 style:height.... 505
19.483 style:leader-char.... 505
19.484 style:leader-color.... 505
19.485 style:leader-style.... 506
19.486 style:leader-text.... 506
19.487 style:leader-text-style.... 507
19.488 style:leader-type.... 507
19.489 style:leader-width.... 507
19.490 style:legend-expansion.... 508
19.491 style:legend-expansion-aspect-ratio.... 508
19.492 style:length.... 508
19.493 style:line-style.... 508
19.494 style:lines.... 509
19.495 style:list-level.... 509
19.496 style:list-style-name.... 509
19.497 style:master-page-name.... 509

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.498 style:name 510
19.498.1 General 510
19.498.2 <number:boolean-style>, <number:currency-style>, <number:date-style>, <number:number-style>, <number:percentage-style>, <number:text-style>, <number:time-style>, <style:master-page>, <style:page-layout>, <style:presentation-page-layout>, <style:style>, <text:list-style>, <text:outline-style> 510
19.498.3 <style:font-face> 511
19.499 style:next-style-name 511
19.499.1 General 511
19.499.2 <style:master-page> 511
19.499.3 <style:style> 511
19.500 style:num-format 511
19.501 style:num-letter-sync 512
19.502 style:num-prefix 512
19.503 style:num-suffix 513
19.504 style:page-layout-name 513
19.505 style:page-usage 513
19.506 style:parent-style-name 514
19.507 style:percentage-data-style-name 514
19.508 style:position 514
19.508.1 General 514
19.508.2 <style:background-image> 514
19.508.3 <style:tab-stop> 515
19.508.4 <text:index-entry-tab-stop> 515
19.509 style:rel-height 515
19.510 style:rel-width 516
19.510.1 General 516
19.510.2 <draw:frame> 516
19.510.3 <style:column> 516
19.510.4 <style:footnote-sep> 516
19.511 style:repeat 517
19.512 style:rfc-language-tag 517
19.513 style:style 517
19.514 style:style-name 518
19.515 style:type 518
19.515.1 General 518
19.515.2 <text:index-entry-tab-stop> 518
19.515.3 <style:tab-stop> 518

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.516 style:vertical-align 519
19.517 style:volatile 519
19.518 style:width 519
19.518.1 General 519
19.518.2 <style:column-sep> 519
19.518.3 <style:footnote-sep> 520
19.519 svg:accent-height 520
19.520 svg:alphabetic 520
19.521 svg:ascent 520
19.522 svg:bbox 520
19.523 svg:cap-height 520
19.524 svg:cx 521
19.524.1 <draw:area-circle> 521
19.524.2 <draw:circle> 521
19.524.3 <draw:ellipse> 521
19.524.4 <svg:radialGradient> 521
19.525 svg:cy 521
19.525.1 <draw:area-circle> 521
19.525.2 <draw:circle> 521
19.525.3 <draw:ellipse> 522
19.525.4 <svg:radialGradient> 522
19.526 svg:d 522
19.527 svg:descent 522
19.528 svg:font-family 522
19.529 svg:font-size 522
19.530 svg:font-stretch 523
19.531 svg:font-style 523
19.532 svg:font-variant 523
19.533 svg:font-weight 523
19.534 svg:fx 523
19.535 svg:fy 523
19.536 svg:gradientTransform 524
19.537 svg:gradientUnits 524
19.538 svg:hanging 524
19.539 svg:height 524
19.539.1 <chart:chart> 524
19.539.2 <chart:plot-area> 524

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.539.3 <dr3d:scene>.....525
19.539.4 <draw:area-polygon>.....525
19.539.5 <draw:area-rectangle>.....525
19.539.6 <draw:contour-polygon>, <draw:contour-path>.....525
19.539.7 <draw:fill-image>.....525
19.539.8 <draw:caption>, <draw:custom-shape>, <draw:circle>, <draw:control>, <draw:ellipse>, <draw:frame>, <draw:rect>, <draw:page-thumbnail>, <draw:path>, <draw:polygon>, <draw:polyline>, <draw:regular-polygon>.....525
19.539.9 <office:annotation>.....526
19.539.10 <presentation:placeholder>.....526
19.540 svg:ideographic.....526
19.541 svg:mathematical.....526
19.542 svg:name.....526
19.543 svg:offset.....527
19.544 svg:origin.....527
19.545 svg:overline-position.....527
19.546 svg:overline-thickness.....527
19.547 svg:panose-1.....527
19.548 svg:path.....527
19.549 svg:r.....528
19.549.1 <draw:area-circle>.....528
19.549.2 <draw:circle>.....528
19.549.3 <svg:radialGradient>.....528
19.550 svg:rx.....528
19.551 svg:ry.....529
19.552 svg:slope.....529
19.553 svg:spreadMethod.....529
19.554 svg:stemh.....529
19.555 svg:stemv.....529
19.556 svg:stop-color.....529
19.557 svg:stop-opacity.....530
19.558 svg:strikethrough-position.....530
19.559 svg:strikethrough-thickness.....530
19.560 svg:string.....530
19.561 svg:type.....530
19.562 svg:underline-position.....530
19.563 svg:underline-thickness.....531
19.564 svg:unicode-range.....531

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.565 svg:units-per-em 531
19.566 svg:v-alphabetic 531
19.567 svg:v-hanging 531
19.568 svg:v-ideographic 531
19.569 svg:v-mathematical 532
19.570 svg:viewBox 532
19.571 svg:width 532
19.571.1 <chart:chart> 532
19.571.2 <chart:floor> 532
19.571.3 <chart:plot-area> 533
19.571.4 <chart:wall> 533
19.571.5 <dr3d:scene> 533
19.571.6 <draw:area-polygon> 533
19.571.7 <draw:area-rectangle> 533
19.571.8 <draw:contour-polygon>, <draw:contour-path> 533
19.571.9 <draw:fill-image> 533
19.571.10 <draw:caption>, <draw:custom-shape>, <draw:circle>, <draw:control>, <draw:ellipse>, <draw:frame>, <draw:rect>, <draw:page-thumbnail>, <draw:path>, <draw:polygon>, <draw:polyline>, <draw:regular-polygon> 534
19.571.11 <office:annotation> 534
19.571.12 <presentation:placeholder> 534
19.572 svg:widths 534
19.573 svg:x 535
19.573.1 <chart:data-label>, <chart:equation>, <chart:footer>, <chart:legend>, <chart:plot-area>, <chart:subtitle>, <chart:title> 535
19.573.2 <draw:area-polygon> 535
19.573.3 <draw:area-rectangle> 535
19.573.4 <dr3d:scene> 535
19.573.5 <draw:caption>, <draw:custom-shape>, <draw:circle>, <draw:control>, <draw:ellipse>, <draw:frame>, <draw:rect>, <draw:page-thumbnail>, <draw:path>, <draw:polygon>, <draw:polyline>, <draw:regular-polygon> 535
19.573.6 <draw:glue-point> 536
19.573.7 <office:annotation> 536
19.573.8 <presentation:placeholder> 536
19.574 svg:x1 536
19.574.1 <draw:connector>, <draw:line> and <draw:measure> 536
19.574.2 <svg:linearGradient> 536
19.575 svg:x2 537
19.575.1 <draw:connector>, <draw:line> and <draw:measure> 537

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.575.2 <svg:linearGradient>..... 537
19.576 svg:x-height..... 537
19.577 svg:y..... 537
19.577.1 <chart:data-label>, <chart:equation>, <chart:footer>, <chart:legend>, <chart:plot-area>, <chart:subtitle>, <chart:title>..... 537
19.577.2 <draw:area-polygon>..... 538
19.577.3 <draw:area-rectangle>..... 538
19.577.4 <dr3d:scene>..... 538
19.577.5 <draw:caption>, <draw:custom-shape>, <draw:circle>, <draw:control>, <draw:ellipse>, <draw:frame>, <draw:g>, <draw:rect>, <draw:page-thumbnail>, <draw:path>, <draw:polygon>, <draw:polyline>, <draw:regular-polygon>..... 538
19.577.6 <draw:glue-point>..... 538
19.577.7 <office:annotation>..... 539
19.577.8 <presentation:placeholder>..... 539
19.578 svg:y1..... 539
19.578.1 <draw:connector>, <draw:line> and <draw:measure>..... 539
19.578.2 <svg:linearGradient>..... 539
19.579 svg:y2..... 539
19.579.1 <draw:connector>, <draw:line> and <draw:measure>..... 539
19.579.2 <svg:linearGradient>..... 540
19.580 table:acceptance-state..... 540
19.581 table:algorithm..... 540
19.582 table:add-empty-lines..... 540
19.583 table:allow-empty-cell..... 541
19.584 table:application-data..... 541
19.585 table:automatic-find-labels..... 541
19.586 table:base-cell-address..... 542
19.587 table:bind-styles-to-content..... 542
19.588 table:border-color..... 542
19.589 table:buttons..... 542
19.590 table:case-sensitive..... 543
19.591 table:cell-address..... 543
19.592 table:cell-range..... 543
19.593 table:cell-range-address..... 543
19.593.1 General..... 543
19.593.2 <chart:categories>..... 544
19.593.3 <chart:domain> - bubble..... 544
19.593.4 <chart:domain>- scatter..... 544

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.593.5 <chart:domain> - surface..... 544
19.593.6 <chart:plot-area> (deprecated)..... 544
19.593.7 <table:highlighted-range>..... 545
19.593.8 <table:named-range>..... 545
19.593.9 <table:source-cell-range>..... 545
19.594 table:column..... 545
19.595 table:comment..... 546
19.596 table:condition..... 546
19.597 table:condition-source..... 547
19.598 table:condition-source-range-address..... 548
19.599 table:contains-error..... 548
19.600 table:contains-header..... 548
19.601 table:content-validation-name..... 548
19.602 table:copy-back..... 549
19.603 table:copy-formulas..... 549
19.604 table:copy-styles..... 549
19.605 table:count..... 550
19.606 table:country..... 550
19.607 table:data-field..... 550
19.608 table:data-cell-range-address..... 550
19.609 table:database-name..... 550
19.610 table:database-table-name..... 551
19.611 table:data-type..... 551
19.611.1 General..... 551
19.611.2 <table:filter-condition>..... 551
19.611.3 <table:sort-by>..... 551
19.611.4 <table:sort-groups>..... 552
19.612 table:date-end..... 552
19.613 table:date-start..... 552
19.614 table:date-value..... 553
19.615 table:default-cell-style-name..... 553
19.616 table:direction..... 553
19.617 table:display..... 553
19.618 table:display-border..... 554
19.619 table:display-duplicates..... 554
19.620 table:display-filter-buttons..... 555
19.621 table:display-list..... 555

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.622 table:display-member-mode 555
19.623 table:drill-down-on-double-click 556
19.624 table:embedded-number-behavior 556
19.625 table:enabled 557
19.626 table:end 557
19.627 table:end-cell-address 558
19.628 table:end-column 558
19.629 table:end-position 558
19.630 table:end-row 558
19.631 table:end-table 559
19.632 table:end-x 559
19.633 table:end-y 559
19.634 table:execute 559
19.635 table:expression 560
19.636 table:field-name 560
19.637 table:field-number 560
19.638 table:filter-name 561
19.639 table:filter-options 561
19.640 table:first-row-end-column (deprecated) 561
19.641 table:first-row-start-column (deprecated) 561
19.642 table:formula 562
19.643 table:function 563
19.643.1 General 563
19.643.2 <table:consolidation> 563
19.643.3 <table:data-pilot-field> 563
19.643.4 <table:data-pilot-subtotal> 564
19.643.5 <table:subtotal-field> 564
19.644 table:grand-total 564
19.645 table:group-by-field-number 565
19.646 table:grouped-by 565
19.647 table:has-persistent-data 565
19.648 table:id 566
19.649 table:identify-categories 566
19.650 table:ignore-empty-rows 566
19.651 table:index 566
19.652 table:is-active 567
19.653 table:is-data-layout-field 567

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.654 table:is-selection 567
19.655 table:is-sub-table 567
19.656 table:label-cell-range-address 568
19.657 table:language 568
19.658 table:last-column-spanned 568
19.659 table:last-row-end-column (deprecated) 568
19.660 table:last-row-spanned 569
19.661 table:last-row-start-column (deprecated) 569
19.662 table:layout-mode 569
19.663 table:link-to-source-data 570
19.664 table:marked-invalid 570
19.665 table:matrix-covered 570
19.666 table:maximum-difference 571
19.667 table:member-count 571
19.668 table:member-name 571
19.669 table:member-type 571
19.670 table:message-type 572
19.671 table:mode 572
19.672 table:multi-deletion-spanned 572
19.673 table:name 573
19.673.1 General 573
19.673.2 <table:cell-range-source> 573
19.673.3 <table:content-validation> 573
19.673.4 <table:data-pilot-group> 573
19.673.5 <table:data-pilot-group-member> 573
19.673.6 <table:data-pilot-member> 573
19.673.7 <table:data-pilot-table> 574
19.673.8 <table:database-range> 574
19.673.9 <table:named-expression> 574
19.673.10 <table:named-range> 574
19.673.11 <table:operation> 574
19.673.12 <table:source-service> 575
19.673.13 <table:table> 575
19.673.14 <table:table-template> 575
19.674 table:null-year 575
19.675 table:number-columns-repeated 575
19.675.1 General 575

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.675.2 <table:covered-table-cell>..... 576
19.675.3 <table:table-cell>..... 576
19.675.4 <table:table-column>..... 576
19.676 table:number-columns-spanned..... 576
19.677 table:number-rows-repeated..... 577
19.678 table:number-rows-spanned..... 577
19.679 table:number-matrix-columns-spanned..... 577
19.680 table:number-matrix-rows-spanned..... 577
19.681 table:object-name..... 578
19.682 table:on-update-keep-size..... 578
19.683 table:on-update-keep-styles..... 578
19.684 table:operator..... 578
19.685 table:order..... 579
19.686 table:orientation..... 580
19.686.1 General..... 580
19.686.2 <table:data-pilot-field>..... 580
19.686.3 <table:database-range>..... 580
19.686.4 <table:label-range>..... 581
19.687 table:page-breaks-on-group-change..... 581
19.688 table:paragraph-style-name..... 581
19.689 table:parse-sql-statement..... 582
19.690 table:password..... 582
19.691 table:position..... 582
19.692 table:precision-as-shown..... 582
19.693 table:print..... 583
19.694 table:print-ranges..... 583
19.695 table:protect..... 583
19.696 table:protected..... 584
19.696.1 General..... 584
19.696.2 <table:covered-table-cell> 584
19.696.3 <table:scenario>..... 584
19.696.4 <table:table>..... 584
19.696.5 <table:table-cell> 585
19.697 table:protection-key..... 585
19.698 table:protection-key-digest-algorithm..... 585
19.699 table:query-name..... 586
19.700 table:range-usable-as..... 586

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.701 table:refresh-delay 586
19.702 table:rejecting-change-id 586
19.703 table:rfc-language-tag 587
19.704 table:row 587
19.705 table:scenario-ranges 587
19.706 table:script 587
19.707 table:search-criteria-must-apply-to-whole-cell 588
19.708 table:selected-page 588
19.709 table:show-details 588
19.710 table:show-empty 589
19.711 table:show-filter-button 589
19.712 table:sort-mode 589
19.713 table:source-cell-range-addresses 589
19.714 table:source-field-name 590
19.715 table:source-name 590
19.716 table:sql-statement 590
19.717 table:start 590
19.718 table:start-column 591
19.719 table:start-position 591
19.720 table:start-row 591
19.721 table:start-table 591
19.722 table:status 591
19.723 table:step 592
19.724 table:steps 592
19.725 table:structure-protected 592
19.726 table:style-name 592
19.726.1 General 592
19.726.2 <table:background> 593
19.726.3 <table:body> 593
19.726.4 <table:covered-table-cell> 593
19.726.5 <table:even-columns> 593
19.726.6 <table:even-rows> 593
19.726.7 <table:first-column> 593
19.726.8 <table:first-row> 594
19.726.9 <table:last-column> 594
19.726.10 <table:last-row> 594
19.726.11 <table:odd-columns> 594

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.726.12 <table:odd-rows>..... 594
19.726.13 <table:table-cell>..... 594
19.726.14 <table:table-column>..... 595
19.726.15 <table:table-row>..... 595
19.726.16 <table:table>..... 595
19.727 table:table..... 595
19.728 table:table-background..... 595
19.729 table:table-name..... 596
19.730 table:target-cell-address..... 596
19.731 table:target-range-address..... 596
19.731.1 General..... 596
19.731.2 <table:data-pilot-table>..... 596
19.731.3 <table:database-range>..... 597
19.731.4 <table:filter>..... 597
19.731.5 <table:sort>..... 597
19.732 table:template-name..... 597
19.733 table:title..... 597
19.734 table:track-changes..... 597
19.735 table:type..... 598
19.735.1 General..... 598
19.735.2 <table:data-pilot-field-reference>..... 598
19.735.3 <table:deletion>..... 599
19.735.4 <table:insertion>..... 599
19.736 table:use-banding-columns-styles..... 599
19.737 table:use-banding-rows-styles..... 600
19.738 table:use-first-column-styles..... 600
19.739 table:use-first-row-styles..... 600
19.740 table:use-last-column-styles..... 601
19.741 table:use-last-row-styles..... 601
19.742 table:use-labels..... 601
19.743 table:use-regular-expressions..... 602
19.744 table:use-wildcards..... 602
19.745 table:used-hierarchy..... 603
19.746 table:user-name..... 603
19.747 table:value..... 603
19.747.1 <table:filter-condition>..... 603
19.747.2 <table:filter-set-item>..... 603

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.748 table:value-type 604
19.749 table:visibility 604
19.750 text:active 604
19.751 text:address 604
19.752 text:alphabetical-separators 605
19.753 text:anchor-page-number 605
19.754 text:anchor-type 605
19.755 text:annote 606
19.756 text:author 607
19.757 text:bibliography-data-field 607
19.758 text:bibliography-type 608
19.759 text:booktitle 609
19.760 text:bullet-char 609
19.761 text:bullet-relative-size 610
19.762 text:capitalize-entries 610
19.763 text:c 611
19.764 text:caption-sequence-format 611
19.765 text:caption-sequence-name 611
19.766 text:change-id 611
19.767 text:chapter 612
19.768 text:citation-body-style-name 612
19.769 text:citation-style-name 612
19.770 text:class-names 612
19.770.1 General 612
19.770.2 <text:h> 612
19.770.3 <text:p> 613
19.770.4 <text:span> 613
19.771 text:column-name 613
19.772 text:combine-entries 613
19.773 text:combine-entries-with-dash 613
19.774 text:combine-entries-with-pp 614
19.775 text:comma-separated 614
19.776 text:cond-style-name 614
19.777 text:condition 615
19.777.1 General 615
19.777.2 <text:conditional-text> 615
19.777.3 <text:database-next> 615

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.777.4 <text:database-row-select>..... 615
19.777.5 <text:hidden-paragraph>..... 616
19.777.6 <text:hidden-text>..... 616
19.777.7 <text:section>..... 616
19.778 text:connection-name..... 616
19.779 text:consecutive-numbering..... 616
19.780 text:continue-list..... 617
19.781 text:continue-numbering..... 617
19.782 text:copy-outline-levels..... 617
19.783 text:count-empty-lines..... 617
19.784 text:count-in-text-boxes..... 618
19.785 text:current-value..... 618
19.786 text:custom1..... 618
19.787 text:custom2..... 618
19.788 text:custom3..... 619
19.789 text:custom4..... 619
19.790 text:custom5..... 619
19.791 text:database-name..... 619
19.792 text:date-adjust..... 619
19.793 text:date-value..... 620
19.794 text:default-style-name..... 620
19.795 text:description..... 620
19.796 text:display..... 620
19.796.1 General..... 620
19.796.2 <text:chapter>..... 620
19.796.3 <text:expression>..... 621
19.796.4 <text:file-name>..... 621
19.796.5 <text:index-entry-chapter>..... 621
19.796.6 <text:section>..... 622
19.796.7 <text:table-formula>..... 622
19.796.8 <text:template-name>..... 623
19.796.9 <text:user-field-get>..... 623
19.796.10 <text:variable-get>..... 623
19.796.11 <text:variable-input>..... 624
19.796.12 <text:variable-set>..... 624
19.797 text:display-levels..... 624
19.798 text:display-outline-level..... 624

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.799 text:duration ... 625
19.800 text:edition ... 625
19.801 text:editor ... 625
19.802 text:filter-name ... 625
19.803 text:fixed ... 625
19.804 text:footnotes-position ... 626
19.805 text:formula ... 626
19.806 text:global (deprecated) ... 626
19.807 text:howpublished ... 627
19.808 text:increment ... 627
19.809 text:id ... 627
19.809.1 General ... 627
19.809.2 <draw:text-box> ... 627
19.809.3 <text:alphabetical-index-mark-end> ... 628
19.809.4 <text:alphabetical-index-mark-start> ... 628
19.809.5 <text:changed-region> ... 628
19.809.6 <text:h> ... 628
19.809.7 <text:note> ... 629
19.809.8 <text:p> ... 629
19.809.9 <text:toc-mark-end> ... 629
19.809.10 <text:toc-mark-start> ... 630
19.809.11 <text:user-index-mark-end> ... 630
19.809.12 <text:user-index-mark-start> ... 630
19.810 text:identifier ... 630
19.811 text:index-name ... 630
19.812 text:index-scope ... 631
19.813 text:ignore-case ... 631
19.814 text:institution ... 631
19.815 text:is-hidden ... 632
19.816 text:is-list-header ... 632
19.817 text:isbn ... 632
19.818 text:issn ... 632
19.819 text:journal ... 632
19.820 text:key ... 633
19.821 text:key1 ... 634
19.822 text:key2 ... 634
19.823 text:key1-phonetic ... 634

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.824 text:key2-phonetic 635
19.825 text:kind 635
19.826 text:label 635
19.827 text:label-followed-by 635
19.828 text:level 636
19.829 text:list-id 636
19.830 text:list-tab-stop-position 636
19.831 text:main-entry 637
19.832 text:main-entry-style-name 637
19.833 text:master-page-name 637
19.834 text:month 638
19.835 text:name 638
19.835.1 General 638
19.835.2 <text:alphabetical-index> 638
19.835.3 <text:bibliography> 638
19.835.4 <text:bookmark> 638
19.835.5 <text:bookmark-end> 638
19.835.6 <text:bookmark-start> 639
19.835.7 <text:execute-macro> 639
19.835.8 <text:illustration-index> 639
19.835.9 <text:index-title> 639
19.835.10 <text:object-index> 639
19.835.11 <text:reference-mark> 639
19.835.12 <text:reference-mark-end> 640
19.835.13 <text:reference-mark-start> 640
19.835.14 <text:section> 640
19.835.15 <text:sequence> 640
19.835.16 <text:sequence-decl> 640
19.835.17 <text:table-of-content> 640
19.835.18 <text:table-index> 641
19.835.19 <text:user-defined> 641
19.835.20 <text:user-field-decl> 641
19.835.21 <text:user-field-get> 641
19.835.22 <text:user-field-input> 641
19.835.23 <text:user-index> 641
19.835.24 <text:variable-set> 642
19.835.25 <text:variable-decl> 642

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.835.26 <text:variable-get>..... 642
19.835.27 <text:variable-input>..... 642
19.836 text:note..... 642
19.837 text:note-class..... 642
19.838 text:number..... 643
19.839 text:number-lines..... 643
19.840 text:number-position..... 643
19.841 text:numbered-entries..... 644
19.842 text:offset..... 644
19.843 text:organizations..... 644
19.844 text:outline-level..... 644
19.844.1 General..... 644
19.844.2 <text:alphabetical-index-entry-template>..... 644
19.844.3 <text:chapter>..... 645
19.844.4 <text:h>..... 645
19.844.5 <text:index-entry-chapter>..... 645
19.844.6 <text:index-source-styles>..... 645
19.844.7 <text:user-index-mark>..... 645
19.844.8 <text:table-of-content-entry-template>..... 646
19.844.9 <text:table-of-content-source>..... 646
19.844.10 <text:toc-mark>..... 646
19.844.11 <text:toc-mark-start>..... 646
19.844.12 <text:user-index-entry-template>..... 646
19.844.13 <text:user-index-mark-start>..... 647
19.845 text:page-adjust..... 647
19.845.1 General..... 647
19.845.2 <text:page-number>..... 647
19.845.3 <text:page-variable-set>..... 647
19.846 text:pages..... 647
19.847 text:placeholder-type..... 647
19.848 text:prefix..... 648
19.849 text:protected..... 648
19.850 text:protection-key..... 648
19.851 text:protection-key-digest-algorithm..... 649
19.852 text:publisher..... 649
19.853 text:ref-name..... 649
19.853.1 General..... 649

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.853.2 <text:bookmark-ref> 649
19.853.3 <text:note-ref> 650
19.853.4 <text:reference-ref> 650
19.853.5 <text:sequence> 650
19.853.6 <text:sequence-ref> 650
19.854 text:reference-format 650
19.855 text:relative-tab-stop-position 652
19.856 text:report-type 652
19.857 text:restart-numbering 652
19.858 text:restart-on-page 653
19.859 text:row-number 653
19.860 text:school 653
19.861 text:section-name 653
19.862 text:series 654
19.863 text:select-page 654
19.863.1 General 654
19.863.2 <text:page-continuation> 654
19.863.3 <text:page-number> 654
19.864 text:separation-character 655
19.865 text:sort-algorithm 655
19.866 text:sort-ascending 655
19.867 text:sort-by-position 655
19.868 text:start-value 656
19.868.1 General 656
19.868.2 <text:h> 656
19.868.3 <text:list-item> 656
19.868.4 <text:list-level-style-number> 656
19.868.5 <text:notes-configuration> 656
19.868.6 <text:numbered-paragraph> 657
19.868.7 <text:outline-level-style> 657
19.869 text:start-numbering-at 657
19.870 text:string-value-phonetic 657
19.871 text:string-value 657
19.871.1 General 657
19.871.2 <text:alphabetical-index-mark> 658
19.871.3 <text:hidden-text> 658
19.871.4 <text:page-continuation> 658

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.871.5 <text:toc-mark>.....658
19.871.6 <text:user-index-mark>.....658
19.872 text:string-value-if-false.....658
19.873 text:string-value-if-true.....659
19.874 text:style-name.....659
19.874.1 General.....659
19.874.2 <text:a>.....659
19.874.3 <text:alphabetical-index>.....659
19.874.4 <text:alphabetical-index-entry-template>.....659
19.874.5 <text:bibliography>.....659
19.874.6 <text:bibliography-entry-template>.....660
19.874.7 <text:h>.....660
19.874.8 <text:illustration-index>.....660
19.874.9 <text:illustration-index-entry-template>.....660
19.874.10 <text:index-entry-bibliography>.....660
19.874.11 <text:index-entry-chapter>.....661
19.874.12 <text:index-entry-link-end>.....661
19.874.13 <text:index-entry-link-start>.....661
19.874.14 <text:index-entry-page-number>.....661
19.874.15 <text:index-entry-span>.....661
19.874.16 <text:index-entry-tab-stop>.....661
19.874.17 <text:index-entry-text>.....662
19.874.18 <text:index-source-style>.....662
19.874.19 <text:index-title>.....662
19.874.20 <text:index-title-template>.....662
19.874.21 <text:linenumbering-configuration>.....662
19.874.22 <text:list>.....662
19.874.23 <text:list-level-style-number>.....663
19.874.24 <text:list-level-style-bullet>.....663
19.874.25 <text:numbered-paragraph>.....663
19.874.26 <text:object-index>.....663
19.874.27 <text:object-index-entry-template>.....664
19.874.28 <text:outline-level-style>.....664
19.874.29 <text:p>.....664
19.874.30 <text:ruby>.....664
19.874.31 <text:ruby-text>.....664
19.874.32 <text:section>.....665

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.874.33 <text:span>..... 665
19.874.34 <text:table-index-entry-template>..... 665
19.874.35 <text:table-of-content>..... 665
19.874.36 <text:table-of-content-entry-template>..... 665
19.874.37 <text:table-index>..... 665
19.874.38 <text:user-index>..... 666
19.874.39 <text:user-index-entry-template>..... 666
19.875 text:style-override..... 666
19.876 text:suffix..... 666
19.877 text:tab-ref..... 666
19.878 text:table-name..... 667
19.879 text:table-type..... 667
19.880 text:time-adjust..... 667
19.881 text:time-value..... 667
19.882 text:title..... 667
19.883 text:track-changes..... 668
19.884 text:url..... 668
19.885 text:use-caption..... 668
19.886 text:use-chart-objects..... 668
19.887 text:use-draw-objects..... 669
19.888 text:use-floating-frames..... 669
19.889 text:use-graphics..... 669
19.890 text:use-index-marks..... 670
19.891 text:use-index-source-styles..... 670
19.892 text:use-keys-as-entries..... 670
19.893 text:use-math-objects..... 671
19.894 text:use-objects..... 671
19.895 text:use-other-objects..... 671
19.896 text:use-outline-level..... 672
19.897 text:use-soft-page-breaks..... 672
19.898 text:use-spreadsheet-objects..... 673
19.899 text:use-tables..... 673
19.900 text:value..... 674
19.901 text:visited-style-name..... 674
19.902 text:volume..... 674
19.903 text:year..... 674
19.904 xforms:bind..... 674

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.905 xhtml:about 675
19.906 xhtml:content 675
19.907 xhtml:datatype 675
19.908 xhtml:property 676
19.909 xlink:actuate 676
19.910 xlink:href 677
19.910.1 General 677
19.910.2 <anim:audio> 677
19.910.3 <chart:chart> 677
19.910.4 <chart:symbol-image> 677
19.910.5 <db:component> 677
19.910.6 <db:connection-resource> 678
19.910.7 <db:file-based-database> 678
19.910.8 <draw:a> 678
19.910.9 <draw:applet> 678
19.910.10 <draw:area-circle> 678
19.910.11 <draw:area-polygon> 678
19.910.12 <draw:area-rectangle> 679
19.910.13 <draw:fill-image> 679
19.910.14 <draw:floating-frame> 679
19.910.15 <draw:image> 679
19.910.16 <draw:object> 679
19.910.17 <draw:object-ole> 679
19.910.18 <draw:plugin> 680
19.910.19 <form:button> 680
19.910.20 <form:connection-resource> 680
19.910.21 <form:image> 680
19.910.22 <form:form> 680
19.910.23 <meta:auto-reload> 680
19.910.24 <meta:template> 680
19.910.25 <presentation:event-listener> 681
19.910.26 <presentation:sound> 681
19.910.27 <script:event-listener> 681
19.910.28 <style:background-image> 681
19.910.29 <svg:definition-src> 681
19.910.30 <svg:font-face-uri> 681
19.910.31 <table:cell-range-source> 682

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.910.32 <table:table-source>..... 682
19.910.33 <text:a>..... 682
19.910.34 <text:alphabetical-index-auto-mark-file>..... 682
19.910.35 <text:list-level-style-image>..... 682
19.910.36 <text:script>..... 682
19.910.37 <text:section-source>..... 683
19.911 xlink:show..... 683
19.912 xlink:title..... 683
19.913 xlink:type..... 684
19.914 xml:id..... 684
20 Formatting Attributes..... 686
20.1 General..... 686
20.2 chart:angle-offset..... 686
20.3 chart:auto-position..... 686
20.4 chart:auto-size..... 686
20.5 chart:axis-label-position..... 687
20.6 chart:axis-position..... 687
20.7 chart:connect-bars..... 688
20.8 chart:data-label-number..... 688
20.9 chart:data-label-symbol..... 689
20.10 chart:data-label-text..... 689
20.11 chart:deep..... 689
20.12 chart:display-label..... 690
20.13 chart:error-category..... 690
20.14 chart:error-lower-indicator..... 691
20.15 chart:error-lower-limit..... 691
20.16 chart:error-lower-range..... 691
20.17 chart:error-margin..... 691
20.18 chart:error-percentage..... 692
20.19 chart:error-upper-indicator..... 692
20.20 chart:error-upper-limit..... 692
20.21 chart:error-upper-range..... 692
20.22 chart:gap-width..... 693
20.23 chart:group-bars-per-axis..... 693
20.24 chart:hole-size..... 693
20.25 chart:include-hidden-cells..... 694
20.26 chart:interpolation..... 694

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.27 chart:interval-major ... 696
20.28 chart:interval-minor-divisor ... 696
20.29 chart:japanese-candle-stick ... 697
20.30 chart:label-arrangement ... 697
20.31 chart:label-position ... 697
20.32 chart:label-position-negative ... 698
20.33 chart:lines (deprecated) ... 699
20.34 chart:link-data-style-to-source ... 699
20.35 chart:logarithmic ... 700
20.36 chart:maximum ... 700
20.37 chart:mean-value ... 700
20.38 chart:minimum ... 701
20.39 chart:origin ... 701
20.40 chart:overlap ... 701
20.41 chart:pie-offset ... 702
20.42 chart:percentage ... 702
20.43 chart:regression-type ... 702
20.44 chart:reverse-direction ... 703
20.45 chart:right-angled-axes ... 703
20.46 chart:scale-text ... 704
20.47 chart:series-source (deprecated) ... 704
20.48 chart:sort-by-x-values ... 704
20.49 chart:solid-type ... 705
20.50 chart:spline-order ... 705
20.51 chart:spline-resolution ... 705
20.52 chart:stacked ... 706
20.53 chart:symbol-height ... 706
20.54 chart:symbol-name ... 706
20.55 chart:symbol-type ... 706
20.56 chart:symbol-width ... 707
20.57 chart:text-overlap ... 707
20.58 chart:three-dimensional ... 707
20.59 chart:tick-marks-major-inner ... 708
20.60 chart:tick-marks-major-outer ... 708
20.61 chart:tick-marks-minor-inner ... 709
20.62 chart:tick-marks-minor-outer ... 709
20.63 chart:tick-mark-position ... 709

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.64 chart:treat-empty-cells ... 710
20.65 chart:vertical ... 710
20.66 chart:visible ... 711
20.67 dr3d:ambient-color ... 711
20.68 dr3d:back-scale ... 711
20.69 dr3d:backface-culling ... 711
20.70 dr3d:close-back ... 712
20.71 dr3d:close-front ... 712
20.72 dr3d:depth ... 712
20.73 dr3d:diffuse-color ... 712
20.74 dr3d:edge-rounding ... 712
20.75 dr3d:edge-rounding-mode ... 713
20.76 dr3d:emissive-color ... 713
20.77 dr3d:end-angle ... 713
20.78 dr3d:horizontal-segments ... 714
20.79 dr3d:lighting-mode ... 714
20.80 dr3d:normals-direction ... 714
20.81 dr3d:normals-kind ... 714
20.82 dr3d:shadow ... 715
20.83 dr3d:shininess ... 715
20.84 dr3d:specular-color ... 715
20.85 dr3d:texture-filter ... 715
20.86 dr3d:texture-kind ... 716
20.87 dr3d:texture-mode ... 716
20.88 dr3d:texture-generation-mode-x ... 716
20.89 dr3d:texture-generation-mode-y ... 717
20.90 dr3d:vertical-segments ... 717
20.91 draw:auto-grow-height ... 717
20.92 draw:auto-grow-width ... 718
20.93 draw:background-size ... 718
20.94 draw:blue ... 718
20.95 draw:caption-angle ... 719
20.96 draw:caption-angle-type ... 719
20.97 draw:caption-escape ... 719
20.98 draw:caption-escape-direction ... 719
20.99 draw:caption-fit-line-length ... 720
20.100 draw:caption-gap ... 720

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.101 draw:caption-line-length..... 720
20.102 draw:caption-type..... 720
20.103 draw:color-inversion..... 721
20.104 draw:color-mode..... 721
20.105 draw:contrast..... 721
20.106 draw:decimal-places..... 722
20.107 draw:draw-aspect..... 722
20.108 draw:end-guide..... 722
20.109 draw:end-line-spacing-horizontal..... 722
20.110 draw:end-line-spacing-vertical..... 723
20.111 draw:fill..... 723
20.112 draw:fill-color..... 723
20.113 draw:fill-gradient-name..... 723
20.114 draw:fill-hatch-name..... 724
20.115 draw:fill-hatch-solid..... 724
20.116 draw:fill-image-height..... 724
20.117 draw:fill-image-name..... 724
20.118 draw:fill-image-ref-point..... 725
20.119 draw:fill-image-ref-point-x..... 725
20.120 draw:fill-image-ref-point-y..... 725
20.121 draw:fill-image-width..... 726
20.122 draw:fit-to-contour..... 726
20.123 draw:fit-to-size..... 726
20.124 draw:frame-display-border..... 727
20.125 draw:frame-margin-horizontal..... 727
20.126 draw:frame-display-scrollbar..... 727
20.127 draw:frame-margin-vertical..... 727
20.128 draw:gamma..... 728
20.129 draw:green..... 728
20.130 draw:gradient-step-count..... 728
20.131 draw:guide-distance..... 728
20.132 draw:guide-overhang..... 729
20.133 draw:image-opacity..... 729
20.134 draw:line-distance..... 729
20.135 draw:luminance..... 729
20.136 draw:marker-end..... 729
20.137 draw:marker-end-center..... 729

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.138 draw:marker-end-width ... 730
20.139 draw:marker-start ... 730
20.140 draw:marker-start-center ... 730
20.141 draw:marker-start-width ... 730
20.142 draw:measure-align ... 731
20.143 draw:measure-vertical-align ... 731
20.144 draw:ole-draw-aspect ... 731
20.145 draw:opacity ... 732
20.146 draw:opacity-name ... 732
20.147 draw:parallel ... 732
20.148 draw:placing ... 732
20.149 draw:red ... 733
20.150 draw:secondary-fill-color ... 733
20.151 draw:shadow ... 733
20.152 draw:shadow-color ... 733
20.153 draw:shadow-offset-x ... 734
20.154 draw:shadow-offset-y ... 734
20.155 draw:shadow-opacity ... 734
20.156 draw:show-unit ... 734
20.157 draw:start-guide ... 734
20.158 draw:start-line-spacing-horizontal ... 735
20.159 draw:start-line-spacing-vertical ... 735
20.160 draw:stroke ... 735
20.161 draw:stroke-dash ... 735
20.162 draw:stroke-dash-names ... 736
20.163 draw:stroke-linejoin ... 736
20.164 svg:stroke-linecap ... 736
20.165 draw:symbol-color ... 737
20.166 draw:textarea-horizontal-align ... 737
20.167 draw:textarea-vertical-align ... 737
20.168 draw:tile-repeat-offset ... 737
20.169 draw:visible-area-height ... 738
20.170 draw:visible-area-left ... 738
20.171 draw:visible-area-top ... 738
20.172 draw:visible-area-width ... 739
20.173 draw:unit ... 739
20.174 draw:wrap-influence-on-position ... 740

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.175 fo:background-color 741
20.176 fo Border Properties 742
20.176.1 General 742
20.176.2 fo:border 742
20.176.3 fo:border-bottom 742
20.176.4 fo:border-left 742
20.176.5 fo:border-right 742
20.176.6 fo:border-top 743
20.177 fo:break-after 743
20.178 fo:break-before 743
20.179 fo:clip 743
20.180 fo:color 744
20.181 fo:country 744
20.182 fo:font-family 744
20.183 fo:font-size 744
20.184 fo:font-style 745
20.185 fo:font-variant 745
20.186 fo:font-weight 745
20.187 fo:height 746
20.188 fo:hyphenate 746
20.189 fo:hyphenation-keep 746
20.190 fo:hyphenation-ladder-count 746
20.191 fo:hyphenation-push-char-count 747
20.192 fo:hyphenation-remain-char-count 747
20.193 fo:keep-together 747
20.194 fo:keep-with-next 747
20.195 fo:language 747
20.196 fo:letter-spacing 748
20.197 fo:line-height 748
20.198 fo:margin 748
20.199 fo:margin-bottom 749
20.200 fo:margin-left 749
20.201 fo:margin-right 749
20.202 fo:margin-top 750
20.203 fo:max-height 750
20.204 fo:max-width 750
20.205 fo:min-height 750

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.205.1 <style:graphic-properties>..... 750
20.205.2 <style:header-footer-properties>..... 751
20.206 fo:min-width..... 751
20.207 fo:orphans..... 751
20.208 fo:page-height..... 751
20.209 fo:page-width..... 751
20.210 fo:padding..... 751
20.211 fo:padding-bottom..... 752
20.212 fo:padding-left..... 752
20.213 fo:padding-right..... 752
20.214 fo:padding-top..... 752
20.215 fo:script..... 753
20.216 fo:text-align..... 753
20.216.1 <style:paragraph-properties>..... 753
20.216.2 <style:list-level-properties>..... 753
20.217 fo:text-align-last..... 754
20.218 fo:text-indent..... 754
20.219 fo:text-shadow..... 754
20.220 fo:text-transform..... 755
20.221 fo:widows..... 755
20.222 fo:width..... 755
20.223 fo:wrap-option..... 755
20.224 presentation:background-objects-visible..... 756
20.225 presentation:background-visible..... 756
20.226 presentation:display-date-time..... 756
20.227 presentation:display-footer..... 757
20.228 presentation:display-header..... 757
20.229 presentation:display-page-number..... 757
20.230 presentation:duration..... 758
20.231 presentation:transition-speed..... 758
20.232 presentation:transition-style..... 758
20.233 presentation:transition-type..... 761
20.234 presentation:visibility..... 762
20.235 smil:direction..... 762
20.236 smil:fadeColor..... 762
20.237 smil:subtype..... 762
20.238 smil:type..... 763

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.239 style:auto-text-indent ... 763
20.240 style:background-transparency ... 763
20.241 style:border-line-width ... 763
20.242 style:border-line-width-bottom ... 764
20.243 style:border-line-width-left ... 764
20.244 style:border-line-width-right ... 765
20.245 style:border-line-width-top ... 765
20.246 style:cell-protect ... 765
20.247 style:column-width ... 766
20.248 style:country-asian ... 766
20.249 style:country-complex ... 766
20.250 style:decimal-places ... 766
20.251 style:diagonal-bl-tr ... 767
20.252 style:diagonal-bl-tr-widths ... 767
20.253 style:diagonal-tl-br ... 767
20.254 style:diagonal-tl-br-widths ... 767
20.255 style:direction ... 767
20.256 style:dynamic-spacing ... 768
20.257 style:editable ... 768
20.258 style:first-page-number ... 768
20.259 style:flow-with-text ... 769
20.260 style:font-charset ... 770
20.261 style:font-charset-asian ... 770
20.262 style:font-charset-complex ... 771
20.263 style:font-family-asian ... 771
20.264 style:font-family-complex ... 771
20.265 style:font-family-generic ... 772
20.266 style:font-family-generic-asian ... 772
20.267 style:font-family-generic-complex ... 773
20.268 style:font-independent-line-spacing ... 773
20.269 style:font-name ... 774
20.270 style:font-name-asian ... 774
20.271 style:font-name-complex ... 774
20.272 style:font-pitch ... 774
20.273 style:font-pitch-asian ... 775
20.274 style:font-pitch-complex ... 775
20.275 style:font-relief ... 775

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.276 style:font-size-asian..... 776
20.277 style:font-size-complex..... 776
20.278 style:font-size-rel..... 776
20.279 style:font-size-rel-asian..... 777
20.280 style:font-size-rel-complex..... 777
20.281 style:font-style-asian..... 777
20.282 style:font-style-complex..... 778
20.283 style:font-style-name..... 778
20.284 style:font-style-name-asian..... 778
20.285 style:font-style-name-complex..... 779
20.286 style:font-weight-asian..... 779
20.287 style:font-weight-complex..... 779
20.288 style:footnote-max-height..... 779
20.289 style:glyph-orientation-vertical..... 780
20.290 style:horizontal-pos..... 780
20.291 style:horizontal-rel..... 782
20.292 style:join-border..... 782
20.293 style:justify-single-word..... 783
20.294 style:language-asian..... 784
20.295 style:language-complex..... 784
20.296 style:layout-grid-base-height..... 784
20.297 style:layout-grid-base-width..... 784
20.298 style:layout-grid-color..... 785
20.299 style:layout-grid-display..... 785
20.300 style:layout-grid-lines..... 785
20.301 style:layout-grid-mode..... 785
20.302 style:layout-grid-print..... 786
20.303 style:layout-grid-ruby-below..... 786
20.304 style:layout-grid-ruby-height..... 786
20.305 style:layout-grid-snap-to..... 786
20.306 style:layout-grid-standard-mode..... 787
20.307 style:line-break..... 787
20.308 style:letter-kerning..... 787
20.309 style:line-height-at-least..... 788
20.310 style:line-spacing..... 788
20.311 style:may-break-between-rows..... 788
20.312 style:min-row-height..... 788

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.313 style:mirror ... 789
20.314 style:num-format ... 789
20.315 style:num-letter-sync ... 790
20.316 style:num-prefix ... 790
20.317 style:num-suffix ... 790
20.318 style:number-wrapped-paragraphs ... 791
20.319 style:overflow-behavior ... 791
20.320 style:page-number ... 791
20.321 style:paper-tray-name ... 792
20.322 style:print ... 792
20.323 style:print-content ... 793
20.323.1 General ... 793
20.323.2 <style:graphic-properties> ... 793
20.323.3 <style:table-cell-properties> ... 793
20.324 style:print-page-order ... 793
20.325 style:print-orientation ... 793
20.326 style:protect ... 794
20.326.1 General ... 794
20.326.2 <style:graphic-properties> ... 794
20.326.3 <style:section-properties> ... 794
20.327 style:punctuation-wrap ... 795
20.328 style:register-true ... 795
20.329 style:register-truth-ref-style-name ... 795
20.330 style:rel-column-width ... 795
20.331 style:rel-height ... 796
20.332 style:rel-width ... 796
20.332.1 <style:graphic-properties> ... 796
20.332.2 <style:table-properties> ... 797
20.333 style:repeat ... 797
20.334 style:repeat-content ... 797
20.335 style:rfc-language-tag ... 797
20.336 style:rfc-language-tag-asian ... 798
20.337 style:rfc-language-tag-complex ... 798
20.338 style:rotation-align ... 799
20.339 style:rotation-angle ... 799
20.340 style:row-height ... 799
20.341 style:ruby-align ... 800

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.342 style:ruby-position ... 800
20.343 style:run-through ... 800
20.344 style:scale-to ... 801
20.345 style:scale-to-pages ... 801
20.346 style:script-asian ... 801
20.347 style:script-complex ... 801
20.348 style:script-type ... 802
20.349 style:shadow ... 803
20.350 style:shrink-to-fit ... 803
20.351 style:snap-to-layout-grid ... 803
20.352 style:tab-stop-distance ... 804
20.353 style:table-centering ... 804
20.354 style:text-align-source ... 804
20.355 style:text-autospace ... 805
20.356 style:text-blinking ... 805
20.357 style:text-combine ... 805
20.358 style:text-combine-start-char ... 806
20.359 style:text-combine-end-char ... 806
20.360 style:text-emphasize ... 806
20.361 style:text-line-through-color ... 806
20.362 style:text-line-through-mode ... 807
20.363 style:text-line-through-style ... 807
20.364 style:text-line-through-text ... 808
20.365 style:text-line-through-text-style ... 808
20.366 style:text-line-through-type ... 808
20.367 style:text-line-through-width ... 809
20.368 style:text-outline ... 809
20.369 style:text-overline-color ... 809
20.370 style:text-overline-mode ... 810
20.371 style:text-overline-style ... 810
20.372 style:text-overline-type ... 811
20.373 style:text-overline-width ... 811
20.374 style:text-position ... 812
20.375 style:text-rotation-angle ... 812
20.376 style:text-rotation-scale ... 812
20.377 style:text-scale ... 812
20.378 style:text-underline-color ... 813

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.379 style:text-underline-mode....813
20.380 style:text-underline-style....813
20.381 style:text-underline-type....814
20.382 style:text-underline-width....814
20.383 style:use-optimal-column-width....815
20.384 style:use-optimal-row-height....815
20.385 style:use-window-font-color....815
20.386 style:vertical-align....816
20.386.1 <style:paragraph-properties>....816
20.386.2 <style:table-cell-properties>....816
20.387 style:vertical-pos....816
20.388 style:vertical-rel....817
20.389 style:width....818
20.390 style:wrap....818
20.391 style:wrap-contour....819
20.392 style:wrap-contour-mode....819
20.393 style:wrap-dynamic-threshold....819
20.394 style:writing-mode....820
20.394.1 General....820
20.394.2 <style:graphic-properties>....820
20.394.3 <style:page-layout-properties>....820
20.394.4 <style:paragraph-properties>....820
20.394.5 <style:section-properties>....820
20.394.6 <style:table-cell-properties>....821
20.394.7 <style:table-properties>....821
20.395 style:writing-mode-automatic....821
20.396 svg:fill-rule....821
20.397 svg:height....822
20.397.1 <style:graphic-properties>....822
20.397.2 <style:header-footer-properties>....822
20.398 svg:stroke-color....822
20.399 svg:stroke-opacity....822
20.400 svg:stroke-width....822
20.401 svg:x....823
20.402 svg:y....823
20.402.1 <style:graphic-properties>....823
20.402.2 <style:list-level-properties>....823

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.403 svg:width ... 823
20.404 table:align ... 823
20.405 table:border-model ... 824
20.406 table:display ... 824
20.407 text:anchor-page-number ... 824
20.408 text:anchor-type ... 825
20.409 text:animation ... 826
20.410 text:animation-delay ... 826
20.411 text:animation-direction ... 826
20.412 text:animation-repeat ... 827
20.413 text:animation-start-inside ... 827
20.414 text:animation-steps ... 827
20.415 text:animation-stop-inside ... 827
20.416 text:condition ... 828
20.417 text:display ... 828
20.418 text:dont-balance-text-columns ... 828
20.419 text:line-break ... 828
20.420 text:line-number ... 829
20.421 text:list-level-position-and-space-mode ... 829
20.422 text:min-label-distance ... 829
20.423 text:min-label-width ... 830
20.424 text:number-lines ... 830
20.425 text:space-before ... 830
Appendix A. OpenDocument Relax NG Schema ... 832
Appendix B. OpenDocument Metadata Manifest Ontology ... 833
Appendix C. MIME Types and File Name Extensions (Non Normative) ... 834
Appendix D. Accessibility Guidelines (Non Normative) ... 836
D.1. Title, Description and Caption of Graphical Elements ... 836
D.1.1. Guidance for authors ... 836
D.1.2. Authoring tool responsibility for presenting and prompting for the <svg:title> and <svg:desc> elements ... 836
D.2. Hyperlink Titles ... 837
D.3. Tables in Presentations ... 837
D.4. Further Guidelines ... 837
Appendix E. Bidirectional (BiDi) Scripts,Numeric Digits Presentation and Calendars (Non Normative) ... 838
E.1. Paragraph and Layout Direction ... 838
E.2. Numeric Digits Presentation and Calendars ... 839

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Appendix F. Recommended Usage of SMIL 840
F.1. Slide Animation 840
F.2. Main Sequence 840
F.3. Interactive Sequence 841
Appendix G. Changes From Previous Specification Versions (Non Normative) 842
G.1. Changes from “Open Document Format for Office Applications (OpenDocument) v1.1” 842

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

1 Introduction

1.1 Introduction

This document is part of the Open Document Format for Office Applications (OpenDocument) Version 1.2 specification. It defines an XML schema for office documents. Office documents includes text documents, spreadsheets, charts and graphical documents like drawings or presentations, but is not restricted to these kinds of documents.

The XML schema for OpenDocument is designed for transformations using XSLT and processing with XML-based tools.

1.2 Terminology

All text is normative unless otherwise labeled.

Text with a gray background color which is contained in boxes is informative. It lists the XML element-element and element-attribute relations for cross reference purposes.

Within the normative text of this specification, the terms "shall", "shall not", "should", "should not", "may" and “need not” are to be interpreted as described in Annex H of [ISO/IEC Directives].

Within this specification, attributes and elements are marked as deprecated. Attributes and elements marked as deprecated should not be used any longer, and may be removed from future versions of the specification.

XML Element, attribute names, attribute value types, and attribute values appear in `monospace` font.

This standard, for illustrative purposes, describes functionality using terminology common in desktop computing environments that contain a display terminal, keyboard and mouse, attached to a computer hosting an operating system with a graphical user interface which includes user interface controls such as input controls, command buttons, selection boxes, etc.

This standard is not limited to such environments. This format can be used by alternative computing environments, with other form factors, non-GUI consumers and producers, assistive technologies, using analogous user interface operations.

Implementation-defined is used in this standard for values or processing that may differ between ODF implementations, but is required to be specified by the implementor for each particular ODF-implementation.

Implementation-dependent is used in this standard for values or processing that may differ between ODF implementations, but is not required to be specified by the implementor for each particular ODF-implementation.

1.3 Normative References

[**CSS2**] Bert Bos, Håkon Wium Lie, Chris Lilley, Ian Jacobs, *Cascading Style Sheets, level 2*, http://www.w3.org/TR/1998/REC-CSS2-19980512, W3C, 1998.

[**DCMI**] *Dublin Core Metadata Element Set, Version 1.1: Reference Description*, http://www.dublincore.org/documents/2008/01/14/dces/, Dublin Core Metadata Initiative, 2003.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

[**DOMEvents2**] Tom Pixley, *Document Object Model (DOM) Level 2 Events Specification*, http://www.w3.org/TR/2000/REC-DOM-Level-2-Events-20001113, W3C, 2000.

[**GRDDL**] Don Conolly, *Gleaning Resource Descriptions from Dialects of Languages (GRDDL)*, http://www.w3.org/TR/2007/REC-grddl-20070911/, W3C, 2007.

[**HTML4**] Dave Raggett, Arnaud Le Hors, Ian Jacobs, *HTML 4.01 Specification*, http://www.w3.org/TR/1999/REC-html401-19991224, W3C, 1999.

[**ISO/IEC Directives**] ISO/IEC Directives, Part 2 (Fifth Edition) *Rules for the structure and drafting of International Standards*, International Organization for Standardization and International Electrotechnical Commission, 2004.

[**ISO15924**] ISO 15924:2004 *Information and documentation -- Codes for the representation of names of scripts*, International Organization for Standardization and International Electrotechnical Commission, 2004.

[**ISO3166-1**] ISO 3166-1:2006/Cor 1:2007 *Codes for the representation of names of countries and their subdivisions -- Part 1: Country codes*, International Organization for Standardization and International Electrotechnical Commission, 2007.

[**ISO3166-2**] ISO 3166-2:2007 *Codes for the representation of names of countries and their subdivisions -- Part 2: Country subdivision code*, International Organization for Standardization and International Electrotechnical Commission, 2007.

[**ISO3166-3**] ISO 3166-3:1999 *Codes for the representation of names of countries and their subdivisions -- Part 3: Code for formerly used names of countries*, International Organization for Standardization and International Electrotechnical Commission, 1999.

[**ISO639-1**] ISO 639-1:2002 *Codes for the representation of names of languages -- Part 1: Alpha-2 code*, International Organization for Standardization and International Electrotechnical Commission, 2002.

[**ISO639-2**] ISO 639-2:1998 *Codes for the representation of names of languages -- Part 2: Alpha-3 code*, International Organization for Standardization and International Electrotechnical Commission, 1998.

[**ISO639-3**] ISO 639-3:2007 *Codes for the representation of names of languages -- Part 3: Alpha-3 code for comprehensive coverage of languages*, International Organization for Standardization and International Electrotechnical Commission, 2007.

[**ISO8601**] ISO 8601:2004 *Data elements and interchange formats -- Information interchange -- Representation of dates and times*, International Organization for Standardization and International Electrotechnical Commission, 2004.

[**JIS X 0301**] JIS X 0301:2002 *Data elements and interchange formats -- Information interchange -- Representation of dates and times*, Japanese Standards Association, 2002.

[**MathML**] David Carlisle, Patrick Ion, Robert Miner, Nico Poppelier, *Mathematical Markup Language (MathML) Version 2.0 (Second Edition)*, http://www.w3.org/TR/2003/REC-MathML2-20031021/, W3C, 2003.

[**OLE**] Kraig Brockschmidt, Inside OLE, Microsoft Press, 1995, ISBN: 1-55615-843-2

[**OWL**] Deborah L. McGuinness, Frank van Harmelen, *OWL Web Ontology Language Overview*, http://www.w3.org/TR/2004/REC-owl-features-20040210/, W3C, 2004.

[**RDF-CONCEPTS**] Graham Klyne, Jeremy J. Carroll, Brian McBride, *Resource Description Framework (RDF): Concepts and Abstract Syntax*, http://www.w3.org/TR/2004/REC-rdf-concepts-20040210/, W3C, 2004.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

[**RDFa**] Ben Adida, Mark Birbeck, Shane McCarron, Steven Pemberton, *RDFa in XHTML: Syntax and Processing*, http://www.w3.org/TR/2008/REC-rdfa-syntax-20081014, W3C, 2008.

[**RFC2045**] N. Freed and N. Borenstein, *Multipurpose Internet Mail Extensions (MIME) Part One: Format of Internet Message Bodies*, http://www.ietf.org/rfc/rfc2045.txt, IETF, 1996.

[**RFC2616**] R. Fielding, et al., *Hypertext Transfer Protocol -- HTTP/1.1*, http://www.ietf.org/rfc/rfc2616.txt, IETF, 1999.

[**RFC3987**] M. Duerst, M. Suignard, *Internationalized Resource Identifiers (IRIs)*, http://www.ietf.org/rfc/rfc3987.txt, IETF, 2005.

[**RFC4288**] N. Freed, J. Klensin, *Media Type Specifications and Registration Procedures*, http://www.ietf.org/rfc/rfc4288.txt, IETF, 2005.

[**RFC4514**] K. Zeilenga, *Lightweight Directory Access Protocol (LDAP): String Representation of Distinguished Names*, http://tools.ietf.org/html/rfc4514, IETF, 2006.

[**RFC5646**] A. Phillips, M. Davis, *Tags for Identifying Languages*, http://www.ietf.org/rfc/rfc5646.txt, IETF, 2009.

[**RNG**] ISO/IEC 19757-2 *Document Schema Definition Language (DSDL) -- Part 2: Regular-grammar-based validation -- RELAX NG*, International Organization for Standardization and International Electrotechnical Commission, 2003.

[**SMIL20**] Jeff Ayars, etc al., *Synchronized Multimedia Integration Language (SMIL 2.0) - [Second Edition]*, http://www.w3.org/TR/2005/REC-SMIL2-20050107/, W3C, 2001.

[**SQL**] ISO/IEC 9075-1:2008 *Information Technology -- Database Language -- SQL -- Part 2: Foundation (SQL/Foundation)*, International Organization for Standardization and International Electrotechnical Commission, 2008.

[**SVG**] Jon Ferraiolo, 藤沢 淳 (FUJISAWA Jun), Dean Jackson, *Scalable Vector Graphics (SVG) 1.1*, http://www.w3.org/TR/2003/REC-SVG11-20030114/, W3C, 2003.

[**UNICODE**] The Unicode Consortium. The Unicode Standard, Version 5.2.0, defined by: *The Unicode Standard, Version 5.2* (Boston, MA, Addison-Wesley, 2009. ISBN 978-1-936213-00-9).

[**UTR18**] Mark Davis, Andy Heninger, *Unicode Regular Expressions*, Unicode Technical Report #18, http://www.unicode.org/reports/tr18/tr18-13.html, 2008.

[**XForms**] John M. Boyer, *XForms 1.0 (Third Edition)*, http://www.w3.org/TR/2007/REC-xforms-20071029/, W3C, 2007.

[**XLink**] Steve DeRose, Eve Maler, David Orchard, *XML Linking Language (XLink) Version 1.0*, http://www.w3.org/TR/2001/REC-xlink-20010627/, W3C, 2001.

[**XML-ID**] Jonathan Marsh, Daniel Veillard, Norman Walsh, *xml:id Version 1.0*, http://www.w3.org/TR/2005/REC-xml-id-20050909/, W3C, 2005.

[**xml-names**] Tim Bray rt al., *Namespaces in XML 1.0 (Second Edition)*, http://www.w3.org/TR/2006/REC-xml-names-20060816, W3C, 2006.

[**XML1.0**] Tim Bray, Jean Paoli, C. M. Sperberg-McQueen, Eve Maler, François Yergeau , *Extensible Markup Language (XML) 1.0 (Fourth Edition)*, http://www.w3.org/TR/2006/REC-xml-20060816/, W3C, 2006.

[**xmlenc-core**] Donald Eastlake, Joseph Reagle, *XML Encryption Syntax and Processing*, http://www.w3.org/TR/2002/REC-xmlenc-core-20021210/, W3C, 2002.

[**xmlschema-2**] Paul V. Biron, Ashok Malhotra, *XML Schema Part 2: Datatypes Second Edition*, http://www.w3.org/TR/2004/REC-xmlschema-2-20041028/, W3C, 2004.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

[**XPath**] James Clark, Steve DeRose, *XML Path Language (XPath) Version 1.0*, http://www.w3.org/TR/1999/REC-xpath-19991116, W3C, 1999.

[**XSL**] Sharon Adler, et al., *Extensible Stylesheet Language (XSL)*, http://www.w3.org/TR/2001/REC-xsl-20011015/, W3C, 2001.

1.4 Non Normative References

[BibTeXing] Oren Patashnik, *BIBT E Xing*, http://citeseerx.ist.psu.edu/viewdoc/summary?doi=10.1.1.49.6093, 1988

[**CSS3Text**] Michel Suignard, *CSS3 Text Module*, http://www.w3.org/TR/2003/CR-css3-text-20030514, W3C, 2003.

[**DAISY**] *ANSI/NISO Z39.86-2005 Specifications for the Digital Talking Book*, http://www.niso.org/standards/resources/Z39-86-2005.html, 2005.

[**MIMETYPES**] *MIME Media Types*, http://www.iana.org/assignments/media-types/, IANA.

[**ODF10**] OASIS Standard, *Open Document Format for Office Applications (OpenDocument) v1.0*, May 2005, http://docs.oasis-open.org/office/v1.0/OpenDocument-v1.0-os.pdf.

[**ODF11**] OASIS Standard, *Open Document Format for Office Applications (OpenDocument) v1.1*, February 2007, http://docs.oasis-open.org/office/v1.1/OS/OpenDocument-v1.1.pdf.

[**PNG**] David Duce, *Portable Network Graphics (PNG) Specification (Second Edition)*, http://www.w3.org/TR/2003/REC-PNG-20031110, W3C, 2003.

[**RFC3066**] H. Alvestrand, *Tags for the Identification of Languages*, http://www.ietf.org/rfc/rfc3066.txt, IETF, 2001.

[**UAX9**] Mark Davis, *The Bidirectional Algorithm*, Unicode Standard Annex #9, http://www.unicode.org/reports/tr9/tr9-15.html, 2005.

[**UTR20**] Martin Dürst and Asmus Freytag, *Unicode in XML and other Markup Languages*, Unicode Technical Report #20, http://www.unicode.org/reports/tr20/tr20-7.html, 2003.

[**Variability**] Dominique Hazaël-Massieux, Lynne Rosenthal, *Variability in Specifications*, http://www.w3.org/TR/2005/NOTE-spec-variability-20050831/, W3C, 2005.

[**XSLT**] James Clark, *XSL Transformations (XSLT) Version 1.0*, http://www.w3.org/TR/1999/REC-xslt-19991116, W3C, 1999.

1.5 Namespaces

The namespaces used or defined by OpenDocument are listed in tables 1-4.

Note: The defined XML namespaces conform to the *Namespaces in XML* specification [xml-names].

This specification uses the prefixes defined in tables 1 and 2 when referring to elements and attributes in this specification. However, implementors may use any prefix, provided that there is a namespace declaration that binds the prefix to the IRI of the corresponding namespace.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Table 1 - XML Namespaces defined by the OpenDocument schema

Prefix	***Description***	***Namespace***
anim	Elements and attributes that describe animation content.	urn:oasis:names:tc:opendocument:xmlns:animation:1.0
chart	Elements and attributes that describe chart content.	urn:oasis:names:tc:opendocument:xmlns:chart:1.0
config	Elements and attributes that describe application specific settings.	urn:oasis:names:tc:opendocument:xmlns:config:1.0
db	For elements and attributes that describe database specific objects.	urn:oasis:names:tc:opendocument:xmlns:database:1.0
dr3d	Elements and attributes that describe 3D graphic content.	urn:oasis:names:tc:opendocument:xmlns:dr3d:1.0
draw	Elements and attributes that describe graphic content.	urn:oasis:names:tc:opendocument:xmlns:drawing:1.0
form	Elements and attributes that describe forms and controls.	urn:oasis:names:tc:opendocument:xmlns:form:1.0
manifest	Elements and attribute contained in the package manifest.	urn:oasis:names:tc:opendocument:xmlns:manifest:1.0
meta	Elements and attributes that describe meta information.	urn:oasis:names:tc:opendocument:xmlns:meta:1.0
number	Elements and attributes that describe data style information.	urn:oasis:names:tc:opendocument:xmlns:datastyle:1.0
office	All common pieces of information that are not contained in another, more specific namespace.	urn:oasis:names:tc:opendocument:xmlns:office:1.0
presentation	Elements and attributes that describe presentation content.	urn:oasis:names:tc:opendocument:xmlns:presentation:1.0
script	Elements and attributes that represent scripts or events.	urn:oasis:names:tc:opendocument:xmlns:script:1.0
table	Elements and attributes that may occur within spreadsheets or within table definitions of a text document.	urn:oasis:names:tc:opendocument:xmlns:table:1.0
text	Elements and attributes that may occur within text documents and text parts of other document types.,	urn:oasis:names:tc:opendocument:xmlns:text:1.0
style	Elements and attributes that describe the style and inheritance model used by the OpenDocument format.	urn:oasis:names:tc:opendocument:xmlns:style:1.0

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Table 2 - XML Namespaces defined by the OpenDocument metadata manifest ontology

Prefix	Description	Namespace
odf	RDF node property and node elements for OpenDocument package entities	http://docs.oasis-open.org/ns/office/1.2/meta/odf#

Table 3 - XML Namespaces defined by the OpenDocument schema that include elements and attributes that are compatible to elements and attributes of other standards.

Prefix	Description	Namespace
fo	Attributes that are compatible to attributes defined in [XSL].	urn:oasis:names:tc:opendocument:xmlns:xsl-fo-compatible:1.0
svg	Elements and attributes that are compatible to elements or attributes defined in [SVG].	urn:oasis:names:tc:opendocument:xmlns:svg-compatible:1.0
smil	Attributes that are compatible to attributes defined in [SMIL20].	urn:oasis:names:tc:opendocument:xmlns:smil-compatible:1.0

Table 4 - XML Namespaces used by the OpenDocument schema

Prefix	Description	Namespace
dc	The Dublin Core Namespace (see [DCMI]).	http://purl.org/dc/elements/1.1/
math	MathML Namespace (see [MathML])	http://www.w3.org/1998/Math/MathML
xforms	The XForms namespace (see [XForms]).	http://www.w3.org/2002/xforms
xlink	The XLink namespace (see [XLink]).	http://www.w3.org/1999/xlink
xhtml	RDFa attributes (see [RDFa]).	http://www.w3.org/1999/xhtml
grddl	GRDDL attributes (see [GRDDL])	http://www.w3.org/2003/g/data-view#

Table 5 - XML Namespaces defined by the OpenDocument metadata manifest ontology

Prefix	Description	Namespace
pkg	OWL classes and properties contained in metadata manifest files.	http://docs.oasis-open.org/ns/office/1.2/meta/pkg#

Table 6 - Other XML Namespaces defined by this specification

Prefix	Description	Namespace
of	Namespace for formulas defined by part 2 of this specification that occur in attribute values.	urn:oasis:names:tc:opendocument:xmlns:of:1.2

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

2 OpenDocument Documents, Consumers and Producers

2.1 Introduction

The OpenDocument specification defines conformance for documents, consumers, and producers, with two conformance classes called conforming and extended conforming. It further defines conforming text, spreadsheet, drawing, presentation, chart, image, formula and database front end documents. This chapter defines the basic requirements for the individual conformance targets.

2.2 Documents

2.2.1 OpenDocument Document

An *OpenDocument document* shall meet the following requirements:

A) If the document is an OpenDocument package, then

A.1) it shall be a conforming OpenDocument package (C19), and

A.2) the package shall contain at least one of the following files: content.xml and styles.xml. It may contain additional files, including files named settings.xml and meta.xml.

B) If the document is an OpenDocument package, then the following requirements shall be met for its contained files named content.xml, styles.xml, settings.xml and meta.xml, if present:

B.1) The files shall be well formed XML documents with respect to the XML 1.0 [XML1.0] specification.

B.2) The XML root elements of the files shall be

B.2.1) `<office:document-content>` or `<math:math>` for files named content.xml,

B.2.2) `<office:document-styles>` for files named styles.xml,

B.2.3) `<office:document-meta>` for files named meta.xml,

B.2.4) `<office:document-settings>` for files named settings.xml.

B.3) If the XML root element of a file is `<office:document-content>`, `<office:document-styles>`, `<office:document-meta>` or `<office:document-settings>`, then the XML file shall be valid with respect to the schema defined in appendix A.

B.4) If the XML root element of a file is `<math:math>`, then the XML file shall be valid with respect to the MathML 2.0 [MathML] schema.

C) If the document is a single XML file, then

C.1) the file shall be a well formed XML document with respect to the XML 1.0 [XML1.0] specification

C.2) the XML root element of the file shall be `<office:document>`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

C.3) the XML file shall be valid with respect to the schema defined in appendix A.

D) The files contained in a package listed in B) or the single file listed in C) meet the following requirements:

D.1) They shall be namespace-well-formed with regard to the XML Namespaces specification [xml-names].

D.2) They shall conform to the xml-id specification [XML-ID].

D.3) If the namespace prefix of a `style:condition`, `table:condition`, `table:expression`, `table:formula` or `text:formula` attribute is associated with the "urn:oasis:names:tc:opendocument:xmlns:of:1.2" namespace, or if a namespace prefix is omitted for any of these attributes, the syntax of any formula which is contained in the values of these attributes shall conform to part 2 of this specification.

E) It shall conform to one of: (C3) OpenDocument Text Document, (C4) OpenDocument Spreadsheet Document, (C5) OpenDocument Drawing Document, (C6) OpenDocument Presentation Document, (C7) OpenDocument Chart Document, (C8) OpenDocument Image Document, (C9) OpenDocument Formula Document, (C10) OpenDocument Database Front End Document.

2.2.2 OpenDocument Extended Document

An *OpenDocument extended document* shall meet all requirements of a conforming document listed in 2.2.1 except A.1), B.3), C.3) and E) and shall meet the following requirements:

A) If the document is an OpenDocument package, then it shall be a conforming ODF extended package (C20)

B) If the document is an OpenDocument package, then the following requirement shall be met for its contained files named content.xml, styles.xml, settings.xml and meta.xml, if present:

B.1) If the XML root element of a file is `<office:document-content>`, `<office:document-styles>`, `<office:document-meta>` or `<office:document-settings>`, then the XML file shall be valid with respect to the schema defined in appendix A, after the following processing of foreign elements has taken place:

B.1.1) Foreign elements and attributes, as defined in section 3.17 have been removed.

B.1.2) The content of foreign elements has been processed as defined in section 3.17.

C) If the document is a single XML file, then the XML files shall be valid with respect to the schema defined in appendix A, after processing of foreign elements as defined in B1) has taken place.

2.2.3 OpenDocument Text Document

An *OpenDocument Text document* shall meet all requirements of a Conforming OpenDocument Document, as well as the following additional requirements:

A) The `<office:document>` element shall have an `office:mimetype` attribute with one of these values: "application/vnd.oasis.opendocument.text", "application/vnd.oasis.opendocument.text-template" or "application/vnd.oasis.opendocument.text-master".

B) If the document is an OpenDocument package then it shall contain a file named mimetype containing one of these strings: "application/vnd.oasis.opendocument.text",

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

"application/vnd.oasis.opendocument.text-template" or "application/vnd.oasis.opendocument.text-master".

C) The `<office:body>` element shall have the child element `<office:text>`.

2.2.4 OpenDocument Spreadsheet Document

An *OpenDocument Spreadsheet document* shall meet all requirements of a Conforming OpenDocument Document, as well as the following additional requirements:

A) The `<office:document>` element shall have an `office:mimetype` attribute with one of these values: "application/vnd.oasis.opendocument.spreadsheet" or "application/vnd.oasis.opendocument.spreadsheet-template".

B) If the document is an OpenDocument package then it shall contain a file named mimetype containing one of these strings: "application/vnd.oasis.opendocument.spreadsheet" or "application/vnd.oasis.opendocument.spreadsheet-template".

C) The `<office:body>` element shall have the child element `<office:spreadsheet>`.

D) All namespace prefixes used in the values of `table:formula` attributes values shall be bound to the "urn:oasis:names:tc:opendocument:xmlns:of:1.2 " namespace.

E) All `table:formula` attribute values shall be a conforming OpenDocument Formula expression (C15).

2.2.5 OpenDocument Drawing Document

An *OpenDocument Drawing document* shall meet all requirements of a Conforming OpenDocument Document, as well as the following additional requirements:

A) The `<office:document>` element shall have an `office:mimetype` attribute with one of these values: "application.vnd.oasis.opendocument.graphics" or "application/vnd.oasis.opendocument.graphic-template".

B) If the document is an OpenDocument package then it shall contain a file named mimetype containing one of these strings: "application.vnd.oasis.opendocument.graphics" or "application/vnd.oasis.opendocument.graphic-template".

C) The `<office:body>` element shall have the child element `<office:drawing>`.

2.2.6 OpenDocument Presentation Document

An *OpenDocument Presentation document* shall meet all requirements of a Conforming OpenDocument Document, as well as the following additional requirements:

A) The `<office:document>` element shall have an `office:mimetype` attribute with one of these values: "application/vnd.oasis.opendocument.presentation" or "application/vnd.oasis.opendocument.presentation-template".

B) If the document is an OpenDocument package then it shall contain a file named mimetype containing one of these strings: "application/vnd.oasis.opendocument.presentation" or "application/vnd.oasis.opendocument.presentation-template".

C) The `<office:body>` element shall have the child element `<office:presentation>`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

2.2.7 OpenDocument Chart Document

An *OpenDocument Chart document* shall meet all requirements of a Conforming OpenDocument Document, as well as the following additional requirements:

A) The `<office:document>` element shall have an `office:mimetype` attribute with one of these values: "application/vnd.oasis.opendocument.chart" or "application/vnd.oasis.opendocument.chart-template".

B) If the document is an OpenDocument package then it shall contain a file named mimetype containing one of these strings: "application/vnd.oasis.opendocument.chart" or "application/vnd.oasis.opendocument.chart-template".

C) The `<office:body>` element shall have the child element `<office:chart>`.

2.2.8 OpenDocument Image Document

An *OpenDocument Image document* shall meet all requirements of a Conforming OpenDocument Document, as well as the following additional requirements:

A) The `<office:document>` element shall have an `office:mimetype` attribute with one of these values: "application/vnd.oasis.opendocument.image" or "application/vnd.oasis.opendocument.image-template".

B) If the document is an OpenDocument package then it shall contain a file named mimetype containing one of these strings: "application/vnd.oasis.opendocument.image" or "application/vnd.oasis.opendocument.image-template".

C) The `<office:body>` element shall have the child element `<office:image>`.

2.2.9 OpenDocument Formula Document

An *OpenDocument Formula document* shall meet all requirements of a Conforming OpenDocument Document, as well as the following additional requirements:

A) If the document is an OpenDocument package. The OpenDocument package shall contain a file named mimetype with content being the string "application/vnd.oasis.opendocument.formula".

B) The package "content.xml" file shall have a `<math:math>` root element.

2.2.10 OpenDocument Database Front End Document

An *OpenDocument Database Front End document* shall meet all requirements of a Conforming OpenDocument Document, as well as the following additional requirements:

A) The `<office:document>` element shall have an `office:mimetype` attribute with the value "application/vnd.oasis.opendocument.base".

B) If the document is an OpenDocument package then it shall contain a file named mimetype containing the string " application/vnd.oasis.opendocument.base".

C) The `<office:body>` element shall have the child element `<office:database>`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

2.3 Producers

2.3.1 OpenDocument Producer

An *OpenDocument producer* is a program that creates at least one conforming OpenDocument document, and that meets the following additional requirements:

A) It may produce conforming OpenDocument extended documents, but it shall have a mode of operation where all OpenDocument documents that are created are conforming OpenDocument documents.

B) It shall be accompanied by a document that defines all implementation-defined values used by the OpenDocument producer.

2.3.2 OpenDocument Extended Producer

An *OpenDocument extended producer* is a program that creates at least one conforming OpenDocument extended document, and that meets the following additional requirements:

A) It shall be accompanied by a document that defines all implementation-defined values used by the OpenDocument extended producer.

B) It should be accompanied by a document that defines all foreign elements and attributes used by the OpenDocument extended producer.

2.4 Consumer

An *OpenDocument consumer* is a program that can parse and interpret OpenDocument documents according to the semantics defined by this specification, and that meets the following additional requirements:

A) It shall be able to parse and interpret OpenDocument documents of one or more of the document types defined by this specification (see 3.3) any of which are represented in packages, but it need not interpret the semantics of all elements, attributes and attribute values.

B) It may be able to parse and interpret OpenDocument documents stored as single XML document, but it need not interpret the semantics of all elements, attributes and attribute values.

C) It shall interpret those elements and attributes it does interpret consistent with the semantics defined for the element or attribute by this specification.

D) It should be able to parse and interpret conforming OpenDocument extended documents, but it need not interpret the semantics of all elements, attributes and attribute values.

E) The XML parser used to parse the files contained in a package listed in 2.2.1, item B) or the single document listed in 2.2.1, item C) meets the following requirements:

E.1) It shall be a nonvalidating XML processor with regard to the XML 1.0 specification [XML1.0].

E.2) It shall be and be a conforming processor with regard to the XML Namespaces specification [xml-names].

E.3) It shall conform to the xml-id specification [XML-ID].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

3 Document Structure

3.1 Document Representation

3.1.1 General

OpenDocument defines two methods of document representation:

- A single XML document.
- A collection of files within a package (see OpenDocument specification part 3), each of which stores a part of a complete document.

3.1.2 <office:document>(Single OpenDocument XML Files)

The `<office:document>` element is the root element of a document in OpenDocument format which is represented as a single XML document. It contains the entire document.

The `<office:document>` element is a root element.

The `<office:document>` element is usable within the following elements: `<db:component>` 12.25.5 and `<draw:object>` 10.4.6.2.

The `<office:document>` element has the following attributes: `grddl:transformation` 19.320, `office:mimetype` 19.375 and `office:version` 19.386.

The `<office:document>` element has the following child elements: `<office:automatic-styles>` 3.15.3, `<office:body>` 3.3, `<office:font-face-decls>` 3.14, `<office:master-styles>` 3.15.4, `<office:meta>` 3.2, `<office:scripts>` 3.12, `<office:settings>` 3.10 and `<office:styles>` 3.15.2.

3.1.3 Package OpenDocument Files

3.1.3.1 General

When an OpenDocument document is represented as a package, there are four root elements, `<office:document-content>`, `<office:document-styles>`, `<office:document-meta>`, and, `<office:document-settings>`, each stored as a separate file.

A package may also contain image files, embedded objects and implementation-dependent files.

3.1.3.2 <office:document-content>

The `<office:document-content>` root element contains document content and automatic styles used in a document. The file within the package for the `<office:document-content>` element is content.xml.

The `<office:document-content>` element is a root element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <office:document-content> element has the following attributes: grddl:transformation 19.320 and office:version 19.386.

The <office:document-content> element has the following child elements: <office:automatic-styles> 3.15.3, <office:body> 3.3, <office:font-face-decls> 3.14 and <office:scripts> 3.12.

3.1.3.3 <office:document-styles>

The <office:document-styles> root element contains styles used in document content and automatic styles used in styles. The file within the package for the <office:document-styles> element is styles.xml.

The <office:document-styles> element is a root element.

The <office:document-styles> element has the following attributes: grddl:transformation 19.320 and office:version 19.386.

The <office:document-styles> element has the following child elements: <office:automatic-styles> 3.15.3, <office:font-face-decls> 3.14, <office:master-styles> 3.15.4 and <office:styles> 3.15.2.

3.1.3.4 <office:document-meta>

The <office:document-meta> root element contains document metadata elements. The file within the package for the <office:document-meta> element is meta.xml.

The <office:document-meta> element is a root element.

The <office:document-meta> element has the following attributes: grddl:transformation 19.320 and office:version 19.386.

The <office:document-meta> element has the following child element: <office:meta> 3.2.

3.1.3.5 <office:document-settings>

The <office:document-settings> root element contains implementation-dependent settings. The file within the package for the <office:document-settings> element is settings.xml.

The <office:document-settings> element is a root element.

The <office:document-settings> element has the following attributes: grddl:transformation 19.320 and office:version 19.386.

The <office:document-settings> element has the following child element: <office:settings> 3.10.

3.1.4 Summary of Document Representation

The models for representing an OpenDocument file are summarized in Table 5.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Table 7 - Root element content models

Root Element	***<office:meta>***	***<office:setting s>***	***<office:scripts>***	***<office:font-face-decls>***	***<office:styles>***	***<office:automatic-styles>***	***<office:master-styles>***	***<office:body>***
`<office:document>`	X	X	X	X	X	X	X	X
`<office:document-content>`			X	X		X		X
`<office:document-styles>`				X	X	X	X	
`<office:document-meta>`	X							
`<office:document-settings>`		X						

3.2 <office:meta>

The `<office:meta>` element contains metadata elements for a document that are not specified by a manifest.rdf file. 4.2.2

All the child elements of an `<office:meta>` element contain metadata about a document as a whole.

The `<office:meta>` element is usable within the following elements: `<office:document>` 3.1.2 and `<office:document-meta>` 3.1.3.4.

The `<office:meta>` element has no attributes.

The `<office:meta>` element has the following child elements: `<dc:creator>` 4.3.2.7, `<dc:date>` 4.3.2.10, `<dc:description>` 4.3.2.3, `<dc:language>` 4.3.2.15, `<dc:subject>` 4.3.2.4, `<dc:title>` 4.3.2.2, `<meta:auto-reload>` 4.3.2.13, `<meta:creation-date>` 4.3.2.9, `<meta:document-statistic>` 4.3.2.18, `<meta:editing-cycles>` 4.3.2.16, `<meta:editing-duration>` 4.3.2.17, `<meta:generator>` 4.3.2.1, `<meta:hyperlink-behaviour>` 4.3.2.14, `<meta:initial-creator>` 4.3.2.6, `<meta:keyword>` 4.3.2.5, `<meta:print-date>` 4.3.2.11, `<meta:printed-by>` 4.3.2.8, `<meta:template>` 4.3.2.12 and `<meta:user-defined>` 4.3.3.

3.3 <office:body>

The `<office:body>` element contains the elements that represent the content of a document.

The `<office:body>` element is usable within the following elements: `<office:document>` 3.1.2 and `<office:document-content>` 3.1.3.2.

The `<office:body>` element has no attributes.

The `<office:body>` element has the following child elements: `<office:chart>` 3.8, `<office:database>` 12.1, `<office:drawing>` 3.5, `<office:image>` 3.9, `<office:presentation>` 3.6, `<office:spreadsheet>` 3.7 and `<office:text>` 3.4.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

3.4 <office:text>

The <office:text> element represents the content of a text document.

The <office:text> element is usable within the following element: <office:body> 3.3.

The <office:text> element has the following attributes: text:global 19.806 and text:use-soft-page-breaks 19.897.

The <office:text> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:forms> 13.2, <table:calculation-settings> 9.4.1, <table:consolidation> 9.7, <table:content-validations> 9.4.4, <table:database-ranges> 9.4.14, <table:data-pilot-tables> 9.6.2, <table:dde-links> 9.8, <table:label-ranges> 9.4.10, <table:named-expressions> 9.4.11, <table:table> 9.1.2, <text:alphabetical-index> 8.8, <text:alphabetical-index-auto-mark-file> 8.8.3, <text:bibliography> 8.9, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:dde-connection-decls> 14.6.2, <text:h> 5.1.2, <text:illustration-index> 8.4, <text:list> 5.3.1, <text:numbered-paragraph> 5.3.6, <text:object-index> 8.6, <text:p> 5.1.3, <text:page-sequence> 5.2, <text:section> 5.4, <text:sequence-decls> 7.4.11, <text:soft-page-break> 5.6, <text:table-index> 8.5, <text:table-of-content> 8.3, <text:tracked-changes> 5.5.1, <text:user-field-decls> 7.4.7, <text:user-index> 8.7 and <text:variable-decls> 7.4.2.

3.5 <office:drawing>

The <office:drawing> element represents a drawing document.

The <office:drawing> element is usable within the following element: <office:body> 3.3.

The <office:drawing> element has no attributes.

The <office:drawing> element has the following child elements: <draw:page> 10.2.4, <table:calculation-settings> 9.4.1, <table:consolidation> 9.7, <table:content-validations> 9.4.4, <table:database-ranges> 9.4.14, <table:data-pilot-tables> 9.6.2, <table:dde-links> 9.8, <table:label-ranges> 9.4.10, <table:named-expressions> 9.4.11, <text:alphabetical-index-auto-mark-file> 8.8.3, <text:dde-connection-decls> 14.6.2, <text:sequence-decls> 7.4.11, <text:user-field-decls> 7.4.7 and <text:variable-decls> 7.4.2.

3.6 <office:presentation>

The <office:presentation> element represents a presentation document.

The <office:presentation> element is usable within the following element: <office:body> 3.3.

The <office:presentation> element has no attributes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <office:presentation> element has the following child elements: <draw:page> 10.2.4, <presentation:date-time-decl> 10.9.3.6, <presentation:footer-decl> 10.9.3.4, <presentation:header-decl> 10.9.3.2, <presentation:settings> 10.9.3.7, <table:calculation-settings> 9.4.1, <table:consolidation> 9.7, <table:content-validations> 9.4.4, <table:database-ranges> 9.4.14, <table:data-pilot-tables> 9.6.2, <table:dde-links> 9.8, <table:label-ranges> 9.4.10, <table:named-expressions> 9.4.11, <text:alphabetical-index-auto-mark-file> 8.8.3, <text:dde-connection-decls> 14.6.2, <text:sequence-decls> 7.4.11, <text:user-field-decls> 7.4.7 and <text:variable-decls> 7.4.2.

3.7 <office:spreadsheet>

The <office:spreadsheet> element represents a spreadsheet document.

The <office:spreadsheet> element is usable within the following element: <office:body> 3.3.

The <office:spreadsheet> element has the following attributes: table:protection-key 19.697, table:protection-key-digest-algorithm 19.698 and table:structure-protected 19.725.

The <office:spreadsheet> element has the following child elements: <table:calculation-settings> 9.4.1, <table:consolidation> 9.7, <table:content-validations> 9.4.4, <table:database-ranges> 9.4.14, <table:data-pilot-tables> 9.6.2, <table:dde-links> 9.8, <table:label-ranges> 9.4.10, <table:named-expressions> 9.4.11, <table:table> 9.1.2, <table:tracked-changes> 9.9.2, <text:alphabetical-index-auto-mark-file> 8.8.3, <text:dde-connection-decls> 14.6.2, <text:sequence-decls> 7.4.11, <text:user-field-decls> 7.4.7 and <text:variable-decls> 7.4.2.

3.8 <office:chart>

The <office:chart> element represents a chart document.

The <office:chart> element is usable within the following element: <office:body> 3.3.

The <office:chart> element has no attributes.

The <office:chart> element has the following child elements: <chart:chart> 11.1, <table:calculation-settings> 9.4.1, <table:consolidation> 9.7, <table:content-validations> 9.4.4, <table:database-ranges> 9.4.14, <table:data-pilot-tables> 9.6.2, <table:dde-links> 9.8, <table:label-ranges> 9.4.10, <table:named-expressions> 9.4.11, <text:alphabetical-index-auto-mark-file> 8.8.3, <text:dde-connection-decls> 14.6.2, <text:sequence-decls> 7.4.11, <text:user-field-decls> 7.4.7 and <text:variable-decls> 7.4.2.

3.9 <office:image>

The <office:image> element represents an image document.

The <office:image> element contains a <draw:frame> element which shall contain a single <draw:image> element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <office:image> element is usable within the following element: <office:body> 3.3.

The <office:image> element has no attributes.

The <office:image> element has the following child element: <draw:frame> 10.4.2.

3.10 <office:settings>

3.10.1 General

The <office:settings> element contains one or more <config:config-item-set> elements, each of which represents a set of application settings.

The <office:settings> element is usable within the following elements: <office:document> 3.1.2 and <office:document-settings> 3.1.3.5.

The <office:settings> element has no attributes.

The <office:settings> element has the following child element: <config:config-item-set> 3.10.2.

3.10.2 <config:config-item-set>

The <config:config-item-set> element is a container element for application setting elements. Setting child elements may occur in any order.

An ODF Consumer shall use application settings to alter application behavior only within the dimensions of variability permitted by this standard.

Note: See [Variability] for variability in specifications.

The <config:config-item-set> element is usable within the following elements: <config:config-item-map-entry> 3.10.5, <config:config-item-set> 3.10.2 and <office:settings> 3.10.

The <config:config-item-set> element has the following attribute: config:name 19.29.

The <config:config-item-set> element has the following child elements: <config:config-item> 3.10.3, <config:config-item-map-indexed> 3.10.4, <config:config-item-map-named> 3.10.6 and <config:config-item-set> 3.10.2.

3.10.3 <config:config-item>

The <config:config-item> element contains the value of an application setting whose name is specified by its config:name attribute.

The <config:config-item> element is usable within the following elements: <config:config-item-map-entry> 3.10.5 and <config:config-item-set> 3.10.2.

The <config:config-item> element has the following attributes: config:name 19.29 and config:type 19.30.

The <config:config-item> element has no child elements.

The <config:config-item> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

3.10.4 <config:config-item-map-indexed>

The `<config:config-item-map-indexed>` element is a container element for ordered sequences of application settings.

The `<config:config-item-map-indexed>` element is usable within the following elements: `<config:config-item-map-entry>` 3.10.5 and `<config:config-item-set>` 3.10.2.

The `<config:config-item-map-indexed>` element has the following attribute: `config:name` 19.29.

The `<config:config-item-map-indexed>` element has the following child element: `<config:config-item-map-entry>` 3.10.5.

3.10.5 <config:config-item-map-entry>

The `<config:config-item-map-entry>` element represents a single setting in a sequence of settings. The setting itself is defined by the child element of `<config:config-item-map-entry>`, and may be a single value, a set of settings, or a sequence of settings.

The `<config:config-item-map-entry>` element is usable within the following elements: `<config:config-item-map-indexed>` 3.10.4 and `<config:config-item-map-named>` 3.10.6.

The `<config:config-item-map-entry>` element has the following attribute: `config:name` 19.29.

The `<config:config-item-map-entry>` element has the following child elements: `<config:config-item>` 3.10.3, `<config:config-item-map-indexed>` 3.10.4, `<config:config-item-map-named>` 3.10.6 and `<config:config-item-set>` 3.10.2.

3.10.6 <config:config-item-map-named>

The `<config:config-item-map-named>` element contains a sequence of application setting elements. Each sequence is identified by the value of its `config:name` attribute.

The `<config:config-item-map-named>` element is usable within the following elements: `<config:config-item-map-entry>` 3.10.5 and `<config:config-item-set>` 3.10.2.

The `<config:config-item-map-named>` element has the following attribute: `config:name` 19.29.

The `<config:config-item-map-named>` element has the following child element: `<config:config-item-map-entry>` 3.10.5.

3.11 Cursor Position Setting

To represent a text cursor position within a document, a processing instruction with `PITarget opendocument` (see §2.6 of [XML1.0]) should be used. The name of the cursor position processing instruction, `cursor-position`, shall follow the `PITarget opendocument`. The processing instruction may have arbitrary implementation-defined attributes.

Note: Where a text cursor position is not sufficient to recreate a document view, producers may use arbitrary document specific settings in addition to a cursor position processing instruction.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

3.12 <office:scripts>

The <office:scripts> element contains all the <office:script> elements for a document.

Each <office:script> element contains a script. A document may contain scripts in different scripting languages.

Note: Scripts need not use XML document models.

The <office:scripts> element may also contain <office:event-listeners> elements which contain the events assigned to the document itself. 14.4.2

The <office:scripts> element is usable within the following elements: <office:document> 3.1.2 and <office:document-content> 3.1.3.2.

The <office:scripts> element has no attributes.

The <office:scripts> element has the following child elements: <office:event-listeners> 10.3.19 and <office:script> 3.13.

3.13 <office:script>

The <office:script> element contains a script.

The <office:script> element is usable within the following element: <office:scripts> 3.12.

The <office:script> element has the following attribute: script:language 19.430.

The <office:script> element has mixed content where arbitrary child elements are permitted.

Note: In most situations, the element contains the source code of the script, but it may also contain a compiled version of the script or a link to external script code.

3.14 <office:font-face-decls>

The <office:font-face-decls> element contains all the font face declarations (<style:font-face> elements) for a document.

The <office:font-face-decls> element is usable within the following elements: <office:document> 3.1.2, <office:document-content> 3.1.3.2 and <office:document-styles> 3.1.3.3.

The <office:font-face-decls> element has no attributes.

The <office:font-face-decls> element has the following child element: <style:font-face> 16.21.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

3.15 Styles

3.15.1 General

Styles for a document are defined in container elements according to their type: common, automatic and master.

Page layouts and styles are defined by <style:page-layout> 17.2 and <style:master-page> 16.9 elements, respectively.

3.15.2 <office:styles>

The <office:styles> element contains common styles used in a document. A common style is a style chosen by a user for a document or portion thereof.

The <office:styles> element is usable within the following elements: <office:document> 3.1.2 and <office:document-styles> 3.1.3.3.

The <office:styles> element has no attributes.

The <office:styles> element has the following child elements: <draw:fill-image> 16.40.6, <draw:gradient> 16.40.1, <draw:hatch> 16.40.5, <draw:marker> 16.40.8, <draw:opacity> 16.40.7, <draw:stroke-dash> 16.40.9, <number:boolean-style> 16.27.23, <number:currency-style> 16.27.7, <number:date-style> 16.27.10, <number:number-style> 16.27.2, <number:percentage-style> 16.27.9, <number:text-style> 16.27.25, <number:time-style> 16.27.18, <style:default-page-layout> 16.8, <style:default-style> 16.4, <style:presentation-page-layout> 16.41, <style:style> 16.2, <svg:linearGradient> 16.40.2, <svg:radialGradient> 16.40.3, <table:table-template> 16.18, <text:bibliography-configuration> 16.29.6, <text:linenumbering-configuration> 16.29.1, <text:list-style> 16.30, <text:notes-configuration> 16.29.3 and <text:outline-style> 16.34.

3.15.3 <office:automatic-styles>

The <office:automatic-styles> element contains automatic styles used in a document.

An automatic style is one contains formatting properties that are considered to be properties of the object to which the style is assigned.

Note: Common and automatic styles behave differently in OpenDocument editing consumers. Common styles are presented to the user as a named set of formatting properties. The formatting properties of an automatic style are presented to a user as properties of the object to which the style is applied.

The <office:automatic-styles> element is usable within the following elements: <office:document> 3.1.2, <office:document-content> 3.1.3.2 and <office:document-styles> 3.1.3.3.

The <office:automatic-styles> element has no attributes.

The <office:automatic-styles> element has the following child elements: <number:boolean-style> 16.27.23, <number:currency-style> 16.27.7, <number:date-style> 16.27.10, <number:number-style> 16.27.2, <number:percentage-style> 16.27.9, <number:text-style> 16.27.25,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<number:time-style> 16.27.18, <style:page-layout> 16.5, <style:style> 16.2 and <text:list-style> 16.30.

3.15.4 <office:master-styles>

The <office:master-styles> element contains master styles that are used in a document. A master style contains formatting and other content that is displayed with document content when the style is used.

The <office:master-styles> element is usable within the following elements: <office:document> 3.1.2 and <office:document-styles> 3.1.3.3.

The <office:master-styles> element has no attributes.

The <office:master-styles> element has the following child elements: <draw:layer-set> 10.2.2, <style:handout-master> 10.2.1 and <style:master-page> 16.9.

3.16 Document Signatures

An OpenDocument document that is stored in a package may have one or more digital signatures applied to the package.

Document signatures shall be stored in a file called META-INF/documentsignatures.xml in the package as described in section 2.4 of the OpenDocument specification part 3. Document signatures shall contain a <ds:Reference> element for each file within the package, with the exception that <ds:Reference> elements for the META-INF/documentsignatures.xml file containing the signature, and any files contained in the package whose relative path starts with "external-data/" should be omitted.

Signatures other than document signatures are implementation-defined.

3.17 Foreign Elements and Attributes

OpenDocument extended documents may contain elements and attributes not defined by the OpenDocument schema. Elements and attributes not defined by the OpenDocument schema are called *foreign elements* and *attributes*. Foreign elements and attributes shall not be associated with a namespace that is listed in tables 1, 2 or 3 of section 1.5.

If a foreign element:

- has a <text:h> or <text:p> ancestor element, and
- is a child element of an element for which the OpenDocument schema permits the inclusion of character data, and
- if the OpenDocument schema permits the inclusion of character data for all its ancestors up to the <text:p> or <text:h> element ancestor element,

then the element's content may be interpreted by conforming OpenDocument consumers, and the document itself shall be valid against the OpenDocument schema as if the foreign element's start- and end-tags or its empty-element-tag are removed.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

For a foreign element that occurs at another location, conforming consumers should not interpret the element's content, but may preserve its content.

Foreign elements may have an `office:process-content` attribute 19.377 attached which controls the processing of the element content.

Note: In OpenDocument 1.0 and 1.1, the content of foreign elements should be processed unless there was an `office:process-content` attribute with value `false`.

Conforming extended producers should not use foreign elements and attributes for features defined in the OpenDocument specification.

A conforming consumer that encounters an OpenDocument defined attribute that has a value that is not defined by OpenDocument, then it should:

1) If the attribute has a specified default value, use its default value, or

2) If the attribute does not have a specified default value, ignore the attribute.

3.18 White Space Processing and EOL Handling

ODF processing of whitespace characters is in conformance with the provisions of [XML1.0].

In addition, OpenDocument Consumers shall ignore all element children ([RNG] section 5, Data Model) of elements defined in this specification that are strings consisting entirely of whitespace characters and which do not satisfy a pattern of the OpenDocument schema definition for the element.

Additional treatment of occurrences of whitespace characters depends on the provisions for specific elements, attributes, and their datatypes in this specification.

Note: There are special OpenDocument rules for the reduction of whitespace sequences to single space characters in the text obtained from `<text:p>`, `<text:h>` and their element children. 6.1.2

3.19 MIME Types and File Name Extensions

Appendix C contains a list of MIME types and file name extensions to be used for office documents that conform to this specification and that are contained in a package. See 3.1.3.

Office documents that conform to this specification but are not contained in a package should use the MIME type `text/xml`.

Only MIME types and extensions that have been registered according to [RFC4288] should used for office documents that conform to this specification. The MIME types and extensions listed in appendix C should be used where appropriate.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

4 Metadata

4.1 General

Metadata is general information about a document or its content.

OpenDocument supports five types of metadata:

1) RDF metadata describing documents or the content of identifiable OpenDocument elements. 4.2.2

2) Text content being used as RDF metadata. 4.2.1

3) Pre-defined metadata (meta.xml). 4.3.2

4) User-defined metadata (using the `<meta:user-defined>` element). 4.3.3

5) Custom metadata (custom XML elements within meta.xml). 4.3.1

Pre-defined and user-defined metadata are both stored in the metadata `<office:meta>` element. The elements representing this metadata may be omitted or occur multiple times. The updating of multiple instances of the same metadata elements is implementation-dependent.

4.2 RDF Metadata

4.2.1 In Content Metadata (RDFa)

Metadata in OpenDocument documents may be expressed using the model of the W3C Resource Description Framework [RDF-CONCEPTS].

In addition to the mechanism defined in Part 3 of this specification RDF metadata can be attached to elements in the "content.xml" and "styles.xml" file. Elements supporting this type of metadata have the following attributes: `xhtml:about` 19.905, `xhtml:property` 19.908, `xhtml:content` 19.906, and `xhtml:datatype` 19.907. When metadata is added using these attributes, it is referred to as in content metadata. If "content.xml" and "styles.xml" files contain in content metadata they shall be listed in the package's "manifest.rdf" file.

4.2.2 manifest.rdf

4.2.2.1 General

The OpenDocument document contains a metadata manifest, as defined in Part 3 of this specification. The [OWL] Metadata Manifest Description ontology defined in Part 3 is extended with additional properties and classes in appendix B. The following OWL classes and properties are defined.

4.2.2.2 odf:ContentFile

An instance of the `odf:ContentFile` class represents a content.xml file.

The `odf:ContentFile` class is a subclass of `pkg:File`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

4.2.2.3 odf:StylesFile

An instance of the `odf:StylesFile` class represents a styles.xml file.

The `odf:StylesFile` class is a subclass of `pkg:File`

4.2.2.4 odf:Element

An instance of the `odf:Element` class represents an OpenDocument XML element in a content.xml or styles.xml file. It is a subclass of the `pkg:Element` class, which represents any XML element in the OpenDocument package.

Note: One or more `rdf:type` properties specify the metadata type of an `odf:Element`.

Every XML element that is defined by this specification and has an attribute of type ID may be described using an OWL class. The IRI of an OWL class for an element is the concatenation of the element's QName namespace IRI and its local name part. These classes are subclasses of `odf:Element`.

The following properties are defined for the subclass describing a `<text:meta-field>` element (`urn:oasis:names:tc:opendocument:xmlns:text:1.0meta-field`) : `odf:prefix` 4.2.2.5 and `odf:suffix` 4.2.2.6.

4.2.2.5 odf:prefix

The `odf:prefix` property defines the prefix content of a `<text:meta-field>` field 7.5.19.

This property can be used with the following class:
`urn:oasis:names:tc:opendocument:xmlns:text:1.0meta-field` 4.2.2.4.

4.2.2.6 odf:suffix

The `odf:suffix` property defines the suffix content of a `<text:meta-field>` field 7.5.19.

This property can be used with the following class:
`urn:oasis:names:tc:opendocument:xmlns:text:1.0meta-field` 4.2.2.4.

4.3 Non-RDF Metadata

4.3.1 General

Non-RDF metadata in OpenDocument is composed of pre-defined metadata elements, user defined metadata elements, and custom metadata elements.

The pre-defined metadata elements have defined semantics. They should be processed by consumers and updated by producers. They can be referenced from within the document using text fields.

The pre-defined metadata elements borrow heavily upon the metadata standards developed by the Dublin Core Metadata Initiative (http://www.dublincore.org). Metadata elements drawn directly from the Dublin Core work are in the http://purl.org/dc/elements/1.1 namespace. “

User-defined metadata specifies a triplet of name, type, and value. Consumers can present these values to the user.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Custom metadata elements are arbitrary elements inside an <office:meta> element. The semantics of custom metadata elements is implementation-defined.

Custom metadata elements shall only occur in OpenDocument extended documents. The use of custom metadata is deprecated in favor of RDF/XML based metadata.

Note: Consumers need not process custom metadata other than to preserve it when editing a document.

4.3.2 Pre-Defined Metadata Elements

4.3.2.1 <meta:generator>

The <meta:generator> element contains a string that identifies the OpenDocument producer that was used to create or last modify the document. This string should match the definition for user-agents in the HTTP protocol as specified in section 14.43 of [RFC2616]. The generator string should allow OpenDocument consumers to distinguish between all released versions of a producer.

Note: Release versions of a producer could be distinguished based on build ids or patch level information.

If an OpenDocument producer that creates a document cannot provide an identifier string, the producer shall not export this element. If a producer stores a modified document created by another producer cannot provide a unique identifier, it shall not export the original identifier belonging to the producer that created the document.

The <meta:generator> element is usable within the following element: <office:meta> 3.2.

The <meta:generator> element has no attributes.

The <meta:generator> element has no child elements.

The <meta:generator> element has content of data type string 18.2.

4.3.2.2 <dc:title>

The <dc:title> element specifies the title of a document.

The <dc:title> element is usable within the following element: <office:meta> 3.2.

The <dc:title> element has no attributes.

The <dc:title> element has no child elements.

The <dc:title> element has content of data type string 18.2.

4.3.2.3 <dc:description>

The <dc:description> element contains a description of a document.

The <dc:description> element is usable within the following element: <office:meta> 3.2.

The <dc:description> element has no attributes.

The <dc:description> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <dc:description> element has content of data type string 18.2.

4.3.2.4 <dc:subject>

The <dc:subject> element specifies the subject of a document.

The <dc:subject> element is usable within the following element: <office:meta> 3.2.

The <dc:subject> element has no attributes.

The <dc:subject> element has no child elements.

The <dc:subject> element has content of data type string 18.2.

4.3.2.5 <meta:keyword>

The <meta:keyword> element contains a keyword pertaining to a document.

The <meta:keyword> element is usable within the following element: <office:meta> 3.2.

The <meta:keyword> element has no attributes.

The <meta:keyword> element has no child elements.

The <meta:keyword> element has content of data type string 18.2.

4.3.2.6 <meta:initial-creator>

The <meta:initial-creator> element specifies the name of the initial creator of a document.

The <meta:initial-creator> element is usable within the following element: <office:meta> 3.2.

The <meta:initial-creator> element has no attributes.

The <meta:initial-creator> element has no child elements.

The <meta:initial-creator> element has content of data type string 18.2.

4.3.2.7 <dc:creator>

The <dc:creator> element specifies the name of the person who last modified a document (<office:meta>), who created an annotation (<office:annotation>), who authored a change (<office:change-info>).

The <dc:creator> element is usable within the following elements: <office:annotation> 14.1, <office:change-info> 5.5.6 and <office:meta> 3.2.

The <dc:creator> element has no attributes.

The <dc:creator> element has no child elements.

The <dc:creator> element has content of data type string 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

4.3.2.8 <meta:printed-by>

The <meta:printed-by> element specifies the name of the last person who printed a document.

The <meta:printed-by> element is usable within the following element: <office:meta> 3.2.

The <meta:printed-by> element has no attributes.

The <meta:printed-by> element has no child elements.

The <meta:printed-by> element has content of data type string 18.2.

4.3.2.9 <meta:creation-date>

The <meta:creation-date> element specifies the date and time when a document was created.

The <meta:creation-date> element is usable within the following element: <office:meta> 3.2.

The <meta:creation-date> element has no attributes.

The <meta:creation-date> element has no child elements.

The <meta:creation-date> element has content of data type dateTime 18.2.

4.3.2.10 <dc:date>

The <dc:date> element specifies the date and time when the document was last modified (<office:meta>), when an annotation was created (<office:annotation>), when a change was made (<office:change-info>).

The <dc:date> element is usable within the following elements: <office:annotation> 14.1, <office:change-info> 5.5.6 and <office:meta> 3.2.

The <dc:date> element has no attributes.

The <dc:date> element has no child elements.

The <dc:date> element has content of data type dateTime 18.2.

4.3.2.11 <meta:print-date>

The <meta:print-date> element specifies the date and time when a document was last printed.

The <meta:print-date> element is usable within the following element: <office:meta> 3.2.

The <meta:print-date> element has no attributes.

The <meta:print-date> element has no child elements.

The <meta:print-date> element has content of data type dateTime 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

4.3.2.12 <meta:template>

The <meta:template> element specifies a IRI for the document template that was used to create a document. The IRI is specified as an Xlink. See [XLink].

The <meta:template> element is usable within the following element: <office:meta> 3.2.

The <meta:template> element has the following attributes: meta:date 19.323, xlink:actuate 19.909, xlink:href 19.910.24, xlink:title 19.912 and xlink:type 19.913.

The <meta:template> element has no child elements.

4.3.2.13 <meta:auto-reload>

The <meta:auto-reload> element specifies whether a document is reloaded or replaced by another document after a specified period of time has elapsed.

The <meta:auto-reload> element is usable within the following element: <office:meta> 3.2.

The <meta:auto-reload> element has the following attributes: meta:delay 19.324, xlink:actuate 19.909, xlink:href 19.910.23, xlink:show 19.911 and xlink:type 19.913.

The <meta:auto-reload> element has no child elements.

4.3.2.14 <meta:hyperlink-behaviour>

The <meta:hyperlink-behaviour> element specifies the default behavior for hyperlinks in a document.

The <meta:hyperlink-behaviour> element is usable within the following element: <office:meta> 3.2.

The <meta:hyperlink-behaviour> element has the following attributes: office:target-frame-name 19.381 and xlink:show 19.911.

The <meta:hyperlink-behaviour> element has no child elements.

4.3.2.15 <dc:language>

The <dc:language> element specifies the default language of a document.

The <dc:language> element is usable within the following element: <office:meta> 3.2.

The <dc:language> element has no attributes.

The <dc:language> element has no child elements.

The <dc:language> element has content of data type language 18.3.16.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

4.3.2.16 <meta:editing-cycles>

The <meta:editing-cycles> element specifies the number of times a document has been edited. When a document is created, this value is set to 1. Each time a document is saved, the editing-cycles number is incremented by 1.

The <meta:editing-cycles> element is usable within the following element: <office:meta> 3.2.

The <meta:editing-cycles> element has no attributes.

The <meta:editing-cycles> element has no child elements.

The <meta:editing-cycles> element has content of data type nonNegativeInteger 18.2.

4.3.2.17 <meta:editing-duration>

The <meta:editing-duration> element specifies the total time spent editing a document.

The <meta:editing-duration> element is usable within the following element: <office:meta> 3.2.

The <meta:editing-duration> element has no attributes.

The <meta:editing-duration> element has no child elements.

The <meta:editing-duration> element has content of data type duration 18.2.

4.3.2.18 <meta:document-statistic>

The <meta:document-statistic> element represents statistics about a document.

The <meta:document-statistic> element is usable within the following element: <office:meta> 3.2.

The <meta:document-statistic> element has the following attributes: meta:cell-count 19.321, meta:character-count 19.322, meta:draw-count 19.325, meta:frame-count 19.326, meta:image-count 19.327, meta:non-whitespace-character-count 19.329, meta:object-count 19.330, meta:ole-object-count 19.331, meta:page-count 19.332, meta:paragraph-count 19.333, meta:row-count 19.334, meta:sentence-count 19.335, meta:syllable-count 19.336, meta:table-count 19.337 and meta:word-count 19.339.

The <meta:document-statistic> element has no child elements.

4.3.3 <meta:user-defined>

The <meta:user-defined> element specifies any additional user-defined metadata for a document.

The <meta:user-defined> element is usable within the following element: <office:meta> 3.2.

The <meta:user-defined> element has the following attributes: meta:name 19.328, meta:value-type 19.338.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `<meta:user-defined>` element has no child elements.

The `<meta:user-defined>` element has character data content, or depending on the value of the `meta:value-type` attribute content of type `double` 18.2, `date` 18.2, `dateTime` 18.2, `duration` 18.2, `boolean` 18.3.3 or `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

5 Text Content

5.1 Headings, Paragraphs and Basic Text Structure

5.1.1 General

The <text:h> and <text:p> elements represent headings and paragraphs, respectively.

Headings and paragraphs are collectively referred to as *paragraph elements*.

5.1.2 <text:h>

The <text:h> element represents a heading in a document. Headings define the division structure for a document. A chapter or section begins with a heading and extends to the next heading at the same or higher level.

The <text:h> element is usable within the following elements: <draw:text-box> 10.4.3, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10, <style:header-left> 16.12, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:deletion> 5.5.4, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:list-header> 5.3.3, <text:list-item> 5.3.4, <text:note-body> 6.3.4, <text:numbered-paragraph> 5.3.6 and <text:section> 5.4.

The <text:h> element has the following attributes: text:class-names 19.770.2, text:cond-style-name 19.776, text:id 19.809.6, text:is-list-header 19.816, text:outline-level 19.844.4, text:restart-numbering 19.857, text:start-value 19.868.2, text:style-name 19.874.7, xhtml:about 19.905, xhtml:content 19.906, xhtml:datatype 19.907, xhtml:property 19.908 and xml:id 19.914.

The <text:h> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:annotation> 14.1, <office:annotation-end> 14.2, <presentation:date-time> 10.9.3.5, <presentation:footer> 10.9.3.3, <presentation:header> 10.9.3.1, <text:a> 6.1.8, <text:alphabetical-index-mark> 8.1.10, <text:alphabetical-index-mark-end> 8.1.9, <text:alphabetical-index-mark-start> 8.1.8, <text:author-initials> 7.3.7.2, <text:author-name> 7.3.7.1, <text:bibliography-mark> 8.1.11, <text:bookmark> 6.2.1.2, <text:bookmark-end> 6.2.1.4, <text:bookmark-ref> 7.7.6, <text:bookmark-start> 6.2.1.3, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:chapter> 7.3.8, <text:character-count> 7.5.18.5, <text:conditional-text> 7.7.3, <text:creation-date> 7.5.3, <text:creation-time> 7.5.4, <text:creator> 7.5.17, <text:database-display> 7.6.3, <text:database-name> 7.6.7, <text:database-next> 7.6.4, <text:database-row-number> 7.6.6, <text:database-row-select> 7.6.5, <text:date> 7.3.2, <text:dde-connection> 7.7.12, <text:description> 7.5.5, <text:editing-cycles> 7.5.13, <text:editing-duration> 7.5.14, <text:execute-macro> 7.7.10, <text:expression> 7.4.14, <text:file-name> 7.3.9, <text:hidden-

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

paragraph> 7.7.11, <text:hidden-text> 7.7.4, <text:image-count> 7.5.18.7, <text:initial-creator> 7.5.2, <text:keywords> 7.5.12, <text:line-break> 6.1.5, <text:measure> 7.7.13, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:modification-date> 7.5.16, <text:modification-time> 7.5.15, <text:note> 6.3.2, <text:note-ref> 7.7.7, <text:number> 6.1.10, <text:object-count> 7.5.18.8, <text:page-continuation> 7.3.5, <text:page-count> 7.5.18.2, <text:page-number> 7.3.4, <text:page-variable-get> 7.7.1.3, <text:page-variable-set> 7.7.1.2, <text:paragraph-count> 7.5.18.3, <text:placeholder> 7.7.2, <text:print-date> 7.5.8, <text:printed-by> 7.5.9, <text:print-time> 7.5.7, <text:reference-mark> 6.2.2.2, <text:reference-mark-end> 6.2.2.4, <text:reference-mark-start> 6.2.2.3, <text:reference-ref> 7.7.5, <text:ruby> 6.4, <text:s> 6.1.3, <text:script> 7.7.9, <text:sender-city> 7.3.6.13, <text:sender-company> 7.3.6.10, <text:sender-country> 7.3.6.15, <text:sender-email> 7.3.6.7, <text:sender-fax> 7.3.6.9, <text:sender-firstname> 7.3.6.2, <text:sender-initials> 7.3.6.4, <text:sender-lastname> 7.3.6.3, <text:sender-phone-private> 7.3.6.8, <text:sender-phone-work> 7.3.6.11, <text:sender-position> 7.3.6.6, <text:sender-postal-code> 7.3.6.14, <text:sender-state-or-province> 7.3.6.16, <text:sender-street> 7.3.6.12, <text:sender-title> 7.3.6.5, <text:sequence> 7.4.13, <text:sequence-ref> 7.7.8, <text:sheet-name> 7.3.11, <text:soft-page-break> 5.6, <text:span> 6.1.7, <text:subject> 7.5.11, <text:tab> 6.1.4, <text:table-count> 7.5.18.6, <text:table-formula> 7.7.14, <text:template-name> 7.3.10, <text:text-input> 7.4.15, <text:time> 7.3.3, <text:title> 7.5.10, <text:toc-mark> 8.1.4, <text:toc-mark-end> 8.1.3, <text:toc-mark-start> 8.1.2, <text:user-defined> 7.5.6, <text:user-field-get> 7.4.9, <text:user-field-input> 7.4.10, <text:user-index-mark> 8.1.7, <text:user-index-mark-end> 8.1.6, <text:user-index-mark-start> 8.1.5, <text:variable-get> 7.4.5, <text:variable-input> 7.4.6, <text:variable-set> 7.4.4 and <text:word-count> 7.5.18.4.

The <text:h> element has mixed content.

5.1.3 <text:p>

The <text:p> element represents a paragraph, which is the basic unit of text in an OpenDocument file.

The <text:p> element is usable within the following elements: <chart:data-label> 11.14, <chart:equation> 11.18, <chart:footer> 11.2.3, <chart:label-separator> 17.24, <chart:legend> 11.3, <chart:subtitle> 11.2.2, <chart:title> 11.2.1, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:image> 10.4.4, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <draw:text-box> 10.4.3, <form:textarea> 13.5.3, <office:annotation> 14.1, <office:change-info> 5.5.6, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10, <style:header-left> 16.12, <style:region-center> 16.15, <style:region-left> 16.14, <style:region-right> 16.16, <table:change-track-table-cell> 9.9.16, <table:covered-table-cell> 9.1.5, <table:error-message> 9.4.7, <table:help-message> 9.4.6, <table:table-cell> 9.1.4, <text:deletion> 5.5.4, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:list-header> 5.3.3, <text:list-item> 5.3.4, <text:note-body> 6.3.4, <text:numbered-paragraph> 5.3.6 and <text:section> 5.4.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:p> element has the following attributes: text:class-names 19.770.3, text:cond-style-name 19.776, text:id 19.809.8, text:style-name 19.874.29, xhtml:about 19.905, xhtml:content 19.906, xhtml:datatype 19.907, xhtml:property 19.908 and xml:id 19.914.

The <text:p> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:annotation> 14.1, <office:annotation-end> 14.2, <presentation:date-time> 10.9.3.5, <presentation:footer> 10.9.3.3, <presentation:header> 10.9.3.1, <text:a> 6.1.8, <text:alphabetical-index-mark> 8.1.10, <text:alphabetical-index-mark-end> 8.1.9, <text:alphabetical-index-mark-start> 8.1.8, <text:author-initials> 7.3.7.2, <text:author-name> 7.3.7.1, <text:bibliography-mark> 8.1.11, <text:bookmark> 6.2.1.2, <text:bookmark-end> 6.2.1.4, <text:bookmark-ref> 7.7.6, <text:bookmark-start> 6.2.1.3, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:chapter> 7.3.8, <text:character-count> 7.5.18.5, <text:conditional-text> 7.7.3, <text:creation-date> 7.5.3, <text:creation-time> 7.5.4, <text:creator> 7.5.17, <text:database-display> 7.6.3, <text:database-name> 7.6.7, <text:database-next> 7.6.4, <text:database-row-number> 7.6.6, <text:database-row-select> 7.6.5, <text:date> 7.3.2, <text:dde-connection> 7.7.12, <text:description> 7.5.5, <text:editing-cycles> 7.5.13, <text:editing-duration> 7.5.14, <text:execute-macro> 7.7.10, <text:expression> 7.4.14, <text:file-name> 7.3.9, <text:hidden-paragraph> 7.7.11, <text:hidden-text> 7.7.4, <text:image-count> 7.5.18.7, <text:initial-creator> 7.5.2, <text:keywords> 7.5.12, <text:line-break> 6.1.5, <text:measure> 7.7.13, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:modification-date> 7.5.16, <text:modification-time> 7.5.15, <text:note> 6.3.2, <text:note-ref> 7.7.7, <text:object-count> 7.5.18.8, <text:page-continuation> 7.3.5, <text:page-count> 7.5.18.2, <text:page-number> 7.3.4, <text:page-variable-get> 7.7.1.3, <text:page-variable-set> 7.7.1.2, <text:paragraph-count> 7.5.18.3, <text:placeholder> 7.7.2, <text:print-date> 7.5.8, <text:printed-by> 7.5.9, <text:print-time> 7.5.7, <text:reference-mark> 6.2.2.2, <text:reference-mark-end> 6.2.2.4, <text:reference-mark-start> 6.2.2.3, <text:reference-ref> 7.7.5, <text:ruby> 6.4, <text:s> 6.1.3, <text:script> 7.7.9, <text:sender-city> 7.3.6.13, <text:sender-company> 7.3.6.10, <text:sender-country> 7.3.6.15, <text:sender-email> 7.3.6.7, <text:sender-fax> 7.3.6.9, <text:sender-firstname> 7.3.6.2, <text:sender-initials> 7.3.6.4, <text:sender-lastname> 7.3.6.3, <text:sender-phone-private> 7.3.6.8, <text:sender-phone-work> 7.3.6.11, <text:sender-position> 7.3.6.6, <text:sender-postal-code> 7.3.6.14, <text:sender-state-or-province> 7.3.6.16, <text:sender-street> 7.3.6.12, <text:sender-title> 7.3.6.5, <text:sequence> 7.4.13, <text:sequence-ref> 7.7.8, <text:sheet-name> 7.3.11, <text:soft-page-break> 5.6, <text:span> 6.1.7, <text:subject> 7.5.11, <text:tab> 6.1.4, <text:table-count> 7.5.18.6, <text:table-formula> 7.7.14, <text:template-name> 7.3.10, <text:text-input> 7.4.15, <text:time> 7.3.3, <text:title> 7.5.10, <text:toc-mark> 8.1.4, <text:toc-mark-end> 8.1.3, <text:toc-mark-start> 8.1.2, <text:user-defined> 7.5.6, <text:user-field-get> 7.4.9, <text:user-field-input> 7.4.10, <text:user-index-mark> 8.1.7, <text:user-index-mark-end> 8.1.6, <text:user-index-mark-start> 8.1.5, <text:variable-get> 7.4.5, <text:variable-input> 7.4.6, <text:variable-set> 7.4.4 and <text:word-count> 7.5.18.4.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:p> element has mixed content.

5.2 <text:page-sequence>

5.2.1 General

The <text:page-sequence> element contains at least one <text:page> element. If there is more than one <text:page> element, the text:master-page-name attribute of the first <text:page> element specifies the default master style for a document.

The <text:page-sequence> element is usable within the following element: <office:text> 3.4.

The <text:page-sequence> element has no attributes.

The <text:page-sequence> element has the following child element: <text:page> 5.2.2.

5.2.2 <text:page>

The <text:page> element represents a page in a <text:page-sequence> element.

The <text:page> element is usable within the following element: <text:page-sequence> 5.2.

The <text:page> element has the following attribute: text:master-page-name 19.833.

The <text:page> element has no child elements.

5.3 Lists

5.3.1 <text:list>

The <text:list> element represents a list. It may contain a <text:list-header> element, followed by any number of <text:list-item> elements.

Lists may be numbered. The numbering may be restarted with a specific numbering at each list item. Lists may also continue numbering from other lists in order to merge lists into a single, discontinuous list. Whether list numbering is displayed or not depends on the list style being used.

Every list has a list level, which is determined by the nesting of the <text:list> element that represents that list. If a list is not contained in another list, its list level is 1. If a list is contained within another list, the list level of the contained list is the list level of the list in which it is contained incremented by one. If a list is contained in a table cell or text box, its list level returns to 1, even if the table or text box is nested in another list.

Every list with a list level of 1 defines a list and the counter domain for its list items and any sub list of that list. Each sub list starts a counter for its list items and any sub list it may contain.

Every list, including sub lists, may have a list style which is applied to its list items and sub lists. A list style specified for a sub list overrides the list style specified for the list in which the sub list is contained.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:list> element is usable within the following elements: <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:image> 10.4.4, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <draw:text-box> 10.4.3, <office:annotation> 14.1, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10, <style:header-left> 16.12, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:deletion> 5.5.4, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:list-header> 5.3.3, <text:list-item> 5.3.4, <text:note-body> 6.3.4 and <text:section> 5.4.

The <text:list> element has the following attributes: text:continue-list 19.780, text:continue-numbering 19.781, text:style-name 19.874.22 and xml:id 19.914.

The <text:list> element has the following child elements: <text:list-header> 5.3.3 and <text:list-item> 5.3.4.

5.3.2 Default List Style

If a list does not have a style:name attribute and therefore no list style is specified, one of the following actions is taken:

- If the list is contained in another list, the list style defaults to the style of the surrounding list.
- If there is no list style specified for the surrounding list, but the list contains paragraphs that have paragraph styles attached that specify a list style, that list style is used.
- An implementation-dependent default is applied to the list.

To determine which formatting properties are applied to a list, the list level and its style name are taken into account. 16.30.

5.3.3 <text:list-header>

The <text:list-header> element represents a list header and is a type of list item. It contains one or more paragraphs that are displayed before a list. The paragraphs are formatted as list items but they do not have a preceding number or bullet.

The <text:list-header> element is usable within the following element: <text:list> 5.3.1.

The <text:list-header> element has the following attribute: xml:id 19.914.

The <text:list-header> element has the following child elements: <text:h> 5.1.2, <text:list> 5.3.1, <text:number> 6.1.10, <text:p> 5.1.3 and <text:soft-page-break> 5.6.

5.3.4 <text:list-item>

The <text:list-item> element represents an item in a list.

The <text:list-item> element is usable within the following element: <text:list> 5.3.1.

The <text:list-item> element has the following attributes: text:start-value 19.868.3, text:style-override 19.875 and xml:id 19.914.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:list-item> element has the following child elements: <text:h> 5.1.2, <text:list> 5.3.1, <text:number> 6.1.10, <text:p> 5.1.3 and <text:soft-page-break> 5.6.

5.3.5 List Item Style Rules

The first line in a list item is preceded by a bullet or number, depending on the list style assigned to the list. If a list item starts another list and does not contain any text, no bullet or number is displayed.

The list style which is applied to a list need not contain a list level style for the list level the list item specifies. The following rules are applied to determine the list level style in this case

- If the list is contained in another list, the list level style defined in the list style which is applied to the surrounding list for the level of the item is used.
- If the list is not contained in another list or if no list level style is not defined by any of the list styles assigned to surrounding lists, the list level style defined by the default list style is used See 5.3.2.

5.3.6 <text:numbered-paragraph>

The <text:numbered-paragraph> element numbers an individual paragraph, as if it was part of a list at a specified level.

Note: Numbered paragraphs form an equivalent, alternative way of specifying lists. A list in <text:list> representation can be converted into a list in <text:numbered-paragraph> representation and vice versa.

A numbered paragraph can be assigned a list level. A numbered paragraph is equivalent to a list nested to the given level, containing one list item with one paragraph. If no level is given, the numbered paragraph is interpreted as being on level 1.

If a list style is not specified for a numbered paragraph, the list style of the previous numbered paragraph in the same sublist is used. If this paragraph is the first in the sublist, the list style of the previous paragraph in the higher list level is used. If there is no specified list style, the default list style is applied. 5.3.2

If a list level style is missing in the applied list style of a numbered paragraph, the same rules are applied to determine this list level style as for list items.

The text of a formatted number can be included in a <text:number> element.

Note: This text can be used by consumers that do not support numbering.

The <text:numbered-paragraph> element is usable within the following elements: <draw:text-box> 10.4.3, <office:text> 3.4, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:deletion> 5.5.4, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:note-body> 6.3.4 and <text:section> 5.4.

The <text:numbered-paragraph> element has the following attributes: text:continue-numbering 19.781, text:level 19.828, text:list-id 19.829, text:start-value 19.868.6, text:style-name 19.874.25 and xml:id 19.914.

The <text:numbered-paragraph> element has the following child elements: <text:h> 5.1.2, <text:number> 6.1.10 and <text:p> 5.1.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

5.3.7 Numbered Paragraph Style Rules

If a list style is not specified for a numbered paragraph, the list style of the previous numbered paragraph in the same list is used. If this paragraph is the first in the list, the list style of the previous numbered paragraph in a higher list level is used. If there is no specified style available, the default style is applied. 5.3.2

If a list level style is missing in the applied list style of a numbered paragraph, the rules for styles on list items are applied. 5.3.5

5.4 <text:section>

5.4.1 General

The `<text:section>` element represents a named region of content in a document.

Sections specify formatting properties for a region of text or text that is automatically acquired from an external data source or document, or another text section.

Sections support two ways of linking to external content. If a section is linked to another document, the link can be through one of the following:

- A resource identified by an XLink, represented by a `<text:section-source>` element
- Dynamic Data Exchange (DDE), represented by a `<office:dde-source>` element

The `<text:section-source>` or `<office:dde-source>` elements occur only in the alternative and then as the first child element of a `<text:section>` element.

A section that links to external content should contain a full representation of the external content that appears in the section.

Linked external content may have an arbitrary file format. Consumers may process links to external content *and the external content itself to update the content that appears in a section.

The `<text:section>` element is usable within the following elements: `<draw:text-box>` 10.4.3, `<office:text>` 3.4, `<style:footer>` 16.11, `<style:footer-left>` 16.13, `<style:header>` 16.10, `<style:header-left>` 16.12, `<table:covered-table-cell>` 9.1.5, `<table:table-cell>` 9.1.4, `<text:deletion>` 5.5.4, `<text:index-body>` 8.2.2, `<text:index-title>` 8.2.3, `<text:note-body>` 6.3.4 and `<text:section>` 5.4.

The `<text:section>` element has the following attributes: `text:condition` 19.777.7, `text:display` 19.796.6, `text:name` 19.835.14, `text:protected` 19.849, `text:protection-key` 19.850, `text:protection-key-digest-algorithm` 19.851, `text:style-name` 19.874.32 and `xml:id` 19.914.

The `<text:section>` element has the following child elements: `<dr3d:scene>` 10.5.2, `<draw:a>` 10.4.12, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:connector>` 10.3.10, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:g>` 10.3.15, `<draw:line>` 10.3.3, `<draw:measure>` 10.3.12, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2, `<draw:regular-polygon>` 10.3.6, `<office:dde-source>` 14.6.5, `<table:table>` 9.1.2, `<text:alphabetical-index>` 8.8, `<text:bibliography>` 8.9, `<text:change>` 5.5.7.4, `<text:change-end>` 5.5.7.3, `<text:change-start>` 5.5.7.2, `<text:h>` 5.1.2, `<text:illustration-index>` 8.4, `<text:list>` 5.3.1, `<text:numbered-paragraph>` 5.3.6, `<text:object-index>` 8.6,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<text:p> 5.1.3, <text:section> 5.4, <text:section-source> 5.4.2, <text:soft-page-break> 5.6, <text:table-index> 8.5, <text:table-of-content> 8.3 and <text:user-index> 8.7.

5.4.2 <text:section-source>

The <text:section-source> element indicates that a section is a linked section.

The <text:section-source> element is usable within the following element: <text:section> 5.4.

The <text:section-source> element has the following attributes: text:filter-name 19.802, text:section-name 19.861, xlink:href 19.910.37, xlink:show 19.911 and xlink:type 19.913.

The <text:section-source> element has no child elements.

5.5 Change Tracking

5.5.1 <text:tracked-changes>

The <text:tracked-changes> element acts as a container for <text:changed-region> elements that represent changes in a certain scope of an OpenDocument document. This scope is the element in which the <text:tracked-changes> element occurs. Changes in this scope shall be tracked by <text:changed-region> elements contained in the <text:tracked-changes> element in this scope.

If a <text:tracked-changes> element is absent, there are no tracked changes in the corresponding scope. In this case, all change mark elements (5.5.7) in this scope shall be ignored.

The <text:tracked-changes> element is usable within the following elements: <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10 and <style:header-left> 16.12.

The <text:tracked-changes> element has the following attribute: text:track-changes 19.883.

The <text:tracked-changes> element has the following child element: <text:changed-region> 5.5.2.

5.5.2 <text:changed-region>

Each <text:changed-region> element contains a single element, one of <text:insertion>, <text:deletion>, or <text:format-change> that corresponds to a change being tracked within the scope of the <text:tracked-changes> element that contains the <text:changed-region> instance.

The xml:id attribute of the <text:changed-region> is referenced from the <text:change>, <text:change-start> and <text:change-end> elements that identify where the change applies to markup in the scope of the <text:tracked-changes> element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

A <text:changed-region> can be referenced by more than one change, but the corresponding referencing change mark elements shall be of the same change type - insertion, format change or deletion.

The <text:changed-region> element is usable within the following element: <text:tracked-changes> 5.5.1.

The <text:changed-region> element has the following attributes: text:id 19.809.5 and xml:id 19.914.

The <text:changed-region> element has the following child elements: <text:deletion> 5.5.4, <text:format-change> 5.5.5 and <text:insertion> 5.5.3.

5.5.3 <text:insertion>

The <text:insertion> element contains the information that identifies the person responsible for a change and the date of that change. This information may also contain one or more <text:p> elements which contains a comment on the insertion.

The <text:insertion> element's parent <text:changed-region> element has an xml:id or text:id attribute, the value of which binds that parent element to the text:change-id attribute on the <text:change-start> and <text:change-end> elements.

The <text:insertion> element is usable within the following element: <text:changed-region> 5.5.2.

The <text:insertion> element has no attributes.

The <text:insertion> element has the following child element: <office:change-info> 5.5.6.

5.5.4 <text:deletion>

The <text:deletion> element contains information that identifies the person responsible for a deletion and the date of that deletion. This information may also contain one or more <text:p> elements which contains a comment on the deletion. The <text:deletion> element may also contain content that was deleted while change tracking was enabled. The position where the text was deleted is marked by a <text:change> element.

Deleted text is contained in a paragraph element. To reconstruct the original text, the paragraph containing the deleted text is merged with its surrounding paragraph or heading element.

To reconstruct the text before a deletion took place:

- If the change mark is inside a paragraph, insert the content that was deleted, but remove all leading start tags up to and including the first <text:p> element and all trailing end tags up to and including the last </text:p> or </text:h> element. If the last trailing element is a </text:h>, change the end tag </text:p> following this insertion to a </text:h> element.
- If the change mark is inside a heading, insert the content that was deleted, but remove all leading start tags up to and including the first <text:h> element and all trailing end tags up to and including the last </text:h> or </text:p> element. If the last trailing element is a </text:p>, change the end tag </text:h> following this insertion to a </text:p> element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- Otherwise, copy the text content of the <text:deletion> element in place of the change mark.

The <text:deletion> element is usable within the following element: <text:changed-region> 5.5.2.

The <text:deletion> element has no attributes.

The <text:deletion> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:change-info> 5.5.6, <table:table> 9.1.2, <text:alphabetical-index> 8.8, <text:bibliography> 8.9, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:h> 5.1.2, <text:illustration-index> 8.4, <text:list> 5.3.1, <text:numbered-paragraph> 5.3.6, <text:object-index> 8.6, <text:p> 5.1.3, <text:section> 5.4, <text:soft-page-break> 5.6, <text:table-index> 8.5, <text:table-of-content> 8.3 and <text:user-index> 8.7.

5.5.5 <text:format-change>

The <text:format-change> element represents any change in formatting attributes. The region where the change took place is marked by <text:change-start>, <text:change-end> or <text:change> elements.

Note: This element does not contain formatting changes that have taken place.

The <text:format-change> element is usable within the following element: <text:changed-region> 5.5.2.

The <text:format-change> element has no attributes.

The <text:format-change> element has the following child element: <office:change-info> 5.5.6.

5.5.6 <office:change-info>

The <office:change-info> element represents who made a change and when. It may also contain a comment (one or more <text:p> elements) on the change.

The <office:change-info> element is usable within the following elements: <table:cell-content-change> 9.9.17, <table:deletion> 9.9.9, <table:insertion> 9.9.3, <table:movement> 9.9.13, <text:deletion> 5.5.4, <text:format-change> 5.5.5 and <text:insertion> 5.5.3.

The <office:change-info> element has no attributes.

The <office:change-info> element has the following child elements: <dc:creator> 4.3.2.7, <dc:date> 4.3.2.10 and <text:p> 5.1.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

5.5.7 Change Marks

5.5.7.1 General

The change mark elements mark start, end and positions in a text where a change has occurred.

These elements use the `text:change-id` attribute to link to `<text:changed-region>` elements that contain the change information.

5.5.7.2 <text:change-start>

The `<text:change-start>` element marks the start of a region with content where text has been inserted or the format has been changed.

The `<text:change-start>` element is usable within the following elements: `<draw:text-box>` 10.4.3, `<office:text>` 3.4, `<style:footer>` 16.11, `<style:footer-left>` 16.13, `<style:header>` 16.10, `<style:header-left>` 16.12, `<table:covered-table-cell>` 9.1.5, `<table:table-cell>` 9.1.4, `<text:a>` 6.1.8, `<text:deletion>` 5.5.4, `<text:h>` 5.1.2, `<text:index-body>` 8.2.2, `<text:index-title>` 8.2.3, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:note-body>` 6.3.4, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2, `<text:section>` 5.4 and `<text:span>` 6.1.7.

The `<text:change-start>` element has the following attribute: `text:change-id` 19.766.

The `<text:change-start>` element has no child elements.

5.5.7.3 <text:change-end>

The `<text:change-end>` element marks the end of a region with content where text has been inserted or the format has been changed.

The `<text:change-end>` element is usable within the following elements: `<draw:text-box>` 10.4.3, `<office:text>` 3.4, `<style:footer>` 16.11, `<style:footer-left>` 16.13, `<style:header>` 16.10, `<style:header-left>` 16.12, `<table:covered-table-cell>` 9.1.5, `<table:table-cell>` 9.1.4, `<text:a>` 6.1.8, `<text:deletion>` 5.5.4, `<text:h>` 5.1.2, `<text:index-body>` 8.2.2, `<text:index-title>` 8.2.3, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:note-body>` 6.3.4, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2, `<text:section>` 5.4 and `<text:span>` 6.1.7.

The `<text:change-end>` element has the following attribute: `text:change-id` 19.766.

The `<text:change-end>` element has no child elements.

5.5.7.4 <text:change>

The `<text:change>` element marks a position in an empty region where text has been deleted.

The `<text:change>` element is usable within the following elements: `<draw:text-box>` 10.4.3, `<office:text>` 3.4, `<style:footer>` 16.11, `<style:footer-left>` 16.13, `<style:header>` 16.10, `<style:header-left>` 16.12, `<table:covered-table-cell>` 9.1.5, `<table:table-cell>` 9.1.4, `<text:a>` 6.1.8, `<text:deletion>` 5.5.4, `<text:h>` 5.1.2, `<text:index-body>` 8.2.2, `<text:index-title>` 8.2.3, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:note-body>` 6.3.4, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2, `<text:section>` 5.4 and `<text:span>` 6.1.7.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:change> element has the following attribute: text:change-id 19.766.

The <text:change> element has no child elements.

5.6 <text:soft-page-break>

The <text:soft-page-break> element represents a soft page break within or between paragraph elements.

As a child element of a <table:table> element it represents a soft page break between two table rows. It may appear in front of a <table:table-row> element.

The <text:soft-page-break> element is usable within the following elements: <draw:text-box> 10.4.3, <office:text> 3.4, <table:covered-table-cell> 9.1.5, <table:table> 9.1.2, <table:table-cell> 9.1.4, <table:table-header-rows> 9.1.7, <table:table-row-group> 9.1.9, <table:table-rows> 9.1.8, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:list-header> 5.3.3, <text:list-item> 5.3.4, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <text:soft-page-break> element has no attributes.

The <text:soft-page-break> element has no child elements.

5.7 Document Declarations

The following declaration elements appear before the main content element of a document:

- <text:variable-decl> – declarations for variable fields.
- <text:user-field-decl> – declarations for user-defined fields.
- <text:sequence-decl> – declarations for sequence fields.
- <text:dde-connection> – declarations for DDE fields and DDE sections.
- <text:alphabetical-index-auto-mark-file> – declaration for generation of alphabetical indexes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

6 Paragraph Elements Content

6.1 Basic Text Content

6.1.1 General

The paragraph elements <text:p> and <text:h> and their descendant elements contain the text content of any document. The *character content* of a paragraph consists of the character data of the paragraph element and the character data of its descendant elements concatenated in document order, with the following exceptions:

Character data contained in the following elements or their descendant elements are not included in the character content of a paragraph:

- <text:note-body>. 6.3.4.
- <text:ruby-text>. 7.5.19
- <office:annotation>. 14.1
- Drawing shape and frame elements defined in sections 10.3, 10.4, 10.5 and 10.6.

Note: This should significantly ease transformations into other formats, since transformations need not interpret most of the descendant elements of a paragraph element to obtain the character content of a paragraph.

The phrase "document order" when used with reference to an OpenDocument document instance is defined by Section 5.0 Data Model [XPath].

6.1.2 White Space Characters

Consumers shall collapse white space characters that occur in

- a <text:p> or <text:h> element (so called paragraph elements), and
- in their descendant elements, if the OpenDocument schema permits the inclusion of character data for the element itself and all its ancestor elements up to the paragraph element.

Collapsing white space characters is defined by the following algorithm:

1) The following [UNICODE] characters are replaced by a " " (U+0020, SPACE) character:
   - HORIZONTAL TABULATION (U+0009)
   - CARRIAGE RETURN (U+000D)
   - LINE FEED (U+000A)
2) The character data of the paragraph element and of all descendant elements for which the OpenDocument schema permits the inclusion of character data for the element itself and all its ancestor elements up to the paragraph element, is concatenated in document order.
3) Leading " " (U+0020, SPACE) characters at the start of the resulting text and trailing SPACE characters at the end of the resulting text are removed.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

4) Sequences of " " (U+0020, SPACE) characters are replaced by a single " " (U+0020, SPACE) character.

6.1.3 <text:s>

The <text:s> element is used to represent the [UNICODE] character " " (U+0020, SPACE).

This element shall be used to represent the second and all following " " (U+0020, SPACE) characters in a sequence of " " (U+0020, SPACE) characters.

Note: It is not an error if the character preceding the element is not a white space character, but it is good practice to use this element only for the second and all following " " (U+0020, SPACE) characters in a sequence.

The <text:s> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:s> element has the following attribute: text:c 19.763.

The <text:s> element has no child elements.

6.1.4 <text:tab>

The <text:tab> element represents the [UNICODE] tab character (HORIZONTAL TABULATION, U+0009). A <text:tab> element specifies that content immediately following it should begin at the next tab stop.

The <text:tab> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:tab> element has the following attribute: text:tab-ref 19.877.

The <text:tab> element has no child elements.

6.1.5 <text:line-break>

The <text:line-break> element represents a line break.

The <text:line-break> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:line-break> element has no attributes.

The <text:line-break> element has no child elements.

6.1.6 Soft Hyphens, Hyphens, and Non-breaking Spaces

Soft hyphens, hyphens, and non-breaking blanks are represented by [UNICODE] characters.

Table 8 - Unicode characters

The [UNICODE] character...	***Represents...***

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

SOFT HYPHEN (U+00AD)	soft hyphens
NON-BREAKING HYPHEN (U+2011)	non-breaking hyphens
NO-BREAK SPACE (U+00A0)	non-breaking spaces

6.1.7 <text:span>

The <text:span> element represents the application of a style to the character data of a portion of text. The content of this element is the text which uses that text style.

The <text:span> element can be nested.

White space characters contained in this element are collapsed.

The <text:span> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:span> element has the following attributes: text:class-names 19.770.4 and text:style-name 19.874.33.

The <text:span> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:annotation> 14.1, <office:annotation-end> 14.2, <presentation:date-time> 10.9.3.5, <presentation:footer> 10.9.3.3, <presentation:header> 10.9.3.1, <text:a> 6.1.8, <text:alphabetical-index-mark> 8.1.10, <text:alphabetical-index-mark-end> 8.1.9, <text:alphabetical-index-mark-start> 8.1.8, <text:author-initials> 7.3.7.2, <text:author-name> 7.3.7.1, <text:bibliography-mark> 8.1.11, <text:bookmark> 6.2.1.2, <text:bookmark-end> 6.2.1.4, <text:bookmark-ref> 7.7.6, <text:bookmark-start> 6.2.1.3, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:chapter> 7.3.8, <text:character-count> 7.5.18.5, <text:conditional-text> 7.7.3, <text:creation-date> 7.5.3, <text:creation-time> 7.5.4, <text:creator> 7.5.17, <text:database-display> 7.6.3, <text:database-name> 7.6.7, <text:database-next> 7.6.4, <text:database-row-number> 7.6.6, <text:database-row-select> 7.6.5, <text:date> 7.3.2, <text:dde-connection> 7.7.12, <text:description> 7.5.5, <text:editing-cycles> 7.5.13, <text:editing-duration> 7.5.14, <text:execute-macro> 7.7.10, <text:expression> 7.4.14, <text:file-name> 7.3.9, <text:hidden-paragraph> 7.7.11, <text:hidden-text> 7.7.4, <text:image-count> 7.5.18.7, <text:initial-creator> 7.5.2, <text:keywords> 7.5.12, <text:line-break> 6.1.5, <text:measure> 7.7.13, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:modification-date> 7.5.16, <text:modification-time> 7.5.15, <text:note> 6.3.2, <text:note-ref> 7.7.7, <text:object-count> 7.5.18.8, <text:page-continuation> 7.3.5, <text:page-count> 7.5.18.2, <text:page-number> 7.3.4, <text:page-variable-get> 7.7.1.3, <text:page-variable-set> 7.7.1.2, <text:paragraph-count> 7.5.18.3, <text:placeholder> 7.7.2, <text:print-date> 7.5.8, <text:printed-by> 7.5.9, <text:print-time> 7.5.7, <text:reference-mark> 6.2.2.2, <text:reference-mark-end> 6.2.2.4, <text:reference-mark-start> 6.2.2.3, <text:reference-ref> 7.7.5, <text:ruby> 6.4, <text:s> 6.1.3, <text:script> 7.7.9,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<text:sender-city> 7.3.6.13, <text:sender-company> 7.3.6.10, <text:sender-country> 7.3.6.15, <text:sender-email> 7.3.6.7, <text:sender-fax> 7.3.6.9, <text:sender-firstname> 7.3.6.2, <text:sender-initials> 7.3.6.4, <text:sender-lastname> 7.3.6.3, <text:sender-phone-private> 7.3.6.8, <text:sender-phone-work> 7.3.6.11, <text:sender-position> 7.3.6.6, <text:sender-postal-code> 7.3.6.14, <text:sender-state-or-province> 7.3.6.16, <text:sender-street> 7.3.6.12, <text:sender-title> 7.3.6.5, <text:sequence> 7.4.13, <text:sequence-ref> 7.7.8, <text:sheet-name> 7.3.11, <text:soft-page-break> 5.6, <text:span> 6.1.7, <text:subject> 7.5.11, <text:tab> 6.1.4, <text:table-count> 7.5.18.6, <text:table-formula> 7.7.14, <text:template-name> 7.3.10, <text:text-input> 7.4.15, <text:time> 7.3.3, <text:title> 7.5.10, <text:toc-mark> 8.1.4, <text:toc-mark-end> 8.1.3, <text:toc-mark-start> 8.1.2, <text:user-defined> 7.5.6, <text:user-field-get> 7.4.9, <text:user-field-input> 7.4.10, <text:user-index-mark> 8.1.7, <text:user-index-mark-end> 8.1.6, <text:user-index-mark-start> 8.1.5, <text:variable-get> 7.4.5, <text:variable-input> 7.4.6, <text:variable-set> 7.4.4 and <text:word-count> 7.5.18.4.

The <text:span> element has mixed content.

6.1.8 <text:a>

The <text:a> element represents a hyperlink.

The anchor of a hyperlink is composed of the character data contained by the <text:a> element and any of its descendant elements which define character data of the surrounding paragraph elements.

The <text:a> element is usable within the following elements: <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:a> element has the following attributes: office:name 19.376.9, office:target-frame-name 19.381, office:title 19.383, text:style-name 19.874.2, text:visited-style-name 19.901, xlink:actuate 19.909, xlink:href 19.910.33, xlink:show 19.911 and xlink:type 19.913.

The <text:a> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:annotation> 14.1, <office:annotation-end> 14.2, <office:event-listeners> 10.3.19, <presentation:date-time> 10.9.3.5, <presentation:footer> 10.9.3.3, <presentation:header> 10.9.3.1, <text:alphabetical-index-mark> 8.1.10, <text:alphabetical-index-mark-end> 8.1.9, <text:alphabetical-index-mark-start> 8.1.8, <text:author-initials> 7.3.7.2, <text:author-name> 7.3.7.1, <text:bibliography-mark> 8.1.11, <text:bookmark> 6.2.1.2, <text:bookmark-end> 6.2.1.4, <text:bookmark-ref> 7.7.6, <text:bookmark-start> 6.2.1.3, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:chapter> 7.3.8, <text:character-count> 7.5.18.5, <text:conditional-text> 7.7.3, <text:creation-date> 7.5.3, <text:creation-time> 7.5.4, <text:creator> 7.5.17, <text:database-display> 7.6.3, <text:database-name> 7.6.7, <text:database-next> 7.6.4, <text:database-row-number> 7.6.6, <text:database-row-select>

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.6.5, <text:date> 7.3.2, <text:dde-connection> 7.7.12, <text:description> 7.5.5, <text:editing-cycles> 7.5.13, <text:editing-duration> 7.5.14, <text:execute-macro> 7.7.10, <text:expression> 7.4.14, <text:file-name> 7.3.9, <text:hidden-paragraph> 7.7.11, <text:hidden-text> 7.7.4, <text:image-count> 7.5.18.7, <text:initial-creator> 7.5.2, <text:keywords> 7.5.12, <text:line-break> 6.1.5, <text:measure> 7.7.13, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:modification-date> 7.5.16, <text:modification-time> 7.5.15, <text:note> 6.3.2, <text:note-ref> 7.7.7, <text:object-count> 7.5.18.8, <text:page-continuation> 7.3.5, <text:page-count> 7.5.18.2, <text:page-number> 7.3.4, <text:page-variable-get> 7.7.1.3, <text:page-variable-set> 7.7.1.2, <text:paragraph-count> 7.5.18.3, <text:placeholder> 7.7.2, <text:print-date> 7.5.8, <text:printed-by> 7.5.9, <text:print-time> 7.5.7, <text:reference-mark> 6.2.2.2, <text:reference-mark-end> 6.2.2.4, <text:reference-mark-start> 6.2.2.3, <text:reference-ref> 7.7.5, <text:ruby> 6.4, <text:s> 6.1.3, <text:script> 7.7.9, <text:sender-city> 7.3.6.13, <text:sender-company> 7.3.6.10, <text:sender-country> 7.3.6.15, <text:sender-email> 7.3.6.7, <text:sender-fax> 7.3.6.9, <text:sender-firstname> 7.3.6.2, <text:sender-initials> 7.3.6.4, <text:sender-lastname> 7.3.6.3, <text:sender-phone-private> 7.3.6.8, <text:sender-phone-work> 7.3.6.11, <text:sender-position> 7.3.6.6, <text:sender-postal-code> 7.3.6.14, <text:sender-state-or-province> 7.3.6.16, <text:sender-street> 7.3.6.12, <text:sender-title> 7.3.6.5, <text:sequence> 7.4.13, <text:sequence-ref> 7.7.8, <text:sheet-name> 7.3.11, <text:soft-page-break> 5.6, <text:span> 6.1.7, <text:subject> 7.5.11, <text:tab> 6.1.4, <text:table-count> 7.5.18.6, <text:table-formula> 7.7.14, <text:template-name> 7.3.10, <text:text-input> 7.4.15, <text:time> 7.3.3, <text:title> 7.5.10, <text:toc-mark> 8.1.4, <text:toc-mark-end> 8.1.3, <text:toc-mark-start> 8.1.2, <text:user-defined> 7.5.6, <text:user-field-get> 7.4.9, <text:user-field-input> 7.4.10, <text:user-index-mark> 8.1.7, <text:user-index-mark-end> 8.1.6, <text:user-index-mark-start> 8.1.5, <text:variable-get> 7.4.5, <text:variable-input> 7.4.6, <text:variable-set> 7.4.4 and <text:word-count> 7.5.18.4.

The <text:a> element has mixed content.

6.1.9 <text:meta>

The <text:meta> element represents portions of text that have in content metadata attached. See 19.905.

The <text:meta> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:meta> element has the following attributes: xhtml:about 19.905, xhtml:content 19.906, xhtml:datatype 19.907, xhtml:property 19.908 and xml:id 19.914.

The <text:meta> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:annotation> 14.1, <office:annotation-end> 14.2, <presentation:date-time> 10.9.3.5, <presentation:footer> 10.9.3.3, <presentation:header> 10.9.3.1,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<text:a> 6.1.8, <text:alphabetical-index-mark> 8.1.10, <text:alphabetical-index-mark-end> 8.1.9, <text:alphabetical-index-mark-start> 8.1.8, <text:author-initials> 7.3.7.2, <text:author-name> 7.3.7.1, <text:bibliography-mark> 8.1.11, <text:bookmark> 6.2.1.2, <text:bookmark-end> 6.2.1.4, <text:bookmark-ref> 7.7.6, <text:bookmark-start> 6.2.1.3, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:chapter> 7.3.8, <text:character-count> 7.5.18.5, <text:conditional-text> 7.7.3, <text:creation-date> 7.5.3, <text:creation-time> 7.5.4, <text:creator> 7.5.17, <text:database-display> 7.6.3, <text:database-name> 7.6.7, <text:database-next> 7.6.4, <text:database-row-number> 7.6.6, <text:database-row-select> 7.6.5, <text:date> 7.3.2, <text:dde-connection> 7.7.12, <text:description> 7.5.5, <text:editing-cycles> 7.5.13, <text:editing-duration> 7.5.14, <text:execute-macro> 7.7.10, <text:expression> 7.4.14, <text:file-name> 7.3.9, <text:hidden-paragraph> 7.7.11, <text:hidden-text> 7.7.4, <text:image-count> 7.5.18.7, <text:initial-creator> 7.5.2, <text:keywords> 7.5.12, <text:line-break> 6.1.5, <text:measure> 7.7.13, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:modification-date> 7.5.16, <text:modification-time> 7.5.15, <text:note> 6.3.2, <text:note-ref> 7.7.7, <text:object-count> 7.5.18.8, <text:page-continuation> 7.3.5, <text:page-count> 7.5.18.2, <text:page-number> 7.3.4, <text:page-variable-get> 7.7.1.3, <text:page-variable-set> 7.7.1.2, <text:paragraph-count> 7.5.18.3, <text:placeholder> 7.7.2, <text:print-date> 7.5.8, <text:printed-by> 7.5.9, <text:print-time> 7.5.7, <text:reference-mark> 6.2.2.2, <text:reference-mark-end> 6.2.2.4, <text:reference-mark-start> 6.2.2.3, <text:reference-ref> 7.7.5, <text:ruby> 6.4, <text:s> 6.1.3, <text:script> 7.7.9, <text:sender-city> 7.3.6.13, <text:sender-company> 7.3.6.10, <text:sender-country> 7.3.6.15, <text:sender-email> 7.3.6.7, <text:sender-fax> 7.3.6.9, <text:sender-firstname> 7.3.6.2, <text:sender-initials> 7.3.6.4, <text:sender-lastname> 7.3.6.3, <text:sender-phone-private> 7.3.6.8, <text:sender-phone-work> 7.3.6.11, <text:sender-position> 7.3.6.6, <text:sender-postal-code> 7.3.6.14, <text:sender-state-or-province> 7.3.6.16, <text:sender-street> 7.3.6.12, <text:sender-title> 7.3.6.5, <text:sequence> 7.4.13, <text:sequence-ref> 7.7.8, <text:sheet-name> 7.3.11, <text:soft-page-break> 5.6, <text:span> 6.1.7, <text:subject> 7.5.11, <text:tab> 6.1.4, <text:table-count> 7.5.18.6, <text:table-formula> 7.7.14, <text:template-name> 7.3.10, <text:text-input> 7.4.15, <text:time> 7.3.3, <text:title> 7.5.10, <text:toc-mark> 8.1.4, <text:toc-mark-end> 8.1.3, <text:toc-mark-start> 8.1.2, <text:user-defined> 7.5.6, <text:user-field-get> 7.4.9, <text:user-field-input> 7.4.10, <text:user-index-mark> 8.1.7, <text:user-index-mark-end> 8.1.6, <text:user-index-mark-start> 8.1.5, <text:variable-get> 7.4.5, <text:variable-input> 7.4.6, <text:variable-set> 7.4.4 and <text:word-count> 7.5.18.4.

The <text:meta> element has mixed content.

6.1.10 <text:number>

The <text:number> element contains the text of a formatted number which is present when a list style is applied to an element whose corresponding list level style specifies that the list label is a number. This text may be used by consumers that do not support the automatic generation of numbering but should be ignored by consumers that do support it.

This element has no attributes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:number> element is usable within the following elements: <text:h> 5.1.2, <text:list-header> 5.3.3, <text:list-item> 5.3.4 and <text:numbered-paragraph> 5.3.6.

The <text:number> element has no attributes.

The <text:number> element has no child elements.

The <text:number> element has content of data type string 18.2.

6.2 Bookmarks and References

6.2.1 Bookmarks

6.2.1.1 General

Bookmarks can either mark a text position or a text range. A text position is a position inside the text content of a document. A text range starts at any text position and ends at another text position.

Bookmarks which mark a text range support overlapping references.

6.2.1.2 <text:bookmark>

The <text:bookmark> element marks a text position.

The <text:bookmark> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:bookmark> element has the following attributes: text:name 19.835.4 and xml:id 19.914.

The <text:bookmark> element has no child elements.

6.2.1.3 <text:bookmark-start>

The <text:bookmark-start> element marks the start position of a bookmark in a text range.

For every <text:bookmark-start> element, there shall be a <text:bookmark-end> element in the same document using the same value for the text:name attribute. Every <text:bookmark-start> element shall precede the <text:bookmark-end> element with the same value for its text:name attribute.

The <text:bookmark-start> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:bookmark-start> element has the following attributes: text:name 19.835.6, xhtml:about 19.905, xhtml:content 19.906, xhtml:datatype 19.907, xhtml:property 19.908 and xml:id 19.914.

The <text:bookmark-start> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

6.2.1.4 <text:bookmark-end>

The <text:bookmark-end> element marks the end position of a bookmark in a text range.

For every <text:bookmark-end> element, there shall be a preceding <text:bookmark-start> element in the same document using the same value for the text:name attribute.

The <text:bookmark-end> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:bookmark-end> element has the following attribute: text:name 19.835.5.

The <text:bookmark-end> element has no child elements.

6.2.2 References

6.2.2.1 General

There are two types of reference marks:

- A point reference

  A point reference marks a position in text and is represented by a single <text:reference-mark> element.

- A range reference

  A range reference marks a range of characters in text and is represented by two elements; a <text:reference-mark-start> element to mark the start of the range and a following <text:reference-mark-end> element to mark the end of the range.

Every reference is identified by the value of its text:name attribute, which shall be unique. In a range reference, the start and end elements shall use the same attribute value.

Range references support overlapping references.

6.2.2.2 <text:reference-mark>

The <text:reference-mark> element represents a point reference.

The <text:reference-mark> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:reference-mark> element has the following attribute: text:name 19.835.11.

The <text:reference-mark> element has no child elements.

6.2.2.3 <text:reference-mark-start>

The <text:reference-mark-start> element represent the start of a range reference.

The <text:reference-mark-start> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:reference-mark-start> element has the following attribute: text:name 19.835.13.

The <text:reference-mark-start> element has no child elements.

6.2.2.4 <text:reference-mark-end>

The <text:reference-mark-end> element represent the end of a range reference.

The <text:reference-mark-end> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:reference-mark-end> element has the following attribute: text:name 19.835.12.

The <text:reference-mark-end> element has no child elements.

6.3 Notes

6.3.1 General

Notes consist of a <text:note> element which occurs in the text stream at the position to which the note is anchored. The numbering and rendering of notes is specified by a <text:notes-configuration> element, which occurs inside an <office:styles> element.

6.3.2 <text:note>

The <text:note> element represents text notes which are attached to a text position.

The <text:note> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:note> element has the following attributes: text:id 19.809.7 and text:note-class 19.837.

The <text:note> element has the following child elements: <text:note-body> 6.3.4 and <text:note-citation> 6.3.3.

6.3.3 <text:note-citation>

The <text:note-citation> element contains a citation, either as a formatted number or a string.

The <text:note-citation> element is usable within the following element: <text:note> 6.3.2.

The <text:note-citation> element has the following attribute: text:label 19.826.

The <text:note-citation> element has no child elements.

The <text:note-citation> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

6.3.4 <text:note-body>

The <text:note-body> element contains the content of a note. It does not have any attributes.

Note: The schema allows for the inclusion of notes into the note body. While this may be reasonable for note types, it is not reasonable for footnotes and endnotes. Conforming consumers need not supportnotes inside notes.

The <text:note-body> element is usable within the following element: <text:note> 6.3.2.

The <text:note-body> element has no attributes.

The <text:note-body> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <table:table> 9.1.2, <text:alphabetical-index> 8.8, <text:bibliography> 8.9, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:h> 5.1.2, <text:illustration-index> 8.4, <text:list> 5.3.1, <text:numbered-paragraph> 5.3.6, <text:object-index> 8.6, <text:p> 5.1.3, <text:section> 5.4, <text:soft-page-break> 5.6, <text:table-index> 8.5, <text:table-of-content> 8.3 and <text:user-index> 8.7.

6.4 <text:ruby>

6.4.1 General

A ruby is additional text that is displayed above or below a base text. The purpose of a ruby is to annotate a base text or provide information about its pronunciation.

The <text:ruby> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:ruby> element has the following attribute: text:style-name 19.874.30.

The <text:ruby> element has the following child elements: <text:ruby-base> 6.4.2 and <text:ruby-text> 6.4.3.

6.4.2 <text:ruby-base>

The <text:ruby-base> element contains the text that is to be annotated. It contains any paragraph element content, like text spans. The element's text:style-name attribute references a ruby style that specifies formatting attributes of the ruby.

The <text:ruby-base> element is usable within the following element: <text:ruby> 6.4.

The <text:ruby-base> element has no attributes.

The <text:ruby-base> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure>

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:annotation> 14.1, <office:annotation-end> 14.2, <presentation:date-time> 10.9.3.5, <presentation:footer> 10.9.3.3, <presentation:header> 10.9.3.1, <text:a> 6.1.8, <text:alphabetical-index-mark> 8.1.10, <text:alphabetical-index-mark-end> 8.1.9, <text:alphabetical-index-mark-start> 8.1.8, <text:author-initials> 7.3.7.2, <text:author-name> 7.3.7.1, <text:bibliography-mark> 8.1.11, <text:bookmark> 6.2.1.2, <text:bookmark-end> 6.2.1.4, <text:bookmark-ref> 7.7.6, <text:bookmark-start> 6.2.1.3, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:chapter> 7.3.8, <text:character-count> 7.5.18.5, <text:conditional-text> 7.7.3, <text:creation-date> 7.5.3, <text:creation-time> 7.5.4, <text:creator> 7.5.17, <text:database-display> 7.6.3, <text:database-name> 7.6.7, <text:database-next> 7.6.4, <text:database-row-number> 7.6.6, <text:database-row-select> 7.6.5, <text:date> 7.3.2, <text:dde-connection> 7.7.12, <text:description> 7.5.5, <text:editing-cycles> 7.5.13, <text:editing-duration> 7.5.14, <text:execute-macro> 7.7.10, <text:expression> 7.4.14, <text:file-name> 7.3.9, <text:hidden-paragraph> 7.7.11, <text:hidden-text> 7.7.4, <text:image-count> 7.5.18.7, <text:initial-creator> 7.5.2, <text:keywords> 7.5.12, <text:line-break> 6.1.5, <text:measure> 7.7.13, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:modification-date> 7.5.16, <text:modification-time> 7.5.15, <text:note> 6.3.2, <text:note-ref> 7.7.7, <text:object-count> 7.5.18.8, <text:page-continuation> 7.3.5, <text:page-count> 7.5.18.2, <text:page-number> 7.3.4, <text:page-variable-get> 7.7.1.3, <text:page-variable-set> 7.7.1.2, <text:paragraph-count> 7.5.18.3, <text:placeholder> 7.7.2, <text:print-date> 7.5.8, <text:printed-by> 7.5.9, <text:print-time> 7.5.7, <text:reference-mark> 6.2.2.2, <text:reference-mark-end> 6.2.2.4, <text:reference-mark-start> 6.2.2.3, <text:reference-ref> 7.7.5, <text:ruby> 6.4, <text:s> 6.1.3, <text:script> 7.7.9, <text:sender-city> 7.3.6.13, <text:sender-company> 7.3.6.10, <text:sender-country> 7.3.6.15, <text:sender-email> 7.3.6.7, <text:sender-fax> 7.3.6.9, <text:sender-firstname> 7.3.6.2, <text:sender-initials> 7.3.6.4, <text:sender-lastname> 7.3.6.3, <text:sender-phone-private> 7.3.6.8, <text:sender-phone-work> 7.3.6.11, <text:sender-position> 7.3.6.6, <text:sender-postal-code> 7.3.6.14, <text:sender-state-or-province> 7.3.6.16, <text:sender-street> 7.3.6.12, <text:sender-title> 7.3.6.5, <text:sequence> 7.4.13, <text:sequence-ref> 7.7.8, <text:sheet-name> 7.3.11, <text:soft-page-break> 5.6, <text:span> 6.1.7, <text:subject> 7.5.11, <text:tab> 6.1.4, <text:table-count> 7.5.18.6, <text:table-formula> 7.7.14, <text:template-name> 7.3.10, <text:text-input> 7.4.15, <text:time> 7.3.3, <text:title> 7.5.10, <text:toc-mark> 8.1.4, <text:toc-mark-end> 8.1.3, <text:toc-mark-start> 8.1.2, <text:user-defined> 7.5.6, <text:user-field-get> 7.4.9, <text:user-field-input> 7.4.10, <text:user-index-mark> 8.1.7, <text:user-index-mark-end> 8.1.6, <text:user-index-mark-start> 8.1.5, <text:variable-get> 7.4.5, <text:variable-input> 7.4.6, <text:variable-set> 7.4.4 and <text:word-count> 7.5.18.4.

The <text:ruby-base> element has mixed content.

6.4.3 <text:ruby-text>

The <text:ruby-text> element contains an annotation text. It may contain only plain text. The element's text:style-name attribute references a text style that specifies further formatting attributes used for the annotation text.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:ruby-text> element is usable within the following element: <text:ruby> 6.4.

The <text:ruby-text> element has the following attribute: text:style-name 19.874.31.

The <text:ruby-text> element has no child elements.

The <text:ruby-text> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7 Text Fields

7.1 General

OpenDocument text documents or OpenDocument text content embedded in other types of documents may contain variable text elements called fields. Fields are commonly used for:

- Page numbers
  A page number field displays the number of the page on which it appears.
- Creation dates
  A creation date field displays the date on which a document was created.

7.2 Common Characteristics of Field Elements

Each field type is represented by a corresponding element type. The content of an element is a textual representation of the current field value as it would be displayed or printed.

The value of a field is stored in an attribute. Storage of the value enables recalculation of the presentation of a field.

Note: For string values, if a value is identical to a presentation, the value attribute can be omitted to avoid duplicate storage of information.

The presentation of information in a field is determined by the style applied to the field.

7.3 Document Fields

7.3.1 General

OpenDocument fields display information about the current document or about a specific part of the current document.,

7.3.2 <text:date>

The `<text:date>` element displays a date, by default this is the current date. The date can be adjusted to display a date other than the current date.

The `<text:date>` element is usable within the following elements: `<text:a>` 6.1.8, `<text:h>` 5.1.2, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2 and `<text:span>` 6.1.7.

The `<text:date>` element has the following attributes: `style:data-style-name` 19.469.7, `text:date-adjust` 19.792, `text:date-value` 19.793 and `text:fixed` 19.803.

The `<text:date>` element has no child elements.

The `<text:date>` element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.3.3 <text:time>

The <text:time> element displays a time, by default this is the current time.

The <text:time> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:time> element has the following attributes: style:data-style-name 19.469.16, text:fixed 19.803, text:time-adjust 19.880 and text:time-value 19.881.

The <text:time> element has no child elements.

The <text:time> element has character data content.

7.3.4 <text:page-number>

The <text:page-number> element displays the current page number.

If a number style is not specified for page numbers, the default is the number style of the current page style.

Note: The <text:page-count> element displays the total number of pages in a document. 7.5.18.2

The <text:page-number> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:page-number> element has the following attributes: style:num-format 19.500, style:num-letter-sync 19.501, text:fixed 19.803, text:page-adjust 19.845.2 and text:select-page 19.863.3.

The <text:page-number> element has no child elements.

The <text:page-number> element has character data content.

7.3.5 <text:page-continuation>

The <text:page-continuation> element displays a continuation reminder printed at the bottom of the page in addition to the page number.

The <text:page-continuation> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:page-continuation> element has the following attributes: text:select-page 19.863.2 and text:string-value 19.871.4.

The <text:page-continuation> element has no child elements.

The <text:page-continuation> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.3.6 Subsequent Author Fields

7.3.6.1 General

Subsequent author fields capture information about second and following authors for a document.

Note: In OpenDocument 1.0/1.1, these fields were referenced as “sender” fields and that terminology still appears in the names of these elements.

If a subsequent author field is marked fixed using the `text:fixed` attribute, the original information in that field is preserved. 19.803 Otherwise, the information is updated each time the file is edited.

7.3.6.2 <text:sender-firstname>

The `<text:sender-firstname>` element represents the first name of a subsequent author.

The `<text:sender-firstname>` element is usable within the following elements: `<text:a>` 6.1.8, `<text:h>` 5.1.2, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2 and `<text:span>` 6.1.7.

The `<text:sender-firstname>` element has the following attribute: `text:fixed` 19.803.

The `<text:sender-firstname>` element has no child elements.

The `<text:sender-firstname>` element has character data content.

7.3.6.3 <text:sender-lastname>

The `<text:sender-lastname>` element represents the last name of a subsequent author.

The `<text:sender-lastname>` element is usable within the following elements: `<text:a>` 6.1.8, `<text:h>` 5.1.2, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2 and `<text:span>` 6.1.7.

The `<text:sender-lastname>` element has the following attribute: `text:fixed` 19.803.

The `<text:sender-lastname>` element has no child elements.

The `<text:sender-lastname>` element has character data content.

7.3.6.4 <text:sender-initials>

The `<text:sender-initials>` element represents the initials of a subsequent author.

The `<text:sender-initials>` element is usable within the following elements: `<text:a>` 6.1.8, `<text:h>` 5.1.2, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2 and `<text:span>` 6.1.7.

The `<text:sender-initials>` element has the following attribute: `text:fixed` 19.803.

The `<text:sender-initials>` element has no child elements.

The `<text:sender-initials>` element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.3.6.5 <text:sender-title>

The <text:sender-title> element represents the title of a subsequent author.

The <text:sender-title> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sender-title> element has the following attribute: text:fixed 19.803.

The <text:sender-title> element has no child elements.

The <text:sender-title> element has character data content.

7.3.6.6 <text:sender-position>

The <text:sender-position> element represents the position of a subsequent author.

The <text:sender-position> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sender-position> element has the following attribute: text:fixed 19.803.

The <text:sender-position> element has no child elements.

The <text:sender-position> element has character data content.

7.3.6.7 <text:sender-email>

The <text:sender-email> element represents the email address of a subsequent author.

The <text:sender-email> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sender-email> element has the following attribute: text:fixed 19.803.

The <text:sender-email> element has no child elements.

The <text:sender-email> element has character data content.

7.3.6.8 <text:sender-phone-private>

The <text:sender-phone-private> element represents the private telephone number of a subsequent author.

The <text:sender-phone-private> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sender-phone-private> element has the following attribute: text:fixed 19.803.

The <text:sender-phone-private> element has no child elements.

The <text:sender-phone-private> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.3.6.9 <text:sender-fax>

The <text:sender-fax> element represents the facsimile number of a subsequent author.

The <text:sender-fax> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sender-fax> element has the following attribute: text:fixed 19.803.

The <text:sender-fax> element has no child elements.

The <text:sender-fax> element has character data content.

7.3.6.10 <text:sender-company>

The <text:sender-company> element represents the name of the company that employs a subsequent author.

The <text:sender-company> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sender-company> element has the following attribute: text:fixed 19.803.

The <text:sender-company> element has no child elements.

The <text:sender-company> element has character data content.

7.3.6.11 <text:sender-phone-work>

The <text:sender-phone-work> element represents the office telephone number of a subsequent author.

The <text:sender-phone-work> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sender-phone-work> element has the following attribute: text:fixed 19.803.

The <text:sender-phone-work> element has no child elements.

The <text:sender-phone-work> element has character data content.

7.3.6.12 <text:sender-street>

The <text:sender-street> element represents the street address of a subsequent author.

The <text:sender-street> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sender-street> element has the following attribute: text:fixed 19.803.

The <text:sender-street> element has no child elements.

The <text:sender-street> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.3.6.13 <text:sender-city>

The <text:sender-city> element represents the city name of the address of a subsequent author.

The <text:sender-city> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sender-city> element has the following attribute: text:fixed 19.803.

The <text:sender-city> element has no child elements.

The <text:sender-city> element has character data content.

7.3.6.14 <text:sender-postal-code>

The <text:sender-postal-code> element represents the postal code of the address of a subsequent author.

The <text:sender-postal-code> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sender-postal-code> element has the following attribute: text:fixed 19.803.

The <text:sender-postal-code> element has no child elements.

The <text:sender-postal-code> element has character data content.

7.3.6.15 <text:sender-country>

The <text:sender-country> element represents the country name of the address of a subsequent author.

The <text:sender-country> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sender-country> element has the following attribute: text:fixed 19.803.

The <text:sender-country> element has no child elements.

The <text:sender-country> element has character data content.

7.3.6.16 <text:sender-state-or-province>

The <text:sender-state-or-province> element represents the state or province name of the address of a subsequent author, if applicable.

The <text:sender-state-or-province> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sender-state-or-province> element has the following attribute: text:fixed 19.803.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:sender-state-or-province> element has no child elements.

The <text:sender-state-or-province> element has character data content.

7.3.7 Author Fields

7.3.7.1 <text:author-name>

The <text:author-name> element represents the full name of the author of a document.

The <text:author-name> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:author-name> element has the following attribute: text:fixed 19.803.

The <text:author-name> element has no child elements.

The <text:author-name> element has character data content.

7.3.7.2 <text:author-initials>

The <text:author-initials> element represents the initials of the author of a document.

The <text:author-initials> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:author-initials> element has the following attribute: text:fixed 19.803.

The <text:author-initials> element has no child elements.

The <text:author-initials> element has character data content.

7.3.8 <text:chapter>

The <text:chapter> element represents a field that displays one of the following:

- The name of the current chapter
- The number of the current chapter
- Both the name and number of the current chapter

If this element is placed inside a header or footer, it displays the current chapter name or number on every page.

The <text:chapter> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:chapter> element has the following attributes: text:display 19.796.2 and text:outline-level 19.844.3.

The <text:chapter> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:chapter> element has character data content.

7.3.9 <text:file-name>

The <text:file-name> element represents a field that displays the name of a file that is being edited.

The <text:file-name> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:file-name> element has the following attributes: text:display 19.796.4 and text:fixed 19.803.

The <text:file-name> element has no child elements.

The <text:file-name> element has character data content.

7.3.10 <text:template-name>

The <text:template-name> element represents a field that displays information about the document template in use.

The <text:template-name> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:template-name> element has the following attribute: text:display 19.796.8.

The <text:template-name> element has no child elements.

The <text:template-name> element has character data content.

7.3.11 <text:sheet-name>

The <text:sheet-name> element displays represents the name of a sheet that is currently being edited in a Spreadsheet document.

The <text:sheet-name> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sheet-name> element has no attributes.

The <text:sheet-name> element has no child elements.

The <text:sheet-name> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.4 Variable Fields

7.4.1 General

OpenDocument documents can contain variables, which are processed or displayed using variable fields. In an OpenDocument file, variable declarations shall precede in document order any use of those variable declarations.

There are three types of variables:

- **Simple variables**

  Simple variables, or variables, can take different values at different positions in a document. Simple variables can be set using either setter or input fields. Setter fields contain an expression, which is used to compute the new value of the variable. Input fields prompt the user for the new value.

  Note: Simple variables can be used to display different text in recurring elements, such as headers or footers.

- **User variables**

  If a user variable is set anywhere within the document, all fields in a document that display that user variable have the same value. The value of the user variable can only be set after the variable is declared.

  Note: In a consumer's user interface, a user variable can be set at any occurrence of a user field, or by using user variable input fields.

- **Sequence variables**

  Sequence variables are used to number items in an OpenDocument text document

  Note: Sequence variables can be used to number images or tables in a text.

The value of a sequence variable is initialized to 0 (zero) by its declaration.

Variables shall be declared before they can be used. The OpenDocument elements for declaring variables are described in sections 7.4.3, 7.4.8 and 7.4.12.

The display of variables is determined by styles which are specified by the element that defines the variable.

7.4.2 <text:variable-decls>

The `<text:variable-decls>` element is a container for `<text:variable-decl>` elements.

The `<text:variable-decls>` element is usable within the following elements: `<office:chart>` 3.8, `<office:drawing>` 3.5, `<office:presentation>` 3.6, `<office:spreadsheet>` 3.7, `<office:text>` 3.4, `<style:footer>` 16.11, `<style:footer-left>` 16.13, `<style:header>` 16.10 and `<style:header-left>` 16.12.

The `<text:variable-decls>` element has no attributes.

The `<text:variable-decls>` element has the following child element: `<text:variable-decl>` 7.4.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.4.3 <text:variable-decl>

The <text:variable-decl> element is used to declare simple variables. This element specifies the name and the value type of a variable.

The <text:variable-decl> element is usable within the following element: <text:variable-decls> 7.4.2.

The <text:variable-decl> element has the following attributes: office:value-type 19.385 and text:name 19.835.25.

The <text:variable-decl> element has no child elements.

7.4.4 <text:variable-set>

The <text:variable-set> element represents a simple variable.

The <text:variable-set> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:variable-set> element has the following attributes: office:boolean-value 19.367, office:currency 19.369, office:date-value 19.370, office:string-value 19.379, office:time-value 19.382, office:value 19.384, office:value-type 19.385, style:data-style-name 19.469.22, text:display 19.796.12, text:formula 19.805 and text:name 19.835.24.

The <text:variable-set> element has no child elements.

The <text:variable-set> element has character data content.

7.4.5 <text:variable-get>

The <text:variable-get> element sets the display of the value of a simple variable. The value of this element is the value of the last preceding <text:variable-set> element with an identical value for its text:name attribute.

If there is no preceding <text:variable-set> element with an identical value for its text:name attribute the value of a <text:variable-get> field is undefined.

The <text:variable-get> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:variable-get> element has the following attributes: style:data-style-name 19.469.20, text:display 19.796.10 and text:name 19.835.26.

The <text:variable-get> element has no child elements.

The <text:variable-get> element has character data content.

7.4.6 <text:variable-input>

The <text:variable-input> element represents user supplied variable values. This element can be empty if its text:display attribute is set to none.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:variable-input> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:variable-input> element has the following attributes: office:value-type 19.385, style:data-style-name 19.469.21, text:description 19.795, text:display 19.796.11 and text:name 19.835.27.

The <text:variable-input> element has no child elements.

The <text:variable-input> element has character data content.

7.4.7 <text:user-field-decls>

The <text:user-field-decls> element is a container for <text:user-field-decl> elements.

The <text:user-field-decls> element is usable within the following elements: <office:chart> 3.8, <office:drawing> 3.5, <office:presentation> 3.6, <office:spreadsheet> 3.7, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10 and <style:header-left> 16.12.

The <text:user-field-decls> element has no attributes.

The <text:user-field-decls> element has the following child element: <text:user-field-decl> 7.4.8.

7.4.8 <text:user-field-decl>

The <text:user-field-decl> element is used to specify user variable values that are displayed using the <text:user-field-get> element.

The <text:user-field-decl> element is usable within the following element: <text:user-field-decls> 7.4.7.

The <text:user-field-decl> element has the following attributes: office:boolean-value 19.367, office:currency 19.369, office:date-value 19.370, office:string-value 19.379, office:time-value 19.382, office:value 19.384, office:value-type 19.385, text:formula 19.805 and text:name 19.835.20.

The <text:user-field-decl> element has no child elements.

7.4.9 <text:user-field-get>

The <text:user-field-get> element displays the content of a user variable. The value of this element is the value of a <text:user-field-decl> element with a text:name attribute value that matches the text:name attribute of this element.

The <text:user-field-get> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:user-field-get> element has the following attributes: style:data-style-name 19.469.18, text:display 19.796.9 and text:name 19.835.21.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:user-field-get> element has no child elements.

The <text:user-field-get> element has character data content.

7.4.10 <text:user-field-input>

The <text:user-field-input> element is an alternative method of displaying user variables. The value of this element is the value of a <text:user-field-decl> element with a text:name attribute value that matches the text:name attribute of this element.

This element can be empty if the text:display attribute is set to none.

The <text:user-field-input> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:user-field-input> element has the following attributes: style:data-style-name 19.469.19, text:description 19.795 and text:name 19.835.22.

The <text:user-field-input> element has no child elements.

The <text:user-field-input> element has character data content.

7.4.11 <text:sequence-decls>

The <text:sequence-decls> element is a container for <text:sequence-decl> elements.

The <text:sequence-decls> element is usable within the following elements: <office:chart> 3.8, <office:drawing> 3.5, <office:presentation> 3.6, <office:spreadsheet> 3.7, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10 and <style:header-left> 16.12.

The <text:sequence-decls> element has no attributes.

The <text:sequence-decls> element has the following child element: <text:sequence-decl> 7.4.12.

7.4.12 <text:sequence-decl>

The <text:sequence-decl> element is used to declare sequence variables used to number items within an OpenDocument text document.

Note: Sequence variables are commonly used for sequential numbering. However, expression formulas can be included in sequence fields to support more advanced sequences.

The <text:sequence-decl> element is usable within the following element: <text:sequence-decls> 7.4.11.

The <text:sequence-decl> element has the following attributes: text:display-outline-level 19.798, text:name 19.835.16 and text:separation-character 19.864.

The <text:sequence-decl> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.4.13 <text:sequence>

A <text:sequence> element specifies a sequence field.

A sequence field changes the value of a sequence variable by a specified formula and displays the changed value of the sequence variable in a specified format.

Note: Sequence variables and fields are used to number repeating document elements such as pages, tables or images. In such cases, the formula could be: "sequenceVariableName + 1." A sequence variable can be set to a specific value or not changed at all.

The <text:sequence> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sequence> element has the following attributes: style:num-format 19.500, style:num-letter-sync 19.501, text:formula 19.805, text:name 19.835.15 and text:ref-name 19.853.5.

The <text:sequence> element has no child elements.

The <text:sequence> element has character data content.

7.4.14 <text:expression>

The <text:expression> element represents expressions that are evaluated and the resulting value displayed.

The <text:expression> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:expression> element has the following attributes: office:boolean-value 19.367, office:currency 19.369, office:date-value 19.370, office:string-value 19.379, office:time-value 19.382, office:value 19.384, office:value-type 19.385, style:data-style-name 19.469.9, text:display 19.796.3 and text:formula 19.805.

The <text:expression> element has no child elements.

The <text:expression> element has character data content.

7.4.15 <text:text-input>

The <text:text-input> element is a text input field. A text input field is used in a user interface to prompt a user to input text. This text is stored and displayed as the content of this element until it is replaced by a user.

The <text:text-input> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:text-input> element has the following attribute: text:description 19.795.

The <text:text-input> element has no child elements.

The <text:text-input> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.5 Metadata Fields

7.5.1 General

Metadata field elements display meta information about a document.

All metadata field elements can be marked as fixed using the `text:fixed` attribute. 19.803

7.5.2 <text:initial-creator>

The `<text:initial-creator>` element displays the value contained by the `<meta:initial-creator>` element of a document. 4.3.2.6

The `<text:initial-creator>` element is usable within the following elements: `<text:a>` 6.1.8, `<text:h>` 5.1.2, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2 and `<text:span>` 6.1.7.

The `<text:initial-creator>` element has the following attribute: `text:fixed` 19.803.

The `<text:initial-creator>` element has no child elements.

The `<text:initial-creator>` element has character data content.

7.5.3 <text:creation-date>

The `<text:creation-date>` element displays the value contained by the `<meta:creation-date>` element of a document. 4.3.2.9

The `<text:creation-date>` element is usable within the following elements: `<text:a>` 6.1.8, `<text:h>` 5.1.2, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2 and `<text:span>` 6.1.7.

The `<text:creation-date>` element has the following attributes: `style:data-style-name` 19.469.4, `text:date-value` 19.793 and `text:fixed` 19.803.

The `<text:creation-date>` element has no child elements.

The `<text:creation-date>` element has character data content.

7.5.4 <text:creation-time>

The `<text:creation-time>` element represents the time at which a document was created.

The `<text:creation-time>` element is usable within the following elements: `<text:a>` 6.1.8, `<text:h>` 5.1.2, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2 and `<text:span>` 6.1.7.

The `<text:creation-time>` element has the following attributes: `style:data-style-name` 19.469.5, `text:fixed` 19.803 and `text:time-value` 19.881.

The `<text:creation-time>` element has no child elements.

The `<text:creation-time>` element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.5.5 <text:description>

The <text:description> element displays the content contained by the <dc:description> element of a document. 4.3.2.3

The <text:description> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:description> element has the following attribute: text:fixed 19.803.

The <text:description> element has no child elements.

The <text:description> element has character data content.

7.5.6 <text:user-defined>

The <text:user-defined> element displays the value contained by a <meta:user-defined> element of a document. 4.3.3

Note: The link between a <text:user-defined> element and a <meta:user-defined> element is established by the text:name and meta:name attributes, respectively, containing the same value.

The <text:user-defined> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:user-defined> element has the following attributes: office:boolean-value 19.367, office:date-value 19.370, office:string-value 19.379, office:time-value 19.382, office:value 19.384, style:data-style-name 19.469.17, text:fixed 19.803 and text:name 19.835.19.

The <text:user-defined> element has no child elements.

The <text:user-defined> element has character data content.

7.5.7 <text:print-time>

The <text:print-time> element represents the time at which a document was last printed.

The <text:print-time> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:print-time> element has the following attributes: style:data-style-name 19.469.14, text:fixed 19.803 and text:time-value 19.881.

The <text:print-time> element has no child elements.

The <text:print-time> element has character data content.

7.5.8 <text:print-date>

The <text:print-date> element displays the value contained by the <meta:print-date> element of a document. 4.3.2.11

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:print-date> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:print-date> element has the following attributes: style:data-style-name 19.469.13, text:date-value 19.793 and text:fixed 19.803.

The <text:print-date> element has no child elements.

The <text:print-date> element has character data content.

7.5.9 <text:printed-by>

The <text:printed-by> element displays the value contained by the <meta:printed-by> element of a document. 4.3.2.8

The <text:printed-by> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:printed-by> element has the following attribute: text:fixed 19.803.

The <text:printed-by> element has no child elements.

The <text:printed-by> element has character data content.

7.5.10 <text:title>

The <text:title> element displays the value contained by the <dc:title> element of a document. 4.3.2.2

The <text:title> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:title> element has the following attribute: text:fixed 19.803.

The <text:title> element has no child elements.

The <text:title> element has character data content.

7.5.11 <text:subject>

The <text:subject> element displays the values contained by the <dc:subject> element of a document. 4.3.2.4

The <text:subject> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:subject> element has the following attribute: text:fixed 19.803.

The <text:subject> element has no child elements.

The <text:subject> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.5.12 <text:keywords>

The <text:keywords> element displays a list of keywords contained in the <meta:keyword> elements of a document.

The format of a list of keywords is implementation-dependent.

The <text:keywords> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:keywords> element has the following attribute: text:fixed 19.803.

The <text:keywords> element has no child elements.

The <text:keywords> element has character data content.

7.5.13 <text:editing-cycles>

The <text:editing-cycles> element displays the value contained by the <meta:editing-cycles> element of a document. 4.3.2.16

The <text:editing-cycles> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:editing-cycles> element has the following attribute: text:fixed 19.803.

The <text:editing-cycles> element has no child elements.

The <text:editing-cycles> element has character data content.

7.5.14 <text:editing-duration>

The <text:editing-duration> element displays the value contained by the <meta:editing-duration> element of a document.

The <text:editing-duration> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:editing-duration> element has the following attributes: style:data-style-name 19.469.8, text:duration 19.799 and text:fixed 19.803.

The <text:editing-duration> element has no child elements.

The <text:editing-duration> element has character data content.

7.5.15 <text:modification-time>

The <text:modification-time> element represents the time at which a document was last modified.

This element displays the time information portion of the value of the <dc:date> element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:modification-time> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:modification-time> element has the following attributes: style:data-style-name 19.469.12, text:fixed 19.803 and text:time-value 19.881.

The <text:modification-time> element has no child elements.

The <text:modification-time> element has character data content.

7.5.16 <text:modification-date>

The <text:modification-date> element displays the value contained by the <dc:date> element of a document. 4.3.2.10

The <text:modification-date> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:modification-date> element has the following attributes: style:data-style-name 19.469.11, text:date-value 19.793 and text:fixed 19.803.

The <text:modification-date> element has no child elements.

The <text:modification-date> element has character data content.

7.5.17 <text:creator>

The <text:creator> element displays the value contained by the <dc:creator> element of a document. 4.3.2.7

The <text:creator> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:creator> element has the following attribute: text:fixed 19.803.

The <text:creator> element has no child elements.

The <text:creator> element has character data content.

7.5.18 Document Statistics Fields

7.5.18.1 General

The contents of <text:word-count> and <text:character-count> elements are locale specific and are not defined by OpenDocument.

7.5.18.2 <text:page-count>

The <text:page-count> element displays the value of the meta:page-count attribute of the <meta:document-statistic> element of a document. 19.332

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:page-count> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:page-count> element has the following attributes: style:num-format 19.500 and style:num-letter-sync 19.501.

The <text:page-count> element has no child elements.

The <text:page-count> element has character data content.

7.5.18.3 <text:paragraph-count>

The <text:paragraph-count> element displays the value of the meta:paragraph-count attribute of the <meta:document-statistic> element of a document. 19.333

The <text:paragraph-count> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:paragraph-count> element has the following attributes: style:num-format 19.500 and style:num-letter-sync 19.501.

The <text:paragraph-count> element has no child elements.

The <text:paragraph-count> element has character data content.

7.5.18.4 <text:word-count>

The <text:word-count> element displays the value of the meta:word-count attribute of the <meta:document-statistic> element of a document. 19.339

The <text:word-count> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:word-count> element has the following attributes: style:num-format 19.500 and style:num-letter-sync 19.501.

The <text:word-count> element has no child elements.

The <text:word-count> element has character data content.

7.5.18.5 <text:character-count>

The <text:character-count> element displays the value of the meta:character-count attribute of the <meta:document-statistic> element of a document. 19.322

The <text:character-count> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:character-count> element has the following attributes: style:num-format 19.500 and style:num-letter-sync 19.501.

The <text:character-count> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:character-count> element has character data content.

7.5.18.6 <text:table-count>

The <text:table-count> element displays the value of the meta:table-count attribute of the <meta:document-statistic> element of a document. 19.337

The <text:table-count> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:table-count> element has the following attributes: style:num-format 19.500 and style:num-letter-sync 19.501.

The <text:table-count> element has no child elements.

The <text:table-count> element has character data content.

7.5.18.7 <text:image-count>

The <text:image-count> element displays the value of the meta:image-count attribute of the <meta:document-statistic> element of a document. 19.327

The <text:image-count> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:image-count> element has the following attributes: style:num-format 19.500 and style:num-letter-sync 19.501.

The <text:image-count> element has no child elements.

The <text:image-count> element has character data content.

7.5.18.8 <text:object-count>

The <text:object-count> element displays the value of the meta:object-count attribute of the <meta:document-statistic> element of a document. 19.330

The <text:object-count> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:object-count> element has the following attributes: style:num-format 19.500 and style:num-letter-sync 19.501.

The <text:object-count> element has no child elements.

The <text:object-count> element has character data content.

7.5.19 <text:meta-field>

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:meta-field> element represents content from a metadata source. The mixed content of this element should be generated from the metadata source. The source of the metadata and the means of generation of the mixed content is implementation-dependent. The <text:meta-field> element may contain any paragraph content.

Note: Alterations of the element's mixed content may be lost if the mixed content is subsequently refreshed from a metadata source.

The <text:meta-field> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:meta-field> element has the following attributes: style:data-style-name 19.469.10 and xml:id 19.914.

The <text:meta-field> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:annotation> 14.1, <office:annotation-end> 14.2, <presentation:date-time> 10.9.3.5, <presentation:footer> 10.9.3.3, <presentation:header> 10.9.3.1, <text:a> 6.1.8, <text:alphabetical-index-mark> 8.1.10, <text:alphabetical-index-mark-end> 8.1.9, <text:alphabetical-index-mark-start> 8.1.8, <text:author-initials> 7.3.7.2, <text:author-name> 7.3.7.1, <text:bibliography-mark> 8.1.11, <text:bookmark> 6.2.1.2, <text:bookmark-end> 6.2.1.4, <text:bookmark-ref> 7.7.6, <text:bookmark-start> 6.2.1.3, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:chapter> 7.3.8, <text:character-count> 7.5.18.5, <text:conditional-text> 7.7.3, <text:creation-date> 7.5.3, <text:creation-time> 7.5.4, <text:creator> 7.5.17, <text:database-display> 7.6.3, <text:database-name> 7.6.7, <text:database-next> 7.6.4, <text:database-row-number> 7.6.6, <text:database-row-select> 7.6.5, <text:date> 7.3.2, <text:dde-connection> 7.7.12, <text:description> 7.5.5, <text:editing-cycles> 7.5.13, <text:editing-duration> 7.5.14, <text:execute-macro> 7.7.10, <text:expression> 7.4.14, <text:file-name> 7.3.9, <text:hidden-paragraph> 7.7.11, <text:hidden-text> 7.7.4, <text:image-count> 7.5.18.7, <text:initial-creator> 7.5.2, <text:keywords> 7.5.12, <text:line-break> 6.1.5, <text:measure> 7.7.13, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:modification-date> 7.5.16, <text:modification-time> 7.5.15, <text:note> 6.3.2, <text:note-ref> 7.7.7, <text:object-count> 7.5.18.8, <text:page-continuation> 7.3.5, <text:page-count> 7.5.18.2, <text:page-number> 7.3.4, <text:page-variable-get> 7.7.1.3, <text:page-variable-set> 7.7.1.2, <text:paragraph-count> 7.5.18.3, <text:placeholder> 7.7.2, <text:print-date> 7.5.8, <text:printed-by> 7.5.9, <text:print-time> 7.5.7, <text:reference-mark> 6.2.2.2, <text:reference-mark-end> 6.2.2.4, <text:reference-mark-start> 6.2.2.3, <text:reference-ref> 7.7.5, <text:ruby> 6.4, <text:s> 6.1.3, <text:script> 7.7.9, <text:sender-city> 7.3.6.13, <text:sender-company> 7.3.6.10, <text:sender-country> 7.3.6.15, <text:sender-email> 7.3.6.7, <text:sender-fax> 7.3.6.9, <text:sender-firstname> 7.3.6.2, <text:sender-initials> 7.3.6.4, <text:sender-lastname> 7.3.6.3, <text:sender-phone-private> 7.3.6.8, <text:sender-phone-work> 7.3.6.11, <text:sender-position> 7.3.6.6, <text:sender-postal-code> 7.3.6.14, <text:sender-state-or-province> 7.3.6.16, <text:sender-street> 7.3.6.12, <text:sender-title> 7.3.6.5, <text:sequence> 7.4.13, <text:sequence-ref> 7.7.8, <text:sheet-name> 7.3.11, <text:soft-page-break> 5.6, <text:span>

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

6.1.7, <text:subject> 7.5.11, <text:tab> 6.1.4, <text:table-count> 7.5.18.6, <text:table-formula> 7.7.14, <text:template-name> 7.3.10, <text:text-input> 7.4.15, <text:time> 7.3.3, <text:title> 7.5.10, <text:toc-mark> 8.1.4, <text:toc-mark-end> 8.1.3, <text:toc-mark-start> 8.1.2, <text:user-defined> 7.5.6, <text:user-field-get> 7.4.9, <text:user-field-input> 7.4.10, <text:user-index-mark> 8.1.7, <text:user-index-mark-end> 8.1.6, <text:user-index-mark-start> 8.1.5, <text:variable-get> 7.4.5, <text:variable-input> 7.4.6, <text:variable-set> 7.4.4 and <text:word-count> 7.5.18.4.

The <text:meta-field> element has mixed content.

7.6 Database Fields

7.6.1 General

Documents can reference databases and display database information as text content. To display database information, the OpenDocument schema uses a group of text fields, collectively called database fields. Consumers may use database tables from SQL servers, therefore database fields can be used to access any SQL database, provided that the appropriate drivers are available.

A database may contain the following components:

- Tables, which store data.
- Queries, which extract a subset of data from one or more tables.
- Forms, which present data. 12.25.2
- Reports, which summarize database content. 12.25.3

Database fields operate on a set of database rows, the so called *current selection*, which is either a database table, or the result of a database query. The current selection is determined by the data source information that is contained in database fields. The current selection is retrieved once per document and data source, regardless of the number of database fields that are associated with a data source.

Database fields display data contained in a particular database row within the current selection. The row within the current selection is controlled by database fields and is known as the current row.

7.6.2 <form:connection-resource>

The <form:connection-resource> element specifies a source database.

The <form:connection-resource> element is usable within the following elements: <form:form> 13.3, <text:database-display> 7.6.3, <text:database-name> 7.6.7, <text:database-next> 7.6.4, <text:database-row-number> 7.6.6 and <text:database-row-select> 7.6.5.

The <form:connection-resource> element has the following attribute: xlink:href 19.910.20.

The <form:connection-resource> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.6.3 <text:database-display>

The <text:database-display> element represents data from the current database row.

The <text:database-display> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:database-display> element has the following attributes: style:data-style-name 19.469.6, text:column-name 19.771, text:database-name 19.791, text:table-name 19.878 and text:table-type 19.879.

The <text:database-display> element has the following child element: <form:connection-resource> 7.6.2.

The <text:database-display> element has character data content.

7.6.4 <text:database-next>

The <text:database-next> element selects the database row following the one currently displayed in a <text:database-display> field.

The <text:database-next> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:database-next> element has the following attributes: text:condition 19.777.3, text:database-name 19.791, text:table-name 19.878 and text:table-type 19.879.

The <text:database-next> element has the following child element: <form:connection-resource> 7.6.2.

7.6.5 <text:database-row-select>

The <text:database-row-select> element selects a specific row from a current selection.

The <text:database-row-select> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:database-row-select> element has the following attributes: text:condition 19.777.4, text:database-name 19.791, text:row-number 19.859, text:table-name 19.878 and text:table-type 19.879.

The <text:database-row-select> element has the following child element: <form:connection-resource> 7.6.2.

7.6.6 <text:database-row-number>

The <text:database-row-number> element displays the current row number for a given table. The element displays the row number from a database and not the row number of a current selection that is used as an attribute value in the <text:database-row-select> element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:database-row-number> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:database-row-number> element has the following attributes: style:num-format 19.500, style:num-letter-sync 19.501, text:database-name 19.791, text:table-name 19.878, text:table-type 19.879 and text:value 19.900.

The <text:database-row-number> element has the following child element: <form:connection-resource> 7.6.2.

The <text:database-row-number> element has character data content.

7.6.7 <text:database-name>

The <text:database-name> element displays the database and table name of the last used table.

The <text:database-name> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:database-name> element has the following attributes: text:database-name 19.791, text:table-name 19.878 and text:table-type 19.879.

The <text:database-name> element has the following child element: <form:connection-resource> 7.6.2.

The <text:database-name> element has character data content.

7.7 More Fields

7.7.1 Page Variable Fields

7.7.1.1 General

Page variables enable an alternative page numbering to be defined for documents. There is only one page variable, and it is set by any set page variable field in the document. The calculation of a page variable is controlled by the text:active attribute

7.7.1.2 <text:page-variable-set>

The <text:page-variable-set> element is used to set a page variable.

The <text:page-variable-set> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:page-variable-set> element has the following attributes: text:active 19.750 and text:page-adjust 19.845.3.

The <text:page-variable-set> element has no child elements.

The <text:page-variable-set> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.7.1.3 <text:page-variable-get>

The <text:page-variable-get> element displays the value of a page variable.

If the text:active attribute 19.750, has the value of false, the <text:page-variable-get> element will have no display for that page.

The <text:page-variable-get> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:page-variable-get> element has the following attributes: style:num-format 19.500 and style:num-letter-sync 19.501.

The <text:page-variable-get> element has no child elements.

The <text:page-variable-get> element has character data content.

7.7.2 <text:placeholder>

The <text:placeholder> element is a placeholder for replacement by content of a particular type as specified in the mandatory text:placeholder-type attribute.

OpenDocument Consumers that support the <text:placeholder> element shall use the text:description attribute value in presenting the placeholder with its text content and in a manner that indicates it is for replacement by content of the specified type.

The <text:placeholder> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:placeholder> element has the following attributes: text:description 19.795 and text:placeholder-type 19.847.

The <text:placeholder> element has no child elements.

The <text:placeholder> element has character data content.

7.7.3 <text:conditional-text>

The <text:conditional-text> element specifies a condition for display of one text string or another. If the condition is true, one of the text strings is displayed. If the condition is false, the other text string is displayed.

The <text:conditional-text> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:conditional-text> element has the following attributes: text:condition 19.777.2, text:current-value 19.785, text:string-value-if-false 19.872 and text:string-value-if-true 19.873.

The <text:conditional-text> element has no child elements.

The <text:conditional-text> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.7.4 <text:hidden-text>

The <text:hidden-text> element hides the text it contains when a specified condition is true. If its text:condition attribute is missing or evaluates to false, the text content is displayed.

The <text:hidden-text> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:hidden-text> element has the following attributes: text:condition 19.777.6, text:is-hidden 19.815 and text:string-value 19.871.3.

The <text:hidden-text> element has no child elements.

The <text:hidden-text> element has character data content.

7.7.5 <text:reference-ref>

The <text:reference-ref> element represents a field that references a <text:reference-mark-start> or <text:reference-mark> element. Its text:reference-format attribute specifies what is displayed from the referenced element.

The <text:reference-ref> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:reference-ref> element has the following attributes: text:reference-format 19.854 and text:ref-name 19.853.4.

The <text:reference-ref> element has no child elements.

The <text:reference-ref> element has character data content.

7.7.6 <text:bookmark-ref>

The <text:bookmark-ref> element represents a field that references a <text:bookmark-start> or <text:bookmark> element. Its text:reference-format attribute specifies what is displayed from the referenced element.

The <text:bookmark-ref> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:bookmark-ref> element has the following attributes: text:reference-format 19.854 and text:ref-name 19.853.2.

The <text:bookmark-ref> element has no child elements.

The <text:bookmark-ref> element has character data content.

7.7.7 <text:note-ref>

The <text:note-ref> element represents a field that references a <text:note> element. Its text:reference-format attribute specifies what is displayed from the referenced element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:note-ref> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:note-ref> element has the following attributes: text:note-class 19.837, text:reference-format 19.854 and text:ref-name 19.853.3.

The <text:note-ref> element has no child elements.

The <text:note-ref> element has character data content.

7.7.8 <text:sequence-ref>

The <text:sequence-ref> element represents a field that references a <text:sequence> element. Its text:reference-format attribute specifies what is displayed from the referenced element.

The <text:sequence-ref> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:sequence-ref> element has the following attributes: text:reference-format 19.854 and text:ref-name 19.853.6.

The <text:sequence-ref> element has no child elements.

The <text:sequence-ref> element has character data content.

7.7.9 <text:script>

The <text:script> element represents a field that stores scripts or sections of scripts. The field can be used to store and edit scripts that are attached to the document.

Note: The primary purpose of this field is to provide an equivalent to the <script> element in [HTML4], so that the content of a <script> element in HTML can be imported, edited, and exported using office application software.

The source code for the script can be stored in one of the following ways:

- The <text:script> element contains the source code.
- The source code is stored in an external file. The xlink:href attribute specifies the location of the source file.

The element should have either an xlink:href attribute or content, but not both.

The <text:script> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:script> element has the following attributes: script:language 19.430, xlink:href 19.910.36 and xlink:type 19.913.

The <text:script> element has no child elements.

The <text:script> element has character data content. Character data content is only permitted if a xlink:href attribute is not present.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.7.10 <text:execute-macro>

The <text:execute-macro> element represents a field that contains the name of a macro that is executed when the field is activated. The element may contain a text description of the macro. The name of the macro to be executed is specified by the text:name attribute.

The <text:execute-macro> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:execute-macro> element has the following attribute: text:name 19.835.7.

The <text:execute-macro> element has the following child element: <office:event-listeners> 10.3.19.

The <text:execute-macro> element has character data content.

7.7.11 <text:hidden-paragraph>

The <text:hidden-paragraph> element is a field that represents a condition. If the condition evaluates to false, the paragraph where this element appears is displayed unless the paragraph is enclosed in any other hiding element. If the condition evaluates to true, the paragraph is hidden unless the paragraph contains another <text:hidden-paragraph> element whose condition evaluates to false.

The <text:hidden-paragraph> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:hidden-paragraph> element has the following attributes: text:condition 19.777.5 and text:is-hidden 19.815.

The <text:hidden-paragraph> element has no child elements.

The <text:hidden-paragraph> element has character data content.

7.7.12 <text:dde-connection>

The <text:dde-connection> element represents a field that is information from a DDE connection. The content of this field is the last data that was received from a DDE connection. This is used as the content of this field if the DDE connection cannot be accessed.

See 14.6 for the use of DDE connections.

The <text:dde-connection> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:dde-connection> element has the following attribute: text:connection-name 19.778.

The <text:dde-connection> element has no child elements.

The <text:dde-connection> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

7.7.13 <text:measure>

The <text:measure> element represents a field that displays measure text. It can only be used within text that is contained in measure drawing objects.

The <text:measure> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:measure> element has the following attribute: text:kind 19.825.

The <text:measure> element has no child elements.

The <text:measure> element has character data content.

7.7.14 <text:table-formula> (deprecated)

The <text:table-formula> element field is deprecated. It stores a formula to be used in tables.

The <text:table-formula> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:table-formula> element has the following attributes: style:data-style-name 19.469.15, text:display 19.796.7 and text:formula 19.805.

The <text:table-formula> element has no child elements.

The <text:table-formula> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

8 Text Indexes

8.1 Index Marks

8.1.1 General

OpenDocument text documents may contain automatically generated indexes. An index contains a sorted list of items of a specified type, where the sorting and the type of items are determined by the type of index.

There are three types of index marks that correspond to the three types of index that make use of index marks. The three types of index marks are:

- Table of contents index marks
- User-defined index marks
- Alphabetical index marks

The rules for index marks are:

- Index marks are represented by start and end elements or by non-enclosing index point elements.
- Start and end index elements use the `text:id` attribute to match start and end elements for an index mark.
- Start and end index elements shall be contained in the same paragraph, with the start element occurring first in document order.
- The attributes associated with an index mark are attached to the start element.
- The text between the start and end index elements is the text of the index entry.
- Index marks can overlap.

8.1.2 <text:toc-mark-start>

The `<text:toc-mark-start>` element marks the start of a table of contents index entry.

The `<text:toc-mark-start>` element is usable within the following elements: `<text:a>` 6.1.8, `<text:h>` 5.1.2, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2 and `<text:span>` 6.1.7.

The `<text:toc-mark-start>` element has the following attributes: `text:id` 19.809.10 and `text:outline-level` 19.844.11.

The `<text:toc-mark-start>` element has no child elements.

8.1.3 <text:toc-mark-end>

The `<text:toc-mark-end>` element marks the end of a table of contents index entry.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:toc-mark-end> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:toc-mark-end> element has the following attribute: text:id 19.809.9.

The <text:toc-mark-end> element has no child elements.

8.1.4 <text:toc-mark>

The <text:toc-mark> element represents a table of content index mark that does not enclose content.

The <text:toc-mark> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:toc-mark> element has the following attributes: text:outline-level 19.844.10 and text:string-value 19.871.5.

The <text:toc-mark> element has no child elements.

8.1.5 <text:user-index-mark-start>

The <text:user-index-mark-start> element marks the start of a user-defined index entry.

The <text:user-index-mark-start> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:user-index-mark-start> element has the following attributes: text:id 19.809.12, text:index-name 19.811 and text:outline-level 19.844.13.

The <text:user-index-mark-start> element has no child elements.

8.1.6 <text:user-index-mark-end>

The <text:user-index-mark-end> element marks the end of the user-defined index entry.

The <text:user-index-mark-end> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:user-index-mark-end> element has the following attribute: text:id 19.809.11.

The <text:user-index-mark-end> element has no child elements.

8.1.7 <text:user-index-mark>

The <text:user-index-mark> element represents a user defined index mark that does not enclose content.

The <text:user-index-mark> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:user-index-mark> element has the following attributes: text:index-name 19.811, text:outline-level 19.844.7 and text:string-value 19.871.6.

The <text:user-index-mark> element has no child elements.

8.1.8 <text:alphabetical-index-mark-start>

The <text:alphabetical-index-mark-start> element marks the start of an alphabetical index entry.

The <text:alphabetical-index-mark-start> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:alphabetical-index-mark-start> element has the following attributes: text:id 19.809.4, text:key1 19.821, text:key1-phonetic 19.823, text:key2 19.822, text:key2-phonetic 19.824, text:main-entry 19.831 and text:string-value-phonetic 19.870.

The <text:alphabetical-index-mark-start> element has no child elements.

8.1.9 <text:alphabetical-index-mark-end>

The <text:alphabetical-index-mark-end> element marks the end of an alphabetical index entry.

The <text:alphabetical-index-mark-end> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:alphabetical-index-mark-end> element has the following attribute: text:id 19.809.3.

The <text:alphabetical-index-mark-end> element has no child elements.

8.1.10 <text:alphabetical-index-mark>

The <text:user-index-mark> element represents a user defined index mark that does not enclose content.

The <text:alphabetical-index-mark> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:alphabetical-index-mark> element has the following attributes: text:key1 19.821, text:key1-phonetic 19.823, text:key2 19.822, text:key2-phonetic 19.824, text:main-entry 19.831, text:string-value 19.871.2 and text:string-value-phonetic 19.870.

The <text:alphabetical-index-mark> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

8.1.11 <text:bibliography-mark>

The <text:bibliography-mark> element contains the text and information for a bibliography index entry.

The <text:bibliography-mark> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <text:bibliography-mark> element has the following attributes: text:address 19.751, text:annote 19.755, text:author 19.756, text:bibliography-type 19.758, text:booktitle 19.759, text:chapter 19.767, text:custom1 19.786, text:custom2 19.787, text:custom3 19.788, text:custom4 19.789, text:custom5 19.790, text:edition 19.800, text:editor 19.801, text:howpublished 19.807, text:identifier 19.810, text:institution 19.814, text:isbn 19.817, text:issn 19.818, text:journal 19.819, text:month 19.834, text:note 19.836, text:number 19.838, text:organizations 19.843, text:pages 19.846, text:publisher 19.852, text:report-type 19.856, text:school 19.860, text:series 19.862, text:title 19.882, text:url 19.884, text:volume 19.902 and text:year 19.903.

The <text:bibliography-mark> element has no child elements.

The <text:bibliography-mark> element has character data content.

8.2 Index Structure

8.2.1 General

An index consists of two parts: the index source, and the index body.

The index source is specific to the type of index it is being used for. It contains the information necessary to generate the index content.

8.2.2 <text:index-body>

The <text:index-body> element contains an index.

The <text:index-body> element is used for all types of indexes. It contains the index content generated to form the index.

The <text:index-body> element is usable within the following elements: <text:alphabetical-index> 8.8, <text:bibliography> 8.9, <text:illustration-index> 8.4, <text:object-index> 8.6, <text:table-index> 8.5, <text:table-of-content> 8.3 and <text:user-index> 8.7.

The <text:index-body> element has no attributes.

The <text:index-body> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <table:table> 9.1.2, <text:alphabetical-index> 8.8, <text:bibliography> 8.9,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:h> 5.1.2, <text:illustration-index> 8.4, <text:index-title> 8.2.3, <text:list> 5.3.1, <text:numbered-paragraph> 5.3.6, <text:object-index> 8.6, <text:p> 5.1.3, <text:section> 5.4, <text:soft-page-break> 5.6, <text:table-index> 8.5, <text:table-of-content> 8.3 and <text:user-index> 8.7.

8.2.3 <text:index-title>

The <text:index-title> element contains the title of an index.

The <text:index-title> element is usable within the following elements: <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10, <style:header-left> 16.12, <text:index-body> 8.2.2 and <text:index-title> 8.2.3.

The <text:index-title> element has the following attributes: text:name 19.835.9, text:protected 19.849, text:protection-key 19.850, text:protection-key-digest-algorithm 19.851, text:style-name 19.874.19 and xml:id 19.914.

The <text:index-title> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <table:table> 9.1.2, <text:alphabetical-index> 8.8, <text:bibliography> 8.9, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:h> 5.1.2, <text:illustration-index> 8.4, <text:index-title> 8.2.3, <text:list> 5.3.1, <text:numbered-paragraph> 5.3.6, <text:object-index> 8.6, <text:p> 5.1.3, <text:section> 5.4, <text:soft-page-break> 5.6, <text:table-index> 8.5, <text:table-of-content> 8.3 and <text:user-index> 8.7.

8.3 <text:table-of-content>

8.3.1 General

The <text:table-of-content> element represents a table of contents for a document.

The items that can be listed in a table of contents are:

- Headings (as defined by the outline structure of the document), up to a selected level.
- Table of contents index marks.
- Paragraphs formatted with specified paragraph styles.

Note: Paragraphs may be selected for inclusion in a table of contents based on their styles. Selection is based on a paragraph's style matching a style specified by the <text:index-source-styles> child element of a <text:table-of-content-source> child element of a <text:table-of-content> element, when the text:use-index-source-styles attribute of the child <text:index-source-styles> element has the value true.

The <text:table-of-content> element is usable within the following elements: <draw:text-box> 10.4.3, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10, <style:header-left> 16.12, <table:covered-

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:deletion> 5.5.4, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:note-body> 6.3.4 and <text:section> 5.4.

The <text:table-of-content> element has the following attributes: text:name 19.835.17, text:protected 19.849, text:protection-key 19.850, text:protection-key-digest-algorithm 19.851, text:style-name 19.874.35 and xml:id 19.914.

The <text:table-of-content> element has the following child elements: <text:index-body> 8.2.2 and <text:table-of-content-source> 8.3.2.

8.3.2 <text:table-of-content-source>

The <text:table-of-content-source> element specifies how a table of contents is generated. It also specifies the styles to be applied to index entries.

The <text:table-of-content-source> element is usable within the following element: <text:table-of-content> 8.3.

The <text:table-of-content-source> element has the following attributes: text:index-scope 19.812, text:outline-level 19.844.9, text:relative-tab-stop-position 19.855, text:use-index-marks 19.890, text:use-index-source-styles 19.891 and text:use-outline-level 19.896.

The <text:table-of-content-source> element has the following child elements: <text:index-source-styles> 8.10, <text:index-title-template> 8.12 and <text:table-of-content-entry-template> 8.3.3.

8.3.3 <text:table-of-content-entry-template>

The <text:table-of-content-entry-template> element specifies the format of an index entry for a specified outline level.

For each <text:table-of-content-source> element, there shall not be more than one <text:table-of-content-entry-template> for a specified outline level.

The <text:table-of-content-entry-template> element is usable within the following element: <text:table-of-content-source> 8.3.2.

The <text:table-of-content-entry-template> element has the following attributes: text:outline-level 19.844.8 and text:style-name 19.874.36.

The <text:table-of-content-entry-template> element has the following child elements: <text:index-entry-chapter> 8.13.1, <text:index-entry-link-end> 8.13.8, <text:index-entry-link-start> 8.13.7, <text:index-entry-page-number> 8.13.3, <text:index-entry-span> 8.13.4, <text:index-entry-tab-stop> 8.13.6 and <text:index-entry-text> 8.13.2.

8.4 <text:illustration-index>

8.4.1 General

The <text:illustration-index> element represents an index of the images and graphics in a current document or chapter.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:illustration-index> element is usable within the following elements: <draw:text-box> 10.4.3, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10, <style:header-left> 16.12, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:deletion> 5.5.4, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:note-body> 6.3.4 and <text:section> 5.4.

The <text:illustration-index> element has the following attributes: text:name 19.835.8, text:protected 19.849, text:protection-key 19.850, text:protection-key-digest-algorithm 19.851, text:style-name 19.874.8 and xml:id 19.914.

The <text:illustration-index> element has the following child elements: <text:illustration-index-source> 8.4.2 and <text:index-body> 8.2.2.

8.4.2 <text:illustration-index-source>

The <text:illustration-index-source> element specifies how an index of illustrations is generated.

The <text:illustration-index-source> element is usable within the following element: <text:illustration-index> 8.4.

The <text:illustration-index-source> element has the following attributes: text:caption-sequence-format 19.764, text:caption-sequence-name 19.765, text:index-scope 19.812, text:relative-tab-stop-position 19.855 and text:use-caption 19.885.

The <text:illustration-index-source> element has the following child elements: <text:illustration-index-entry-template> 8.4.3 and <text:index-title-template> 8.12.

8.4.3 <text:illustration-index-entry-template>

The <text:illustration-index-entry-template> element specifies the format of an index entry.

The <text:illustration-index-entry-template> element is usable within the following element: <text:illustration-index-source> 8.4.2.

The <text:illustration-index-entry-template> element has the following attribute: text:style-name 19.874.9.

The <text:illustration-index-entry-template> element has the following child elements: <text:index-entry-chapter> 8.13.1, <text:index-entry-page-number> 8.13.3, <text:index-entry-span> 8.13.4, <text:index-entry-tab-stop> 8.13.6 and <text:index-entry-text> 8.13.2.

8.5 <text:table-index>

8.5.1 General

The <text:table-index> element represents an index of the tables in a document or chapter.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:table-index> element is usable within the following elements: <draw:text-box> 10.4.3, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10, <style:header-left> 16.12, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:deletion> 5.5.4, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:note-body> 6.3.4 and <text:section> 5.4.

The <text:table-index> element has the following attributes: text:name 19.835.18, text:protected 19.849, text:protection-key 19.850, text:protection-key-digest-algorithm 19.851, text:style-name 19.874.37 and xml:id 19.914.

The <text:table-index> element has the following child elements: <text:index-body> 8.2.2 and <text:table-index-source> 8.5.2.

8.5.2 <text:table-index-source>

The <text:table-index-source> element specifies how an index of tables is generated.

The <text:table-index-source> element is usable within the following element: <text:table-index> 8.5.

The <text:table-index-source> element has the following attributes: text:caption-sequence-format 19.764, text:caption-sequence-name 19.765, text:index-scope 19.812, text:relative-tab-stop-position 19.855 and text:use-caption 19.885.

The <text:table-index-source> element has the following child elements: <text:index-title-template> 8.12 and <text:table-index-entry-template> 8.5.3.

8.5.3 <text:table-index-entry-template>

The <text:table-index-entry-template> element specifies the format of an index entry.

The <text:table-index-entry-template> element is usable within the following element: <text:table-index-source> 8.5.2.

The <text:table-index-entry-template> element has the following attribute: text:style-name 19.874.34.

The <text:table-index-entry-template> element has the following child elements: <text:index-entry-chapter> 8.13.1, <text:index-entry-page-number> 8.13.3, <text:index-entry-span> 8.13.4, <text:index-entry-tab-stop> 8.13.6 and <text:index-entry-text> 8.13.2.

8.6 <text:object-index>

8.6.1 General

The <text:object-index> element represents an index of the objects in a document or chapter. The types of objects that should be included in the index are defined by the <text:object-index-source> element. 8.6.2

The <text:object-index> element is usable within the following elements: <draw:text-box> 10.4.3, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<style:header> 16.10, <style:header-left> 16.12, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:deletion> 5.5.4, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:note-body> 6.3.4 and <text:section> 5.4.

The <text:object-index> element has the following attributes: text:name 19.835.10, text:protected 19.849, text:protection-key 19.850, text:protection-key-digest-algorithm 19.851, text:style-name 19.874.26 and xml:id 19.914.

The <text:object-index> element has the following child elements: <text:index-body> 8.2.2 and <text:object-index-source> 8.6.2.

8.6.2 <text:object-index-source>

The <text:object-index-source> element specifies which object types to include in the index of objects.

The <text:object-index-source> element is usable within the following element: <text:object-index> 8.6.

The <text:object-index-source> element has the following attributes: text:index-scope 19.812, text:relative-tab-stop-position 19.855, text:use-chart-objects 19.886, text:use-draw-objects 19.887, text:use-math-objects 19.893, text:use-other-objects 19.895 and text:use-spreadsheet-objects 19.898.

The <text:object-index-source> element has the following child elements: <text:index-title-template> 8.12 and <text:object-index-entry-template> 8.6.3.

8.6.3 <text:object-index-entry-template>

The <text:object-index-entry-template> element specifies the format of an index entry.

The <text:object-index-entry-template> element is usable within the following element: <text:object-index-source> 8.6.2.

The <text:object-index-entry-template> element has the following attribute: text:style-name 19.874.27.

The <text:object-index-entry-template> element has the following child elements: <text:index-entry-chapter> 8.13.1, <text:index-entry-page-number> 8.13.3, <text:index-entry-span> 8.13.4, <text:index-entry-tab-stop> 8.13.6 and <text:index-entry-text> 8.13.2.

8.7 <text:user-index>

8.7.1 General

The <text:user-index> element represents a user-defined index. A user-defined index may include entries from the following sources:

- Index marks
- Paragraphs formatted using specified paragraph styles

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- Tables, images, or objects
- Text frames

The <text:user-index> element is usable within the following elements: <draw:text-box> 10.4.3, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10, <style:header-left> 16.12, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:deletion> 5.5.4, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:note-body> 6.3.4 and <text:section> 5.4.

The <text:user-index> element has the following attributes: text:name 19.835.23, text:protected 19.849, text:protection-key 19.850, text:protection-key-digest-algorithm 19.851, text:style-name 19.874.38 and xml:id 19.914.

The <text:user-index> element has the following child elements: <text:index-body> 8.2.2 and <text:user-index-source> 8.7.2.

8.7.2 <text:user-index-source>

The <text:user-index-source> element defines the generation of user defined indexes.

The <text:user-index-source> element is usable within the following element: <text:user-index> 8.7.

The <text:user-index-source> element has the following attributes: text:copy-outline-levels 19.782, text:index-name 19.811, text:index-scope 19.812, text:relative-tab-stop-position 19.855, text:use-floating-frames 19.888, text:use-graphics 19.889, text:use-index-marks 19.890, text:use-index-source-styles 19.891, text:use-objects 19.894 and text:use-tables 19.899.

The <text:user-index-source> element has the following child elements: <text:index-source-styles> 8.10, <text:index-title-template> 8.12 and <text:user-index-entry-template> 8.7.3.

8.7.3 <text:user-index-entry-template>

The <text:user-index-entry-template> element contains entry elements for chapter number, page number, entry text, text spans, and tab stops.

The <text:user-index-entry-template> element is usable within the following element: <text:user-index-source> 8.7.2.

The <text:user-index-entry-template> element has the following attributes: text:outline-level 19.844.12 and text:style-name 19.874.39.

The <text:user-index-entry-template> element has the following child elements: <text:index-entry-chapter> 8.13.1, <text:index-entry-page-number> 8.13.3, <text:index-entry-span> 8.13.4, <text:index-entry-tab-stop> 8.13.6 and <text:index-entry-text> 8.13.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

8.8 <text:alphabetical-index>

8.8.1 General

The <text:alphabetical-index> element represents an index which is based on alphabetical index marks. The entries in an alphabetical index are sorted.

Note: Sort orders are locale specific.

The <text:alphabetical-index> element is usable within the following elements: <draw:text-box> 10.4.3, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10, <style:header-left> 16.12, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:deletion> 5.5.4, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:note-body> 6.3.4 and <text:section> 5.4.

The <text:alphabetical-index> element has the following attributes: text:name 19.835.2, text:protected 19.849, text:protection-key 19.850, text:protection-key-digest-algorithm 19.851, text:style-name 19.874.3 and xml:id 19.914.

The <text:alphabetical-index> element has the following child elements: <text:alphabetical-index-source> 8.8.2 and <text:index-body> 8.2.2.

8.8.2 <text:alphabetical-index-source>

The <text:alphabetical-index-source> element specifies how an alphabetical index is generated.

The <text:alphabetical-index-source> element is usable within the following element: <text:alphabetical-index> 8.8.

The <text:alphabetical-index-source> element has the following attributes: fo:country 19.234.1, fo:language 19.236.2, fo:script 19.242.2, style:rfc-language-tag 19.512, text:alphabetical-separators 19.752, text:capitalize-entries 19.762, text:combine-entries 19.772, text:combine-entries-with-dash 19.773, text:combine-entries-with-pp 19.774, text:comma-separated 19.775, text:ignore-case 19.813, text:index-scope 19.812, text:main-entry-style-name 19.832, text:relative-tab-stop-position 19.855, text:sort-algorithm 19.865 and text:use-keys-as-entries 19.892.

The <text:alphabetical-index-source> element has the following child elements: <text:alphabetical-index-entry-template> 8.8.4 and <text:index-title-template> 8.12.

8.8.3 <text:alphabetical-index-auto-mark-file>

The <text:alphabetical-index-auto-mark-file> element specifies an auto mark file. An auto mark file is a file that defines a list of terms that may be used by consumers to automatically insert alphabetical index marks (see 8.1.8, 8.1.10).

The format of an index mark file is implementation-defined.

The <text:alphabetical-index-auto-mark-file> element is usable within the following elements: <office:chart> 3.8, <office:drawing> 3.5, <office:presentation> 3.6,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<office:spreadsheet> 3.7, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10 and <style:header-left> 16.12.

The <text:alphabetical-index-auto-mark-file> element has the following attributes: xlink:href 19.910.34 and xlink:type 19.913.

The <text:alphabetical-index-auto-mark-file> element has no child elements.

8.8.4 <text:alphabetical-index-entry-template>

The <text:alphabetical-index-entry-template> element specifies the format of an alphabetical index entry.

The <text:alphabetical-index-entry-template> element is usable within the following element: <text:alphabetical-index-source> 8.8.2.

The <text:alphabetical-index-entry-template> element has the following attributes: text:outline-level 19.844.2 and text:style-name 19.874.4.

The <text:alphabetical-index-entry-template> element has the following child elements: <text:index-entry-chapter> 8.13.1, <text:index-entry-page-number> 8.13.3, <text:index-entry-span> 8.13.4, <text:index-entry-tab-stop> 8.13.6 and <text:index-entry-text> 8.13.2.

8.9 <text:bibliography>

8.9.1 General

The <text:bibliography> element represents a bibliography constructed from bibliography index marks.

The <text:bibliography> element is usable within the following elements: <draw:text-box> 10.4.3, <office:text> 3.4, <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10, <style:header-left> 16.12, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:deletion> 5.5.4, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:note-body> 6.3.4 and <text:section> 5.4.

The <text:bibliography> element has the following attributes: text:name 19.835.3, text:protected 19.849, text:protection-key 19.850, text:protection-key-digest-algorithm 19.851, text:style-name 19.874.5 and xml:id 19.914.

The <text:bibliography> element has the following child elements: <text:bibliography-source> 8.9.2 and <text:index-body> 8.2.2.

8.9.2 <text:bibliography-source>

The <text:bibliography-source> element specifies how a bibliography is generated.

The <text:bibliography-source> element is usable within the following element: <text:bibliography> 8.9.

The <text:bibliography-source> element has no attributes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:bibliography-source> element has the following child elements: <text:bibliography-entry-template> 8.9.3 and <text:index-title-template> 8.12.

8.9.3 <text:bibliography-entry-template>

The <text:bibliography-entry-template> element specifies the formatting for a bibliographic entry.

There shall be no more than one <text:bibliography-entry-template> element for each type of entry within any <text:bibliography-source> element. 8.9.2

The <text:bibliography-entry-template> element is usable within the following element: <text:bibliography-source> 8.9.2.

The <text:bibliography-entry-template> element has the following attributes: text:bibliography-type 19.758 and text:style-name 19.874.6.

The <text:bibliography-entry-template> element has the following child elements: <text:index-entry-bibliography> 8.13.5, <text:index-entry-span> 8.13.4 and <text:index-entry-tab-stop> 8.13.6.

8.10 <text:index-source-styles>

The <text:index-source-styles> element contains all of the <text:index-source-style> elements for a specified outline level. There can only be one <text:index-source-styles> element for each outline level.

The <text:index-source-styles> element is usable within the following elements: <text:table-of-content-source> 8.3.2 and <text:user-index-source> 8.7.2.

The <text:index-source-styles> element has the following attribute: text:outline-level 19.844.6.

The <text:index-source-styles> element has the following child element: <text:index-source-style> 8.11.

8.11 <text:index-source-style>

The <text:index-source-style> element specifies the name of a style or a class. Paragraphs formatted using that style or class are included in the index.

The <text:index-source-style> element is usable within the following element: <text:index-source-styles> 8.10.

The <text:index-source-style> element has the following attribute: text:style-name 19.874.18.

The <text:index-source-style> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

8.12 <text:index-title-template>

The <text:index-title-template> element specifies the style and content of the index title. There can only be one <text:index-title-template> element contained in a <text:table-of-content-source> element.

The <text:index-title-template> element is usable within the following elements: <text:alphabetical-index-source> 8.8.2, <text:bibliography-source> 8.9.2, <text:illustration-index-source> 8.4.2, <text:object-index-source> 8.6.2, <text:table-index-source> 8.5.2, <text:table-of-content-source> 8.3.2 and <text:user-index-source> 8.7.2.

The <text:index-title-template> element has the following attribute: text:style-name 19.874.20.

The <text:index-title-template> element has no child elements.

The <text:index-title-template> element has character data content.

8.13 Index Template Entries

8.13.1 <text:index-entry-chapter>

The <text:index-entry-chapter> element represents the chapter number where an index entry is located.

The <text:index-entry-chapter> element is usable within the following elements: <text:alphabetical-index-entry-template> 8.8.4, <text:illustration-index-entry-template> 8.4.3, <text:object-index-entry-template> 8.6.3, <text:table-index-entry-template> 8.5.3, <text:table-of-content-entry-template> 8.3.3 and <text:user-index-entry-template> 8.7.3.

The <text:index-entry-chapter> element has the following attributes: text:display 19.796.5, text:outline-level 19.844.5 and text:style-name 19.874.11.

The <text:index-entry-chapter> element has no child elements.

8.13.2 <text:index-entry-text>

The <text:index-entry-text> element contains the text of an index entry.

The <text:index-entry-text> element is usable within the following elements: <text:alphabetical-index-entry-template> 8.8.4, <text:illustration-index-entry-template> 8.4.3, <text:object-index-entry-template> 8.6.3, <text:table-index-entry-template> 8.5.3, <text:table-of-content-entry-template> 8.3.3 and <text:user-index-entry-template> 8.7.3.

The <text:index-entry-text> element has the following attribute: text:style-name 19.874.17.

The <text:index-entry-text> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

8.13.3 <text:index-entry-page-number>

The <text:index-entry-page-number> element represents the number of the chapter where an index entry is located.

The <text:index-entry-page-number> element is usable within the following elements: <text:alphabetical-index-entry-template> 8.8.4, <text:illustration-index-entry-template> 8.4.3, <text:object-index-entry-template> 8.6.3, <text:table-index-entry-template> 8.5.3, <text:table-of-content-entry-template> 8.3.3 and <text:user-index-entry-template> 8.7.3.

The <text:index-entry-page-number> element has the following attribute: text:style-name 19.874.14.

The <text:index-entry-page-number> element has no child elements.

8.13.4 <text:index-entry-span>

The <text:index-entry-span> element represents a fixed string within an index entry.

The <text:index-entry-span> element is usable within the following elements: <text:alphabetical-index-entry-template> 8.8.4, <text:bibliography-entry-template> 8.9.3, <text:illustration-index-entry-template> 8.4.3, <text:object-index-entry-template> 8.6.3, <text:table-index-entry-template> 8.5.3, <text:table-of-content-entry-template> 8.3.3 and <text:user-index-entry-template> 8.7.3.

The <text:index-entry-span> element has the following attribute: text:style-name 19.874.15.

The <text:index-entry-span> element has no child elements.

The <text:index-entry-span> element has character data content.

8.13.5 <text:index-entry-bibliography>

The <text:index-entry-bibliography> element specifies the field of a bibliographic entry that will be displayed in an index.

The <text:index-entry-bibliography> element is usable within the following element: <text:bibliography-entry-template> 8.9.3.

The <text:index-entry-bibliography> element has the following attributes: text:bibliography-data-field 19.757 and text:style-name 19.874.10.

The <text:index-entry-bibliography> element has no child elements.

8.13.6 <text:index-entry-tab-stop>

The <text:index-entry-tab-stop> element represents a tab stop within an index entry.

The <text:index-entry-tab-stop> element is usable within the following elements: <text:alphabetical-index-entry-template> 8.8.4, <text:bibliography-entry-template> 8.9.3, <text:illustration-index-entry-template> 8.4.3, <text:object-index-entry-template> 8.6.3, <text:table-index-entry-

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

template> 8.5.3, <text:table-of-content-entry-template> 8.3.3 and <text:user-index-entry-template> 8.7.3.

The <text:index-entry-tab-stop> element has the following attributes: style:leader-char 19.483, style:position 19.508.4, style:type 19.515.2 and text:style-name 19.874.16.

The <text:index-entry-tab-stop> element has no child elements.

8.13.7 <text:index-entry-link-start>

The <text:index-entry-link-start> element represents the start of a hyperlink index entry.

The <text:index-entry-link-start> element is usable within the following element: <text:table-of-content-entry-template> 8.3.3.

The <text:index-entry-link-start> element has the following attribute: text:style-name 19.874.13.

The <text:index-entry-link-start> element has no child elements.

8.13.8 <text:index-entry-link-end>

The <text:index-entry-link-end> element represents the end of a hyperlink index entry.

The <text:index-entry-link-end> element is usable within the following element: <text:table-of-content-entry-template> 8.3.3.

The <text:index-entry-link-end> element has the following attribute: text:style-name 19.874.12.

The <text:index-entry-link-end> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9 Tables

9.1 Basic Tables

9.1.1 General

The representation of tables is based on the concept of grids of rows and columns. In markup, rows are partitioned into table cells. Columns are implied by taking together all cells with the same position within the rows.

Rows and columns appear in *row groups* and *column groups*. These groups specify whether to repeat a row or column on the next page.

Note: There is only one model for tables, although tables, such as for spreadsheets, may have additional capabilities when compared to tables in text documents.

Tables may be nested, that is, tables may occur within tables.

9.1.2 <table:table>

The `<table:table>` element is the root element for a table.

The `<table:table>` element is usable within the following elements: `<chart:chart>` 11.1, `<draw:frame>` 10.4.2, `<draw:text-box>` 10.4.3, `<office:spreadsheet>` 3.7, `<office:text>` 3.4, `<style:footer>` 16.11, `<style:footer-left>` 16.13, `<style:header>` 16.10, `<style:header-left>` 16.12, `<table:covered-table-cell>` 9.1.5, `<table:dde-link>` 14.6.4, `<table:table-cell>` 9.1.4, `<text:deletion>` 5.5.4, `<text:index-body>` 8.2.2, `<text:index-title>` 8.2.3, `<text:note-body>` 6.3.4 and `<text:section>` 5.4.

The `<table:table>` element has the following attributes: `table:is-sub-table` 19.655, `table:name` 19.673.13, `table:print` 19.693, `table:print-ranges` 19.694, `table:protected` 19.696.4, `table:protection-key` 19.697, `table:protection-key-digest-algorithm` 19.698, `table:style-name` 19.726.16, `table:template-name` 19.732, `table:use-banding-columns-styles` 19.736, `table:use-banding-rows-styles` 19.737, `table:use-first-column-styles` 19.738, `table:use-first-row-styles` 19.739, `table:use-last-column-styles` 19.740, `table:use-last-row-styles` 19.741 and `xml:id` 19.914.

The `<table:table>` element has the following child elements: `<office:dde-source>` 14.6.5, `<office:forms>` 13.2, `<table:desc>` 9.1.14, `<table:named-expressions>` 9.4.11, `<table:scenario>` 9.2.7, `<table:shapes>` 9.2.8, `<table:table-column>` 9.1.6, `<table:table-column-group>` 9.1.10, `<table:table-columns>` 9.1.12, `<table:table-header-columns>` 9.1.11, `<table:table-header-rows>` 9.1.7, `<table:table-row>` 9.1.3, `<table:table-row-group>` 9.1.9, `<table:table-rows>` 9.1.8, `<table:table-source>` 9.2.6, `<table:title>` 9.1.13, `<text:soft-page-break>` 5.6.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9.1.3 <table:table-row>

The <table:table-row> element represents a row in a table. It contains elements that specify the cells of the table row.

The <table:table-row> element is usable within the following elements: <table:table> 9.1.2, <table:table-header-rows> 9.1.7, <table:table-row-group> 9.1.9 and <table:table-rows> 9.1.8.

The <table:table-row> element has the following attributes: table:default-cell-style-name 19.615, table:number-rows-repeated 19.677, table:style-name 19.726.15, table:visibility 19.749 and xml:id 19.914.

The <table:table-row> element has the following child elements: <table:covered-table-cell> 9.1.5 and <table:table-cell> 9.1.4.

9.1.4 <table:table-cell>

The <table:table-cell> element represents a table cell. It is contained in a table row element. A table cell can contain paragraphs and other text content as well as sub tables. Table cells may span multiple columns and rows. Table cells may be empty.

The <table:table-cell> element is usable within the following element: <table:table-row> 9.1.3.

The <table:table-cell> element has the following attributes: office:boolean-value 19.367, office:currency 19.369, office:date-value 19.370, office:string-value 19.379, office:time-value 19.382, office:value 19.384, office:value-type 19.385, table:content-validation-name 19.601, table:formula 19.642, table:number-columns-repeated 19.675.3, table:number-columns-spanned 19.676, table:number-matrix-columns-spanned 19.679, table:number-matrix-rows-spanned 19.680, table:number-rows-spanned 19.678, table:protect 19.695, table:protected 19.696.5, table:style-name 19.726.13, xhtml:about 19.905, xhtml:content 19.906, xhtml:datatype 19.907, xhtml:property 19.908 and xml:id 19.914.

The <table:table-cell> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:annotation> 14.1, <table:cell-range-source> 9.3.1, <table:detective> 9.3.2, <table:table> 9.1.2, <text:alphabetical-index> 8.8, <text:bibliography> 8.9, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:h> 5.1.2, <text:illustration-index> 8.4, <text:list> 5.3.1, <text:numbered-paragraph> 5.3.6, <text:object-index> 8.6, <text:p> 5.1.3, <text:section> 5.4, <text:soft-page-break> 5.6, <text:table-index> 8.5, <text:table-of-content> 8.3 and <text:user-index> 8.7.

9.1.5 <table:covered-table-cell>

The <table:covered-table-cell> element represents cells that are covered by a <table:table-cell> 9.1.4 element that spans multiple columns or rows. The <table:covered-table-cell> elements occupy the same position in document order as the

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

cells spanned. There is one <table:covered-table-cell> element for each cell that is spanned.

The <table:covered-table-cell> element is usable within the following element: <table:table-row> 9.1.3.

The <table:covered-table-cell> element has the following attributes: office:boolean-value 19.367, office:currency 19.369, office:date-value 19.370, office:string-value 19.379, office:time-value 19.382, office:value 19.384, office:value-type 19.385, table:content-validation-name 19.601, table:formula 19.642, table:number-columns-repeated 19.675.2, table:protect 19.695, table:protected 19.696.2, table:style-name 19.726.4, xhtml:about 19.905, xhtml:content 19.906, xhtml:datatype 19.907, xhtml:property 19.908 and xml:id 19.914.

The <table:covered-table-cell> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:annotation> 14.1, <table:cell-range-source> 9.3.1, <table:detective> 9.3.2, <table:table> 9.1.2, <text:alphabetical-index> 8.8, <text:bibliography> 8.9, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:h> 5.1.2, <text:illustration-index> 8.4, <text:list> 5.3.1, <text:numbered-paragraph> 5.3.6, <text:object-index> 8.6, <text:p> 5.1.3, <text:section> 5.4, <text:soft-page-break> 5.6, <text:table-index> 8.5, <text:table-of-content> 8.3 and <text:user-index> 8.7.

9.1.6 <table:table-column>

The <table:table-column> element specifies properties for one or more adjacent columns in a table.

The <table:table-column> element is usable within the following elements: <table:table> 9.1.2, <table:table-column-group> 9.1.10, <table:table-columns> 9.1.12 and <table:table-header-columns> 9.1.11.

The <table:table-column> element has the following attributes: table:default-cell-style-name 19.615, table:number-columns-repeated 19.675.4, table:style-name 19.726.14, table:visibility 19.749 and xml:id 19.914.

The <table:table-column> element has no child elements.

9.1.7 <table:table-header-rows>

The <table:table-header-rows> element represents row headers in a table. It is composed of adjacent <table:table-row> 9.1.3 elements.

Note: Use of the <table:table-header-rows> element increases accessibility. The use of styles to designate row headers diminishes accessibility.

If a table does not fit on a single page, table rows that are included in a <table:table-header-rows> element are automatically repeated on every page.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

A table shall not contain more than one <table:table-header-rows> element, except that the table contains grouped rows defined by one or more <table:table-row-group> 9.1.9 elements. In this case, the table and each distinct group may contain one <table:table-header-rows> element, if and only if the table rows contained in the <table:table-header-rows> elements are adjacent.

Consumers that do not support header rows shall process header rows as non-header rows.

The <table:table-header-rows> element is usable within the following elements: <table:table> 9.1.2 and <table:table-row-group> 9.1.9.

The <table:table-header-rows> element has no attributes.

The <table:table-header-rows> element has the following child elements: <table:table-row> 9.1.3 and <text:soft-page-break> 5.6.

9.1.8 <table:table-rows>

The <table:table-rows> element contains groups of <table:table-row> 9.1.3 elements that do not repeat when a table spans more than one page.

The <table:table-rows> element is usable within the following elements: <table:table> 9.1.2 and <table:table-row-group> 9.1.9.

The <table:table-rows> element has no attributes.

The <table:table-rows> element has the following child elements: <table:table-row> 9.1.3 and <text:soft-page-break> 5.6.

9.1.9 <table:table-row-group>

The <table:table-row-group> element groups adjacent table rows that do not appear as table headers. Every group can contain a new group, rows, and row headers. A row group can be visible or hidden.

The <table:table-row-group> element is usable within the following elements: <table:table> 9.1.2 and <table:table-row-group> 9.1.9.

The <table:table-row-group> element has the following attribute: table:display 19.617.

The <table:table-row-group> element has the following child elements: <table:table-header-rows> 9.1.7, <table:table-row> 9.1.3, <table:table-row-group> 9.1.9, <table:table-rows> 9.1.8, <text:soft-page-break> 5.6.

9.1.10 <table:table-column-group>

The <table:table-column-group> element groups adjacent table columns. Every group can contain a new group, columns, and column headers. A column group can be visible or hidden.

If a set of header columns and a column group overlap, the header column group breaks the column header set. That is, the <table:table-column-group> may contain <table:table-header-columns> elements, but not vice versa.

The <table:table-column-group> element is usable within the following elements: <table:table> 9.1.2 and <table:table-column-group> 9.1.10.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:table-column-group> element has the following attribute: table:display 19.617.

The <table:table-column-group> element has the following child elements: <table:table-column> 9.1.6, <table:table-column-group> 9.1.10, <table:table-columns> 9.1.12, <table:table-header-columns> 9.1.11.

9.1.11 <table:table-header-columns>

The <table:table-header-columns> element represents column headers in a table. It is composed of adjacent <table:table-column> 9.1.6 elements.

Note: Use of the <table:table-header-columns> element increases accessibility The use of styles to designate column headers diminishes accessibility.

If a table does not fit on a single page, table columns that are included in a <table:table-header-columns> element are automatically repeated on every page.

A table shall not contain more than one <table:table-header-columns> element, except that the table contains grouped rows defined by one or more <table:table-column-group> 9.1.10 elements. In this case, the table and each distinct group may contain one <table:table-header-columns> element, if and only if the table columns contained in the <table:table-header-columns> elements are adjacent.

Consumers that do not support header columns shall process header column as non header columns .

The <table:table-header-columns> element is usable within the following elements: <table:table> 9.1.2 and <table:table-column-group> 9.1.10.

The <table:table-header-columns> element has no attributes.

The <table:table-header-columns> element has the following child element: <table:table-column> 9.1.6.

9.1.12 <table:table-columns>

The <table:table-columns> element contains groups of <table:table-column> 9.1.6 elements that do not repeat when a table spans more than one page.

The <table:table-columns> element is usable within the following elements: <table:table> 9.1.2 and <table:table-column-group> 9.1.10.

The <table:table-columns> element has no attributes.

The <table:table-columns> element has the following child element: <table:table-column> 9.1.6.

9.1.13 <table:title>

The <table:title> element specifies a title for a table. The element shall not be used if the parent <table:table> element is contained within a <draw:frame> element. In that case, the table's title is specified the by <svg:title> child element of <draw:frame>.

The <table:title> element is usable within the following element: <table:table> 9.1.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:title> element has no attributes.

The <table:title> element has no child elements.

The <table:title> element has character data content.

9.1.14 <table:desc>

The <table:desc> element specifies a prose description of a table that may be used to support accessibility. See appendix D The element shall not be used if the parent <table:table> element is contained within a <draw:frame> element. In that case, the table's description is specified the by <svg:desc> child element of <draw:frame>.

The <table:desc> element is usable within the following element: <table:table> 9.1.2.

The <table:desc> element has no attributes.

The <table:desc> element has no child elements.

The <table:desc> element has character data content.

9.2 Advanced Tables

9.2.1 Referencing Table Cells

To reference cells in a table, cell addresses are used. Cell addresses are constructed as follows:

1) The name of the table.

2) A dot “.” (U+002E, FULL STOP).

3) An alphabetic value representing the column. The letter A represents column 1, B represents column 2, and so on. AA represents column 27, AB represents column 28, and so on.

4) A numeric value representing the row. The number 1 represents the first row, the number 2 represents the second row, and so on.

This means that A1 represents the cell in column 1 and row 1. B1 represents the cell in column 2 and row 1. A2 represents the cell in column 1 and row 2.

The structure of the address of a cell in a subtable is as follows:

1) The address of the cell that contains the subtable.

2) A dot “.” (U+002E, FULL STOP).

3) The address of the cell in the subtable.

If the name of the table contains blanks, dots “.” (U+002E, FULL STOP) or apostrophes “'” (U+0027, APOSTROPHE), the name shall be quoted with apostrophes “'” (U+0027, APOSTROPHE). Any apostrophes in the name shall be escaped by doubling the”'”(U+0027, APOSTROPHE) character.

The behavior of a consumer when a cell is referenced but not declared is implementation-dependent

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9.2.2 Absolute and relative cell addressing

Cells can be referenced by using either absolute addresses or relative addresses. When an operation is performed on a table cell absolute cell references do not change. Relative cell references are adapted to the address of the target cell of a copy operation.

To create an absolute address, a dollar sign “$” (U+0024, DOLLAR SIGN) shall be placed before each table name, column reference, and row reference. Absolute and relative references may be mixed within a single cell address. Absolute addresses shall contain a table name.

When differentiation between absolute and relative addresses is not necessary, the dollar signs in absolute addresses may be omitted.

9.2.3 Cell Range Address

A cell range is a number of adjacent cells forming a rectangular shape. The rectangle stretches from the cell on the logical top left to the cell on the logical bottom right.

A cell range address references a cell range. A cell range address consists of:

1) The address of the cell at the top left of the range.

2) A colon “:” (U+003A, COLON).

3) The address of the cell at the bottom right of the range.

The smallest range is a single cell. The range address of a single cell is the same as the cell address.

9.2.4 Column and Row Range Addresses

Column and row addresses are cell range addresses that reference a entire rows or columns.

The syntax of a row address is the same as a cell address, except the alphabetic values that indicate the column are omitted.

The syntax of a column address is the same as a cell address, except the numeric values that indicate the row are omitted.

9.2.5 Cell Range Address List

A cell range address list is a list of cell range addresses and cell addresses. Each item in the list is separated by white space. If any table name used in the list contains a “ “ (U+0020, SPACE) character, the table name is quoted within apostrophes “'” (U+0027, APOSTROPHE).

9.2.6 <table:table-source>

The `<table:table-source>` element represents a link to a table that provides a source for a table.

The `<table:table-source>` element is usable within the following element: `<table:table>` 9.1.2.

The `<table:table-source>` element has the following attributes: `table:filter-name` 19.638, `table:filter-options` 19.639, `table:mode` 19.671, `table:refresh-delay` 19.701, `table:table-name` 19.729, `xlink:actuate` 19.909, `xlink:href` 19.910.32 and `xlink:type` 19.913.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:table-source> element has no child elements.

9.2.7 <table:scenario>

The <table:scenario> element defines a scenario for display on a table. A table represented by a <table:table> element which contains a <table:scenario> child element is called a scenario table.

A scenario is one or more cell ranges of a table whose contents replaces the contents of the cell ranges in the nearest non-scenario table preceding the scenario table in document order. If multiple scenarios are defined for a cell range, an user may choose between the scenarios. The names of the scenarios are the same as the names of tables which contain the <table:scenario> elements.

Display of the border of a scenario table is controlled by its table:display-border attribute.19.618

Note: Display of the border of a scenario is the only visible indication that the displayed data is the result of the application of a scenario to the data in the table.

Only one scenario table can be applied to a range at one time.

Note: A table can have multiple scenarios applied to it so long as the ranges of application do not overlap.

The <table:scenario> element is usable within the following element: <table:table> 9.1.2.

The <table:scenario> element has the following attributes: table:border-color 19.588, table:comment 19.595, table:copy-back 19.602, table:copy-formulas 19.603, table:copy-styles 19.604, table:display-border 19.618, table:is-active 19.652, table:protected 19.696.3 and table:scenario-ranges 19.705.

The <table:scenario> element has no child elements.

9.2.8 <table:shapes>

The <table:shapes> element contains all the elements that represent graphic shapes that are anchored on a table where this element occurs.

The <table:shapes> element is usable within the following element: <table:table> 9.1.2.

The <table:shapes> element has no attributes.

The <table:shapes> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2 and <draw:regular-polygon> 10.3.6.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9.3 Advanced Table Cells

9.3.1 <table:cell-range-source>

The `<table:cell-range-source>` element represents a database range or named range of another file in a cell range. The first cell in the cell range contains this element. A cell range can be linked to a database range or named range of another file.

The `<table:cell-range-source>` element is usable within the following elements: `<table:covered-table-cell>` 9.1.5 and `<table:table-cell>` 9.1.4.

The `<table:cell-range-source>` element has the following attributes: `table:filter-name` 19.638, `table:filter-options` 19.639, `table:last-column-spanned` 19.658, `table:last-row-spanned` 19.660, `table:name` 19.673.2, `table:refresh-delay` 19.701, `xlink:actuate` 19.909, `xlink:href` 19.910.31 and `xlink:type` 19.913.

The `<table:cell-range-source>` element has no child elements.

9.3.2 <table:detective>

The `<table:detective>` element is a container for `<table:operation>` 9.3.3 and `<table:highlighted-range>` 9.3.4 elements, providing information about what relationships between the current cell and other cells are revealed in the presentation of the table.

The `<table:detective>` element is usable within the following elements: `<table:covered-table-cell>` 9.1.5 and `<table:table-cell>` 9.1.4.

The `<table:detective>` element has no attributes.

The `<table:detective>` element has the following child elements: `<table:highlighted-range>` 9.3.4 and `<table:operation>` 9.3.3.

9.3.3 <table:operation>

The `<table:operation>` element specifies the name of a detective operation that leads to the discovery of relationships between cells (`table:name`, 19.673) and the order in which those operations are applied (`table:index`, 19.651).Once relationships between cells have been discovered, those cells are highlighted to show those relationships.

Note: A single cell may be the subject of one or more detective operations.

The `<table:operation>` element is usable within the following element: `<table:detective>` 9.3.2.

The `<table:operation>` element has the following attributes: `table:index` 19.651 and `table:name` 19.673.11.

The `<table:operation>` element has no child elements.

9.3.4 <table:highlighted-range>

The `<table:highlighted-range>` element specifies a cell range that is highlighted in the UI either because of detective operations defined by a `<table:operation>` element or because it contains an error or invalid data.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The nature of the highlighting is implementation dependent.

This element represents the state of the document at the time the detective operations or error conditions were calculated. It may not accurately represent the current state of the document.

The <table:highlighted-range> element is usable within the following element: <table:detective> 9.3.2.

The <table:highlighted-range> element has the following attributes: table:cell-range-address 19.593.7, table:contains-error 19.599, table:direction 19.616 and table:marked-invalid 19.664.

The <table:highlighted-range> element has no child elements.

9.4 Spreadsheet Document Content

9.4.1 <table:calculation-settings>

The <table:calculation-settings> element is a container for settings that affect the calculation of formula.

The <table:calculation-settings> element is usable within the following elements: <office:chart> 3.8, <office:drawing> 3.5, <office:presentation> 3.6, <office:spreadsheet> 3.7 and <office:text> 3.4.

The <table:calculation-settings> element has the following attributes: table:automatic-find-labels 19.585, table:case-sensitive 19.590, table:null-year 19.674, table:precision-as-shown 19.692, table:search-criteria-must-apply-to-whole-cell 19.707, table:use-regular-expressions 19.743 and table:use-wildcards 19.744.

The <table:calculation-settings> element has the following child elements: <table:iteration> 9.4.3 and <table:null-date> 9.4.2.

9.4.2 <table:null-date>

The <table:null-date> element specifies the null date for a spreadsheet document. The null date is the date that results in the value “0” if a date value is converted into a numeric value. The null date is specified in the element's table:date-value attribute.

Note: Commonly used values are 12/30/1899, 01/01/1900, and 01/01/1904.

The <table:null-date> element is usable within the following element: <table:calculation-settings> 9.4.1.

The <table:null-date> element has the following attributes: table:date-value 19.614 and table:value-type 19.748.

The <table:null-date> element has no child elements.

9.4.3 <table:iteration>

The <table:iteration> element enables formulas with iterative (or cyclic) references to be calculated after a specific number of iterations. If iterative calculations are not enabled, a formula expression containing a cyclic cell reference returns an error.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If the table:status attribute has the value enable and iterating through the cyclic dependencies does not deliver a result that satisfies the condition specified by the table:maximum-difference attribute within a number of iterations specified by the table:steps attribute for all cells in the cyclic dependencies, an error is returned.

The <table:iteration> element is usable within the following element: <table:calculation-settings> 9.4.1.

The <table:iteration> element has the following attributes: table:maximum-difference 19.666, table:status 19.722 and table:steps 19.724.

The <table:iteration> element has no child elements.

9.4.4 <table:content-validations>

The <table:content-validations> element contains all the validation rules for the content of table cells.

The <table:content-validations> element is usable within the following elements: <office:chart> 3.8, <office:drawing> 3.5, <office:presentation> 3.6, <office:spreadsheet> 3.7 and <office:text> 3.4.

The <table:content-validations> element has no attributes.

The <table:content-validations> element has the following child element: <table:content-validation> 9.4.5.

9.4.5 <table:content-validation>

The <table:content-validation> element specifies a validation rule for table cell content.

The names of validation rules are stored in the table:name attribute of a <table:content-validation> element.

The <table:content-validation> element is usable within the following element: <table:content-validations> 9.4.4.

The <table:content-validation> element has the following attributes: table:allow-empty-cell 19.583, table:base-cell-address 19.586, table:condition 19.596, table:display-list 19.621 and table:name 19.673.3.

The <table:content-validation> element has the following child elements: <office:event-listeners> 10.3.19, <table:error-macro> 9.4.8, <table:error-message> 9.4.7 and <table:help-message> 9.4.6.

9.4.6 <table:help-message>

The <table:help-message> element specifies a message to display if a user selects a cell.

The <table:help-message> element is usable within the following element: <table:content-validation> 9.4.5.

The <table:help-message> element has the following attributes: table:display 19.617 and table:title 19.733.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:help-message> element has the following child element: <text:p> 5.1.3.

9.4.7 <table:error-message>

The <table:error-message> element specifies a message to display if a user tries to enter invalid content into a cell. That is when a validation rule's condition evaluates to “false” on the content the user attempts to enter.

The <table:error-message> element is usable within the following element: <table:content-validation> 9.4.5.

The <table:error-message> element has the following attributes: table:display 19.617, table:message-type 19.670 and table:title 19.733.

The <table:error-message> element has the following child element: <text:p> 5.1.3.

9.4.8 <table:error-macro>

The <table:error-macro> element specifies if a macro should be executed upon an attempt to enter invalid content.

A macro is specified by an <office:event-listeners> element. 14.4 The event name shall be one that specifies an event that is called on invalid user input.

The <table:error-macro> element is usable within the following element: <table:content-validation> 9.4.5.

The <table:error-macro> element has the following attribute: table:execute 19.634.

The <table:error-macro> element has no child elements.

9.4.9 <table:label-range>

The <table:label-range> element specifies a label cell range which contain labels, and a data cell range which specifies the rows or columns whose content is referenced by the labels.

There are two types of label ranges:

- Label ranges for columns.
- Label ranges for rows.

Data and label ranges should match in both height and vertical position for row orientation, or in both width and horizontal position for column orientation.

The <table:label-range> element is usable within the following element: <table:label-ranges> 9.4.10.

The <table:label-range> element has the following attributes: table:data-cell-range-address 19.608, table:label-cell-range-address 19.656 and table:orientation 19.686.4.

The <table:label-range> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9.4.10 <table:label-ranges>

The <table:label-ranges> element contains all the <table:label-range> elements in a document.

The <table:label-ranges> element is usable within the following elements: <office:chart> 3.8, <office:drawing> 3.5, <office:presentation> 3.6, <office:spreadsheet> 3.7 and <office:text> 3.4.

The <table:label-ranges> element has no attributes.

The <table:label-ranges> element has the following child element: <table:label-range> 9.4.9.

9.4.11 <table:named-expressions>

The <table:named-expressions> element contains assignments of names to expressions.

The following expressions may have names:

- cell ranges.
- Other expressions.

If the <table:named-expressions> element is used with a <table:table> element, the scope of the named expressions are local to that table element.

The <table:named-expressions> element is usable within the following elements: <office:chart> 3.8, <office:drawing> 3.5, <office:presentation> 3.6, <office:spreadsheet> 3.7, <office:text> 3.4 and <table:table> 9.1.2.

The <table:named-expressions> element has no attributes.

The <table:named-expressions> element has the following child elements: <table:named-expression> 9.4.13 and <table:named-range> 9.4.12.

9.4.12 <table:named-range>

The <table:named-range> element specifies a cell range that has a name assigned.

The <table:named-range> element is usable within the following element: <table:named-expressions> 9.4.11.

The <table:named-range> element has the following attributes: table:base-cell-address 19.586, table:cell-range-address 19.593.8, table:name 19.673.10 and table:range-usable-as 19.700.

The <table:named-range> element has no child elements.

9.4.13 <table:named-expression>

The <table:named-expression> element represents an expression with a name.

The <table:named-expression> element is usable within the following element: <table:named-expressions> 9.4.11.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:named-expression> element has the following attributes: table:base-cell-address 19.586, table:expression 19.635 and table:name 19.673.9.

The <table:named-expression> element has no child elements.

9.4.14 <table:database-ranges>

The <table:database-ranges> element contains all the <table:database-range> elements in a document.

The <table:database-ranges> element is usable within the following elements: <office:chart> 3.8, <office:drawing> 3.5, <office:presentation> 3.6, <office:spreadsheet> 3.7 and <office:text> 3.4.

The <table:database-ranges> element has no attributes.

The <table:database-ranges> element has the following child element: <table:database-range> 9.4.15.

9.4.15 <table:database-range>

The <table:database-range> element defines a single database range. A database range is a named area in a table upon which database operations are performed.

The <table:database-range> element is usable within the following element: <table:database-ranges> 9.4.14.

The <table:database-range> element has the following attributes: table:contains-header 19.600, table:display-filter-buttons 19.620, table:has-persistent-data 19.647, table:is-selection 19.654, table:name 19.673.8, table:on-update-keep-size 19.682, table:on-update-keep-styles 19.683, table:orientation 19.686.3, table:refresh-delay 19.701 and table:target-range-address 19.731.3.

The <table:database-range> element has the following child elements: <table:database-source-query> 9.4.18, <table:database-source-sql> 9.4.16, <table:database-source-table> 9.4.17, <table:filter> 9.5.2, <table:sort> 9.4.19 and <table:subtotal-rules> 9.4.21.

9.4.16 <table:database-source-sql>

The <table:database-source-sql> element specifies an [SQL] database that contains the source data of a database range.

The <table:database-source-sql> element is usable within the following elements: <table:database-range> 9.4.15 and <table:data-pilot-table> 9.6.3.

The <table:database-source-sql> element has the following attributes: table:database-name 19.609, table:parse-sql-statement 19.689 and table:sql-statement 19.716.

The <table:database-source-sql> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9.4.17 <table:database-source-table>

The `<table:database-source-table>` element specifies the database and table that acts as the source data for a database range.

The `<table:database-source-table>` element is usable within the following elements: `<table:database-range>` 9.4.15 and `<table:data-pilot-table>` 9.6.3.

The `<table:database-source-table>` element has the following attributes: `table:database-name` 19.609 and `table:database-table-name` 19.610.

The `<table:database-source-table>` element has no child elements.

9.4.18 <table:database-source-query>

The `<table:database-source-query>` element specifies the query that produces the source data for a database range.

The `<table:database-source-query>` element is usable within the following elements: `<table:database-range>` 9.4.15 and `<table:data-pilot-table>` 9.6.3.

The `<table:database-source-query>` element has the following attributes: `table:database-name` 19.609 and `table:query-name` 19.699.

The `<table:database-source-query>` element has no child elements.

9.4.19 <table:sort>

The `<table:sort>` element `<table:sort>` specifies the sort keys to be applied to a database range.

The `<table:sort>` element is usable within the following element: `<table:database-range>` 9.4.15.

The `<table:sort>` element has the following attributes: `table:algorithm` 19.581, `table:bind-styles-to-content` 19.587, `table:case-sensitive` 19.590, `table:country` 19.606, `table:embedded-number-behavior` 19.624, `table:language` 19.657, `table:rfc-language-tag` 19.703, `table:script` 19.706 and `table:target-range-address` 19.731.5.

The `<table:sort>` element has the following child element: `<table:sort-by>` 9.4.20.

9.4.20 <table:sort-by>

The `<table:sort-by>` element specifies a key or field to sort, the data type of this field, and how to sort it for a database range.

The `<table:sort-by>` element is usable within the following element: `<table:sort>` 9.4.19.

The `<table:sort-by>` element has the following attributes: `table:data-type` 19.611.3, `table:field-number` 19.637 and `table:order` 19.685.

The `<table:sort-by>` element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9.4.21 <table:subtotal-rules>

The `<table:subtotal-rules>` element is a container for `<table:subtotal-rule>` elements which specify the calculation of provisional results (called subtotals) for a database range. Cells of the same field form a group. A provisional result is calculated and display at the end of each group.

The `<table:subtotal-rules>` element is usable within the following element: `<table:database-range>` 9.4.15.

The `<table:subtotal-rules>` element has the following attributes: `table:bind-styles-to-content` 19.587, `table:case-sensitive` 19.590 and `table:page-breaks-on-group-change` 19.687.

The `<table:subtotal-rules>` element has the following child elements: `<table:sort-groups>` 9.4.22 and `<table:subtotal-rule>` 9.4.23.

9.4.22 <table:sort-groups>

The `<table:sort-groups>` element specifies a sort order for columns or rows of a table.

The `<table:sort-groups>` element is usable within the following element: `<table:subtotal-rules>` 9.4.21.

The `<table:sort-groups>` element has the following attributes: `table:data-type` 19.611.4 and `table:order` 19.685.

The `<table:sort-groups>` element has no child elements.

9.4.23 <table:subtotal-rule>

The `<table:subtotal-rule>` element specifies the calculation of subtotals for a row or column. As the container element for `<table:subtotal-field>`, the calculation specified by this element may use provisional results in its calculation.

The `<table:subtotal-rule>` element is usable within the following element: `<table:subtotal-rules>` 9.4.21.

The `<table:subtotal-rule>` element has the following attribute: `table:group-by-field-number` 19.645.

The `<table:subtotal-rule>` element has the following child element: `<table:subtotal-field>` 9.4.24.

9.4.24 <table:subtotal-field>

The `<table:subtotal-field>` element specifies the field number and the function that is applied to the content of that field to calculate a provisional result.

The `<table:subtotal-field>` element is usable within the following element: `<table:subtotal-rule>` 9.4.23.

The `<table:subtotal-field>` element has the following attributes: `table:field-number` 19.637 and `table:function` 19.643.5.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:subtotal-field> element has no child elements.

9.5 Filters

9.5.1 General

Filter element specify conditions that if not met, render portions of a table invisible.

9.5.2 <table:filter>

The <table:filter> element is a container for elements that specify filters for data contained in database ranges or data pilot tables. The filters are applied to all rows in the database range or the data pilot table. Rows where one or more filter conditions do not evaluate to true are made invisible.

The <table:filter> element is usable within the following elements: <table:database-range> 9.4.15 and <table:source-cell-range> 9.6.5.

The <table:filter> element has the following attributes: table:condition-source 19.597, table:condition-source-range-address 19.598, table:display-duplicates 19.619 and table:target-range-address 19.731.4.

The <table:filter> element has the following child elements: <table:filter-and> 9.5.3, <table:filter-condition> 9.5.5 and <table:filter-or> 9.5.4.

9.5.3 <table:filter-and>

The <table:filter-and> element specifies that the logical operator AND is applied to conditions specified by the child elements of this element.

The <table:filter-and> element is usable within the following elements: <table:filter> 9.5.2 and <table:filter-or> 9.5.4.

The <table:filter-and> element has no attributes.

The <table:filter-and> element has the following child elements: <table:filter-condition> 9.5.5 and <table:filter-or> 9.5.4.

9.5.4 <table:filter-or>

The <table:filter-or> element specifies that the logical operator OR is applied to conditions specified by the child elements of this element.

The <table:filter-or> element is usable within the following elements: <table:filter> 9.5.2 and <table:filter-and> 9.5.3.

The <table:filter-or> element has no attributes.

The <table:filter-or> element has the following child elements: <table:filter-and> 9.5.3 and <table:filter-condition> 9.5.5.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9.5.5 <table:filter-condition>

The `<table:filter-condition>` element specifies a single condition to apply in a filter operation.

The filter condition is either specified

- by the `table:operator` 19.684, `table:value` 19.747 and `table:data-type` 19.611 attributes or
- a set of `<table:filter-set-item>` 9.5.6 child elements as a set of values.

If one or more of `<table:filter-set-item>` elements are present as children of the `<table:filter-condition>` element, the `table:operator`, `table:value` and `table:data-type` attributes are ignored.

Note: To improve backward compatibility with OpenDocument 1.1 documents, the following attributes should have these values if `<table:filter-set-item>` elements are included: `table:operator`: "=", `table:value`: value of the first `<table:filter-set-item>` child element, `table:data-type`: "`text`".

The `<table:filter-condition>` element is usable within the following elements: `<table:filter>` 9.5.2, `<table:filter-and>` 9.5.3 and `<table:filter-or>` 9.5.4.

The `<table:filter-condition>` element has the following attributes: `table:case-sensitive` 19.590, `table:data-type` 19.611.2, `table:field-number` 19.637, `table:operator` 19.684 and `table:value` 19.747.1.

The `<table:filter-condition>` element has the following child element: `<table:filter-set-item>` 9.5.6.

9.5.6 <table:filter-set-item>

The `<table:filter-set-item>` element specifies a single value used in a filter condition where the `table:operator` attribute is set to "=", and the `table:data-type` attribute to `text`. The filter sub condition in which the element is included evaluates to true for a specified cell, if, and only if, the value of the cell is equal to one of the values in the set specified by be `<table:filter>` element.

The `<table:filter-set-item>` element is usable within the following element: `<table:filter-condition>` 9.5.5.

The `<table:filter-set-item>` element has the following attribute: `table:value` 19.747.2.

The `<table:filter-set-item>` element has no child elements.

9.6 Data Pilot Tables

9.6.1 General

Data pilot tables enable users to rearrange data from data sources so as to create new relationships between data elements or to view data from a variety of perspectives. This is in contrast to scenario tables 9.2.7, where the data elements remain fixed but the values and operations on them are varied to illustrate different outcomes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The behavior of a data pilot table is specified by fields, where each field has a name and an orientation. The category columns are specified by fields with the orientation “row” or “column” and data columns are specified by fields that have the orientation “data”.

A third type of fields are data layout fields. Data layout fields are not connected to a column in the source table, but are used to change the layout of the data pilot table.

The order in which fields are specified determines the order in which the data of category columns are grouped and results are displayed.

9.6.2 <table:data-pilot-tables>

The `<table:data-pilot-tables>` element contains all the data pilot tables within a document.

The `<table:data-pilot-tables>` element is usable within the following elements: `<office:chart>` 3.8, `<office:drawing>` 3.5, `<office:presentation>` 3.6, `<office:spreadsheet>` 3.7 and `<office:text>` 3.4.

The `<table:data-pilot-tables>` element has no attributes.

The `<table:data-pilot-tables>` element has the following child element: `<table:data-pilot-table>` 9.6.3.

9.6.3 <table:data-pilot-table>

The `<table:data-pilot-table>` element contains the elements that define the sources of a data pilot table.

The `<table:data-pilot-table>` element is usable within the following element: `<table:data-pilot-tables>` 9.6.2.

The `<table:data-pilot-table>` element has the following attributes: `table:application-data` 19.584, `table:buttons` 19.589, `table:drill-down-on-double-click` 19.623, `table:grand-total` 19.644, `table:identify-categories` 19.649, `table:ignore-empty-rows` 19.650, `table:name` 19.673.7, `table:show-filter-button` 19.711 and `table:target-range-address` 19.731.2.

The `<table:data-pilot-table>` element has the following child elements: `<table:database-source-query>` 9.4.18, `<table:database-source-sql>` 9.4.16, `<table:database-source-table>` 9.4.17, `<table:data-pilot-field>` 9.6.7, `<table:source-cell-range>` 9.6.5 and `<table:source-service>` 9.6.6.

9.6.4 Data Pilot Table Source

The source of a data pilot table is specified by one of the following elements:

- `<table:database-source-query>` 9.4.18
- `<table:database-source-sql>` 9.4.16
- `<table:database-source-table>` 9.4.17
- `<table:source-cell-range>` 9.6.5
- `<table:source-service>` 9.6.6

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9.6.5 <table:source-cell-range>

The <table:source-cell-range> element specifies a cell range as a source of data for a data pilot table. A filter may be specified by a <table:filter> child element that is applied prior to return of data to a data pilot table.

The <table:source-cell-range> element is usable within the following element: <table:data-pilot-table> 9.6.3.

The <table:source-cell-range> element has the following attribute: table:cell-range-address 19.593.9.

The <table:source-cell-range> element has the following child element: <table:filter> 9.5.2.

9.6.6 <table:source-service>

The <table:source-service> element specifies a service that returns data to a data pilot table.

The <table:source-service> element is usable within the following element: <table:data-pilot-table> 9.6.3.

The <table:source-service> element has the following attributes: table:name 19.673.12, table:object-name 19.681, table:password 19.690, table:source-name 19.715 and table:user-name 19.746.

The <table:source-service> element has no child elements.

9.6.7 <table:data-pilot-field>

The <table:data-pilot-field> element specifies a field for a data pilot table.

The <table:data-pilot-field> element is usable within the following element: <table:data-pilot-table> 9.6.3.

The <table:data-pilot-field> element has the following attributes: table:function 19.643.3, table:is-data-layout-field 19.653, table:orientation 19.686.2, table:selected-page 19.708, table:source-field-name 19.714 and table:used-hierarchy 19.745.

The <table:data-pilot-field> element has the following child elements: <table:data-pilot-field-reference> 9.6.16, <table:data-pilot-groups> 9.6.17 and <table:data-pilot-level> 9.6.8.

9.6.8 <table:data-pilot-level>

The <table:data-pilot-level> element acts as a container for elements that specify addition information about a data pilot field.

The <table:data-pilot-level> element is usable within the following element: <table:data-pilot-field> 9.6.7.

The <table:data-pilot-level> element has the following attribute: table:show-empty 19.710.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:data-pilot-level> element has the following child elements: <table:data-pilot-display-info> 9.6.13, <table:data-pilot-layout-info> 9.6.15, <table:data-pilot-members> 9.6.11, <table:data-pilot-sort-info> 9.6.14 and <table:data-pilot-subtotals> 9.6.9.

9.6.9 <table:data-pilot-subtotals>

The <table:data-pilot-subtotals> element contains the <table:data-pilot-subtotal> elements for a data pilot table.

The <table:data-pilot-subtotals> element is usable within the following element: <table:data-pilot-level> 9.6.8.

The <table:data-pilot-subtotals> element has no attributes.

The <table:data-pilot-subtotals> element has the following child element: <table:data-pilot-subtotal> 9.6.10.

9.6.10 <table:data-pilot-subtotal>

The <table:data-pilot-subtotal> element contains the results of a single subtotal calculation.

The <table:data-pilot-subtotal> element is usable within the following element: <table:data-pilot-subtotals> 9.6.9.

The <table:data-pilot-subtotal> element has the following attribute: table:function 19.643.4.

The <table:data-pilot-subtotal> element has no child elements.

9.6.11 <table:data-pilot-members>

The <table:data-pilot-members> element specifies whether category columns in data pilot tables or information for category columns is displayed or not.

The <table:data-pilot-members> element is usable within the following element: <table:data-pilot-level> 9.6.8.

The <table:data-pilot-members> element has no attributes.

The <table:data-pilot-members> element has the following child element: <table:data-pilot-member> 9.6.12.

9.6.12 <table:data-pilot-member>

The <table:data-pilot-member> element specifies what information is displayed for a member.

The <table:data-pilot-member> element is usable within the following element: <table:data-pilot-members> 9.6.11.

The <table:data-pilot-member> element has the following attributes: table:display 19.617, table:name 19.673.6 and table:show-details 19.709.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:data-pilot-member> element has no child elements.

9.6.13 <table:data-pilot-display-info>

The <table:data-pilot-display-info> element restricts the number rows that are displayed for a category column to a specific number of values of a data field.

The <table:data-pilot-display-info> element is usable within the following element: <table:data-pilot-level> 9.6.8.

The <table:data-pilot-display-info> element has the following attributes: table:data-field 19.607, table:display-member-mode 19.622, table:enabled 19.625 and table:member-count 19.667.

The <table:data-pilot-display-info> element has no child elements.

9.6.14 <table:data-pilot-sort-info>

The <table:data-pilot-sort-info> element specifies how the members of a category column are sorted.

The <table:data-pilot-sort-info> element is usable within the following element: <table:data-pilot-level> 9.6.8.

The <table:data-pilot-sort-info> element has the following attributes: table:data-field 19.607, table:order 19.685, table:sort-mode 19.712.

The <table:data-pilot-sort-info> element has no child elements.

9.6.15 <table:data-pilot-layout-info>

The <table:data-pilot-layout-info> element specifies how to layout a field.

The <table:data-pilot-layout-info> element is usable within the following element: <table:data-pilot-level> 9.6.8.

The <table:data-pilot-layout-info> element has the following attributes: table:add-empty-lines 19.582 and table:layout-mode 19.662.

The <table:data-pilot-layout-info> element has no child elements.

9.6.16 <table:data-pilot-field-reference>

The <table:data-pilot-field-reference> element specifies data which can be used to modify the displayed values of data fields.

The <table:data-pilot-field-reference> element is usable within the following element: <table:data-pilot-field> 9.6.7.

The <table:data-pilot-field-reference> element has the following attributes: table:field-name 19.636, table:member-name 19.668, table:member-type 19.669 and table:type 19.735.2.

The <table:data-pilot-field-reference> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

9.6.17 <table:data-pilot-groups>

The <table:data-pilot-groups> element specifies that a data pilot field is a group field. A group field allows grouping of other fields.

Grouping may also take place for numeric or date values.

The <table:data-pilot-groups> element is usable within the following element: <table:data-pilot-field> 9.6.7.

The <table:data-pilot-groups> element has the following attributes: table:date-end 19.612, table:date-start 19.613, table:end 19.626, table:grouped-by 19.646, table:source-field-name 19.714, table:start 19.717 and table:step 19.723.

The <table:data-pilot-groups> element has the following child element: <table:data-pilot-group> 9.6.18.

9.6.18 <table:data-pilot-group>

The <table:data-pilot-group> element specifies names of groups if grouping takes place by specifying the member names.

The <table:data-pilot-group> element is usable within the following element: <table:data-pilot-groups> 9.6.17.

The <table:data-pilot-group> element has the following attribute: table:name 19.673.4.

The <table:data-pilot-group> element has the following child element: <table:data-pilot-group-member> 9.6.19.

9.6.19 <table:data-pilot-group-member>

The <table:data-pilot-group-member> element specifies the name of a single group member.

The <table:data-pilot-group-member> element is usable within the following element: <table:data-pilot-group> 9.6.18.

The <table:data-pilot-group-member> element has the following attribute: table:name 19.673.5.

The <table:data-pilot-group-member> element has no child elements.

9.7 <table:consolidation>

The <table:consolidation> element defines the consolidation of data from multiple table ranges. Consolidation means that a new table range is filled with values calculated by applying a mathematical function to all cells in the source table ranges that have the same relative address within these ranges.

The <table:consolidation> element is usable within the following elements: <office:chart> 3.8, <office:drawing> 3.5, <office:presentation> 3.6, <office:spreadsheet> 3.7 and <office:text> 3.4.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:consolidation> element has the following attributes: table:function 19.643.2, table:link-to-source-data 19.663, table:source-cell-range-addresses 19.713, table:target-cell-address 19.730 and table:use-labels 19.742.

The <table:consolidation> element has no child elements.

9.8 <table:dde-links>

The <table:dde-links> container element stores all DDE links for use in spreadsheet formulas. Every link contains the DDE Source and the data of the last connection.

See 14.6 for the use of DDE connections.

The <table:dde-links> element is usable within the following elements: <office:chart> 3.8, <office:drawing> 3.5, <office:presentation> 3.6, <office:spreadsheet> 3.7 and <office:text> 3.4.

The <table:dde-links> element has no attributes.

The <table:dde-links> element has the following child element: <table:dde-link> 14.6.4.

9.9 Change Tracking in Spreadsheets

9.9.1 General

All changes that have been applied to a spreadsheet document are stored in a list. The list contains an element for each change made to the table.

9.9.2 <table:tracked-changes>

The <table:tracked-changes> element is a container for tracked changes of a spreadsheet. Its presence further enables change tracking for a spreadsheet.

The <table:tracked-changes> element is usable within the following element: <office:spreadsheet> 3.7.

The <table:tracked-changes> element has the following attribute: table:track-changes 19.734.

The <table:tracked-changes> element has the following child elements: <table:cell-content-change> 9.9.17, <table:deletion> 9.9.9, <table:insertion> 9.9.3 and <table:movement> 9.9.13.

9.9.3 <table:insertion>

The <table:insertion> element contains the information that identifies any insertion of content. This content can be one or more rows, one or more columns, or a table.

The <table:insertion> element is usable within the following element: <table:tracked-changes> 9.9.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:insertion> element has the following attributes: table:acceptance-state 19.580, table:count 19.605, table:id 19.648, table:position 19.691, table:rejecting-change-id 19.702, table:table 19.727 and table:type 19.735.4.

The <table:insertion> element has the following child elements: <office:change-info> 5.5.6, <table:deletions> 9.9.6 and <table:dependencies> 9.9.4.

9.9.4 <table:dependencies>

The <table:dependencies> element contains the information on which other tracked changes a tracked change depends.

The <table:dependencies> element is usable within the following elements: <table:cell-content-change> 9.9.17, <table:deletion> 9.9.9, <table:insertion> 9.9.3 and <table:movement> 9.9.13.

The <table:dependencies> element has no attributes.

The <table:dependencies> element has the following child element: <table:dependency> 9.9.5.

9.9.5 <table:dependency>

The <table:dependency> element contains the information about one change action on which its parent element depends. The change action on which the current change depends is referenced by its table:id attribute

The <table:dependency> element is usable within the following element: <table:dependencies> 9.9.4.

The <table:dependency> element has the following attribute: table:id 19.648.

The <table:dependency> element has no child elements.

9.9.6 <table:deletions>

The <table:deletions> element contains all deletions which are performed while tracking a single change to a table.

The <table:deletions> element is usable within the following elements: <table:cell-content-change> 9.9.17, <table:deletion> 9.9.9, <table:insertion> 9.9.3 and <table:movement> 9.9.13.

The <table:deletions> element has no attributes.

The <table:deletions> element has the following child elements: <table:cell-content-deletion> 9.9.7 and <table:change-deletion> 9.9.8.

9.9.7 <table:cell-content-deletion>

The <table:cell-content-deletion> element specifies that a cell content has been deleted. It contains the address of the effected cell and its former content. If a table:id attribute is present, it specifies the id of a previously tracked change for the cell that gets deleted by the current change.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:cell-content-deletion> element is usable within the following element: <table:deletions> 9.9.6.

The <table:cell-content-deletion> element has the following attribute: table:id 19.648.

The <table:cell-content-deletion> element has the following child elements: <table:cell-address> 9.9.18 and <table:change-track-table-cell> 9.9.16.

9.9.8 <table:change-deletion>

The <table:change-deletion> element specifies the value of the table:id of a previously tracked change that is deleted by the current change.

The <table:change-deletion> element is usable within the following element: <table:deletions> 9.9.6.

The <table:change-deletion> element has the following attribute: table:id 19.648.

The <table:change-deletion> element has no child elements.

9.9.9 <table:deletion>

A <table:deletion> element contains content that was deleted while change tracking was enabled. The content of a cell that was deleted is contained in either a <table:dependencies>, or a <table:deletions> element.

The <table:deletion> element is usable within the following element: <table:tracked-changes> 9.9.2.

The <table:deletion> element has the following attributes: table:acceptance-state 19.580, table:id 19.648, table:multi-deletion-spanned 19.672, table:position 19.691, table:rejecting-change-id 19.702, table:table 19.727 and table:type 19.735.3.

The <table:deletion> element has the following child elements: <office:change-info> 5.5.6, <table:cut-offs> 9.9.10, <table:deletions> 9.9.6 and <table:dependencies> 9.9.4.

9.9.10 <table:cut-offs>

A <table:cut-offs> element contains elements that specify the location of tracked but deleted insertions or movements.

The <table:cut-offs> element is usable within the following element: <table:deletion> 9.9.9.

The <table:cut-offs> element has no attributes.

The <table:cut-offs> element has the following child elements: <table:insertion-cut-off> 9.9.11, <table:movement-cut-off> 9.9.12.

9.9.11 <table:insertion-cut-off>

The <table:insertion-cut-off> element specifies where an insertion was deleted.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:insertion-cut-off> element is usable within the following element: <table:cut-offs> 9.9.10.

The <table:insertion-cut-off> element has the following attributes: table:id 19.648 and table:position 19.691.

The <table:insertion-cut-off> element has no child elements.

9.9.12 <table:movement-cut-off>

The <table:movement-cut-off> element specifies the deletion of a movement.

The <table:movement-cut-off> element is usable within the following element: <table:cut-offs> 9.9.10.

The <table:movement-cut-off> element has the following attributes: table:end-position 19.629, table:position 19.691 and table:start-position 19.719.

The <table:movement-cut-off> element has no child elements.

9.9.13 <table:movement>

A <table:movement> element specifies the information that identifies movement of content. This content can be a cell content or a cell range content.

The <table:movement> element is usable within the following element: <table:tracked-changes> 9.9.2.

The <table:movement> element has the following attributes: table:acceptance-state 19.580, table:id 19.648 and table:rejecting-change-id 19.702.

The <table:movement> element has the following child elements: <office:change-info> 5.5.6, <table:deletions> 9.9.6, <table:dependencies> 9.9.4, <table:source-range-address> 9.9.14 and <table:target-range-address> 9.9.15.

9.9.14 <table:source-range-address>

The <table:source-range-address> element specifies the source or cell range address of a movement.

The <table:source-range-address> element is usable within the following element: <table:movement> 9.9.13.

The <table:source-range-address> element has the following attributes: table:column 19.594, table:end-column 19.628, table:end-row 19.630, table:end-table 19.631, table:row 19.704, table:start-column 19.718, table:start-row 19.720, table:start-table 19.721 and table:table 19.727.

The <table:source-range-address> element has no child elements.

9.9.15 <table:target-range-address>

The <table:target-range-address> element specifies the target cell address or cell range address of a movement.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:target-range-address> element is usable within the following element: <table:movement> 9.9.13.

The <table:target-range-address> element has the following attributes: table:column 19.594, table:end-column 19.628, table:end-row 19.630, table:end-table 19.631, table:row 19.704, table:start-column 19.718, table:start-row 19.720, table:start-table 19.721 and table:table 19.727.

The <table:target-range-address> element has no child elements.

9.9.16 <table:change-track-table-cell>

The <table:change-track-table-cell> element specifies the information that tracks changes to a table cell.

The <table:change-track-table-cell> element is usable within the following elements: <table:cell-content-deletion> 9.9.7 and <table:previous> 9.9.19.

The <table:change-track-table-cell> element has the following attributes: office:boolean-value 19.367, office:currency 19.369, office:date-value 19.370, office:string-value 19.379, office:time-value 19.382, office:value 19.384, office:value-type 19.385, table:cell-address 19.591, table:formula 19.642, table:matrix-covered 19.665, table:number-matrix-columns-spanned 19.679 and table:number-matrix-rows-spanned 19.680.

The <table:change-track-table-cell> element has the following child element: <text:p> 5.1.3.

9.9.17 <table:cell-content-change>

A <table:cell-content-change> element specifies the information that identifies changes of the cell content.

The <table:cell-content-change> element is usable within the following element: <table:tracked-changes> 9.9.2.

The <table:cell-content-change> element has the following attributes: table:acceptance-state 19.580, table:id 19.648 and table:rejecting-change-id 19.702.

The <table:cell-content-change> element has the following child elements: <office:change-info> 5.5.6, <table:cell-address> 9.9.18, <table:deletions> 9.9.6, <table:dependencies> 9.9.4 and <table:previous> 9.9.19.

9.9.18 <table:cell-address>

The <table:cell-address> element contains the address of a cell that has changed. Unlike other cell addresses, the cell address consists of the row, column and table number of the cell. This allows specifying addresses that are outside a valid cell address range.

The <table:cell-address> element is usable within the following elements: <table:cell-content-change> 9.9.17 and <table:cell-content-deletion> 9.9.7.

The <table:cell-address> element has the following attributes: table:column 19.594, table:row 19.704 and table:table 19.727.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:cell-address> element has no child elements.

9.9.19 <table:previous>

The <table:previous> element contains the previous cell content which is overwritten by the current change. If a table:id attribute is present, it specifies the id of a previously tracked change for the cell that is changed again by the current change.

The <table:previous> element is usable within the following element: <table:cell-content-change> 9.9.17.

The <table:previous> element has the following attribute: table:id 19.648.

The <table:previous> element has the following child element: <table:change-track-table-cell> 9.9.16.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10 Graphic Content

10.1 General

This chapter specifies the elements that represent graphic objects and elements used in the representation of graphical objects.

10.2 Enhanced Page Features for Graphical Applications

10.2.1 <style:handout-master>

The `<style:handout-master>` element represents a template for the generation of handout pages.

The `<style:handout-master>` element is usable within the following element: `<office:master-styles>` 3.15.4.

The `<style:handout-master>` element has the following attributes: `draw:style-name` 19.219.26, `presentation:presentation-page-layout-name` 19.409, `presentation:use-date-time-name` 19.424, `presentation:use-footer-name` 19.425, `presentation:use-header-name` 19.426 and `style:page-layout-name` 19.504.

The `<style:handout-master>` element has the following child elements: `<dr3d:scene>` 10.5.2, `<draw:a>` 10.4.12, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:connector>` 10.3.10, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:g>` 10.3.15, `<draw:line>` 10.3.3, `<draw:measure>` 10.3.12, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2 and `<draw:regular-polygon>` 10.3.6.

10.2.2 <draw:layer-set>

The `<draw:layer-set>` element defines a set of layers. If placed inside a `<style:master-page>` or `<draw:page>` element it defines a set of layers for that page. If placed inside the `<office:master-styles>` element it defines a set of layers for all pages that do not have their own set of layers.

Layers group drawing objects. Assigning a shape to a layer does not change its rendering order as defined by its `draw:z-index` attribute. 19.231

The `<draw:layer-set>` schema element contains a set of `<draw:layer>` elements.

The `<draw:layer-set>` element is usable within the following elements: `<draw:page>` 10.2.4, `<office:master-styles>` 3.15.4 and `<style:master-page>` 16.9.

The `<draw:layer-set>` element has no attributes.

The `<draw:layer-set>` element has the following child element: `<draw:layer>` 10.2.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.2.3 <draw:layer>

The <draw:layer> element defines a single layer. Layers group drawing objects.

Each drawing object inside a drawing or presentation document can be assigned to a layer. Each object that is assigned to a layer inherits the settings of that layer. Drawing objects may be assigned to these layers by the value of their draw:layer attribute.

The <draw:layer> element is usable within the following element: <draw:layer-set> 10.2.2.

The <draw:layer> element has the following attributes: draw:display 19.132, draw:name 19.197.14 and draw:protected 19.207.

The <draw:layer> element has the following child elements: <svg:desc> 10.3.18 and <svg:title> 10.3.17.

10.2.4 <draw:page>

The <draw:page> element is a container for content in a drawing or presentation document. This element is used for the following:

- Layers 10.2.2
- Forms 13.2
- Drawing Objects 10.3
- Frames 10.4
- Presentation Animations 10.9
- Presentation Notes 16.17

The <draw:page> element is usable within the following elements: <office:drawing> 3.5 and <office:presentation> 3.6.

The <draw:page> element has the following attributes: draw:id 19.187.3, draw:master-page-name 19.194, draw:name 19.197.19, draw:nav-order 19.198, draw:style-name 19.219.17, presentation:presentation-page-layout-name 19.409, presentation:use-date-time-name 19.424, presentation:use-footer-name 19.425, presentation:use-header-name 19.426 and xml:id 19.914.

The <draw:page> element has the following child elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3, <anim:audio> 15.5, <anim:command> 15.6.1, <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <anim:set> 15.2.4, <anim:transitionFilter> 15.2.7, <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:layer-set> 10.2.2, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:forms> 13.2, <presentation:animations> 10.8.1, <presentation:notes> 16.17, <svg:desc> 10.3.18 and <svg:title> 10.3.17.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.2.5 <draw:equation>

The <draw:equation> element specifies a formula for the calculation of a value and the name by which that formula can be referenced.

The <draw:equation> element is usable within the following element: <draw:enhanced-geometry> 10.6.2.

The <draw:equation> element has the following attributes: draw:formula 19.171 and draw:name 19.197.8.

The <draw:equation> element has no child elements.

10.3 Drawing Shapes

10.3.1 General

This section defines graphical objects that may occur within all types of documents.

10.3.2 <draw:rect>

The <draw:rect> element represents a rectangular drawing shape.

The <draw:rect> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:rect> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:corner-radius 19.127, draw:id 19.187.3, draw:layer 19.189, draw:name 19.197.25, draw:style-name 19.219.22, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:height 19.539.8, svg:rx 19.550, svg:ry 19.551, svg:width 19.571.10, svg:x 19.573.5, svg:y 19.577.5, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:rect> element has the following child elements: <draw:glue-point> 10.3.16, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18, <svg:title> 10.3.17, <text:list> 5.3.1 and <text:p> 5.1.3.

10.3.3 <draw:line>

The <draw:line> element represents a line.

The <draw:line> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:line> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:id 19.187.3, draw:layer 19.189, draw:name 19.197.15, draw:style-name 19.219.15, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:x1 19.574.1, svg:x2 19.575.1, svg:y1 19.578.1, svg:y2 19.579.1, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:line> element has the following child elements: <draw:glue-point> 10.3.16, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18, <svg:title> 10.3.17, <text:list> 5.3.1 and <text:p> 5.1.3.

10.3.4 <draw:polyline>

The <draw:polyline> element represents a polyline drawing shape.

Consumers may ignore svg:height and svg:width attributes, and determine the size of a shape from the polygon vertices.

The <draw:polyline> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:polyline> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:id 19.187.3, draw:layer 19.189, draw:name 19.197.24, draw:points 19.206, draw:style-name 19.219.21, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:height 19.539.8, svg:viewBox 19.570, svg:width 19.571.10, svg:x 19.573.5, svg:y 19.577.5, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:polyline> element has the following child elements: <draw:glue-point> 10.3.16, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18, <svg:title> 10.3.17, <text:list> 5.3.1 and <text:p> 5.1.3.

10.3.5 <draw:polygon>

The <draw:polygon> element represents a polygon. A polygon is a closed set of straight lines.

Consumers may ignore svg:height and svg:width attributes, and determine the size of a shape from the polygon vertices.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <draw:polygon> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:polygon> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:id 19.187.3, draw:layer 19.189, draw:name 19.197.23, draw:points 19.206, draw:style-name 19.219.20, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:height 19.539.8, svg:viewBox 19.570, svg:width 19.571.10, svg:x 19.573.5, svg:y 19.577.5, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:polygon> element has the following child elements: <draw:glue-point> 10.3.16, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18, <svg:title> 10.3.17, <text:list> 5.3.1 and <text:p> 5.1.3.

10.3.6 <draw:regular-polygon>

The <draw:regular-polygon> element represents a regular polygon. A regular polygon is a polygon that is specified by its number of edges (that is equal to the number of its corners), rather than by arbitrary points.

The <draw:regular-polygon> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:regular-polygon> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:concave 19.123, draw:corners 19.128, draw:id 19.187.3, draw:layer 19.189, draw:name 19.197.26, draw:sharpness 19.211, draw:style-name 19.219.23, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:height 19.539.8, svg:width 19.571.10, svg:x 19.573.5, svg:y 19.577.5, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:regular-polygon> element has the following child elements: <draw:glue-point> 10.3.16, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18, <svg:title> 10.3.17, <text:list> 5.3.1 and <text:p> 5.1.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.3.7 <draw:path>

The <draw:path> element represents a path. A path is a shape with a user-defined outline. The outline is defined by the svg:d attribute. 19.526

The <draw:path> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:path> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:id 19.187.3, draw:layer 19.189, draw:name 19.197.22, draw:style-name 19.219.19, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:d 19.526, svg:height 19.539.8, svg:viewBox 19.570, svg:width 19.571.10, svg:x 19.573.5, svg:y 19.577.5, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:path> element has the following child elements: <draw:glue-point> 10.3.16, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18, <svg:title> 10.3.17, <text:list> 5.3.1 and <text:p> 5.1.3.

10.3.8 <draw:circle>

The <draw:circle> element represents a circular drawing shape.

The <draw:circle> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:circle> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:end-angle 19.140, draw:id 19.187.3, draw:kind 19.188, draw:layer 19.189, draw:name 19.197.3, draw:start-angle 19.213, draw:style-name 19.219.8, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:cx 19.524.2, svg:cy 19.525.2, svg:height 19.539.8, svg:r 19.549.2, svg:width 19.571.10, svg:x 19.573.5, svg:y 19.577.5, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:circle> element has the following child elements: <draw:glue-point> 10.3.16, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18, <svg:title> 10.3.17, <text:list> 5.3.1 and <text:p> 5.1.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.3.9 <draw:ellipse>

The <draw:ellipse> element represents an ellipse.

The <draw:ellipse> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:ellipse> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:end-angle 19.140, draw:id 19.187.3, draw:kind 19.188, draw:layer 19.189, draw:name 19.197.7, draw:start-angle 19.213, draw:style-name 19.219.12, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:cx 19.524.3, svg:cy 19.525.3, svg:height 19.539.8, svg:rx 19.550, svg:ry 19.551, svg:width 19.571.10, svg:x 19.573.5, svg:y 19.577.5, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:ellipse> element has the following child elements: <draw:glue-point> 10.3.16, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18, <svg:title> 10.3.17, <text:list> 5.3.1 and <text:p> 5.1.3.

10.3.10 <draw:connector>

The <draw:connector> element represents a connected set of one or more lines that visually connects a start and an end point.

Start and/or end points can be defined by references to glue points 10.3.16 or as absolute positions. The connector's geometric path is defined by the svg:d 19.526 attribute. Consumers may also compute the connector's geometric path considering the draw:type 19.229.2 and draw:line-skew 19.190 attributes, and the formatting properties defined for connectors.

If the svg:d attribute is not present, the connector's geometric path is implementation-dependent. Producers should export the connector's geometric path using the svg:d attribute.

Note: This assists consumers that are not capable of computing a connector path.

The <draw:connector> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:connector> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:end-glue-point 19.142, draw:end-shape 19.144, draw:id 19.187.3, draw:layer 19.189, draw:line-skew 19.190, draw:name 19.197.4,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

draw:start-glue-point 19.215, draw:start-shape 19.217, draw:style-name 19.219.9, draw:text-style-name 19.227, draw:transform 19.228, draw:type 19.229.2, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:d 19.526, svg:viewBox 19.570, svg:x1 19.574.1, svg:x2 19.575.1, svg:y1 19.578.1, svg:y2 19.579.1, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:connector> element has the following child elements: <draw:glue-point> 10.3.16, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18, <svg:title> 10.3.17, <text:list> 5.3.1 and <text:p> 5.1.3.

10.3.11 <draw:caption>

The <draw:caption> element represents a description attached to a fixed point. It consists of rectangular drawing shape with an additional set of connected lines that connect the rectangle with the fixed point.

The <draw:caption> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:caption> element has the following attributes: draw:caption-id 19.115, draw:caption-point-x 19.116, draw:caption-point-y 19.117, draw:class-names 19.120, draw:corner-radius 19.127, draw:id 19.187.3, draw:layer 19.189, draw:name 19.197.2, draw:style-name 19.219.7, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:height 19.539.8, svg:width 19.571.10, svg:x 19.573.5, svg:y 19.577.5, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:caption> element has the following child elements: <draw:glue-point> 10.3.16, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18, <svg:title> 10.3.17, <text:list> 5.3.1 and <text:p> 5.1.3.

10.3.12 <draw:measure>

The <draw:measure> element represents a shape that is used to measure distances in drawings.

A measure shape consists of two parallel lines, called *extension lines*, and a line perpendicular to the extension lines, called a *dimension line*. The dimension line has arrows at its endpoints. It is displayed between the extension lines and terminated by them.

The positions of extension lines and the dimension line are determined by two reference points, called *start* and *end reference points*.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:line-distance style attribute defines the distance between the (virtual) line between the reference points, called *reference line*, and the dimension line. The draw:placing style attributes defines if the measure shape is placed above or below the reference line.

The start reference point is defined by the attributes svg:x1 and svg:y1

The first extension line is drawn on a line as defined by the vector from the start reference point to the start point of the dimension line. The extension line will start along this vector at a distance from the start reference point that is defined by the draw:guide-distance style attribute minus the value of draw:start-guide style attribute.

The end reference point is defined by the attributes svg:x2, and svg:y2.

The second extension line is drawn on a line as defined by the vector from the end reference point to the end point of the dimension line. The extension line will start along this vector at the distance from the end reference point that is defined by the draw:guide-distance style attribute minus the value of draw:end-guide style attribute.

The end points of the extension lines are at the distance defined by the draw:guide-overhang style attribute after the intersection with the dimension line.

The <draw:measure> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:measure> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:id 19.187.3, draw:layer 19.189, draw:name 19.197.17, draw:style-name 19.219.16, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:x1 19.574.1, svg:x2 19.575.1, svg:y1 19.578.1, svg:y2 19.579.1, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:measure> element has the following child elements: <draw:glue-point> 10.3.16, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18, <svg:title> 10.3.17, <text:list> 5.3.1 and <text:p> 5.1.3.

10.3.13 <draw:control>

The <draw:control> element represents a shape that is linked to a control inside an <office:forms> element.

The <draw:control> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <draw:control> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:control 19.125, draw:id 19.187.3, draw:layer 19.189, draw:name 19.197.5, draw:style-name 19.219.10, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:height 19.539.8, svg:width 19.571.10, svg:x 19.573.5, svg:y 19.577.5, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:control> element has the following child elements: <draw:glue-point> 10.3.16, <svg:desc> 10.3.18 and <svg:title> 10.3.17.

10.3.14 <draw:page-thumbnail>

The <draw:page-thumbnail> element represents a rectangular area that displays the thumbnail of a drawing page.

The <draw:page-thumbnail> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:page-thumbnail> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:id 19.187.3, draw:layer 19.189, draw:name 19.197.20, draw:page-number 19.203, draw:style-name 19.219.18, draw:transform 19.228, draw:z-index 19.231, presentation:class 19.389, presentation:class-names 19.390, presentation:placeholder 19.407, presentation:style-name 19.422, presentation:user-transformed 19.427, svg:height 19.539.8, svg:width 19.571.10, svg:x 19.573.5, svg:y 19.577.5, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:page-thumbnail> element has the following child elements: <svg:desc> 10.3.18 and <svg:title> 10.3.17.

10.3.15 <draw:g>

The <draw:g> element represents a group of drawing shapes.

Drawing shapes contained by a <draw:g> element that is itself contained by a <draw:a> element, act as hyperlinks using the xlink:href attribute of the containing <draw:a> element. If the included drawing shapes are themselves contained within <draw:a> elements, then the xlink:href attributes of those <draw:a> elements act as the hyperlink information for the shapes they contain.

The <draw:g> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:g> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:id 19.187.3, draw:name 19.197.11, draw:style-name 19.219.14, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:y 19.577.5, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:g> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:glue-point> 10.3.16, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18 and <svg:title> 10.3.17.

10.3.16 <draw:glue-point>

The <draw:glue-point> element specifies a point in the area of a drawing object to which a connector shape can connect. All drawing objects have four standard glue points located at the center of the four edges of the object's bounding box. Additional glue points may be added to a drawing object by inserting one or more <draw:glue-point> elements into a drawing object element.

The <draw:glue-point> element is usable within the following elements: <dr3d:scene> 10.5.2, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2 and <draw:regular-polygon> 10.3.6.

The <draw:glue-point> element has the following attributes: draw:align 19.111, draw:escape-direction 19.147, draw:id 19.187.2, svg:x 19.573.6 and svg:y 19.577.6.

The <draw:glue-point> element has no child elements.

10.3.17 <svg:title>

The <svg:title> element specifies a name for a graphic object.

The <svg:title> element is usable within the following elements: <dr3d:scene> 10.5.2, <draw:area-circle> 10.4.13.4, <draw:area-polygon> 10.4.13.5, <draw:area-rectangle> 10.4.13.3, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:layer> 10.2.3, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page> 10.2.4, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2 and <draw:regular-polygon> 10.3.6.

The <svg:title> element has no attributes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <svg:title> element has no child elements.

The <svg:title> element has character data content.

10.3.18 <svg:desc>

The <svg:desc> element specifies a prose description of a graphic object that may be used to support accessibility. See appendix D.

The <svg:desc> element is usable within the following elements: <dr3d:scene> 10.5.2, <draw:area-circle> 10.4.13.4, <draw:area-polygon> 10.4.13.5, <draw:area-rectangle> 10.4.13.3, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:layer> 10.2.3, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page> 10.2.4, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2 and <draw:regular-polygon> 10.3.6.

The <svg:desc> element has no attributes.

The <svg:desc> element has no child elements.

The <svg:desc> element has character data content.

10.3.19 <office:event-listeners>

The <office:event-listeners> element represents the attachment of an event listener to a drawing shape. See 14.4.

The <office:event-listeners> element is usable within the following elements: <draw:area-circle> 10.4.13.4, <draw:area-polygon> 10.4.13.5, <draw:area-rectangle> 10.4.13.3, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <form:button> 13.5.15, <form:checkbox> 13.5.17, <form:combobox> 13.5.11, <form:date> 13.5.8, <form:file> 13.5.5, <form:fixed-text> 13.5.10, <form:form> 13.3, <form:formatted-text> 13.5.6, <form:frame> 13.5.19, <form:generic-control> 13.5.25, <form:grid> 13.5.22, <form:hidden> 13.5.21, <form:image> 13.5.16, <form:image-frame> 13.5.20, <form:listbox> 13.5.13, <form:number> 13.5.7, <form:password> 13.5.4, <form:radio> 13.5.18, <form:text> 13.5.2, <form:textarea> 13.5.3, <form:time> 13.5.9, <form:value-range> 13.5.24, <office:scripts> 3.12, <table:content-validation> 9.4.5, <text:a> 6.1.8 and <text:execute-macro> 7.7.10.

The <office:event-listeners> element has no attributes.

The <office:event-listeners> element has the following child elements: <presentation:event-listener> 10.9.2 and <script:event-listener> 14.4.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.4 Frames

10.4.1 General

A frame is a container for enhanced content like text boxes, images or objects. A frame may contain multiple renditions of content. A consumer may choose the representation that it supports best.

Multiple representations may share `<svg:desc>` and `<svg:title>` elements.

Each child element of a frame is a different representation of the same content. The order of content elements reflects the document author's preference for rendering, with the first child element being preferred. That means that consumers should render the first child element that they support. A frame may contain multiple content elements, but shall contain at least one content element.

Within text documents, frames are also used to position content outside the default text flow of a document.

10.4.2 <draw:frame>

The `<draw:frame>` element represents a frame and serves as the container for elements that may occur in a frame.

Frame formatting properties are stored in styles belonging to the `graphic` family.

The `<draw:frame>` element is usable within the following elements: `<draw:a>` 10.4.12, `<draw:g>` 10.3.15, `<draw:page>` 10.2.4, `<draw:text-box>` 10.4.3, `<office:image>` 3.9, `<office:text>` 3.4, `<presentation:notes>` 16.17, `<style:handout-master>` 10.2.1, `<style:master-page>` 16.9, `<table:covered-table-cell>` 9.1.5, `<table:shapes>` 9.2.8, `<table:table-cell>` 9.1.4, `<text:a>` 6.1.8, `<text:deletion>` 5.5.4, `<text:h>` 5.1.2, `<text:index-body>` 8.2.2, `<text:index-title>` 8.2.3, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:note-body>` 6.3.4, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2, `<text:section>` 5.4 and `<text:span>` 6.1.7.

The `<draw:frame>` element has the following attributes: `draw:caption-id` 19.115, `draw:class-names` 19.120, `draw:copy-of` 19.126, `draw:id` 19.187.3, `draw:layer` 19.189, `draw:name` 19.197.10, `draw:style-name` 19.219.13, `draw:text-style-name` 19.227, `draw:transform` 19.228, `draw:z-index` 19.231, `presentation:class` 19.389, `presentation:class-names` 19.390, `presentation:placeholder` 19.407, `presentation:style-name` 19.422, `presentation:user-transformed` 19.427, `style:rel-height` 19.509, `style:rel-width` 19.510.2, `svg:height` 19.539.8, `svg:width` 19.571.10, `svg:x` 19.573.5, `svg:y` 19.577.5, `table:end-cell-address` 19.627, `table:end-x` 19.632, `table:end-y` 19.633, `table:table-background` 19.728, `text:anchor-page-number` 19.753, `text:anchor-type` 19.754 and `xml:id` 19.914.

The `<draw:frame>` element has the following child elements: `<draw:applet>` 10.4.7, `<draw:contour-path>` 10.4.11.3, `<draw:contour-polygon>` 10.4.11.2, `<draw:floating-frame>` 10.4.10, `<draw:glue-point>` 10.3.16, `<draw:image>` 10.4.4, `<draw:image-map>` 10.4.13.2, `<draw:object>` 10.4.6.2, `<draw:object-ole>` 10.4.6.3, `<draw:plugin>` 10.4.8, `<draw:text-box>` 10.4.3, `<office:event-listeners>` 10.3.19, `<svg:desc>` 10.3.18, `<svg:title>` 10.3.17 and `<table:table>` 9.1.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.4.3 <draw:text-box>

The <draw:text-box> element represents a text box. This element may be used to place text in a container that is outside of the flow of the document.

The <draw:text-box> element is usable within the following element: <draw:frame> 10.4.2.

The <draw:text-box> element has the following attributes: draw:chain-next-name 19.118, draw:corner-radius 19.127, fo:max-height 19.238, fo:max-width 19.239, fo:min-height 19.240, fo:min-width 19.241, text:id 19.809.2 and xml:id 19.914.

The <draw:text-box> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <table:table> 9.1.2, <text:alphabetical-index> 8.8, <text:bibliography> 8.9, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:h> 5.1.2, <text:illustration-index> 8.4, <text:list> 5.3.1, <text:numbered-paragraph> 5.3.6, <text:object-index> 8.6, <text:p> 5.1.3, <text:section> 5.4, <text:soft-page-break> 5.6, <text:table-index> 8.5, <text:table-of-content> 8.3 and <text:user-index> 8.7.

10.4.4 <draw:image>

The <draw:image> element represents an image. An image can be either:

- A link to an external resource

or

- Embedded in the document

Note: While the image data may have an arbitrary format, vector graphics should be stored in the [SVG] format and bitmap graphics in the [PNG] format.

The <draw:image> element is usable within the following element: <draw:frame> 10.4.2.

The <draw:image> element has the following attributes: draw:filter-name 19.170, xlink:actuate 19.909, xlink:href 19.910.15, xlink:show 19.911, xlink:type 19.913 and xml:id 19.914.

The <draw:image> element has the following child elements: <office:binary-data> 10.4.5, <text:list> 5.3.1 and <text:p> 5.1.3.

10.4.5 <office:binary-data>

The <office:binary-data> element contains image data in BASE64 encoding (as defined in [RFC2045]). If this element is present, an xlink:href attribute in its parent element shall be ignored.

Note: The image data may be in an arbitrary data format. Consumers have to analyze the image data to determine the data format that is used.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <office:binary-data> element is usable within the following elements: <draw:image> 10.4.4, <draw:object-ole> 10.4.6.3, <style:background-image> 17.3 and <text:list-level-style-image> 16.33.

The <office:binary-data> element has no attributes.

The <office:binary-data> element has no child elements.

The <office:binary-data> element has content of data type base64Binary 18.2.

10.4.6 Objects

10.4.6.1 General

A document in OpenDocument format can contain two types of embedded objects, as follows:

- Objects that have an OpenDocument representation.
- Objects that do not have an OpenDocument representation.

Note: OLE objects are an example of objects without an OpenDocument representation. See [OLE].

10.4.6.2 <draw:object>

The <draw:object> element represents objects that have a OpenDocument representation.

Objects with an OpenDocument representation can either be:

- Contained in the same package as a document, in which case the Object is a subdocument within the package. The xlink:href attribute of this element references that folder.
- Contained in a separate OpenDocument document instance. The xlink:href attribute of this element references that document's package.
- Contained in a child <office:document> element of this element.
- Contained in a child <math:math> element of this element.

Note: An image representation of an object should be included in a frame in addition to the object itself.

The <draw:object> element is usable within the following element: <draw:frame> 10.4.2.

The <draw:object> element has the following attributes: draw:notify-on-update-of-ranges 19.200, xlink:actuate 19.909, xlink:href 19.910.16, xlink:show 19.911, xlink:type 19.913 and xml:id 19.914.

The <draw:object> element has the following child elements: <math:math> 14.5 and <office:document> 3.1.2.

10.4.6.3 <draw:object-ole>

The <draw:object-ole> element represents objects that do not have an OpenDocument representation.

Objects without an OpenDocument representation can either be:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- Contained in the same package as a document, in which case it is contained in a file within the package. The `xlink:href` attribute of this element references that file.
- Contained in a separate file. The `xlink:href` attribute of this element references that file.
- Contained in a child `<office:binary-data>` element of this element.

The `<draw:object-ole>` element is usable within the following element: `<draw:frame>` 10.4.2.

The `<draw:object-ole>` element has the following attributes: `draw:class-id` 19.119, `xlink:actuate` 19.909, `xlink:href` 19.910.17, `xlink:show` 19.911, `xlink:type` 19.913 and `xml:id` 19.914.

The `<draw:object-ole>` element has the following child element: `<office:binary-data>` 10.4.5.

10.4.7 <draw:applet>

The `<draw:applet>` element represents an applet that is embedded in a document. Its semantics are the same as the `<applet>` element in HTML. §13.4 of [HTML4]. This element shall have either a `draw:code` or `draw:object` attribute.

The applet name, width, height, margins, title and description are specified by the `<draw:applet>` element's `<draw:frame>` parent element. The `<draw:applet>` element does not support character data content.

The `<draw:applet>` element is usable within the following element: `<draw:frame>` 10.4.2.

The `<draw:applet>` element has the following attributes: `draw:archive` 19.113, `draw:code` 19.121, `draw:may-script` 19.195, `draw:object` 19.201, `xlink:actuate` 19.909, `xlink:href` 19.910.9, `xlink:show` 19.911, `xlink:type` 19.913 and `xml:id` 19.914.

The `<draw:applet>` element has the following child element: `<draw:param>` 10.4.9.

10.4.8 <draw:plugin>

The `<draw:plugin>` element represents an external application that processes data with a specified media-type.

How OpenDocument consumers interact with external applications is not defined by this specification.

Note: Consumers are responsible for any and all security issues that may arise from interaction with an external application referenced by a `<draw:plugin>` element.

The `<draw:plugin>` element is usable within the following element: `<draw:frame>` 10.4.2.

The `<draw:plugin>` element has the following attributes: `draw:mime-type` 19.191, `xlink:actuate` 19.909, `xlink:href` 19.910.18, `xlink:show` 19.911, `xlink:type` 19.913 and `xml:id` 19.914.

The `<draw:plugin>` element has the following child element: `<draw:param>` 10.4.9.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.4.9 <draw:param>

The <draw:param> element contains parameters that are passed to an applet or plugin when they are initialized.

The <draw:param> element is usable within the following elements: <draw:applet> 10.4.7 and <draw:plugin> 10.4.8.

The <draw:param> element has the following attributes: draw:name 19.197.21 and draw:value 19.230.

The <draw:param> element has no child elements.

10.4.10 <draw:floating-frame>

The <draw:floating-frame> element represents a frame that is embedded in a document.

Floating frames cannot be transformed as described in section 19.228.

The <draw:floating-frame> element is usable within the following element: <draw:frame> 10.4.2.

The <draw:floating-frame> element has the following attributes: draw:frame-name 19.172, xlink:actuate 19.909, xlink:href 19.910.14, xlink:show 19.911, xlink:type 19.913 and xml:id 19.914.

The <draw:floating-frame> element has no child elements.

10.4.11 Contours

10.4.11.1 General

The <draw:contour-polygon> and <draw:contour-path> elements are used to specify contours to be applied to object or images.

Consumers should support pixel lengths for the svg:width and svg:height attributes of the <draw:contour-polygon> and <draw:contour-path> elements.

Note: A contour of an object or image establishes an outer boundary around an object or image. One use would be the wrapping of text around a contour specified for an image, if style:wrap-contour="true" and a contour is specified.

10.4.11.2 <draw:contour-polygon>

The <draw:contour-polygon> element specifies a contour using a polygon.

The <draw:contour-polygon> element is usable within the following element: <draw:frame> 10.4.2.

The <draw:contour-polygon> element has the following attributes: draw:points 19.206, draw:recreate-on-edit 19.208, svg:height 19.539.6, svg:viewBox 19.570 and svg:width 19.571.8.

The <draw:contour-polygon> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.4.11.3 <draw:contour-path>

The <draw:contour-path> element specifies a contour using a path.

The <draw:contour-path> element is usable within the following element: <draw:frame> 10.4.2.

The <draw:contour-path> element has the following attributes: draw:recreate-on-edit 19.208, svg:d 19.526, svg:height 19.539.6, svg:viewBox 19.570 and svg:width 19.571.8.

The <draw:contour-path> element has no child elements.

10.4.12 <draw:a>

The <draw:a> element enables both frames and drawing shapes to act as hyperlinks.

The <draw:a> element contains a drawing shape that should behave as a hyperlink.

The <draw:a> element is usable within the following elements: <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

The <draw:a> element has the following attributes: office:name 19.376.2, office:server-map 19.378, office:target-frame-name 19.381, office:title 19.383, xlink:actuate 19.909, xlink:href 19.910.8, xlink:show 19.911, xlink:type 19.913 and xml:id 19.914.

The <draw:a> element has the following child elements: <dr3d:scene> 10.5.2, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2 and <draw:regular-polygon> 10.3.6.

10.4.13 Client Side Image Maps

10.4.13.1 General

An client side image map is a collection of hyperlinks that are associated with graphic elements. The image map is a sequence of image map elements. Each image map element associates a hyperlink with an area. The area can be a rectangle, circle or polygon.

10.4.13.2 <draw:image-map>

The <draw:image-map> element represents an image map.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Image map elements are specified as absolute positions relative to the original size of its associated graphical element. OpenDocument consumer shall scale the image map to match the current size of the image.

The `<draw:image-map>` element is usable within the following element: `<draw:frame>` 10.4.2.

The `<draw:image-map>` element has no attributes.

The `<draw:image-map>` element has the following child elements: `<draw:area-circle>` 10.4.13.4, `<draw:area-polygon>` 10.4.13.5 and `<draw:area-rectangle>` 10.4.13.3.

10.4.13.3 <draw:area-rectangle>

The `<draw:area-rectangle>` element specifies a rectangular image map area.

The `<draw:area-rectangle>` element is usable within the following element: `<draw:image-map>` 10.4.13.2.

The `<draw:area-rectangle>` element has the following attributes: `draw:nohref` 19.199, `office:name` 19.376.4, `office:target-frame-name` 19.381, `svg:height` 19.539.5, `svg:width` 19.571.7, `svg:x` 19.573.3, `svg:y` 19.577.3, `xlink:href` 19.910.12, `xlink:show` 19.911 and `xlink:type` 19.913.

The `<draw:area-rectangle>` element has the following child elements: `<office:event-listeners>` 10.3.19, `<svg:desc>` 10.3.18 and `<svg:title>` 10.3.17.

10.4.13.4 <draw:area-circle>

The `<draw:area-circle>` element represents a circular image map area.

The `<draw:area-circle>` element is usable within the following element: `<draw:image-map>` 10.4.13.2.

The `<draw:area-circle>` element has the following attributes: `draw:nohref` 19.199, `office:name` 19.376.3, `office:target-frame-name` 19.381, `svg:cx` 19.524.1, `svg:cy` 19.525.1, `svg:r` 19.549.1, `xlink:href` 19.910.10, `xlink:show` 19.911 and `xlink:type` 19.913.

The `<draw:area-circle>` element has the following child elements: `<office:event-listeners>` 10.3.19, `<svg:desc>` 10.3.18 and `<svg:title>` 10.3.17.

10.4.13.5 <draw:area-polygon>

The `<draw:area-polygon>` element specifies a polygonal image map area. A polygonal image map area has the following components:

- A bounding box.
  The bounding box establishes the reference frame for the view box and the polygon point sequence. The reference frame enables the coordinates to be translated into absolute coordinates.
- A view box.
  The view box attribute establishes a coordinate system for the point sequence. The view box avoids the need to record every point of the point sequence as absolute coordinates with length and unit of measurement.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- A sequence of points in view box-coordinates in the `draw:points` attribute.

Note: For more information about how to represent polygons, see `<draw:polygon>` 10.3.5.

The `<draw:area-polygon>` element is usable within the following element: `<draw:image-map>` 10.4.13.2.

The `<draw:area-polygon>` element has the following attributes: `draw:nohref` 19.199, `draw:points` 19.206, `office:name` 19.376.5, `office:target-frame-name` 19.381, `svg:height` 19.539.4, `svg:viewBox` 19.570, `svg:width` 19.571.6, `svg:x` 19.573.2, `svg:y` 19.577.2, `xlink:href` 19.910.11, `xlink:show` 19.911 and `xlink:type` 19.913.

The `<draw:area-polygon>` element has the following child elements: `<office:event-listeners>` 10.3.19, `<svg:desc>` 10.3.18 and `<svg:title>` 10.3.17.

10.5 3D Shapes

10.5.1 General

3D shapes are used to define three-dimensional coordinate systems and geometrical figures within them. All OpenDocument 3D coordinate systems are right-handed. Geometry is represented by a tree of scenes. Each scene may contain zero or more 3D shapes, with a scene being a special case of shape. The root scene defines the world coordinate system. Each 3D shape may define a local coordinate system relative to its parent 3D scene.

10.5.2 <dr3d:scene>

The `<dr3d:scene>` element is the only element that can contain three-dimensional shapes. Like the `<draw:g>` element it groups shapes, but it also defines the projection, lighting, and other rendering details for the shapes inside the scene.

The `<dr3d:scene>` element is usable within the following elements: `<dr3d:scene>` 10.5.2, `<draw:a>` 10.4.12, `<draw:g>` 10.3.15, `<draw:page>` 10.2.4, `<draw:text-box>` 10.4.3, `<office:text>` 3.4, `<presentation:notes>` 16.17, `<style:handout-master>` 10.2.1, `<style:master-page>` 16.9, `<table:covered-table-cell>` 9.1.5, `<table:shapes>` 9.2.8, `<table:table-cell>` 9.1.4, `<text:a>` 6.1.8, `<text:deletion>` 5.5.4, `<text:h>` 5.1.2, `<text:index-body>` 8.2.2, `<text:index-title>` 8.2.3, `<text:meta>` 6.1.9, `<text:meta-field>` 7.5.19, `<text:note-body>` 6.3.4, `<text:p>` 5.1.3, `<text:ruby-base>` 6.4.2, `<text:section>` 5.4 and `<text:span>` 6.1.7.

The `<dr3d:scene>` element has the following attributes: `dr3d:ambient-color` 19.92, `dr3d:distance` 19.96, `dr3d:focal-length` 19.98, `dr3d:lighting-mode` 19.99.3, `dr3d:projection` 19.102, `dr3d:shade-mode` 19.103, `dr3d:shadow-slant` 19.104, `dr3d:transform` 19.107, `dr3d:vpn` 19.108, `dr3d:vrp` 19.109, `dr3d:vup` 19.110, `draw:caption-id` 19.115, `draw:class-names` 19.120, `draw:id` 19.187.3, `draw:layer` 19.189, `draw:style-name` 19.219.5, `draw:z-index` 19.231, `presentation:class-names` 19.390, `presentation:style-name` 19.422, `svg:height` 19.539.3, `svg:width` 19.571.5, `svg:x` 19.573.4, `svg:y` 19.577.4, `table:end-cell-address` 19.627, `table:end-x` 19.632, `table:end-y` 19.633, `table:table-background` 19.728, `text:anchor-page-number` 19.753, `text:anchor-type` 19.754 and `xml:id` 19.914.

The `<dr3d:scene>` element has the following child elements: `<dr3d:cube>` 10.5.4, `<dr3d:extrude>` 10.5.6, `<dr3d:light>` 10.5.3, `<dr3d:rotate>` 10.5.7, `<dr3d:scene>`

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.5.2, <dr3d:sphere> 10.5.5, <draw:glue-point> 10.3.16, <svg:desc> 10.3.18 and <svg:title> 10.3.17.

10.5.3 <dr3d:light>

The <dr3d:light> element represents a light inside a scene.

Note: There may be several lights, but consumers may limit the number of lights per scene to 8.

The <dr3d:light> element is usable within the following elements: <chart:plot-area> 11.4 and <dr3d:scene> 10.5.2.

The <dr3d:light> element has the following attributes: dr3d:diffuse-color 19.94, dr3d:direction 19.95, dr3d:enabled 19.97 and dr3d:specular 19.106.

The <dr3d:light> element has no child elements.

10.5.4 <dr3d:cube>

The <dr3d:cube> element represents a three-dimensional cube shape.

The <dr3d:cube> element is usable within the following element: <dr3d:scene> 10.5.2.

The <dr3d:cube> element has the following attributes: dr3d:max-edge 19.100, dr3d:min-edge 19.101, dr3d:transform 19.107, draw:class-names 19.120, draw:id 19.187.3, draw:layer 19.189, draw:style-name 19.219.2, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422 and xml:id 19.914.

The <dr3d:cube> element has no child elements.

10.5.5 <dr3d:sphere>

The <dr3d:sphere> element represents a three-dimensional sphere shape.

The <dr3d:sphere> element is usable within the following element: <dr3d:scene> 10.5.2.

The <dr3d:sphere> element has the following attributes: dr3d:center 19.93, dr3d:size 19.105, dr3d:transform 19.107, draw:class-names 19.120, draw:id 19.187.3, draw:layer 19.189, draw:style-name 19.219.6, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422 and xml:id 19.914.

The <dr3d:sphere> element has no child elements.

10.5.6 <dr3d:extrude>

The <dr3d:extrude> element represents a three-dimensional extruded object based on the given polygon. The 3D geometry is formed by extruding a polygon perpendicular to the plane of the given polygon by a depth (see dr3d:depth, 20.72), creating a front face, a back face and side faces. The side faces are formed by connecting all corresponding single edges of the front and back faces. When no depth is given, the polygon forms a shape without depth. The closing of the front face depends on the value of the dr3d:close-front attribute 20.71. The closing of the back face depends on the value of the dr3d:close-back attribute 20.70. The size of the

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

back face can be relative to the size of the front face when the dr3d:back-scale attribute is used. The side faces defined by the extrusion of the shape are always closed.

The <dr3d:extrude> element is usable within the following element: <dr3d:scene> 10.5.2.

The <dr3d:extrude> element has the following attributes: dr3d:transform 19.107, draw:class-names 19.120, draw:id 19.187.3, draw:layer 19.189, draw:style-name 19.219.3, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:d 19.526, svg:viewBox 19.570 and xml:id 19.914.

The <dr3d:extrude> element has no child elements.

10.5.7 <dr3d:rotate>

The <dr3d:rotate> element represents a three-dimensional rotation shape based on the given polygon. The 3D geometry is defined by rotating the XY-plane with the polygon around the Y-axis of the local coordinate system. This rotation is linearly interpolated in the given number of steps (dr3d:horizontal-segments 20.78) around the given angle (dr3d:end-angle 20.77). The side faces are formed by connecting all corresponding single edges of a neighboring pairs of rotated polygons. By default, the rotation uses a full rotation (360 degrees, dr3d:end-angle attribute 20.77). In that case the 3D geometry is implicitly closed and no front face or back face is created (unless they are of different sizes). If the rotation is different, a front face is created using the first, unrotated polygon and a back face is created using the last rotated polygon. The closing of a front face also depends on the value of the dr3d:close-front attribute 20.71 and the closing of a back face on the value of the dr3d:close-back 20.70 attribute. The size of the back face can be different than the size of the front face when the dr3d:back-scale attribute 20.68 is used.

The <dr3d:rotate> element is usable within the following element: <dr3d:scene> 10.5.2.

The <dr3d:rotate> element has the following attributes: dr3d:transform 19.107, draw:class-names 19.120, draw:id 19.187.3, draw:layer 19.189, draw:style-name 19.219.4, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:d 19.526, svg:viewBox 19.570 and xml:id 19.914.

The <dr3d:rotate> element has no child elements.

10.6 Custom Shape

10.6.1 <draw:custom-shape>

The <draw:custom-shape> element represents a complex figure. It supports font geometry effects and extrusion. A custom shape may have a geometry that influences its shape.

The <draw:custom-shape> element is usable within the following elements: <draw:a> 10.4.12, <draw:g> 10.3.15, <draw:page> 10.2.4, <draw:text-box> 10.4.3, <office:text> 3.4, <presentation:notes> 16.17, <style:handout-master> 10.2.1, <style:master-page> 16.9, <table:covered-table-cell> 9.1.5, <table:shapes> 9.2.8, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:deletion> 5.5.4, <text:h> 5.1.2, <text:index-body> 8.2.2, <text:index-title> 8.2.3, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:note-body> 6.3.4, <text:p> 5.1.3, <text:ruby-base> 6.4.2, <text:section> 5.4 and <text:span> 6.1.7.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <draw:custom-shape> element has the following attributes: draw:caption-id 19.115, draw:class-names 19.120, draw:data 19.131, draw:engine 19.146, draw:id 19.187.3, draw:layer 19.189, draw:name 19.197.6, draw:style-name 19.219.11, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, presentation:class-names 19.390, presentation:style-name 19.422, svg:height 19.539.8, svg:width 19.571.10, svg:x 19.573.5, svg:y 19.577.5, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <draw:custom-shape> element has the following child elements: <draw:enhanced-geometry> 10.6.2, <draw:glue-point> 10.3.16, <office:event-listeners> 10.3.19, <svg:desc> 10.3.18, <svg:title> 10.3.17, <text:list> 5.3.1 and <text:p> 5.1.3.

10.6.2 <draw:enhanced-geometry>

The <draw:enhanced-geometry> element contains the geometry for a <draw:custom-shape> element if its draw:engine attribute has been omitted.

The <draw:enhanced-geometry> element is usable within the following element: <draw:custom-shape> 10.6.1.

The <draw:enhanced-geometry> element has the following attributes: dr3d:projection 19.102, dr3d:shade-mode 19.103, draw:concentric-gradient-fill-allowed 19.124, draw:enhanced-path 19.145, draw:extrusion 19.148, draw:extrusion-allowed 19.149, draw:extrusion-brightness 19.150, draw:extrusion-color 19.151, draw:extrusion-depth 19.152, draw:extrusion-diffusion 19.153, draw:extrusion-first-light-direction 19.154, draw:extrusion-first-light-harsh 19.155, draw:extrusion-first-light-level 19.156, draw:extrusion-light-face 19.157, draw:extrusion-metal 19.158, draw:extrusion-number-of-line-segments 19.159, draw:extrusion-origin 19.160, draw:extrusion-rotation-angle 19.161, draw:extrusion-rotation-center 19.162, draw:extrusion-second-light-direction 19.163, draw:extrusion-second-light-harsh 19.164, draw:extrusion-second-light-level 19.165, draw:extrusion-shininess 19.166, draw:extrusion-skew 19.167, draw:extrusion-specularity 19.168, draw:extrusion-viewpoint 19.169, draw:glue-point-leaving-directions 19.173, draw:glue-points 19.175, draw:glue-point-type 19.174, draw:mirror-horizontal 19.192, draw:mirror-vertical 19.193, draw:modifiers 19.196, draw:path-stretchpoint-x 19.204, draw:path-stretchpoint-y 19.205, draw:text-areas 19.220, draw:text-path 19.221, draw:text-path-allowed 19.222, draw:text-path-mode 19.223, draw:text-path-same-letter-heights 19.224, draw:text-path-scale 19.225, draw:text-rotate-angle 19.226, draw:type 19.229.3 and svg:viewBox 19.570.

The <draw:enhanced-geometry> element has the following child elements: <draw:equation> 10.2.5 and <draw:handle> 10.6.3.

10.6.3 <draw:handle>

The <draw:handle> element represents a single interaction handle for a drawing shape.

The <draw:handle> element is usable within the following element: <draw:enhanced-geometry> 10.6.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <draw:handle> element has the following attributes: draw:handle-mirror-horizontal 19.176, draw:handle-mirror-vertical 19.177, draw:handle-polar 19.178, draw:handle-position 19.179, draw:handle-radius-range-maximum 19.180, draw:handle-radius-range-minimum 19.181, draw:handle-range-x-maximum 19.182, draw:handle-range-x-minimum 19.183, draw:handle-range-y-maximum 19.184, draw:handle-range-y-minimum 19.185 and draw:handle-switched 19.186.

The <draw:handle> element has no child elements.

10.7 Presentation Shapes

Presentation shapes are shapes on a draw page that are part of a presentation page layout.16.41 They use styles with a style family value of presentation, unlike drawing shapes which use styles with a style family value of graphic. Presentation shapes can be empty, acting only as placeholders. If a draw page's presentation layout is changed, all presentation shapes contained in that draw page are adapted automatically.

Standard drawing shapes can also be used in presentations. The presentation:class attribute distinguishes presentation shapes from drawing shapes. Unlike presentation shapes, standard drawing shapes are not adapted if the presentation page layout is changed.

10.8 Presentation Animations

10.8.1 <presentation:animations>

The <presentation:animations> element is a container for animation effects. Animation effects are executed when a page represented by a <draw:page> 10.2.4 element containing this element is displayed.

A single shape may be the subject of multiple effects.

The <presentation:animations> element is usable within the following element: <draw:page> 10.2.4.

The <presentation:animations> element has no attributes.

The <presentation:animations> element has the following child elements: <presentation:animation-group> 10.8.9, <presentation:dim> 10.8.7, <presentation:hide-shape> 10.8.5, <presentation:hide-text> 10.8.6, <presentation:play> 10.8.8, <presentation:show-shape> 10.8.3 and <presentation:show-text> 10.8.4.

10.8.2 <presentation:sound>

The <presentation:sound> element represents a sound.

The <presentation:sound> element is usable within the following elements: <presentation:dim> 10.8.7, <presentation:event-listener> 10.9.2, <presentation:hide-shape> 10.8.5, <presentation:hide-text> 10.8.6, <presentation:show-shape> 10.8.3, <presentation:show-text> 10.8.4 and <style:drawing-page-properties> 17.25.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <presentation:sound> element has the following attributes: presentation:play-full 19.408, xlink:actuate 19.909, xlink:href 19.910.26, xlink:show 19.911, xlink:type 19.913 and xml:id 19.914.

The <presentation:sound> element has no child elements.

10.8.3 <presentation:show-shape>

The <presentation:show-shape> element specifies when and how a shape becomes visible. Prior to execution of the effect defined by this element the shape containing it is invisible.

The <presentation:show-shape> element is usable within the following elements: <presentation:animation-group> 10.8.9 and <presentation:animations> 10.8.1.

The <presentation:show-shape> element has the following attributes: draw:shape-id 19.210, presentation:delay 19.391, presentation:direction 19.392, presentation:effect 19.394, presentation:path-id 19.405, presentation:speed 19.417 and presentation:start-scale 19.418.

The <presentation:show-shape> element has the following child element: <presentation:sound> 10.8.2.

10.8.4 <presentation:show-text>

The <presentation:show-text> element defines an effect that makes text within a shape visible. Prior to execution of the effect defined by this element the shape and the text it contains are invisible.

The <presentation:show-text> element is usable within the following elements: <presentation:animation-group> 10.8.9 and <presentation:animations> 10.8.1.

The <presentation:show-text> element has the following attributes: draw:shape-id 19.210, presentation:delay 19.391, presentation:direction 19.392, presentation:effect 19.394, presentation:path-id 19.405, presentation:speed 19.417 and presentation:start-scale 19.418.

The <presentation:show-text> element has the following child element: <presentation:sound> 10.8.2.

10.8.5 <presentation:hide-shape>

The <presentation:hide-shape> element specifies that a shape is invisible.

The <presentation:hide-shape> element is usable within the following elements: <presentation:animation-group> 10.8.9 and <presentation:animations> 10.8.1.

The <presentation:hide-shape> element has the following attributes: draw:shape-id 19.210, presentation:delay 19.391, presentation:direction 19.392, presentation:effect 19.394, presentation:path-id 19.405, presentation:speed 19.417 and presentation:start-scale 19.418.

The <presentation:hide-shape> element has the following child element: <presentation:sound> 10.8.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.8.6 <presentation:hide-text>

The <presentation:hide-text> element specifies an effect that makes text within a shape visible. Prior to execution of the effect specified by this element, the text contained inside a shape is invisible.

The <presentation:hide-text> element is usable within the following elements: <presentation:animation-group> 10.8.9 and <presentation:animations> 10.8.1.

The <presentation:hide-text> element has the following attributes: draw:shape-id 19.210, presentation:delay 19.391, presentation:direction 19.392, presentation:effect 19.394, presentation:path-id 19.405, presentation:speed 19.417 and presentation:start-scale 19.418.

The <presentation:hide-text> element has the following child element: <presentation:sound> 10.8.2.

10.8.7 <presentation:dim>

The <presentation:dim> element specifies a fill color for a shape.

The <presentation:dim> element is usable within the following elements: <presentation:animation-group> 10.8.9 and <presentation:animations> 10.8.1.

The <presentation:dim> element has the following attributes: draw:color 19.122.3 and draw:shape-id 19.210.

The <presentation:dim> element has the following child element: <presentation:sound> 10.8.2.

10.8.8 <presentation:play>

The <presentation:play> element specifies the presentation speed of animation of a shape.

The <presentation:play> element is usable within the following elements: <presentation:animation-group> 10.8.9 and <presentation:animations> 10.8.1.

The <presentation:play> element has the following attributes: draw:shape-id 19.210 and presentation:speed 19.417.

The <presentation:play> element has no child elements.

10.8.9 <presentation:animation-group>

The <presentation:animation-group> element contains elements that specify multiple animation effects. Containment results in all effects occurring at the same time.

The <presentation:animation-group> element is usable within the following element: <presentation:animations> 10.8.1.

The <presentation:animation-group> element has no attributes.

The <presentation:animation-group> element has the following child elements: <presentation:dim> 10.8.7, <presentation:hide-shape> 10.8.5,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<presentation:hide-text> 10.8.6, <presentation:play> 10.8.8, <presentation:show-shape> 10.8.3 and <presentation:show-text> 10.8.4.

10.9 SMIL Presentation Animations

10.9.1 General

SMIL based shape animations are specified for presentation documents. This type of animation can be used instead of that specified by <presentation:animations> elements if one of the following items is required:

- Multiple animations per shape.
- A mixture of animations starting on user interaction and starting automatically per page.
- Multiple animations running at the same time.
- Additional effects ”programmed” in XML by combining animation elements.
- Document transformations to SVG.

An *effect* is a combination of one or more animation elements that animate a single shape and or a shape's paragraphs.

10.9.2 <presentation:event-listener>

The <presentation:event-listener> element defines the trigger for a presentation event.

The <presentation:event-listener> element is usable within the following element: <office:event-listeners> 10.3.19.

The <presentation:event-listener> element has the following attributes: presentation:action 19.387, presentation:direction 19.392, presentation:effect 19.394, presentation:speed 19.417, presentation:start-scale 19.418, presentation:verb 19.428, script:event-name 19.429, xlink:actuate 19.909, xlink:href 19.910.25, xlink:show 19.911 and xlink:type 19.913.

The <presentation:event-listener> element has the following child element: <presentation:sound> 10.8.2.

10.9.3 Presentation Document Content

10.9.3.1 <presentation:header>

The <presentation:header> element defines a field that contains a header for a presentation. Which header field declaration is used is specified by the presentation:use-header-name attribute of the draw page where the field occurs. In a presentation shape inside a master page 19.389, the presentation:use-header-name attribute of the <draw:page> element for which the drawing shape is displayed is used.

Note: This field is mainly used inside master pages. Since its value may differ for the individual drawing pages that make use of a master page, the current field value is not available.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <presentation:header> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <presentation:header> element has no attributes.

The <presentation:header> element has no child elements.

10.9.3.2 <presentation:header-decl>

The <presentation:header-decl> element specifies the text of a header field.

The <presentation:header-decl> element is usable within the following element: <office:presentation> 3.6.

The <presentation:header-decl> element has the following attribute: presentation:name 19.401.

The <presentation:header-decl> element has no child elements.

The <presentation:header-decl> element has character data content.

10.9.3.3 <presentation:footer>

The <presentation:footer> element defines a field that contains a footer for a presentation. Footer fields display a footer text specified in a footer field declaration. See 10.9.3.4. Which footer field declaration is used is specified by the presentation:use-footer-name attribute of the draw page where the field occurs. In a presentation drawing shape inside a master page 19.389, the presentation:use-footer-name attribute of the <draw:page> for which the drawing shape is displayed is used.

Note: This field is mainly used inside master pages. Since its value may differ for the individual drawing pages that make use of a master page, the current field value is not available.

The <presentation:footer> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <presentation:footer> element has no attributes.

The <presentation:footer> element has no child elements.

10.9.3.4 <presentation:footer-decl>

The <presentation:footer-decl> element specifies the text of a footer field.

The <presentation:footer-decl> element is usable within the following element: <office:presentation> 3.6.

The <presentation:footer-decl> element has the following attribute: presentation:name 19.401.

The <presentation:footer-decl> element has no child elements.

The <presentation:footer-decl> element has character data content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.9.3.5 <presentation:date-time>

The <presentation:date-time> element defines a field that contains the date/time text for a presentation. Date and time fields display a date/time text as specified in the date/time field declaration. See 10.9.3.6. Which date-time field declaration is used is specified by the presentation:use-date-time-name attribute of the draw page where the field occurs. In a presentation drawing shape inside a master page 19.389, the presentation:use-date-time-name attribute of the drawing page for which the drawing shape is displayed is used.

Note: This field is mainly used inside master pages. Since its value may differ for the individual drawing pages that make use of a master page, the current field value is not available.

The <presentation:date-time> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <presentation:date-time> element has no attributes.

The <presentation:date-time> element has no child elements.

10.9.3.6 <presentation:date-time-decl>

The <presentation:date-time-decl> element specifies the text of a date-time field.

The <presentation:date-time-decl> element is usable within the following element: <office:presentation> 3.6.

The <presentation:date-time-decl> element has the following attributes: presentation:name 19.401, presentation:source 19.416 and style:data-style-name 19.469.2.

The <presentation:date-time-decl> element has no child elements.

The <presentation:date-time-decl> element has character data content.

10.9.3.7 <presentation:settings>

The <presentation:settings> element is a container for the settings for a presentation in a document.

The <presentation:settings> element is usable within the following element: <office:presentation> 3.6.

The <presentation:settings> element has the following attributes: presentation:animations 19.388, presentation:endless 19.393, presentation:force-manual 19.395, presentation:full-screen 19.396, presentation:mouse-as-pen 19.399, presentation:mouse-visible 19.400, presentation:pause 19.406, presentation:show 19.413, presentation:show-end-of-presentation-slide 19.414, presentation:show-logo 19.415, presentation:start-page 19.419, presentation:start-with-navigator 19.420, presentation:stay-on-top 19.421 and presentation:transition-on-click 19.423.

The <presentation:settings> element has the following child element: <presentation:show> 10.9.3.8.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.9.3.8 <presentation:show>

The `<presentation:show>` element specifies the order in which pages are displayed during a presentation.

Note: The order of pages can be used to omit or repeat pages in a presentation.

The `<presentation:show>` element is usable within the following element: `<presentation:settings>` 10.9.3.7.

The `<presentation:show>` element has the following attributes: `presentation:name` 19.401 and `presentation:pages` 19.404.

The `<presentation:show>` element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

11 Chart Content

11.1 <chart:chart>

The <chart:chart> element represents a chart.

The <chart:chart> element is usable within the following element: <office:chart> 3.8.

The <chart:chart> element has the following attributes: chart:class 19.15.1, chart:column-mapping 19.16, chart:row-mapping 19.26, chart:style-name 19.27, svg:height 19.539.1, svg:width 19.571.1, xlink:href 19.910.3, xlink:type 19.913 and xml:id 19.914.

The <chart:chart> element has the following child elements: <chart:footer> 11.2.3, <chart:legend> 11.3, <chart:plot-area> 11.4, <chart:subtitle> 11.2.2, <chart:title> 11.2.1 and <table:table> 9.1.2.

11.2 Title, Subtitle and Footer

11.2.1 <chart:title>

The <chart:title> element represents a title in a chart document.

The text of a title is specified by a child <text:p> element or a table:cell-range attribute. If a child <text:p> element and a table:cell-range attribute are both present, the text specified by the table:cell-range attribute is used as the title. By default, the content of a child <text:p> element is displayed as the title.

This element can also be a sub-element of <chart:axis>. 11.8 In that case the title is displayed beside the axis specified by the <chart:axis> element.

The <chart:title> element is usable within the following elements: <chart:axis> 11.8 and <chart:chart> 11.1.

The <chart:title> element has the following attributes: chart:style-name 19.27, svg:x 19.573.1, svg:y 19.577.1 and table:cell-range 19.592.

The <chart:title> element has the following child element: <text:p> 5.1.3.

11.2.2 <chart:subtitle>

The <chart:subtitle> element represents a subtitle for a chart.

The text of a subtitle is specified by a child <text:p> element or a table:cell-range attribute. If a child <text:p> element and a table:cell-range attribute are both present, the text specified by the table:cell-range attribute is used as the subtitle. By default, the content of a child <text:p> element is displayed as the title.

The <chart:subtitle> element is usable within the following element: <chart:chart> 11.1.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <chart:subtitle> element has the following attributes: chart:style-name 19.27, svg:x 19.573.1, svg:y 19.577.1 and table:cell-range 19.592.

The <chart:subtitle> element has the following child element: <text:p> 5.1.3.

11.2.3 <chart:footer>

The <chart:footer> element represents a footer below a chart's plot area.

The text of a footer is specified by a child <text:p> element or a table:cell-range attribute. If a child <text:p> element and a table:cell-range attribute are both present, the text specified by the table:cell-range attribute is used as the footer. By default, the content of a child <text:p> element is displayed as the footer.

The <chart:footer> element is usable within the following element: <chart:chart> 11.1.

The <chart:footer> element has the following attributes: chart:style-name 19.27, svg:x 19.573.1, svg:y 19.577.1 and table:cell-range 19.592.

The <chart:footer> element has the following child element: <text:p> 5.1.3.

11.3 <chart:legend>

The <chart:legend> element represents a legend for a chart. If there is no <chart:legend> element for a chart, no legend is displayed.

A legend contains a list of legend entries. Each entry consists of a graphical entry key and an entry text.

For circle and ring charts each legend entry represents an individual data point of the first series. The graphical entry key represents the visual appearance of a data point while the entry text is the category of the point.

The categories to use are given as a list of labels defined by the <chart:categories> element at the x-axis. They are paired with matching data points in the order in which they appear.

For surface charts each graphic entry key represents the graphical appearance of the surface within a major interval of the altitude axis and the entry text represents the value range of that interval.

For all other chart types the legend entries represent the series of the chart. The graphical entry keys represent the visual appearance of each series while the entry texts contain the names of the series.

The legend may include additional entries for regression-curves and mean-value lines.

The <chart:legend> element may contain a <text:p> element. If present, it defines a title for the legend.

The <chart:legend> element is usable within the following element: <chart:chart> 11.1.

The <chart:legend> element has the following attributes: chart:legend-align 19.22, chart:legend-position 19.23, chart:style-name 19.27, style:legend-expansion 19.490, style:legend-expansion-aspect-ratio 19.491, svg:x 19.573.1 and svg:y 19.577.1.

The <chart:legend> element has the following child element: <text:p> 5.1.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

11.4 <chart:plot-area>

The <chart:plot-area> element represents a coordinate system in which data is plotted including defined axes.

The <chart:plot-area> element is usable within the following element: <chart:chart> 11.1.

The <chart:plot-area> element has the following attributes: chart:data-source-has-labels 19.17, chart:style-name 19.27, dr3d:ambient-color 19.92, dr3d:distance 19.96, dr3d:focal-length 19.98, dr3d:lighting-mode 19.99.2, dr3d:projection 19.102, dr3d:shade-mode 19.103, dr3d:shadow-slant 19.104, dr3d:transform 19.107, dr3d:vpn 19.108, dr3d:vrp 19.109, dr3d:vup 19.110, svg:height 19.539.2, svg:width 19.571.3, svg:x 19.573.1, svg:y 19.577.1, table:cell-range-address 19.593.6 and xml:id 19.914.

The <chart:plot-area> element has the following child elements: <chart:axis> 11.8, <chart:floor> 11.7, <chart:series> 11.11, <chart:stock-gain-marker> 11.19, <chart:stock-loss-marker> 11.20, <chart:stock-range-line> 11.21, <chart:wall> 11.6 and <dr3d:light> 10.5.3.

11.5 3D Plot Area

The plot area may be displayed as an 3D scene as specified in section 10.5.2. All 3D attributes that can be applied to the <dr3d:scene> element can be applied to the <chart:plot-area> element. This includes the dr3d:transform attribute that specifies the rotation of the three-dimensional plot area. 10.5.2 The <chart:plot-area> element may contain a <dr3d:light> element as specified in section 10.5.3.

11.6 <chart:wall>

The <chart:wall> element specifies the wall of a chart. For two-dimensional charts, the wall spans the entire plot area. For three-dimensional charts, the wall consists of two perpendicular rectangles.

The svg:width attribute specifies the thickness of a wall for three-dimensional charts.

The <chart:wall> element is usable within the following element: <chart:plot-area> 11.4.

The <chart:wall> element has the following attributes: chart:style-name 19.27 and svg:width 19.571.4.

The <chart:wall> element has no child elements.

11.7 <chart:floor>

The <chart:floor> element specifies the floor of a chart. For three-dimensional charts, the <chart:floor> element shall be present in addition to the <chart:wall> element.

The svg:width attribute specifies the thickness of the floor.

The <chart:floor> element is usable within the following element: <chart:plot-area> 11.4.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <chart:floor> element has the following attributes: chart:style-name 19.27 and svg:width 19.571.2.

The <chart:floor> element has no child elements.

11.8 <chart:axis>

The <chart:axis> element specifies an axis for a chart.

The <chart:axis> element is usable within the following element: <chart:plot-area> 11.4.

The <chart:axis> element has the following attributes: chart:dimension 19.18, chart:name 19.24 and chart:style-name 19.27.

The <chart:axis> element has the following child elements: <chart:categories> 11.9, <chart:grid> 11.10 and <chart:title> 11.2.1.

11.9 <chart:categories>

The <chart:categories> element represents labels that are displayed on a category-axis.

This element may have a table:cell-range-address attribute that specifies a range from which category labels are taken. If this attribute or the <chart:categories> element itself is omitted, the chart:data-source-has-labels attribute of the <chart:plot-area> element should be evaluated for labels to display on a category-axis.

The <chart:categories> element is usable within the following element: <chart:axis> 11.8.

The <chart:categories> element has the following attribute: table:cell-range-address 19.593.2.

The <chart:categories> element has no child elements.

11.10 <chart:grid>

The <chart:grid> element specifies a grid for an axis.

The <chart:grid> element is usable within the following element: <chart:axis> 11.8.

The <chart:grid> element has the following attributes: chart:class 19.15.2 and chart:style-name 19.27.

The <chart:grid> element has no child elements.

11.11 <chart:series>

The <chart:series> element represents a data series in a chart. If the chart requires more input data, like it is the case for scatter and bubble charts, <chart:domain> sub-elements shall be defined that contain the cell range addresses of the corresponding data.

The <chart:series> element is usable within the following element: <chart:plot-area> 11.4.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <chart:series> element has the following attributes: chart:attached-axis 19.13, chart:class 19.15.1, chart:label-cell-address 19.21, chart:style-name 19.27, chart:values-cell-range-address 19.28 and xml:id 19.914.

The <chart:series> element has the following child elements: <chart:data-label> 11.14, <chart:data-point> 11.13, <chart:domain> 11.12, <chart:error-indicator> 11.16, <chart:mean-value> 11.15 and <chart:regression-curve> 11.17.

11.12 <chart:domain>

The <chart:domain> element specifies coordinate values required by particular chart types.

For scatter charts, one <chart:domain> element shall exist. Its table:cell-range-address attribute references the x-coordinate values for the scatter chart.

For bubble charts, two <chart:domain> elements shall exist. The values for the y-coordinates are given by the first <chart:domain> element. The values for the x-coordinates are given by the second <chart:domain> element.

For surface charts, up to two <chart:domain> elements are allowed to exist. The values for the y-coordinates are given by the first <chart:domain> element. The values for the x-coordinates are given by the second <chart:domain> element.

At least one <chart:series> element of a given chart:class shall have the necessary number of <chart:domain> sub-elements. All other <chart:series> elements with the same chart:class may omit the <chart:domain> sub-elements and use the previously defined values for that type of chart.

The <chart:domain> element is usable within the following element: <chart:series> 11.11.

The <chart:domain> element has the following attribute: table:cell-range-address 19.593.3.

The <chart:domain> element has no child elements.

11.13 <chart:data-point>

The <chart:data-point> element specifies a style for a single data point in a data series.

Note: This element can be used if a single data point has a special or distinct appearance.

The <chart:data-point> element is usable within the following element: <chart:series> 11.11.

The <chart:data-point> element has the following attributes: chart:repeated 19.25, chart:style-name 19.27 and xml:id 19.914.

The <chart:data-point> element has the following child element: <chart:data-label> 11.14.

11.14 <chart:data-label>

The <chart:data-label> element represents the data label of a data point.

The <chart:data-label> element can also be a sub-element of a data series. In that case, the data label serves as default for all the data points of this series.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <chart:data-label> element is usable within the following elements: <chart:data-point> 11.13 and <chart:series> 11.11.

The <chart:data-label> element has the following attributes: chart:style-name 19.27, svg:x 19.573.1 and svg:y 19.577.1.

The <chart:data-label> element has the following child element: <text:p> 5.1.3.

11.15 <chart:mean-value>

The <chart:mean-value> element specifies a style for a mean-value line.

The <chart:mean-value> element is usable within the following element: <chart:series> 11.11.

The <chart:mean-value> element has the following attribute: chart:style-name 19.27.

The <chart:mean-value> element has no child elements.

11.16 <chart:error-indicator>

The <chart:error-indicator> element specifies a style for error-indicators.

The <chart:error-indicator> element is usable within the following element: <chart:series> 11.11.

The <chart:error-indicator> element has the following attributes: chart:dimension 19.18 and chart:style-name 19.27.

The <chart:error-indicator> element has no child elements.

11.17 <chart:regression-curve>

The <chart:regression-curve> element specifies the properties of regression-lines.

The <chart:regression-curve> element is usable within the following element: <chart:series> 11.11.

The <chart:regression-curve> element has the following attribute: chart:style-name 19.27.

The <chart:regression-curve> element has the following child element: <chart:equation> 11.18.

11.18 <chart:equation>

The <chart:equation> element represents the equation for a containing regression curve.

The <chart:equation> element is usable within the following element: <chart:regression-curve> 11.17.

The <chart:equation> element has the following attributes: chart:automatic-content 19.14, chart:display-equation 19.19, chart:display-r-square 19.20, chart:style-name 19.27, svg:x 19.573.1 and svg:y 19.577.1.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <chart:equation> element has the following child element: <text:p> 5.1.3.

11.19 <chart:stock-gain-marker>

The <chart:stock-gain-marker> element specifies a style for candlestick-bars in a stock chart that have a higher closing value than opening value.

The <chart:stock-gain-marker> element is usable within the following element: <chart:plot-area> 11.4.

The <chart:stock-gain-marker> element has the following attribute: chart:style-name 19.27.

The <chart:stock-gain-marker> element has no child elements.

11.20 <chart:stock-loss-marker>

The <chart:stock-loss-marker> element specifies the style for candlestick-bars in a stock chart that have a lower closing value than opening value.

The <chart:stock-loss-marker> element is usable within the following element: <chart:plot-area> 11.4.

The <chart:stock-loss-marker> element has the following attribute: chart:style-name 19.27.

The <chart:stock-loss-marker> element has no child elements.

11.21 <chart:stock-range-line>

The <chart:stock-range-line> element specifies a style for the range-lines in a stock chart. A range-line is a line connecting the minimum value with the maximum value.

The <chart:stock-range-line> element is usable within the following element: <chart:plot-area> 11.4.

The <chart:stock-range-line> element has the following attribute: chart:style-name 19.27.

The <chart:stock-range-line> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

12 Database Front-end Document Content

12.1 <office:database>

A <office:database> element is a container of database elements.

The <office:database> element is usable within the following element: <office:body> 3.3.

The <office:database> element has no attributes.

The <office:database> element has the following child elements: <db:data-source> 12.2, <db:forms> 12.25.2, <db:queries> 12.26, <db:reports> 12.25.3, <db:schema-definition> 12.36 and <db:table-representations> 12.32.

12.2 <db:data-source>

A <db:data-source> element is a container for data source specific elements that are needed to create a connection to a database.

The <db:data-source> element is usable within the following element: <office:database> 12.1.

The <db:data-source> element has no attributes.

The <db:data-source> element has the following child elements: <db:application-connection-settings> 12.15, <db:connection-data> 12.3 and <db:driver-settings> 12.9.

12.3 <db:connection-data>

The <db:connection-data> element specifies the information necessary to connect to a database.

The <db:connection-data> element is usable within the following element: <db:data-source> 12.2.

The <db:connection-data> element has no attributes.

The <db:connection-data> element has the following child elements: <db:connection-resource> 12.7, <db:database-description> 12.4 and <db:login> 12.8.

12.4 <db:database-description>

The <db:database-description> element specifies a database resource by its type and access parameters.

The <db:database-description> element is usable within the following element: <db:connection-data> 12.3.

The <db:database-description> element has no attributes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <db:database-description> element has the following child elements: <db:file-based-database> 12.5 and <db:server-database> 12.6.

12.5 <db:file-based-database>

The <db:file-based-database> element specifies a database which is composed of one or more files in an arbitrary file system.

The <db:file-based-database> element is usable within the following element: <db:database-description> 12.4.

The <db:file-based-database> element has the following attributes: db:extension 19.52, db:media-type 19.69, xlink:href 19.910.7 and xlink:type 19.913.

The <db:file-based-database> element has no child elements.

12.6 <db:server-database>

The <db:server-database> element specifies connection information for a server-based database.

The <db:server-database> element is usable within the following element: <db:database-description> 12.4.

The <db:server-database> element has the following attributes: db:database-name 19.43, db:hostname 19.54, db:local-socket 19.67, db:port 19.72 and db:type 19.85.3.

The <db:server-database> element has no child elements.

12.7 <db:connection-resource>

The <db:connection-resource> element specifies a database connection by an IRI.

The <db:connection-resource> element is usable within the following element: <db:connection-data> 12.3.

The <db:connection-resource> element has the following attributes: xlink:actuate 19.909, xlink:href 19.910.6, xlink:show 19.911 and xlink:type 19.913.

The <db:connection-resource> element has no child elements.

12.8 <db:login>

The <db:login> element specifies the information needed to establish a connection to a database.

Note: For security reasons, the <db:login> element does not have an attribute to store a password that may be required to establish a connection.

The <db:login> element is usable within the following element: <db:connection-data> 12.3.

The <db:login> element has the following attributes: db:is-password-required 19.63, db:login-timeout 19.61, db:user-name 19.90 and db:use-system-user 19.89.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <db:login> element has no child elements.

12.9 <db:driver-settings>

The <db:driver-settings> element specifies settings for a driver establishing the database connection.

The <db:driver-settings> element is usable within the following element: <db:data-source> 12.2.

The <db:driver-settings> element has the following attributes: db:base-dn 19.35, db:is-first-row-header-line 19.60, db:parameter-name-substitution 19.71, db:show-deleted 19.78 and db:system-driver-settings 19.82.

The <db:driver-settings> element has the following child elements: <db:auto-increment> 12.10, <db:character-set> 12.12, <db:delimiter> 12.11 and <db:table-settings> 12.13.

12.10 <db:auto-increment>

The <db:auto-increment> element specifies SQL statements to retrieve auto-generated row values and to set AUTO_INCREMENT values for columns.

The <db:auto-increment> element is usable within the following element: <db:driver-settings> 12.9.

The <db:auto-increment> element has the following attributes: db:additional-column-statement 19.31 and db:row-retrieving-statement 19.75.

The <db:auto-increment> element has no child elements.

12.11 <db:delimiter>

The <db:delimiter> element defines a delimiter for parsing data.

The <db:delimiter> element is usable within the following elements: <db:driver-settings> 12.9 and <db:table-setting> 12.14.

The <db:delimiter> element has the following attributes: db:decimal 19.44, db:field 19.53, db:string 19.79 and db:thousand 19.83.

The <db:delimiter> element has no child elements.

12.12 <db:character-set>

The <db:character-set> element defines the text encoding that is used to transform string data obtained from a database.

The <db:character-set> element is usable within the following elements: <db:driver-settings> 12.9 and <db:table-setting> 12.14.

The <db:character-set> element has the following attribute: db:encoding 19.50.

The <db:character-set> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

12.13 <db:table-settings>

The <db:table-settings> element is a container for <db:table-setting> elements.

The <db:table-settings> element is usable within the following element: <db:driver-settings> 12.9.

The <db:table-settings> element has no attributes.

The <db:table-settings> element has the following child element: <db:table-setting> 12.14.

12.14 <db:table-setting>

The <db:table-setting> element specifies driver-level settings which are used by a database driver for defining a single database table.

The <db:table-setting> element is usable within the following element: <db:table-settings> 12.13.

The <db:table-setting> element has the following attributes: db:is-first-row-header-line 19.60 and db:show-deleted 19.78.

The <db:table-setting> element has the following child elements: <db:character-set> 12.12 and <db:delimiter> 12.11.

12.15 <db:application-connection-settings>

The <db:application-connection-settings> element specifies settings which define how a consumer uses a database connection.

The <db:application-connection-settings> element is usable within the following element: <db:data-source> 12.2.

The <db:application-connection-settings> element has the following attributes: db:append-table-alias-name 19.32, db:boolean-comparison-mode 19.36, db:enable-sql92-check 19.49, db:ignore-driver-privileges 19.55, db:is-table-name-length-limited 19.66, db:max-row-count 19.68, db:suppress-version-columns 19.81 and db:use-catalog 19.88.

The <db:application-connection-settings> element has the following child elements: <db:data-source-settings> 12.22, <db:table-filter> 12.16 and <db:table-type-filter> 12.20.

12.16 <db:table-filter>

A <db:table-filter> element defines a list of filter patterns which are applied on the table names returned by a database. Only tables which match at least one include filter, and do not match any exclude filter, will be displayed.

The <db:table-filter> element is usable within the following element: <db:application-connection-settings> 12.15.

The <db:table-filter> element has no attributes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <db:table-filter> element has the following child elements: <db:table-exclude-filter> 12.18 and <db:table-include-filter> 12.17.

12.17 <db:table-include-filter>

The <db:table-include-filter> element specifies a list of filter patterns which determine inclusion of tables in a consumer's table display.

The <db:table-include-filter> element is usable within the following element: <db:table-filter> 12.16.

The <db:table-include-filter> element has no attributes.

The <db:table-include-filter> element has the following child element: <db:table-filter-pattern> 12.19.

12.18 <db:table-exclude-filter>

The <db:table-exclude-filter> element specifies a list of filter patterns which determine exclusion of tables in an consumer's table display.

The <db:table-exclude-filter> element is usable within the following element: <db:table-filter> 12.16.

The <db:table-exclude-filter> element has no attributes.

The <db:table-exclude-filter> element has the following child element: <db:table-filter-pattern> 12.19.

12.19 <db:table-filter-pattern>

The <db:table-filter-pattern> element specifies a filter pattern.

The "%" (U+0025. PERCENT SIGN) character is used as wildcard.

The <db:table-filter-pattern> element is usable within the following elements: <db:table-exclude-filter> 12.18 and <db:table-include-filter> 12.17.

The <db:table-filter-pattern> element has no attributes.

The <db:table-filter-pattern> element has no child elements.

The <db:table-filter-pattern> element has content of data type string 18.2.

12.20 <db:table-type-filter>

A <db:table-type-filter> element defines a list of table types which a database uses to filter tables.

The <db:table-type-filter> element is usable within the following element: <db:application-connection-settings> 12.15.

The <db:table-type-filter> element has no attributes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <db:table-type-filter> element has the following child element: <db:table-type> 12.21.

12.21 <db:table-type>

The <db:table-type> element specifies a table type.

Note: Table types are database specific.

The <db:table-type> element is usable within the following element: <db:table-type-filter> 12.20.

The <db:table-type> element has no attributes.

The <db:table-type> element has no child elements.

The <db:table-type> element has content of data type string 18.2.

12.22 <db:data-source-settings>

The <db:data-source-settings> element is a container element for <db:data-source-setting> elements.

The <db:data-source-settings> element is usable within the following element: <db:application-connection-settings> 12.15.

The <db:data-source-settings> element has no attributes.

The <db:data-source-settings> element has the following child element: <db:data-source-setting> 12.23.

12.23 <db:data-source-setting>

The <db:data-source-setting> element specifies the name of a data-source-setting, a data-source-setting type, and whether a data-source-setting contains a list of data or single data.

The <db:data-source-setting> element is usable within the following element: <db:data-source-settings> 12.22.

The <db:data-source-setting> element has the following attributes: db:data-source-setting-is-list 19.39, db:data-source-setting-name 19.40 and db:data-source-setting-type 19.41.

The <db:data-source-setting> element has the following child element: <db:data-source-setting-value> 12.24.

12.24 <db:data-source-setting-value>

The <db:data-source-setting-value> element specifies the content of a data-source-setting.

The <db:data-source-setting-value> element is usable within the following element: <db:data-source-setting> 12.23.

The <db:data-source-setting-value> element has no attributes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <db:data-source-setting-value> element has no child elements.

The <db:data-source-setting-value> element has content of data type string 18.2.

12.25 Forms and Reports

12.25.1 General

Database documents can contain forms and reports as sub documents. They're included in database front end documents by XLinks. Alternatively, the content of sub documents may be included in the <db:component> elements as child elements.

12.25.2 <db:forms>

The <db:forms> element may contain <db:component> or <db:component-collection> elements or both. It specifies a list of form documents and sub collections.

The <db:forms> element is usable within the following element: <office:database> 12.1.

The <db:forms> element has no attributes.

The <db:forms> element has the following child elements: <db:component> 12.25.5 and <db:component-collection> 12.25.4.

12.25.3 <db:reports>

The <db:reports> element may contain <db:component> or <db:component-collection> elements or both. It specifies a list of report documents and sub collections.

The <db:reports> element is usable within the following element: <office:database> 12.1.

The <db:reports> element has no attributes.

The <db:reports> element has the following child elements: <db:component> 12.25.5 and <db:component-collection> 12.25.4.

12.25.4 <db:component-collection>

The <db:component-collection> element specifies a collection of <db:component> elements and <db:component-collection> elements.

The <db:component-collection> element is usable within the following elements: <db:component-collection> 12.25.4, <db:forms> 12.25.2 and <db:reports> 12.25.3.

The <db:component-collection> element has the following attributes: db:description 19.48, db:name 19.70.5 and db:title 19.84.

The <db:component-collection> element has the following child elements: <db:component> 12.25.5 and <db:component-collection> 12.25.4.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

12.25.5 <db:component>

The <db:component> element specifies a database component which can be either a form or a report.

A database component is either referenced using the xlink:href attribute or it is contained in a child <office:document> or <math:math> element.

The <db:component> element is usable within the following elements: <db:component-collection> 12.25.4, <db:forms> 12.25.2 and <db:reports> 12.25.3.

The <db:component> element has the following attributes: db:as-template 19.34, db:description 19.48, db:name 19.70.4, db:title 19.84, xlink:actuate 19.909, xlink:href 19.910.5, xlink:show 19.911 and xlink:type 19.913.

The <db:component> element has the following child elements: <math:math> 14.5 and <office:document> 3.1.2.

12.26 <db:queries>

The <db:queries> element may contain <db:query> or <db:query-collection> elements or both.

The <db:queries> element is usable within the following element: <office:database> 12.1.

The <db:queries> element has no attributes.

The <db:queries> element has the following child elements: <db:query> 12.28 and <db:query-collection> 12.27.

12.27 <db:query-collection>

The <db:query-collection> element may contain <db:query> or <db:query-collection> elements or both.

The <db:query-collection> element is usable within the following elements: <db:queries> 12.26 and <db:query-collection> 12.27.

The <db:query-collection> element has the following attributes: db:description 19.48, db:name 19.70.11 and db:title 19.84.

The <db:query-collection> element has the following child elements: <db:query> 12.28 and <db:query-collection> 12.27.

12.28 <db:query>

The <db:query> element specifies a database query.

The <db:query> element is usable within the following elements: <db:queries> 12.26 and <db:query-collection> 12.27.

The <db:query> element has the following attributes: db:command 19.38, db:default-row-style-name 19.46, db:description 19.48, db:escape-processing 19.51, db:name 19.70.10, db:style-name 19.80.3 and db:title 19.84.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <db:query> element has the following child elements: <db:columns> 12.34, <db:filter-statement> 12.30, <db:order-statement> 12.29 and <db:update-table> 12.31.

12.29 <db:order-statement>

The <db:order-statement> element specifies a sort ("ORDER BY") SQL clause which is to be applied on top of another SQL statement producing a result set.

The <db:order-statement> element is usable within the following elements: <db:query> 12.28 and <db:table-representation> 12.33.

The <db:order-statement> element has the following attributes: db:apply-command 19.33 and db:command 19.38.

The <db:order-statement> element has no child elements.

12.30 <db:filter-statement>

The <db:filter-statement> element specifies a filter ("WHERE") SQL clause which is to be applied on top of another SQL-statement producing a result set.

The <db:filter-statement> element is usable within the following elements: <db:query> 12.28 and <db:table-representation> 12.33.

The <db:filter-statement> element has the following attributes: db:apply-command 19.33 and db:command 19.38.

The <db:filter-statement> element has no child elements.

12.31 <db:update-table>

The <db:update-table> element specifies the name of the table which will be updated when an UPDATE, INSERT or DELETE SQL statement is executed. It defines the table which should be updated when the select statement contains more than one table.

The <db:update-table> element is usable within the following element: <db:query> 12.28.

The <db:update-table> element has the following attributes: db:catalog-name 19.37, db:name 19.70.14 and db:schema-name 19.77.

The <db:update-table> element has no child elements.

12.32 <db:table-representations>

The <db:table-representations> element specifies a collection of tables.

The <db:table-representations> element is usable within the following element: <office:database> 12.1.

The <db:table-representations> element has no attributes.

The <db:table-representations> element has the following child element: <db:table-representation> 12.33.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

12.33 <db:table-representation>

A <db:table-representation> element specifies how an consumer displays a table to the user.

The <db:table-representation> element is usable within the following element: <db:table-representations> 12.32.

The <db:table-representation> element has the following attributes: db:catalog-name 19.37, db:default-row-style-name 19.46, db:description 19.48, db:name 19.70.13, db:schema-name 19.77, db:style-name 19.80.4 and db:title 19.84.

The <db:table-representation> element has the following child elements: <db:columns> 12.34, <db:filter-statement> 12.30 and <db:order-statement> 12.29.

12.34 <db:columns>

The <db:columns> element is a collection of <db:column> elements.

The <db:columns> element is usable within the following elements: <db:query> 12.28 and <db:table-representation> 12.33.

The <db:columns> element has no attributes.

The <db:columns> element has the following child element: <db:column> 12.35.

12.35 <db:column>

The <db:column> element specifies settings for a column.

The <db:column> element is usable within the following element: <db:columns> 12.34.

The <db:column> element has the following attributes: db:default-cell-style-name 19.45, db:description 19.48, db:name 19.70.2, db:style-name 19.80.2, db:title 19.84, db:visible 19.91, office:boolean-value 19.367, office:currency 19.369, office:date-value 19.370, office:string-value 19.379, office:time-value 19.382, office:value 19.384, office:value-type 19.385.

The <db:column> element has no child elements.

12.36 <db:schema-definition>

The <db:schema-definition> element specifies a database schema.

The <db:schema-definition> element is usable within the following element: <office:database> 12.1.

The <db:schema-definition> element has no attributes.

The <db:schema-definition> element has the following child element: <db:table-definitions> 12.37.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

12.37 <db:table-definitions>

The <db:table-definitions> element is a container for multiple <db:table-definition> elements.

The <db:table-definitions> element is usable within the following element: <db:schema-definition> 12.36.

The <db:table-definitions> element has no attributes.

The <db:table-definitions> element has the following child element: <db:table-definition> 12.38.

12.38 <db:table-definition>

The <db:table-definition> element specifies the schema of a single table.

The <db:table-definition> element is usable within the following element: <db:table-definitions> 12.37.

The <db:table-definition> element has the following attributes: db:catalog-name 19.37, db:name 19.70.12, db:schema-name 19.77 and db:type 19.85.4.

The <db:table-definition> element has the following child elements: <db:column-definitions> 12.39, <db:indices> 12.45 and <db:keys> 12.41.

12.39 <db:column-definitions>

The <db:column-definitions> element is a container for <db:column-definition> elements.

The <db:column-definitions> element is usable within the following element: <db:table-definition> 12.38.

The <db:column-definitions> element has no attributes.

The <db:column-definitions> element has the following child element: <db:column-definition> 12.40.

12.40 <db:column-definition>

The <db:column-definition> element defines a table column.

The <db:column-definition> element is usable within the following element: <db:column-definitions> 12.39.

The <db:column-definition> element has the following attributes: db:data-type 19.42, db:is-autoincrement 19.57, db:is-empty-allowed 19.59, db:is-nullable 19.62, db:name 19.70.3, db:precision 19.65, db:scale 19.76, db:type-name 19.86, office:boolean-value 19.367, office:currency 19.369, office:date-value 19.370, office:string-value 19.379, office:time-value 19.382, office:value 19.384, office:value-type 19.385.

The <db:column-definition> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

12.41 <db:keys>

The <db:keys> element is a container for one or more <db:key> elements.

The <db:keys> element is usable within the following element: <db:table-definition> 12.38.

The <db:keys> element has no attributes.

The <db:keys> element has the following child element: <db:key> 12.42.

12.42 <db:key>

The <db:key> element specifies a key for a table.

The <db:key> element is usable within the following element: <db:keys> 12.41.

The <db:key> element has the following attributes: db:delete-rule 19.47, db:name 19.70.8, db:referenced-table-name 19.73, db:type 19.85.2 and db:update-rule 19.87.

The <db:key> element has the following child element: <db:key-columns> 12.43.

12.43 <db:key-columns>

The <db:key-columns> element specifies the columns of a key.

The <db:key-columns> element is usable within the following element: <db:key> 12.42.

The <db:key-columns> element has no attributes.

The <db:key-columns> element has the following child element: <db:key-column> 12.44.

12.44 <db:key-column>

The <db:key-column> element specifies a description of a column of a table key

The <db:key-column> element is usable within the following element: <db:key-columns> 12.43.

The <db:key-column> element has the following attributes: db:name 19.70.9 and db:related-column-name 19.74.

The <db:key-column> element has no child elements.

12.45 <db:indices>

The <db:indices> element defines the indexes of a table.

The <db:indices> element is usable within the following element: <db:table-definition> 12.38.

The <db:indices> element has no attributes.

The <db:indices> element has the following child element: <db:index> 12.46.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

12.46 <db:index>

The <db:index> element defines the types of indexes of a table.

The <db:index> element is usable within the following element: <db:indices> 12.45.

The <db:index> element has the following attributes: db:catalog-name 19.37, db:is-clustered 19.58, db:is-unique 19.64 and db:name 19.70.6.

The <db:index> element has the following child element: <db:index-columns> 12.47.

12.47 <db:index-columns>

The <db:index-columns> element specifies the columns of an index.

The <db:index-columns> element is usable within the following element: <db:index> 12.46.

The <db:index-columns> element has no attributes.

The <db:index-columns> element has the following child element: <db:index-column> 12.48.

12.48 <db:index-column>

The <db:index-column> element specifies the description of a column of a table index.

The <db:index-column> element is usable within the following element: <db:index-columns> 12.47.

The <db:index-column> element has the following attributes: db:is-ascending 19.56 and db:name 19.70.7.

The <db:index-column> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

13 Form Content

13.1 General

A form is a container for user interface controls.

Note: Buttons, text boxes, check boxes, and drop-down lists are user interface controls that can be contained in a form.

In the OpenDocument format, the following rules apply to user interface controls and forms:

- All controls shall be located in a form.
- All controls that are not hidden are assigned an absolute or relative position. These visual aspects of a control are represented by drawing shapes that contain a reference to the control.
- Forms may be nested. The containing form provides a context for the contained form.
- Forms are not connected with the text flow and layout of a document. This does not apply to controls.
- Forms can be data-aware. A form is data-aware if the values subject to its controls are populated from and updated to a database.

Form behavior is defined for submission and connection to a data source only for forms defined by a `<form:form>` element.

The result set of values subject to the controls of the form is defined by the `form:datasource`, `form:command`, and `form:command-type` attributes. At any point in time, only one row of the result set is subject to the forms controls.

Form behavior is not defined for forms defined by a `<xforms:model>` element.

13.2 <office:forms>

The `<office:forms>` element is a container for `<form:form>` or `<xforms:model>` elements.

The `<office:forms>` element is usable within the following elements: `<draw:page>` 10.2.4, `<office:text>` 3.4, `<presentation:notes>` 16.17, `<style:master-page>` 16.9 and `<table:table>` 9.1.2.

The `<office:forms>` element has the following attributes: `form:apply-design-mode` 19.250 and `form:automatic-focus` 19.253.

The `<office:forms>` element has the following child elements: `<form:form>` 13.3 and `<xforms:model>` 13.4.

13.3 <form:form>

The `<form:form>` element specifies a user interface form and defines the contents and properties of the form.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <form:form> element is usable within the following elements: <form:form> 13.3 and <office:forms> 13.2.

The <form:form> element has the following attributes: form:allow-deletes 19.247, form:allow-inserts 19.248, form:allow-updates 19.249, form:apply-filter 19.251, form:command 19.256, form:command-type 19.257, form:control-implementation 19.258, form:datasource 19.264, form:detail-fields 19.267, form:enctype 19.271, form:escape-processing 19.272, form:filter 19.273, form:ignore-result 19.277, form:master-fields 19.287, form:method 19.291, form:name 19.294, form:navigation-mode 19.295, form:order 19.296, form:tab-cycle 19.309, office:target-frame 19.380, xlink:actuate 19.909, xlink:href 19.910.22 and xlink:type 19.913.

The <form:form> element has the following child elements: <form:button> 13.5.15, <form:checkbox> 13.5.17, <form:combobox> 13.5.11, <form:connection-resource> 7.6.2, <form:date> 13.5.8, <form:file> 13.5.5, <form:fixed-text> 13.5.10, <form:form> 13.3, <form:formatted-text> 13.5.6, <form:frame> 13.5.19, <form:generic-control> 13.5.25, <form:grid> 13.5.22, <form:hidden> 13.5.21, <form:image> 13.5.16, <form:image-frame> 13.5.20, <form:listbox> 13.5.13, <form:number> 13.5.7, <form:password> 13.5.4, <form:properties> 13.7, <form:radio> 13.5.18, <form:text> 13.5.2, <form:textarea> 13.5.3, <form:time> 13.5.9, <form:value-range> 13.5.24 and <office:event-listeners> 10.3.19.

13.4 <xforms:model>

The <xforms:model> element is imported from [XForms] and is embedded in the <office:forms> element. XForms consists of two major parts, the XForms model which contains the form logic plus form data, and XForms controls, which can be bound to a data model.

Controls defined by OpenDocument (see 13.5) may be bound to an XForms model by an xforms:bind attribute.

The <xforms:model> element has the attributes and content defined in §3.3.1 of [XForms].

The <xforms:model> element is usable within the following element: <office:forms> 13.2.

13.5 Controls

13.5.1 General

Controls are used to interact with forms. Each control in a form is identified by a name. The name of a control need not be unique in a form.

Controls are connected to the surrounding document (and its text flow, if applicable) by binding them to a shape that acts as a placeholder for the control. 10.3.13

In addition to the attributes defined in this standard, controls may have implementation-dependent attributes. Those attributes are stored in a <form:properties> element in each control. Control events are specified in a <office:event-listeners> element.

13.5.2 <form:text>

The <form:text> element defines a control for displaying and inputting text on a single line.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <form:text> element is usable within the following elements: <form:column> 13.5.23 and <form:form> 13.3.

The <form:text> element has the following attributes: form:control-implementation 19.258, form:convert-empty-to-null 19.259, form:current-value 19.262, form:data-field 19.263, form:disabled 19.268, form:id 19.276, form:linked-cell 19.283, form:max-length 19.288, form:name 19.294, form:printable 19.299, form:readonly 19.301, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:value 19.316.5, xforms:bind 19.904 and xml:id 19.914.

The <form:text> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.3 <form:textarea>

The <form:textarea> element defines a control for displaying and inputting text on multiple lines.

The <form:textarea> element may be used with plain text values (specified by the form:current-value attribute) as well as with formatted text (specified as paragraph content). If both a form:current-value attribute and one or more <text:p> elements are present, , it is implementation dependent which text is used.

The <form:textarea> element is usable within the following elements: <form:column> 13.5.23 and <form:form> 13.3.

The <form:textarea> element has the following attributes: form:control-implementation 19.258, form:convert-empty-to-null 19.259, form:current-value 19.262, form:data-field 19.263, form:disabled 19.268, form:id 19.276, form:linked-cell 19.283, form:max-length 19.288, form:name 19.294, form:printable 19.299, form:readonly 19.301, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:value 19.316.5, xforms:bind 19.904 and xml:id 19.914.

The <form:textarea> element has the following child elements: <form:properties> 13.7, <office:event-listeners> 10.3.19 and <text:p> 5.1.3.

13.5.4 <form:password>

The <form:password> element defines a control that hides text a user inputs using an echo character.

The <form:password> element is usable within the following element: <form:form> 13.3.

The <form:password> element has the following attributes: form:control-implementation 19.258, form:convert-empty-to-null 19.259, form:disabled 19.268, form:echo-char 19.270, form:id 19.276, form:linked-cell 19.283, form:max-length 19.288, form:name 19.294, form:printable 19.299, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:value 19.316.5, xforms:bind 19.904 and xml:id 19.914.

The <form:password> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

13.5.5 <form:file>

The <form:file> element defines a control for selecting a file.

The <form:file> element is usable within the following element: <form:form> 13.3.

The <form:file> element has the following attributes: form:control-implementation 19.258, form:current-value 19.262, form:disabled 19.268, form:id 19.276, form:linked-cell 19.283, form:max-length 19.288, form:name 19.294, form:printable 19.299, form:readonly 19.301, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:value 19.316.5, xforms:bind 19.904 and xml:id 19.914.

The <form:file> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.6 <form:formatted-text>

The <form:formatted-text> element defines a control for inputting text, which follows the format defined by a data style that is assigned to the control's graphical shape.

The <form:formatted-text> element is usable within the following elements: <form:column> 13.5.23 and <form:form> 13.3.

The <form:formatted-text> element has the following attributes: form:control-implementation 19.258, form:convert-empty-to-null 19.259, form:current-value 19.262, form:data-field 19.263, form:delay-for-repeat 19.266, form:disabled 19.268, form:id 19.276, form:linked-cell 19.283, form:max-length 19.288, form:max-value 19.289.3, form:min-value 19.290.3, form:name 19.294, form:printable 19.299, form:readonly 19.301, form:repeat 19.302, form:spin-button 19.306, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:validation 19.315, form:value 19.316.5, xforms:bind 19.904 and xml:id 19.914.

The <form:formatted-text> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.7 <form:number>

The <form:number> element defines a control which allows the user to enter a floating point number.

The <form:number> element is usable within the following elements: <form:column> 13.5.23 and <form:form> 13.3.

The <form:number> element has the following attributes: form:control-implementation 19.258, form:convert-empty-to-null 19.259, form:current-value 19.262, form:data-field 19.263, form:delay-for-repeat 19.266, form:disabled 19.268, form:id 19.276, form:linked-cell 19.283, form:max-length 19.288, form:max-value 19.289.4, form:min-value 19.290.4, form:name 19.294, form:printable 19.299, form:readonly 19.301, form:repeat 19.302, form:spin-button 19.306, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:value 19.316.4, xforms:bind 19.904 and xml:id 19.914.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <form:number> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.8 <form:date>

The <form:date> element defines a control for inputting date data.

The <form:date> element is usable within the following elements: <form:column> 13.5.23 and <form:form> 13.3.

The <form:date> element has the following attributes: form:control-implementation 19.258, form:convert-empty-to-null 19.259, form:current-value 19.262, form:data-field 19.263, form:delay-for-repeat 19.266, form:disabled 19.268, form:id 19.276, form:linked-cell 19.283, form:max-length 19.288, form:max-value 19.289.2, form:min-value 19.290.2, form:name 19.294, form:printable 19.299, form:readonly 19.301, form:repeat 19.302, form:spin-button 19.306, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:value 19.316.3, xforms:bind 19.904 and xml:id 19.914.

The <form:date> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.9 <form:time>

The <form:time> element defines a control for inputting time data.

The <form:time> element is usable within the following elements: <form:column> 13.5.23 and <form:form> 13.3.

The <form:time> element has the following attributes: form:control-implementation 19.258, form:convert-empty-to-null 19.259, form:current-value 19.262, form:data-field 19.263, form:delay-for-repeat 19.266, form:disabled 19.268, form:id 19.276, form:linked-cell 19.283, form:max-length 19.288, form:max-value 19.289.5, form:min-value 19.290.5, form:name 19.294, form:printable 19.299, form:readonly 19.301, form:repeat 19.302, form:spin-button 19.306, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:value 19.316.6, xforms:bind 19.904 and xml:id 19.914.

The <form:time> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.10 <form:fixed-text>

The <form:fixed-text> element defines a control which attaches additional information to controls, or displays information. Only one label may be associated with a control.

The <form:fixed-text> element is usable within the following element: <form:form> 13.3.

The <form:fixed-text> element has the following attributes: form:control-implementation 19.258, form:disabled 19.268, form:for 19.275, form:id 19.276, form:label 19.282, form:multi-line 19.292, form:name 19.294, form:printable 19.299, form:title 19.313, xforms:bind 19.904 and xml:id 19.914.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <form:fixed-text> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.11 <form:combobox>

The <form:combobox> element defines a control which allows displaying and editing of text, and contains a list of possible values for that text.

The <form:combobox> element is usable within the following elements: <form:column> 13.5.23 and <form:form> 13.3.

The <form:combobox> element has the following attributes: form:auto-complete 19.252, form:control-implementation 19.258, form:convert-empty-to-null 19.259, form:current-value 19.262, form:data-field 19.263, form:disabled 19.268, form:dropdown 19.269, form:id 19.276, form:linked-cell 19.283, form:list-source 19.285, form:list-source-type 19.286, form:max-length 19.288, form:name 19.294, form:printable 19.299, form:readonly 19.301, form:size 19.304, form:source-cell-range 19.305, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:value 19.316.5, xforms:bind 19.904 and xml:id 19.914.

The <form:combobox> element has the following child elements: <form:item> 13.5.12, <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.12 <form:item>

The <form:item> element defines a list item for a <form:combobox> control.

The <form:item> element is usable within the following element: <form:combobox> 13.5.11.

The <form:item> element has the following attribute: form:label 19.282.

The <form:item> element has no child elements.

The <form:item> element has character data content.

13.5.13 <form:listbox>

The <form:listbox> element defines an input control that allows a user to select one or more items from a list. It is an alternative representation for a group of radio buttons.

The <form:listbox> element is usable within the following elements: <form:column> 13.5.23 and <form:form> 13.3.

The <form:listbox> element has the following attributes: form:bound-column 19.254, form:control-implementation 19.258, form:data-field 19.263, form:disabled 19.268, form:dropdown 19.269, form:id 19.276, form:linked-cell 19.283, form:list-linkage-type 19.284, form:list-source 19.285, form:list-source-type 19.286, form:multiple 19.293, form:name 19.294, form:printable 19.299, form:size 19.304, form:source-cell-range 19.305, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:xforms-list-source 19.318, xforms:bind 19.904 and xml:id 19.914.

The <form:listbox> element has the following child elements: <form:option> 13.5.14, <form:properties> 13.7 and <office:event-listeners> 10.3.19.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

13.5.14 <form:option>

The <form:option> element defines a list item for a <form:listbox> control.

The <form:option> element is usable within the following element: <form:listbox> 13.5.13.

The <form:option> element has the following attributes: form:current-selected 19.260, form:label 19.282, form:selected 19.303 and form:value 19.316.5.

The <form:option> element has no child elements.

The <form:option> element has character data content.

13.5.15 <form:button>

The <form:button> element defines a button.

The <form:button> element is usable within the following element: <form:form> 13.3.

The <form:button> element has the following attributes: form:button-type 19.255, form:control-implementation 19.258, form:default-button 19.265, form:delay-for-repeat 19.266, form:disabled 19.268, form:focus-on-click 19.274, form:id 19.276, form:image-align 19.278, form:image-data 19.279, form:image-position 19.280, form:label 19.282, form:name 19.294, form:printable 19.299, form:repeat 19.302, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:toggle 19.314, form:value 19.316.2, form:xforms-submission 19.319, office:target-frame 19.380, xforms:bind 19.904, xlink:href 19.910.19 and xml:id 19.914.

The <form:button> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.16 <form:image>

The <form:image> element defines a graphical button control.

Note: HTML 4.01 only allows the button type to be “submit” for an image button. In OpenDocument, an image button can be of any type.

The <form:image> element is usable within the following element: <form:form> 13.3.

The <form:image> element has the following attributes: form:button-type 19.255, form:control-implementation 19.258, form:disabled 19.268, form:id 19.276, form:image-data 19.279, form:name 19.294, form:printable 19.299, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:value 19.316.5, office:target-frame 19.380, xforms:bind 19.904, xlink:href 19.910.21 and xml:id 19.914.

The <form:image> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

13.5.17 <form:checkbox>

The <form:checkbox> element defines an on/off control. The control is on when the value of the form:current-state attribute associated with the control element is checked.

The <form:checkbox> element is usable within the following elements: <form:column> 13.5.23 and <form:form> 13.3.

The <form:checkbox> element has the following attributes: form:control-implementation 19.258, form:current-state 19.261, form:data-field 19.263, form:disabled 19.268, form:id 19.276, form:image-align 19.278, form:image-position 19.280, form:is-tristate 19.281, form:label 19.282, form:linked-cell 19.283, form:name 19.294, form:printable 19.299, form:state 19.307, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:value 19.316.5, form:visual-effect 19.317, xforms:bind 19.904 and xml:id 19.914.

The <form:checkbox> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.18 <form:radio>

The <form:radio> element defines a control which acts like a check box except that when multiple radio buttons belong to the same group they are mutually exclusive. When one button is on, all of the other buttons with the same name are off. If no radio button is defined to be initially on, it is undefined which radio button is initially on.

Radio buttons are defined to belong to the same group if they have the same control name, as specified by their form:name attribute.

If a group of radio buttons is bound to one database field, and a user selects any given button, the reference value of the selected radio button is written into its database field.

The <form:radio> element is usable within the following element: <form:form> 13.3.

The <form:radio> element has the following attributes: form:control-implementation 19.258, form:current-selected 19.260, form:data-field 19.263, form:disabled 19.268, form:id 19.276, form:image-align 19.278, form:image-position 19.280, form:label 19.282, form:linked-cell 19.283, form:name 19.294, form:printable 19.299, form:selected 19.303, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:value 19.316.5, form:visual-effect 19.317, xforms:bind 19.904 and xml:id 19.914.

The <form:radio> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.19 <form:frame>

The <form:frame> element defines a frame in which controls may be visually arranged.

The <form:frame> element is usable within the following element: <form:form> 13.3.

The <form:frame> element has the following attributes: form:control-implementation 19.258, form:disabled 19.268, form:for 19.275, form:id 19.276, form:label 19.282, form:name 19.294, form:printable 19.299, form:title 19.313, xforms:bind 19.904 and xml:id 19.914.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <form:frame> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.20 <form:image-frame>

The <form:image-frame> element defines a graphical control. The control displays an image, whose location is described in the control.

The <form:image-frame> element is usable within the following element: <form:form> 13.3.

The <form:image-frame> element has the following attributes: form:control-implementation 19.258, form:data-field 19.263, form:disabled 19.268, form:id 19.276, form:image-data 19.279, form:name 19.294, form:printable 19.299, form:readonly 19.301, form:title 19.313, xforms:bind 19.904 and xml:id 19.914.

The <form:image-frame> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.21 <form:hidden>

The <form:hidden> element defines a control that does not have a visual representation.

Note: A control without visual representation can be used for information not displayed to the user but is submitted as part of a form.

The <form:hidden> element is usable within the following element: <form:form> 13.3.

The <form:hidden> element has the following attributes: form:control-implementation 19.258, form:id 19.276, form:name 19.294, form:value 19.316.5, xforms:bind 19.904 and xml:id 19.914.

The <form:hidden> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.22 <form:grid>

The <form:grid> element defines a control that displays table data.

Each column in the grid is specified by a <form:column> element.

The <form:grid> element is usable within the following element: <form:form> 13.3.

The <form:grid> element has the following attributes: form:control-implementation 19.258, form:disabled 19.268, form:id 19.276, form:name 19.294, form:printable 19.299, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, xforms:bind 19.904 and xml:id 19.914.

The <form:grid> element has the following child elements: <form:column> 13.5.23, <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.23 <form:column>

The <form:column> element defines a column in a grid control.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <form:column> element is usable within the following element: <form:grid> 13.5.22.

The <form:column> element has the following attributes: form:control-implementation 19.258, form:label 19.282, form:name 19.294 and form:text-style-name 19.312.

The <form:column> element has the following child elements: <form:checkbox> 13.5.17, <form:combobox> 13.5.11, <form:date> 13.5.8, <form:formatted-text> 13.5.6, <form:listbox> 13.5.13, <form:number> 13.5.7, <form:text> 13.5.2, <form:textarea> 13.5.3 and <form:time> 13.5.9.

13.5.24 <form:value-range>

The <form:value-range> element defines a control which allows the user to select a value from a number range.

The <form:value-range> element is usable within the following element: <form:form> 13.3.

The <form:value-range> element has the following attributes: form:control-implementation 19.258, form:delay-for-repeat 19.266, form:disabled 19.268, form:id 19.276, form:linked-cell 19.283, form:max-value 19.289.4, form:min-value 19.290.4, form:name 19.294, form:orientation 19.297, form:page-step-size 19.298, form:printable 19.299, form:repeat 19.302, form:step-size 19.308, form:tab-index 19.310, form:tab-stop 19.311, form:title 19.313, form:value 19.316.4, xforms:bind 19.904 and xml:id 19.914.

The <form:value-range> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.5.25 <form:generic-control>

The <form:generic-control> element defines an implementation-defined placeholder for a generic control. The generic control can contain any properties and any events.

The <form:generic-control> element is usable within the following element: <form:form> 13.3.

The <form:generic-control> element has the following attributes: form:control-implementation 19.258, form:id 19.276, form:name 19.294, xforms:bind 19.904 and xml:id 19.914.

The <form:generic-control> element has the following child elements: <form:properties> 13.7 and <office:event-listeners> 10.3.19.

13.6 Event Listeners

Forms and form controls may have event listeners attached. The event listeners that are attached to a control are represented by an event listener element as described in section 14.4. This element is contained within form or form control elements.,

Section 19.429 contains guidelines for event names that may be used within forms and form controls. In addition to those, the events listed in Table 9 may be used in forms and form controls.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Table 9 - Form control event names

Value of `script:event-name` Attribute	***Applies To***	***Description of Event***
`form:approveaction`	Button or image.	Occurs before an “on perform action” event takes place. Allows a user to veto an action.
`form:performaction`	Button or image.	Occurs when the control action is to be performed. The common interpretation of this event is “pressing the button”.
`form:textchange`	All controls that allow text input.	Occurs when a user changes the text in a control.
`form:itemstatechange`	Check box or radio button.	Occurs when the state of a check box or radio button changes.
`form:mousedrag`	All controls.	Occurs when a user presses and holds one of the mouse buttons and moves the mouse pointer onto a control.
`form:approvereset`	same objects as for `form:on-reset`	Occurs before an “on-reset” event takes place. Allows a user to veto a reset event.
`form:approveupdate`	All controls that can be bound to a database field, that is controls that contain the data-field attribute.	Occurs before an “on update” event takes place. Allows a user to veto an update.
`form:update`	All controls that can be bound to a database field, that is controls that contain the data-field attribute.	Occurs when the content of a control that is bound to a database field is committed.
`form:load`	Forms.	Occurs when a form establishes a connection to the data source.
`form:startreload`	Forms.	Occurs when a form is about to refresh a data source connection.
`form:reload`	Forms.	Occurs when a form has refreshed a data source connection.
`form:startunload`	Forms.	Occurs when a form is about to drop a data source connection.
`form:unload`	Forms.	Occurs when a form has dropped a data source connection.
`form:confirmdelete`	Forms.	Occurs when a user is about to delete a record.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Value of `script:event-name` Attribute	*Applies To*	*Description of Event*
`form:approverowchange`	Forms.	Occurs before an “on row change” event takes place. Allows a user to veto a change.
`form:rowchange`	Forms.	Occurs after changes to a row are complete.
`form:approvecursormove`	Forms.	Occurs before a form is moved to another row. Allows a user to veto a move.
`form:cursormove`	Forms.	Occurs after a form is moved to another row.
`form:supplyparameter`	Forms.	Occurs when a form asks for parameters to connect to a data source.
`form:error`	Forms, combo boxes and list boxes.	Occurs when a database-related error occurs.
`form:adjust`	Value Range	Occurs when the value of a Value Range element has been adjusted.

13.7 <form:properties>

The `<form:properties>` element is a container for `<form:property>` and `<form:list-property>` elements.

The `<form:properties>` element is usable within the following elements: `<form:button>` 13.5.15, `<form:checkbox>` 13.5.17, `<form:combobox>` 13.5.11, `<form:date>` 13.5.8, `<form:file>` 13.5.5, `<form:fixed-text>` 13.5.10, `<form:form>` 13.3, `<form:formatted-text>` 13.5.6, `<form:frame>` 13.5.19, `<form:generic-control>` 13.5.25, `<form:grid>` 13.5.22, `<form:hidden>` 13.5.21, `<form:image>` 13.5.16, `<form:image-frame>` 13.5.20, `<form:listbox>` 13.5.13, `<form:number>` 13.5.7, `<form:password>` 13.5.4, `<form:radio>` 13.5.18, `<form:text>` 13.5.2, `<form:textarea>` 13.5.3, `<form:time>` 13.5.9 and `<form:value-range>` 13.5.24.

The `<form:properties>` element has no attributes.

The `<form:properties>` element has the following child elements: `<form:list-property>` 13.9 and `<form:property>` 13.8.

13.8 <form:property>

The `<form:property>` element defines the name, type and value of a property.

The `<form:property>` element is usable within the following element: `<form:properties>` 13.7.

The `<form:property>` element has the following attributes: `form:property-name` 19.300, `office:boolean-value` 19.367, `office:currency` 19.369, `office:date-value` 19.370, `office:string-value` 19.379, `office:time-value` 19.382, `office:value` 19.384, `office:value-type` 19.385.

The `<form:property>` element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

13.9 <form:list-property>

The <form:list-property> element container for <form:list-value> elements.

The <form:list-property> element has an office:value-type attribute (19.385) that acts as a constraint on the attributes that may appear on its child <form:list-value> element.

The <form:list-property> element is usable within the following element: <form:properties> 13.7.

The <form:list-property> element has the following attributes: form:property-name 19.300, office:value-type 19.385.

The <form:list-property> element has the following child elements: <form:list-value> 13.10.

13.10 <form:list-value>

The list value element contains value attributes for the value type given in the containing <form:list-property> element.

The <form:list-value> element is usable within the following element: <form:list-property> 13.9.

The <form:list-value> element has the following attributes: office:boolean-value 19.367, office:currency 19.369, office:date-value 19.370, office:string-value 19.379, office:time-value 19.382, office:value 19.384.

The <form:list-value> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

14 Common Content

14.1 <office:annotation>

The <office:annotation> element specifies an OpenDocument annotation. The annotation's text is contained in <text:p> and <text:list> elements.

The <office:annotation> element is usable within the following elements: <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <office:annotation> element has the following attributes: draw:caption-point-x 19.116, draw:caption-point-y 19.117, draw:class-names 19.120, draw:corner-radius 19.127, draw:id 19.187.3, draw:layer 19.189, draw:name 19.197.28, draw:style-name 19.219.24, draw:text-style-name 19.227, draw:transform 19.228, draw:z-index 19.231, office:display 19.374, office:name 19.376.6, presentation:class-names 19.390, presentation:style-name 19.422, svg:height 19.539.9, svg:width 19.571.11, svg:x 19.573.7, svg:y 19.577.7, table:end-cell-address 19.627, table:end-x 19.632, table:end-y 19.633, table:table-background 19.728, text:anchor-page-number 19.753, text:anchor-type 19.754 and xml:id 19.914.

The <office:annotation> element has the following child elements: <dc:creator> 4.3.2.7, <dc:date> 4.3.2.10, <meta:date-string> 14.3, <text:list> 5.3.1 and <text:p> 5.1.3.

14.2 <office:annotation-end>

The <office:annotation-end> element may be used to define the end of a text range of document content that spans element boundaries. In that case, an <office:annotation> element shall precede the <office:annotation-end> element. Both elements shall have the same value for their office:name attribute.

The <office:annotation-end> element shall be preceded by an <office:annotation> element that has the same value for its office:name attribute as the <office:annotation-end> element.

An <office:annotation-end> element without a preceding <office:annotation> element that has the same name assigned is ignored.

The <office:annotation-end> element is usable within the following elements: <text:a> 6.1.8, <text:h> 5.1.2, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:p> 5.1.3, <text:ruby-base> 6.4.2 and <text:span> 6.1.7.

The <office:annotation-end> element has the following attribute: office:name 19.376.7.

The <office:annotation-end> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

14.3 <meta:date-string>

The <meta:date-string> element contains a date that is of type string and not a date type. This value is used only for display as entered.

The <meta:date-string> element is usable within the following element: <office:annotation> 14.1.

The <meta:date-string> element has no attributes.

The <meta:date-string> element has no child elements.

The <meta:date-string> element has content of data type string 18.2.

14.4 Event Listener Tables

14.4.1 General

Controls, images, text boxes, or an entire document can support events. An event binds the occurrence of a condition to an action that is executed if the condition arises.

Events are represented as follows:

- All of the event elements that are associated with an object are located in an <office:event-listeners> element.
- Each event-to-action association is recorded in one child element.
- Depending on the type of action that the event triggers, the following child elements are used:
  - The <script:event-listener> 14.4.2 element represents events that are bound to a macro or script.
  - The <presentation:event-listener> 10.9.2 element represents events that are bound to an action that is specific to a presentation.

14.4.2 <script:event-listener>

The <script:event-listener> element binds an event to a macro.

The <script:event-listener> element is usable within the following element: <office:event-listeners> 10.3.19.

The <script:event-listener> element has the following attributes: script:event-name 19.429, script:language 19.430, script:macro-name 19.431, xlink:actuate 19.909, xlink:href 19.910.27 and xlink:type 19.913.

The <script:event-listener> element has no child elements.

14.4.3 Event Types

Event types are implementation-defined. See 19.429.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

14.4.4 Macro Name and Location

Macro code for an event may be specified by either an `xlink:href` attribute as an IRI, or a `script:macro-name` attribute by name. Macro names and applicable IRI schemes are script language dependent.

14.5 <math:math>

The `<math:math>` element serves as a container for content defined by the MathML 2.0 standard. See [MathML].

The `<math:math>` element is usable within the following elements: `<db:component>` 12.25.5 and `<draw:object>` 10.4.6.2.

14.6 DDE Connections

14.6.1 General

A Dynamic Data Exchange (DDE) connection consists of parameters for a DDE target application, a file name, and a command string. A DDE connection also takes a parameter that specifies whether it will be updated automatically or only on the user's request. Every DDE connection shall be named.

All elements making use of DDE connections shall contain their content (or its presentation), so that documents using DDE can still be properly displayed on machines which do not support the DDE mechanism, or where the DDE target is not available. Consumers should preserve the DDE connection information even if they cannot make use of it.

Note: DDE only is available on some operating systems. In order to create portable documents, authors are advised to use this feature in their documents with great care.

14.6.2 <text:dde-connection-decls>

The `<text:dde-connection-decls>` element is a container element for `<text:dde-connection-decl>` elements in text documents.

The `<text:dde-connection-decls>` element is usable within the following elements: `<office:chart>` 3.8, `<office:drawing>` 3.5, `<office:presentation>` 3.6, `<office:spreadsheet>` 3.7, `<office:text>` 3.4, `<style:footer>` 16.11, `<style:footer-left>` 16.13, `<style:header>` 16.10 and `<style:header-left>` 16.12.

The `<text:dde-connection-decls>` element has no attributes.

The `<text:dde-connection-decls>` element has the following child element: `<text:dde-connection-decl>` 14.6.3.

14.6.3 <text:dde-connection-decl>

The `<text:dde-connection-decl>` element defines a DDE connection for use in DDE text fields. Multiple DDE fields can refer to one DDE connection by using the same name.

The `<text:dde-connection-decl>` element is usable within the following element: `<text:dde-connection-decls>` 14.6.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:dde-connection-decl> element has the following attributes: office:automatic-update 19.366, office:dde-application 19.371, office:dde-item 19.372, office:dde-topic 19.373 and office:name 19.376.10.

The <text:dde-connection-decl> element has no child elements.

14.6.4 <table:dde-link>

The <table:dde-link> element contains DDE source data for use in spreadsheet formulas. It contains a <office:dde-source> element and a simple table element that may be used to cache the data of a DDE source. The table does not need a name and does not contain style information. Only the data contained in the cell attributes is used. The cells themselves remain empty.

The <table:dde-link> element is usable within the following element: <table:dde-links> 9.8.

The <table:dde-link> element has no attributes.

The <table:dde-link> element has the following child elements: <office:dde-source> 14.6.5 and <table:table> 9.1.2.

14.6.5 <office:dde-source>

The <office:dde-source> element defines a DDE connection.

If the element is a child element of a <table:table> element, the <office:dde-source> element specifies that the table is linked through DDE along the the connection data.

If the element is a child element of a <text:section> element, the <office:dde-source> element specifies that the text section is linked through DDE along the the connection data.

If the element is a child element of a <table:dde-link> element, the <office:dde-source> element specifies the connection data for a DDE link that can be used in spreadsheet formulas.

The <office:dde-source> element is usable within the following elements: <table:dde-link> 14.6.4, <table:table> 9.1.2 and <text:section> 5.4.

The <office:dde-source> element has the following attributes: office:automatic-update 19.366, office:conversion-mode 19.368, office:dde-application 19.371, office:dde-item 19.372, office:dde-topic 19.373 and office:name 19.376.8.

The <office:dde-source> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

15 SMIL Animations

15.1 General

This section specifies [SMIL20] based elements and attributes that can be used within the OpenDocument format for animation effects.

15.2 Basic Animation Elements

15.2.1 General

The animation elements are based upon §3.5 and §12.5 of [SMIL20], and section §19.2 of [SVG].

15.2.2 <anim:animate>

See §3.5.1 of [SMIL20].

The `<anim:animate>` element is usable within the following elements: `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2, `<anim:seq>` 15.4.3, `<draw:page>` 10.2.4 and `<style:master-page>` 16.9.

The `<anim:animate>` element has the following attributes: `anim:formula` 19.6, `anim:sub-item` 19.11, `smil:accelerate` 19.432, `smil:accumulate` 19.433, `smil:additive` 19.434, `smil:attributeName` 19.435, `smil:autoReverse` 19.436, `smil:begin` 19.437, `smil:by` 19.438, `smil:calcMode` 19.439, `smil:decelerate` 19.440, `smil:dur` 19.442, `smil:end` 19.443, `smil:fill` 19.446, `smil:fillDefault` 19.447, `smil:from` 19.448, `smil:keySplines` 19.449, `smil:keyTimes` 19.450, `smil:repeatCount` 19.452, `smil:repeatDur` 19.453, `smil:restart` 19.454, `smil:restartDefault` 19.455, `smil:targetElement` 19.457, `smil:to` 19.458 and `smil:values` 19.460.

The `<anim:animate>` element has no child elements.

15.2.3 <anim:animateTransform>

The `<anim:animateTransform>` element defines the transformation of an animation. It is based on the [SVG] `<svg:animateTransform>` element. See §19.2.14 of [SVG].

The `<anim:animateTransform>` element is usable within the following elements: `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2, `<anim:seq>` 15.4.3, `<draw:page>` 10.2.4 and `<style:master-page>` 16.9.

The `<anim:animateTransform>` element has the following attributes: `anim:formula` 19.6, `anim:sub-item` 19.11, `smil:accelerate` 19.432, `smil:accumulate` 19.433, `smil:additive` 19.434, `smil:attributeName` 19.435, `smil:autoReverse` 19.436, `smil:begin` 19.437, `smil:by` 19.438, `smil:decelerate` 19.440, `smil:dur` 19.442, `smil:end` 19.443, `smil:fill` 19.446, `smil:fillDefault` 19.447, `smil:from` 19.448, `smil:repeatCount` 19.452, `smil:repeatDur` 19.453, `smil:restart` 19.454, `smil:restartDefault` 19.455, `smil:targetElement` 19.457, `smil:to` 19.458, `smil:values` 19.460 and `svg:type` 19.561.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <anim:animateTransform> element has no child elements.

15.2.4 <anim:set>

See §3.5.2 of [SMIL20].

The <anim:set> element is usable within the following elements: <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <draw:page> 10.2.4 and <style:master-page> 16.9.

The <anim:set> element has the following attributes: anim:sub-item 19.11, smil:accelerate 19.432, smil:accumulate 19.433, smil:additive 19.434, smil:attributeName 19.435, smil:autoReverse 19.436, smil:begin 19.437, smil:decelerate 19.440, smil:dur 19.442, smil:end 19.443, smil:fill 19.446, smil:fillDefault 19.447, smil:repeatCount 19.452, smil:repeatDur 19.453, smil:restart 19.454, smil:restartDefault 19.455, smil:targetElement 19.457 and smil:to 19.458.

The <anim:set> element has no child elements.

15.2.5 <anim:animateMotion>

See §19.2.12 of [SVG] and §3.5.3 of [SMIL20].

The <anim:animateMotion> element is usable within the following elements: <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <draw:page> 10.2.4 and <style:master-page> 16.9.

The <anim:animateMotion> element has the following attributes: anim:formula 19.6, anim:sub-item 19.11, smil:accelerate 19.432, smil:accumulate 19.433, smil:additive 19.434, smil:attributeName 19.435, smil:autoReverse 19.436, smil:begin 19.437, smil:by 19.438, smil:calcMode 19.439, smil:decelerate 19.440, smil:dur 19.442, smil:end 19.443, smil:fill 19.446, smil:fillDefault 19.447, smil:from 19.448, smil:keySplines 19.449, smil:keyTimes 19.450, smil:repeatCount 19.452, smil:repeatDur 19.453, smil:restart 19.454, smil:restartDefault 19.455, smil:targetElement 19.457, smil:to 19.458, smil:values 19.460, svg:origin 19.544 and svg:path 19.548.

The <anim:animateMotion> element has no child elements.

15.2.6 <anim:animateColor>

See §3.5.4 of [SMIL20].

The <anim:animateColor> element is usable within the following elements: <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <draw:page> 10.2.4 and <style:master-page> 16.9.

The <anim:animateColor> element has the following attributes: anim:color-interpolation 19.2, anim:color-interpolation-direction 19.3, anim:formula 19.6, anim:sub-item 19.11, smil:accelerate 19.432, smil:accumulate 19.433, smil:additive 19.434, smil:attributeName 19.435, smil:autoReverse 19.436, smil:begin 19.437, smil:by 19.438, smil:calcMode 19.439, smil:decelerate 19.440, smil:dur 19.442, smil:end 19.443, smil:fill 19.446, smil:fillDefault 19.447,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

smil:from 19.448, smil:keySplines 19.449, smil:keyTimes 19.450, smil:repeatCount 19.452, smil:repeatDur 19.453, smil:restart 19.454, smil:restartDefault 19.455, smil:targetElement 19.457, smil:to 19.458 and smil:values 19.460.

The <anim:animateColor> element has no child elements.

15.2.7 <anim:transitionFilter>

The <anim:transitionFilter> element is based on the [SMIL20] <smil:transitionFilter> element. See §12.5.1 of [SMIL20].

The <anim:transitionFilter> element is usable within the following elements: <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <draw:page> 10.2.4 and <style:master-page> 16.9.

The <anim:transitionFilter> element has the following attributes: anim:formula 19.6, anim:sub-item 19.11, smil:accelerate 19.432, smil:accumulate 19.433, smil:additive 19.434, smil:autoReverse 19.436, smil:begin 19.437, smil:by 19.438, smil:calcMode 19.439, smil:decelerate 19.440, smil:direction 19.441, smil:dur 19.442, smil:end 19.443, smil:fadeColor 19.445, smil:fill 19.446, smil:fillDefault 19.447, smil:from 19.448, smil:mode 19.451, smil:repeatCount 19.452, smil:repeatDur 19.453, smil:restart 19.454, smil:restartDefault 19.455, smil:subtype 19.456, smil:targetElement 19.457, smil:to 19.458, smil:type 19.459 and smil:values 19.460.

The <anim:transitionFilter> element has no child elements.

15.3 Animation Model Attributes

15.3.1 General

The animation model uses the same concepts and syntax as specified in §3 of [SMIL20].

15.3.2 Simple Animation Functions

Simplified animations can be specified using the [SMIL20] smil:from, smil:to and smil:by attributes. See §3.4.4 of [SMIL20].

15.4 Animation Timing

15.4.1 General

Animation timing uses the same concepts and syntax as specified in §10 and §11 of [SMIL20].

15.4.2 <anim:par>

The <anim:par> element is a container of child animation nodes that have a common starting point.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <anim:par> element is usable within the following elements: <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <draw:page> 10.2.4 and <style:master-page> 16.9.

The <anim:par> element has the following attributes: anim:id 19.7, presentation:group-id 19.397, presentation:master-element 19.398, presentation:node-type 19.402, presentation:preset-class 19.410, presentation:preset-id 19.411, presentation:preset-sub-type 19.412, smil:accelerate 19.432, smil:autoReverse 19.436, smil:begin 19.437, smil:decelerate 19.440, smil:dur 19.442, smil:end 19.443, smil:endsync 19.444, smil:fill 19.446, smil:fillDefault 19.447, smil:repeatCount 19.452, smil:repeatDur 19.453, smil:restart 19.454, smil:restartDefault 19.455 and xml:id 19.914.

The <anim:par> element has the following child elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3, <anim:audio> 15.5, <anim:command> 15.6.1, <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <anim:set> 15.2.4 and <anim:transitionFilter> 15.2.7.

15.4.3 <anim:seq>

The <anim:seq> element is a container for child animation nodes that start in a sequential fashion.

The <anim:seq> element is usable within the following elements: <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <draw:page> 10.2.4 and <style:master-page> 16.9.

The <anim:seq> element has the following attributes: anim:id 19.7, presentation:group-id 19.397, presentation:master-element 19.398, presentation:node-type 19.402, presentation:preset-class 19.410, presentation:preset-id 19.411, presentation:preset-sub-type 19.412, smil:accelerate 19.432, smil:autoReverse 19.436, smil:begin 19.437, smil:decelerate 19.440, smil:dur 19.442, smil:end 19.443, smil:endsync 19.444, smil:fill 19.446, smil:fillDefault 19.447, smil:repeatCount 19.452, smil:repeatDur 19.453, smil:restart 19.454, smil:restartDefault 19.455 and xml:id 19.914.

The <anim:seq> element has the following child elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3, <anim:audio> 15.5, <anim:command> 15.6.1, <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <anim:set> 15.2.4 and <anim:transitionFilter> 15.2.7.

15.4.4 <anim:iterate>

The <anim:iterate> element defines a parallel time container. The animation effects are applied to the child objects of the target element. The effects for each child object are started one after another, where the delay between the start of the effects of two subsequent children is specified by the anim:iterate-interval attribute. 19.8

The <anim:iterate> element is usable within the following elements: <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <draw:page> 10.2.4 and <style:master-page> 16.9.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <anim:iterate> element has the following attributes: anim:id 19.7, anim:iterate-interval 19.8, anim:iterate-type 19.9, anim:sub-item 19.11, presentation:group-id 19.397, presentation:master-element 19.398, presentation:node-type 19.402, presentation:preset-class 19.410, presentation:preset-id 19.411, presentation:preset-sub-type 19.412, smil:accelerate 19.432, smil:autoReverse 19.436, smil:begin 19.437, smil:decelerate 19.440, smil:dur 19.442, smil:end 19.443, smil:endsync 19.444, smil:fill 19.446, smil:fillDefault 19.447, smil:repeatCount 19.452, smil:repeatDur 19.453, smil:restart 19.454, smil:restartDefault 19.455, smil:targetElement 19.457 and xml:id 19.914.

The <anim:iterate> element has the following child elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3, <anim:audio> 15.5, <anim:command> 15.6.1, <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <anim:set> 15.2.4 and <anim:transitionFilter> 15.2.7.

15.5 <anim:audio>

The <anim:audio> element is based on the [SMIL20] <smil:audio> element. It specifies the playback of audio streams during an animation. See §7.3.1 of [SMIL20].

The <anim:audio> element is usable within the following elements: <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <draw:page> 10.2.4 and <style:master-page> 16.9.

The <anim:audio> element has the following attributes: anim:audio-level 19.4, anim:id 19.7, presentation:group-id 19.397, presentation:master-element 19.398, presentation:node-type 19.402, presentation:preset-class 19.410, presentation:preset-id 19.411, presentation:preset-sub-type 19.412, smil:begin 19.437, smil:dur 19.442, smil:end 19.443, smil:fill 19.446, smil:fillDefault 19.447, smil:repeatCount 19.452, smil:repeatDur 19.453, smil:restart 19.454, smil:restartDefault 19.455, xlink:href 19.910.2 and xml:id 19.914.

The <anim:audio> element has no child elements.

15.6 Animation Command Elements

15.6.1 <anim:command>

The <anim:command> element specifies an animation command.

Note: See 19.5 for details about the element's usage in presentation documents.

The <anim:command> element is usable within the following elements: <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <draw:page> 10.2.4 and <style:master-page> 16.9.

The <anim:command> element has the following attributes: anim:command 19.5, anim:id 19.7, anim:sub-item 19.11, presentation:group-id 19.397, presentation:master-element 19.398, presentation:node-type 19.402, presentation:preset-class

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.410, presentation:preset-id 19.411, presentation:preset-sub-type 19.412, smil:begin 19.437, smil:end 19.443, smil:targetElement 19.457 and xml:id 19.914.

The <anim:command> element has the following child element: <anim:param> 15.6.2.

15.6.2 <anim:param>

The <anim:param> element specifies a parameter for an <anim:command> element.

The <anim:param> element is usable within the following element: <anim:command> 15.6.1.

The <anim:param> element has the following attributes: anim:name 19.10 and anim:value 19.12.

The <anim:param> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16 Styles

16.1 General

Objects in an office document may have formatting properties. A formatting property influences the visual representation of an object.

In the OpenDocument format, formatting properties are stored in styles.

There are two reasons for using styles to store formatting properties:

1) Format information is separated from document content.

2) Styles enable consistent formatting and changing of formatting for objects subject to styles.

Styles and font face declarations are referenced by their `style:name` attribute. A referenced style or font face declaration should be defined in the same file as the reference, or in styles.xml.

16.2 <style:style>

The `<style:style>` element represents styles.

Styles defined by the `<style:style>` element use a hierarchical style model. The `<style:style>` element supports inheritance of formatting properties by a style from its parent style. A parent style is specified by the `style:parent-style-name` attribute on a `<style:style>` element.

The determination of the value of a formatting property begins with any style that is specified by an element. If the formatting property is present in that style, its value is used.

If that style does not specify a value for that formatting property and it has a parent style, the value of the formatting element is taken from the parent style, if present.

If the parent style does not have a value for the formatting property, the search for the formatting property value continues up parent styles until either the formatting property has been found or a style is found with no parent style.

If a search of the parent styles of a style does not result in a value for a formatting property, the determination of its value depends on the style family and the element to which a style is applied.

For styles with family `text` which are applied to elements which are contained in another element that specifies a style with family `text`, the search continues within the `text` style that is applied to the nearest ancestor element that specifies a style with family `text`, and continues in its parent styles.

For styles with family `text` which are applied to elements which are contained in a paragraph element 6.1.1, the search continues within the `paragraph` style that is applied to the paragraph element, and continues in its parent styles.

For styles with family `paragraph` which are applied to paragraph elements which are contained in a drawing shape or a chart element, the search continues within the `graphic`, `presentation` or `chart` style that is applied to the drawing object or chart element, and continues in its parent styles.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

For styles with family `paragraph` which are applied to paragraph elements which are contained in a table cell, the search continues within the `table-cell` style that is applied to the table-cell, and continues in its parent styles. If a value for the formatting property has not been found, the search continues as defined for styles with family `table-cell`.

For styles with family `table-cell` which are applied to a table cell, the search continues with the style specified by the `table:default-cell-style-name` attribute 19.615 of the table cell's `<table:table-row>` parent element, if present, and then with the style specified by the `table:default-cell-style-name` attribute of the `<table:table-column>` element associated with the table cell.

In all other cases, or if a value for the formatting property has not been found by any of the family specific rules, a default style 16.4 that has the same family as the style initially declared sets the value. If there is no value specified in that default style, an implementation-dependent value is used.

The `<style:style>` element is usable within the following elements: `<office:automatic-styles>` 3.15.3 and `<office:styles>` 3.15.2.

The `<style:style>` element has the following attributes: `style:auto-update` 19.463, `style:class` 19.466, `style:data-style-name` 19.469.3, `style:default-outline-level` 19.470, `style:display-name` 19.472, `style:family` 19.476, `style:list-level` 19.495, `style:list-style-name` 19.496, `style:master-page-name` 19.497, `style:name` 19.498.2, `style:next-style-name` 19.499.3, `style:parent-style-name` 19.506 and `style:percentage-data-style-name` 19.507.

The `<style:style>` element has the following child elements: `<style:chart-properties>` 17.22, `<style:drawing-page-properties>` 17.25, `<style:graphic-properties>` 17.21, `<style:map>` 16.3, `<style:paragraph-properties>` 17.6, `<style:ruby-properties>` 17.10, `<style:section-properties>` 17.11, `<style:table-cell-properties>` 17.18, `<style:table-column-properties>` 17.16, `<style:table-properties>` 17.15, `<style:table-row-properties>` 17.17, `<style:text-properties>` 16.27.28.

16.3 <style:map>

The `<style:map>` element represents a condition, which if met, results in the mapping of a style. A style that contains one or more mappings is called an conditional style. Each condition is represented by a unique `<style:map>` element.

Conditional styles are supported by:

- paragraph styles contained in text documents
- table cell styles contained in spreadsheets
- data styles

The `<style:map>` element is usable within the following elements: `<number:boolean-style>` 16.27.23, `<number:currency-style>` 16.27.7, `<number:date-style>` 16.27.10, `<number:number-style>` 16.27.2, `<number:percentage-style>` 16.27.9, `<number:text-style>` 16.27.25, `<number:time-style>` 16.27.18 and `<style:style>` 16.2.

The `<style:map>` element has the following attributes: `style:apply-style-name` 19.462, `style:base-cell-address` 19.464 and `style:condition` 19.468.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <style:map> element has no child elements.

16.4 <style:default-style>

The <style:default-style> element represents default styles. A default style specifies default formatting properties for a style family. These defaults are used if a formatting property is neither specified by an automatic nor a common style. Default styles exist for all style families that are represented by the <style:style> element specified by the style:family attribute 19.476.

An OpenDocument document should contain the default styles of the style families for which are used in common or automatic styles in the document.

The <style:default-style> element is usable within the following element: <office:styles> 3.15.2.

The <style:default-style> element has the following attributes: style:family 19.476.

The <style:default-style> element has the following child elements: <style:chart-properties> 17.22, <style:drawing-page-properties> 17.25, <style:graphic-properties> 17.21, <style:paragraph-properties> 17.6, <style:ruby-properties> 17.10, <style:section-properties> 17.11, <style:table-cell-properties> 17.18, <style:table-column-properties> 17.16, <style:table-properties> 17.15, <style:table-row-properties> 17.17, <style:text-properties> 16.27.28.

16.5 <style:page-layout>

The <style:page-layout> element represents the styles that specify the formatting properties of a page.

The <style:page-layout> element is usable within the following element: <office:automatic-styles> 3.15.3.

The <style:page-layout> element has the following attributes: style:name 19.498.2 and style:page-usage 19.505.

The <style:page-layout> element has the following child elements: <style:footer-style> 16.7, <style:header-style> 16.6 and <style:page-layout-properties> 17.2.

16.6 <style:header-style>

The <style:header-style> element specifies the formatting properties for a header element.

The <style:header-style> element is usable within the following elements: <style:default-page-layout> 16.8 and <style:page-layout> 16.5.

The <style:header-style> element has no attributes.

The <style:header-style> element has the following child element: <style:header-footer-properties> 17.5.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.7 <style:footer-style>

The <style:footer-style> element specifies the formatting properties for a footer element.

The <style:footer-style> element is usable within the following elements: <style:default-page-layout> 16.8 and <style:page-layout> 16.5.

The <style:footer-style> element has no attributes.

The <style:footer-style> element has the following child element: <style:header-footer-properties> 17.5.

16.8 <style:default-page-layout>

The <style:default-page-layout> element specifies default formatting properties for page layouts. These defaults are used if a formatting property is not specified in a <style:page-layout-properties> element. 17.2

The <style:default-page-layout> element is usable within the following element: <office:styles> 3.15.2.

The <style:default-page-layout> element has no attributes.

The <style:default-page-layout> element has the following child elements: <style:footer-style> 16.7, <style:header-style> 16.6 and <style:page-layout-properties> 17.2.

16.9 <style:master-page>

In text and spreadsheet documents, the <style:master-page> element contains the content of headers and footers. For these types of documents, consumers may generate a sequence of pages by making use of a single master page or a set of master pages.

In drawing and presentation documents, the <style:master-page> element is used to define master pages as common backgrounds for drawing pages. Each drawing page is directly linked to one master page, which is specified by the draw:master-page-name attribute of the drawing pages style.

Master pages are contained in the <office:master-styles> element.

All documents shall contain at least one master page element.

If a text or spreadsheet document is displayed in a paged layout, master pages are used to generate a sequence of pages containing the document content. When a page is created, an empty page is generated with the properties of the master page and the static content of the master page. The body of the page is then filled with content. A single master pages can be used to created multiple pages within a document.

In text and spreadsheet documents, a master page can be assigned to paragraph and table styles using a style:master-page-name attribute. Each time the paragraph or table style is applied to text, a page break is inserted before the paragraph or table. A page that starts at the page break position uses the specified master page.

In drawings and presentations, master pages can be assigned to drawing pages using a style:parent-style-name attribute.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Note: The OpenDocument paging methodology differs significantly from the methodology used in [XSL]. In XSL, headers and footers are contained within page sequences that also contain the document content. In the OpenDocument format, headers and footers are contained in page styles. With either approach, the content of headers and footers can be changed or omitted without affecting the document content.

The `<style:master-page>` element is usable within the following element: `<office:master-styles>` 3.15.4.

The `<style:master-page>` element has the following attributes: `draw:style-name` 19.219.27, `style:display-name` 19.472, `style:name` 19.498.2, `style:next-style-name` 19.499.2 and `style:page-layout-name` 19.504.

The `<style:master-page>` element has the following child elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3, `<anim:audio>` 15.5, `<anim:command>` 15.6.1, `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2, `<anim:seq>` 15.4.3, `<anim:set>` 15.2.4, `<anim:transitionFilter>` 15.2.7, `<dr3d:scene>` 10.5.2, `<draw:a>` 10.4.12, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:connector>` 10.3.10, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:g>` 10.3.15, `<draw:layer-set>` 10.2.2, `<draw:line>` 10.3.3, `<draw:measure>` 10.3.12, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2, `<draw:regular-polygon>` 10.3.6, `<office:forms>` 13.2, `<presentation:notes>` 16.17, `<style:footer>` 16.11, `<style:footer-left>` 16.13, `<style:header>` 16.10 and `<style:header-left>` 16.12.

16.10 <style:header>

The `<style:header>` element represents the content of a header in a `<style:master-page>` element.

The `<style:header>` element is usable within the following element: `<style:master-page>` 16.9.

The `<style:header>` element has the following attribute: `style:display` 19.471.

The `<style:header>` element has the following child elements: `<style:region-center>` 16.15, `<style:region-left>` 16.14, `<style:region-right>` 16.16, `<table:table>` 9.1.2, `<text:alphabetical-index>` 8.8, `<text:alphabetical-index-auto-mark-file>` 8.8.3, `<text:bibliography>` 8.9, `<text:change>` 5.5.7.4, `<text:change-end>` 5.5.7.3, `<text:change-start>` 5.5.7.2, `<text:dde-connection-decls>` 14.6.2, `<text:h>` 5.1.2, `<text:illustration-index>` 8.4, `<text:index-title>` 8.2.3, `<text:list>` 5.3.1, `<text:object-index>` 8.6, `<text:p>` 5.1.3, `<text:section>` 5.4, `<text:sequence-decls>` 7.4.11, `<text:table-index>` 8.5, `<text:table-of-content>` 8.3, `<text:tracked-changes>` 5.5.1, `<text:user-field-decls>` 7.4.7, `<text:user-index>` 8.7 and `<text:variable-decls>` 7.4.2.

16.11 <style:footer>

The `<style:footer>` element represents the content of a footer in a `<style:master-page>` element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <style:footer> element is usable within the following element: <style:master-page> 16.9.

The <style:footer> element has the following attribute: style:display 19.471.

The <style:footer> element has the following child elements: <style:region-center> 16.15, <style:region-left> 16.14, <style:region-right> 16.16, <table:table> 9.1.2, <text:alphabetical-index> 8.8, <text:alphabetical-index-auto-mark-file> 8.8.3, <text:bibliography> 8.9, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:dde-connection-decls> 14.6.2, <text:h> 5.1.2, <text:illustration-index> 8.4, <text:index-title> 8.2.3, <text:list> 5.3.1, <text:object-index> 8.6, <text:p> 5.1.3, <text:section> 5.4, <text:sequence-decls> 7.4.11, <text:table-index> 8.5, <text:table-of-content> 8.3, <text:tracked-changes> 5.5.1, <text:user-field-decls> 7.4.7, <text:user-index> 8.7 and <text:variable-decls> 7.4.2.

16.12 <style:header-left>

The <style:header-left> element represents the content for a header for a left page, if different from the right page in a <style:master-page> element.

The <style:header-left> element is usable within the following element: <style:master-page> 16.9.

The <style:header-left> element has the following attribute: style:display 19.471.

The <style:header-left> element has the following child elements: <style:region-center> 16.15, <style:region-left> 16.14, <style:region-right> 16.16, <table:table> 9.1.2, <text:alphabetical-index> 8.8, <text:alphabetical-index-auto-mark-file> 8.8.3, <text:bibliography> 8.9, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:dde-connection-decls> 14.6.2, <text:h> 5.1.2, <text:illustration-index> 8.4, <text:index-title> 8.2.3, <text:list> 5.3.1, <text:object-index> 8.6, <text:p> 5.1.3, <text:section> 5.4, <text:sequence-decls> 7.4.11, <text:table-index> 8.5, <text:table-of-content> 8.3, <text:tracked-changes> 5.5.1, <text:user-field-decls> 7.4.7, <text:user-index> 8.7 and <text:variable-decls> 7.4.2.

16.13 <style:footer-left>

The <style:footer-left> element represents the content for a footer for a left page, if different from the right page for a <style:master-page> element.

The <style:footer-left> element is usable within the following element: <style:master-page> 16.9.

The <style:footer-left> element has the following attribute: style:display 19.471.

The <style:footer-left> element has the following child elements: <style:region-center> 16.15, <style:region-left> 16.14, <style:region-right> 16.16, <table:table> 9.1.2, <text:alphabetical-index> 8.8, <text:alphabetical-index-auto-mark-file> 8.8.3, <text:bibliography> 8.9, <text:change> 5.5.7.4, <text:change-end> 5.5.7.3, <text:change-start> 5.5.7.2, <text:dde-connection-decls> 14.6.2, <text:h> 5.1.2, <text:illustration-index> 8.4, <text:index-title> 8.2.3, <text:list> 5.3.1, <text:object-index> 8.6, <text:p> 5.1.3,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<text:section> 5.4, <text:sequence-decls> 7.4.11, <text:table-index> 8.5, <text:table-of-content> 8.3, <text:tracked-changes> 5.5.1, <text:user-field-decls> 7.4.7, <text:user-index> 8.7 and <text:variable-decls> 7.4.2.

16.14 <style:region-left>

The <style:region-left> element specifies a left-aligned portion of a header or footer. That region may contain a sequence of <text:p> elements.

The <style:region-left> element is usable within the following elements: <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10 and <style:header-left> 16.12.

The <style:region-left> element has no attributes.

The <style:region-left> element has the following child element: <text:p> 5.1.3.

16.15 <style:region-center>

The <style:region-center> element specifies a center-aligned portion of a header or footer. That region may contain a sequence of <text:p> elements.

The <style:region-center> element is usable within the following elements: <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10 and <style:header-left> 16.12.

The <style:region-center> element has no attributes.

The <style:region-center> element has the following child element: <text:p> 5.1.3.

16.16 <style:region-right>

The <style:region-right> element specifies a right-aligned portion of a header or footer. That region may contain a sequence of <text:p> elements.

The <style:region-right> element is usable within the following elements: <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10 and <style:header-left> 16.12.

The <style:region-right> element has no attributes.

The <style:region-right> element has the following child element: <text:p> 5.1.3.

16.17 <presentation:notes>

The <presentation:notes> element defines a notes page. A notes page contains a preview of a drawing page and additional graphic shapes.

The <presentation:notes> element is usable within the following elements: <draw:page> 10.2.4 and <style:master-page> 16.9.

The <presentation:notes> element has the following attributes: draw:style-name 19.219.25, presentation:use-date-time-name 19.424, presentation:use-footer-

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

name 19.425, presentation:use-header-name 19.426 and style:page-layout-name 19.504.

The <presentation:notes> element has the following child elements: <dr3d:scene> 10.5.2, <draw:a> 10.4.12, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6 and <office:forms> 13.2.

16.18 <table:table-template>

A <table:table-template> element represents a set of references to table cell styles that specify the formatting to be used when creating a table.

If more than one table cell style reference is applicable to a cell, the first style that is applicable is chosen in the following order:

- First Column <table:first-column> 16.19.4
- Last Column <table:last-column> 16.19.5
- First Row <table:first-row> 16.19.2
- Last Row <table:last-row> 16.19.3
- Even rows <table:even-rows> 16.19.7, odd rows <table:odd-rows> 16.19.8 (Banded Rows)
- Even columns <table:even-columns> 16.19.9, odd columns <table:odd-columns> 16.19.10 (Banded Columns)
- Body <table:body> 16.19.6

Table templates are contained in a <office:styles> element.

The <table:table-template> element is usable within the following element: <office:styles> 3.15.2.

The <table:table-template> element has the following attributes: table:first-row-end-column 19.640, table:first-row-start-column 19.641, table:last-row-end-column 19.659, table:last-row-start-column 19.661 and table:name 19.673.14.

The <table:table-template> element has the following child elements: <table:background> 16.20, <table:body> 16.19.6, <table:even-columns> 16.19.9, <table:even-rows> 16.19.7, <table:first-column> 16.19.4, <table:first-row> 16.19.2, <table:last-column> 16.19.5, <table:last-row> 16.19.3, <table:odd-columns> 16.19.10 and <table:odd-rows> 16.19.8.

16.19 Cell Styles

16.19.1 General

The cell styles applied in a table are based on the position of cells in a table.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.19.2 <table:first-row>

The `<table:first-row>` element specifies a cell style that shall be applied to the first row of a table.

The `<table:first-row>` element is usable within the following element: `<table:table-template>` 16.18.

The `<table:first-row>` element has the following attributes: `table:paragraph-style-name` 19.688 and `table:style-name` 19.726.8.

The `<table:first-row>` element has no child elements.

16.19.3 <table:last-row>

The `<table:last-row>` element specifies a cell style that shall be applied to the last row of a table.

The `<table:last-row>` element is usable within the following element: `<table:table-template>` 16.18.

The `<table:last-row>` element has the following attributes: `table:paragraph-style-name` 19.688 and `table:style-name` 19.726.10.

The `<table:last-row>` element has no child elements.

16.19.4 <table:first-column>

The `<table:first-column>` element specifies a cell style that shall be applied to the first table column in a table.

The `<table:first-column>` element is usable within the following element: `<table:table-template>` 16.18.

The `<table:first-column>` element has the following attributes: `table:paragraph-style-name` 19.688 and `table:style-name` 19.726.7.

The `<table:first-column>` element has no child elements.

16.19.5 <table:last-column>

The `<table:last-column>` element specifies a cell style that shall be applied to the last table column in a table.

The `<table:last-column>` element is usable within the following element: `<table:table-template>` 16.18.

The `<table:last-column>` element has the following attributes: `table:paragraph-style-name` 19.688 and `table:style-name` 19.726.9.

The `<table:last-column>` element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.19.6 <table:body>

The <table:body> element specifies styles for cells that are not governed by other specified styles.

The <table:body> element is usable within the following element: <table:table-template> 16.18.

The <table:body> element has the following attributes: table:paragraph-style-name 19.688 and table:style-name 19.726.3.

The <table:body> element has no child elements.

16.19.7 <table:even-rows>

The <table:even-rows> element specifies styles to be applied to even rows in a table.

The <table:even-rows> element is usable within the following element: <table:table-template> 16.18.

The <table:even-rows> element has the following attributes: table:paragraph-style-name 19.688 and table:style-name 19.726.6.

The <table:even-rows> element has no child elements.

16.19.8 <table:odd-rows>

The <table:odd-rows> element specifies styles to be applied to odd rows in a table.

The <table:odd-rows> element is usable within the following element: <table:table-template> 16.18.

The <table:odd-rows> element has the following attributes: table:paragraph-style-name 19.688 and table:style-name 19.726.12.

The <table:odd-rows> element has no child elements.

16.19.9 <table:even-columns>

The <table:even-columns> element specifies styles to be applied to even columns in a table.

The <table:even-columns> element is usable within the following element: <table:table-template> 16.18.

The <table:even-columns> element has the following attributes: table:paragraph-style-name 19.688 and table:style-name 19.726.5.

The <table:even-columns> element has no child elements.

16.19.10 <table:odd-columns>

The <table:odd-columns> element specifies styles to be applied to odd columns in a table.

The <table:odd-columns> element is usable within the following element: <table:table-template> 16.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <table:odd-columns> element has the following attributes: table:paragraph-style-name 19.688 and table:style-name 19.726.11.

The <table:odd-columns> element has no child elements.

16.20 <table:background>

The <table:background> element specifies a table style that provides a background to a table that is visible if all or part of the table is transparent.

The <table:background> element is usable within the following element: <table:table-template> 16.18.

The <table:background> element has the following attribute: table:style-name 19.726.2.

The <table:background> element has no child elements.

16.21 <style:font-face>

The <style:font-face> element represents a font face declaration which documents the properties of a font used in a document.

OpenDocument font face declarations directly correspond to the @font-face font description of [CSS2] (see §15.3.1) and the <font-face> element of [SVG] (see §20.8.3).

OpenDocument font face declarations may have an unique name. This name can be used inside styles (as an attribute of <style:text-properties> element) as value of the style:font-name attribute to select a font face declaration. If a font face declaration is referenced by name, the font matching algorithms for selecting a font declaration based on the font-family, font-style, font-variant, font-weight and font-size descriptors are not used but the referenced font face declaration is used directly. (See §15.5 [CSS2])

Consumers should implement the CSS2 font matching algorithm with the OpenDocument font face extensions. They may implement variations of the CSS2 font matching algorithm. They may implement a font matching based only on the font face declarations, that is, a font matching that is not applied to every character independently but only once for each font face declaration. (See §15.5 [CSS2])

Font face declarations support the font descriptor attributes and elements described in §20.8.3 of [SVG].

The <style:font-face> element is usable within the following element: <office:font-face-decls> 3.14.

The <style:font-face> element has the following attributes: style:font-adornments 19.478, style:font-charset 19.479, style:font-family-generic 19.480, style:font-pitch 19.481, style:name 19.498.3, svg:accent-height 19.519, svg:alphabetic 19.520, svg:ascent 19.521, svg:bbox 19.522, svg:cap-height 19.523, svg:descent 19.527, svg:font-family 19.528, svg:font-size 19.529, svg:font-stretch 19.530, svg:font-style 19.531, svg:font-variant 19.532, svg:font-weight 19.533, svg:hanging 19.538, svg:ideographic 19.540, svg:mathematical 19.541, svg:overline-position 19.545, svg:overline-thickness 19.546, svg:panose-1 19.547, svg:slope 19.552, svg:stemh 19.554, svg:stemv 19.555, svg:strikethrough-position 19.558, svg:strikethrough-thickness 19.559, svg:underline-position 19.562, svg:underline-thickness 19.563, svg:unicode-range 19.564, svg:units-

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

per-em 19.565, svg:v-alphabetic 19.566, svg:v-hanging 19.567, svg:v-ideographic 19.568, svg:v-mathematical 19.569, svg:widths 19.572 and svg:x-height 19.576.

The <style:font-face> element has the following child elements: <svg:definition-src> 16.25 and <svg:font-face-src> 16.22.

16.22 <svg:font-face-src>

See §20.8.3 of [SVG].

The <svg:font-face-src> element is usable within the following element: <style:font-face> 16.21.

The <svg:font-face-src> element has no attributes.

The <svg:font-face-src> element has the following child elements: <svg:font-face-name> 16.23 and <svg:font-face-uri> 16.24.

16.23 <svg:font-face-name>

See §20.8.3 of [SVG].

The <svg:font-face-name> element is usable within the following element: <svg:font-face-src> 16.22.

The <svg:font-face-name> element has the following attribute: svg:name 19.542.

The <svg:font-face-name> element has no child elements.

16.24 <svg:font-face-uri>

See § 20.8.3 of [SVG].

The <svg:font-face-uri> element is usable within the following element: <svg:font-face-src> 16.22.

The <svg:font-face-uri> element has the following attributes: xlink:actuate 19.909, xlink:href 19.910.30 and xlink:type 19.913.

The <svg:font-face-uri> element has the following child element: <svg:font-face-format> 16.26.

16.25 <svg:definition-src>

See § 20.8.3 of [SVG].

The <svg:definition-src> element is usable within the following element: <style:font-face> 16.21.

The <svg:definition-src> element has the following attributes: xlink:actuate 19.909, xlink:href 19.910.29 and xlink:type 19.913.

The <svg:definition-src> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.26 <svg:font-face-format>

See §20.8.3 of [SVG].

The <svg:font-face-format> element is usable within the following element: <svg:font-face-uri> 16.24.

The <svg:font-face-format> element has the following attribute: svg:string 19.560.

The <svg:font-face-format> element has no child elements.

16.27 Data Styles

16.27.1 General

Data styles specify the styles to be applied to defined data types for display.

Data styles shall not specify two <number:text> elements in sequence as part of a data style.

16.27.2 <number:number-style>

The <number:number-style> element is a container for elements that define a style for decimal numbers.

The <number:number-style> element is usable within the following elements: <office:automatic-styles> 3.15.3 and <office:styles> 3.15.2.

The <number:number-style> element has the following attributes: number:country 19.342, number:language 19.349, number:rfc-language-tag 19.356, number:script 19.357, number:title 19.360, number:transliteration-country 19.361, number:transliteration-format 19.362, number:transliteration-language 19.363, number:transliteration-style 19.364, style:display-name 19.472, style:name 19.498.2 and style:volatile 19.517.

The <number:number-style> element has the following child elements: <number:fraction> 16.27.6, <number:number> 16.27.3, <number:scientific-number> 16.27.5, <number:text> 16.27.26, <style:map> 16.3 and <style:text-properties> 16.27.28.

16.27.3 <number:number>

The <number:number> element specifies the display formatting properties for a decimal number.

The <number:number> element is usable within the following elements: <number:currency-style> 16.27.7, <number:number-style> 16.27.2 and <number:percentage-style> 16.27.9.

The <number:number> element has the following attributes: number:decimal-places 19.343.2, number:decimal-replacement 19.344, number:display-factor 19.346, number:grouping 19.348 and number:min-integer-digits 19.352.

The <number:number> element has the following child element: <number:embedded-text> 16.27.4.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.27.4 <number:embedded-text>

The <number:embedded-text> element specifies text that is displayed at one specific position within a number.

The <number:embedded-text> element is usable within the following element: <number:number> 16.27.3.

The <number:embedded-text> element has the following attribute: number:position 19.354.

The <number:embedded-text> element has no child elements.

The <number:embedded-text> element has character data content.

16.27.5 <number:scientific-number>

The <number:scientific-number> element specifies the display formatting properties for a number style that should be displayed in scientific format.

The <number:scientific-number> element is usable within the following element: <number:number-style> 16.27.2.

The <number:scientific-number> element has the following attributes: number:decimal-places 19.343.4, number:grouping 19.348, number:min-exponent-digits 19.351 and number:min-integer-digits 19.352.

The <number:scientific-number> element has no child elements.

16.27.6 <number:fraction>

The <number:fraction> element specifies the display formatting properties for a number style that should be displayed as a fraction.

The <number:fraction> element is usable within the following element: <number:number-style> 16.27.2.

The <number:fraction> element has the following attributes: number:denominator-value 19.345, number:grouping 19.348, number:min-denominator-digits 19.350, number:min-integer-digits 19.352 and number:min-numerator-digits 19.353.

The <number:fraction> element has no child elements.

16.27.7 <number:currency-style>

The <number:currency-style> element specifies the style for currency values.

The <number:currency-style> element is usable within the following elements: <office:automatic-styles> 3.15.3 and <office:styles> 3.15.2.

The <number:currency-style> element has the following attributes: number:automatic-order 19.340, number:country 19.342, number:language 19.349, number:rfc-language-tag 19.356, number:script 19.357, number:title 19.360, number:transliteration-country 19.361, number:transliteration-format 19.362,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

number:transliteration-language 19.363, number:transliteration-style 19.364, style:display-name 19.472, style:name 19.498.2 and style:volatile 19.517.

The <number:currency-style> element has the following child elements: <number:currency-symbol> 16.27.8, <number:number> 16.27.3, <number:text> 16.27.26, <style:map> 16.3 and <style:text-properties> 16.27.28.

16.27.8 <number:currency-symbol>

The <number:currency-symbol> element specifies whether a currency symbol is displayed in a currency style.

The content of this element is the text that is displayed as the currency symbol. If the element is empty or contains white space characters only, the default currency symbol for the currency style or the language and country of the currency style is displayed.

The <number:currency-symbol> element is usable within the following element: <number:currency-style> 16.27.7.

The <number:currency-symbol> element has the following attributes: number:country 19.342, number:language 19.349, number:rfc-language-tag 19.356 and number:script 19.357.

The <number:currency-symbol> element has no child elements.

The <number:currency-symbol> element has character data content.

16.27.9 <number:percentage-style>

The <number:percentage-style> element specifies the style for percentage values.

A <number:percentage-style> element should have <number:text> child element whose character data contains a “%” (U+0025, PERCENT SIGN) character.

The <number:percentage-style> element is usable within the following elements: <office:automatic-styles> 3.15.3 and <office:styles> 3.15.2.

The <number:percentage-style> element has the following attributes: number:country 19.342, number:language 19.349, number:rfc-language-tag 19.356, number:script 19.357, number:title 19.360, number:transliteration-country 19.361, number:transliteration-format 19.362, number:transliteration-language 19.363, number:transliteration-style 19.364, style:display-name 19.472, style:name 19.498.2 and style:volatile 19.517.

The <number:percentage-style> element has the following child elements: <number:number> 16.27.3, <number:text> 16.27.26, <style:map> 16.3 and <style:text-properties> 16.27.28.

16.27.10 <number:date-style>

The <number:date-style> element specifies a style for date values.

This element can contain *one* instance of each of the following elements: <number:day>, <number:month>, <number:year>, <number:era>, <number:day-of-week>,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<number:week-of-year>, <number:quarter>, <number:hours>, <number:minutes>, <number:seconds>, and <number:am-pm>.

The <number:date-style> element is usable within the following elements: <office:automatic-styles> 3.15.3 and <office:styles> 3.15.2.

The <number:date-style> element has the following attributes: number:automatic-order 19.340, number:country 19.342, number:format-source 19.347, number:language 19.349, number:rfc-language-tag 19.356, number:script 19.357, number:title 19.360, number:transliteration-country 19.361, number:transliteration-format 19.362, number:transliteration-language 19.363, number:transliteration-style 19.364, style:display-name 19.472, style:name 19.498.2 and style:volatile 19.517.

The <number:date-style> element has the following child elements: <number:am-pm> 16.27.22, <number:day> 16.27.11, <number:day-of-week> 16.27.15, <number:era> 16.27.14, <number:hours> 16.27.19, <number:minutes> 16.27.20, <number:month> 16.27.12, <number:quarter> 16.27.17, <number:seconds> 16.27.21, <number:text> 16.27.26, <number:week-of-year> 16.27.16, <number:year> 16.27.13, <style:map> 16.3 and <style:text-properties> 16.27.28.

16.27.11 <number:day>

The <number:day> element specifies a day of a month in a date.

The <number:day> element is usable within the following element: <number:date-style> 16.27.10.

The <number:day> element has the following attributes: number:calendar 19.341 and number:style 19.358.2.

The <number:day> element has no child elements.

16.27.12 <number:month>

The <number:month> element specifies a month in a date.

The <number:month> element is usable within the following element: <number:date-style> 16.27.10.

The <number:month> element has the following attributes: number:calendar 19.341, number:possessive-form 19.355, number:style 19.358.7 and number:textual 19.359.

The <number:month> element has no child elements.

16.27.13 <number:year>

The <number:year> element specifies a year in a date.

The <number:year> element is usable within the following element: <number:date-style> 16.27.10.

The <number:year> element has the following attributes: number:calendar 19.341 and number:style 19.358.10.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <number:year> element has no child elements.

16.27.14 <number:era>

The <number:era> element specifies an era in which a year is counted.

The <number:era> element is usable within the following element: <number:date-style> 16.27.10.

The <number:era> element has the following attributes: number:calendar 19.341 and number:style 19.358.4.

The <number:era> element has no child elements.

16.27.15 <number:day-of-week>

The <number:day-of-week> element specifies a day of a week in a date.

The <number:day-of-week> element is usable within the following element: <number:date-style> 16.27.10.

The <number:day-of-week> element has the following attributes: number:calendar 19.341 and number:style 19.358.3.

The <number:day-of-week> element has no child elements.

16.27.16 <number:week-of-year>

The <number:week-of-year> element specifies a week of a year in a date.

The <number:week-of-year> element is usable within the following element: <number:date-style> 16.27.10.

The <number:week-of-year> element has the following attribute: number:calendar 19.341.

The <number:week-of-year> element has no child elements.

16.27.17 <number:quarter>

The <number:quarter> element specifies a quarter of the year in a date.

The <number:quarter> element is usable within the following element: <number:date-style> 16.27.10.

The <number:quarter> element has the following attributes: number:calendar 19.341 and number:style 19.358.8.

The <number:quarter> element has no child elements.

16.27.18 <number:time-style>

The <number:time-style> element specifies a style for time values.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

This element can contain *one* instance of any of the following elements: <number:hours>, <number:minutes>, <number:seconds> and <number:am-pm>.

The <number:time-style> element can also contain <number:text> elements, which display additional text.

The <number:time-style> element is usable within the following elements: <office:automatic-styles> 3.15.3 and <office:styles> 3.15.2.

The <number:time-style> element has the following attributes: number:country 19.342, number:format-source 19.347, number:language 19.349, number:rfc-language-tag 19.356, number:script 19.357, number:title 19.360, number:transliteration-country 19.361, number:transliteration-format 19.362, number:transliteration-language 19.363, number:transliteration-style 19.364, number:truncate-on-overflow 19.365, style:display-name 19.472, style:name 19.498.2 and style:volatile 19.517.

The <number:time-style> element has the following child elements: <number:am-pm> 16.27.22, <number:hours> 16.27.19, <number:minutes> 16.27.20, <number:seconds> 16.27.21, <number:text> 16.27.26, <style:map> 16.3 and <style:text-properties> 16.27.28.

16.27.19 <number:hours>

The <number:hours> element specifies whether hours are displayed as part of a date or time.

The <number:hours> element is usable within the following elements: <number:date-style> 16.27.10 and <number:time-style> 16.27.18.

The <number:hours> element has the following attribute: number:style 19.358.5.

The <number:hours> element has no child elements.

16.27.20 <number:minutes>

The <number:minutes> element specifies whether minutes are displayed as part of a date or time.

The <number:minutes> element is usable within the following elements: <number:date-style> 16.27.10 and <number:time-style> 16.27.18.

The <number:minutes> element has the following attribute: number:style 19.358.6.

The <number:minutes> element has no child elements.

16.27.21 <number:seconds>

The <number:seconds> element specifies whether seconds are displayed as part of a date or time.

The <number:seconds> element is usable within the following elements: <number:date-style> 16.27.10 and <number:time-style> 16.27.18.

The <number:seconds> element has the following attributes: number:decimal-places 19.343.3 and number:style 19.358.9.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <number:seconds> element has no child elements.

16.27.22 <number:am-pm>

The <number:am-pm> element specifies whether AM/PM is included as part of a date or time.

If a <number:am-pm> element is contained in a date or time style, hours are displayed using values from 1 to 12 only.

The <number:am-pm> element is usable within the following elements: <number:date-style> 16.27.10 and <number:time-style> 16.27.18.

The <number:am-pm> element has no attributes.

The <number:am-pm> element has no child elements.

16.27.23 <number:boolean-style>

The <number:boolean-style> element defines a style for Boolean values.

The <number:boolean-style> element is usable within the following elements: <office:automatic-styles> 3.15.3 and <office:styles> 3.15.2.

The <number:boolean-style> element has the following attributes: number:country 19.342, number:language 19.349, number:rfc-language-tag 19.356, number:script 19.357, number:title 19.360, number:transliteration-country 19.361, number:transliteration-format 19.362, number:transliteration-language 19.363, number:transliteration-style 19.364, style:display-name 19.472, style:name 19.498.2 and style:volatile 19.517.

The <number:boolean-style> element has the following child elements: <number:boolean> 16.27.24, <number:text> 16.27.26, <style:map> 16.3 and <style:text-properties> 16.27.28.

16.27.24 <number:boolean>

The <number:boolean> element marks the position of the Boolean value of a Boolean style.

The <number:boolean> element is usable within the following element: <number:boolean-style> 16.27.23.

The <number:boolean> element has no attributes.

The <number:boolean> element has no child elements.

16.27.25 <number:text-style>

The <number:text-style> element defines a style for displaying text.

It can also contain <number:text> elements, which display additional text.

The <number:text-style> element is usable within the following elements: <office:automatic-styles> 3.15.3 and <office:styles> 3.15.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <number:text-style> element has the following attributes: number:country 19.342, number:language 19.349, number:rfc-language-tag 19.356, number:script 19.357, number:title 19.360, number:transliteration-country 19.361, number:transliteration-format 19.362, number:transliteration-language 19.363, number:transliteration-style 19.364, style:display-name 19.472, style:name 19.498.2 and style:volatile 19.517.

The <number:text-style> element has the following child elements: <number:text> 16.27.26, <number:text-content> 16.27.27, <style:map> 16.3 and <style:text-properties> 16.27.28.

16.27.26 <number:text>

The <number:text> element contains any fixed text for a data style.

The <number:text> element is usable within the following elements: <number:boolean-style> 16.27.23, <number:currency-style> 16.27.7, <number:date-style> 16.27.10, <number:number-style> 16.27.2, <number:percentage-style> 16.27.9, <number:text-style> 16.27.25 and <number:time-style> 16.27.18.

The <number:text> element has no attributes.

The <number:text> element has no child elements.

The <number:text> element has character data content.

16.27.27 <number:text-content>

The <number:text-content> element marks the position of variable text content of a text style.

The <number:text-content> element is usable within the following element: <number:text-style> 16.27.25.

The <number:text-content> element has no attributes.

The <number:text-content> element has no child elements.

16.27.28 <style:text-properties>

The <style:text-properties> element specifies formatting properties for text.

It also specifies the formatting properties for a section.

The <style:text-properties> element is usable within the following elements: <number:boolean-style> 16.27.23, <number:currency-style> 16.27.7, <number:date-style> 16.27.10, <number:number-style> 16.27.2, <number:percentage-style> 16.27.9, <number:text-style> 16.27.25, <number:time-style> 16.27.18, <style:default-style> 16.4, <style:style> 16.2, <text:list-level-style-bullet> 16.31, <text:list-level-style-number> 16.32 and <text:outline-level-style> 16.35.

The <style:text-properties> element has the following attributes: fo:background-color 20.175, fo:color 20.180, fo:country 20.181, fo:font-family 20.182, fo:font-size 20.183, fo:font-style 20.184, fo:font-variant 20.185, fo:font-weight 20.186,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

fo:hyphenate 20.188, fo:hyphenation-push-char-count 20.191, fo:hyphenation-remain-char-count 20.192, fo:language 20.195, fo:letter-spacing 20.196, fo:script 20.215, fo:text-shadow 20.219, fo:text-transform 20.220, style:country-asian 20.248, style:country-complex 20.249, style:font-charset 20.260, style:font-charset-asian 20.261, style:font-charset-complex 20.262, style:font-family-asian 20.263, style:font-family-complex 20.264, style:font-family-generic 20.265, style:font-family-generic-asian 20.266, style:font-family-generic-complex 20.267, style:font-name 20.269, style:font-name-asian 20.270, style:font-name-complex 20.271, style:font-pitch 20.272, style:font-pitch-asian 20.273, style:font-pitch-complex 20.274, style:font-relief 20.275, style:font-size-asian 20.276, style:font-size-complex 20.277, style:font-size-rel 20.278, style:font-size-rel-asian 20.279, style:font-size-rel-complex 20.280, style:font-style-asian 20.281, style:font-style-complex 20.282, style:font-style-name 20.283, style:font-style-name-asian 20.284, style:font-style-name-complex 20.285, style:font-weight-asian 20.286, style:font-weight-complex 20.287, style:language-asian 20.294, style:language-complex 20.295, style:letter-kerning 20.308, style:rfc-language-tag 20.335, style:rfc-language-tag-asian 20.336, style:rfc-language-tag-complex 20.337, style:script-asian 20.346, style:script-complex 20.347, style:script-type 20.348, style:text-blinking 20.356, style:text-combine 20.357, style:text-combine-end-char 20.359, style:text-combine-start-char 20.358, style:text-emphasize 20.360, style:text-line-through-color 20.361, style:text-line-through-mode 20.362, style:text-line-through-style 20.363, style:text-line-through-text 20.364, style:text-line-through-text-style 20.365, style:text-line-through-type 20.366, style:text-line-through-width 20.367, style:text-outline 20.368, style:text-overline-color 20.369, style:text-overline-mode 20.370, style:text-overline-style 20.371, style:text-overline-type 20.372, style:text-overline-width 20.373, style:text-position 20.374, style:text-rotation-angle 20.375, style:text-rotation-scale 20.376, style:text-scale 20.377, style:text-underline-color 20.378, style:text-underline-mode 20.379, style:text-underline-style 20.380, style:text-underline-type 20.381, style:text-underline-width 20.382, style:use-window-font-color 20.385, text:condition 20.416, text:display 20.417.

The <style:text-properties> element has no child elements.

16.28 Text Style Families

16.28.1 Text Styles

Text styles are represented by <style:style> elements whose style:family attribute has the value text.

16.28.2 Paragraph Styles

Paragraph styles are represented by <style:style> elements whose style:family attribute has the value paragraph.

In addition to paragraph properties, paragraph styles may define text properties. These are applied to the character content of the paragraph unless they are overwritten by a text style that is specified by any of the descendant elements of the paragraph element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.28.3 Section Styles

Section styles are represented by `<style:style>` elements whose `style:family` attribute has the value `section`.

16.28.4 Ruby Styles

Ruby styles are represented by `<style:style>` elements whose `style:family` attribute has the value `ruby`.

16.29 Enhanced Text Styles

16.29.1 <text:linenumbering-configuration>

The `<text:linenumbering-configuration>` element specifies line numbering within the `<office:styles>` element.

The `<text:linenumbering-configuration>` element is usable within the following element: `<office:styles>` 3.15.2.

The `<text:linenumbering-configuration>` element has the following attributes: `style:num-format` 19.500, `style:num-letter-sync` 19.501, `text:count-empty-lines` 19.783, `text:count-in-text-boxes` 19.784, `text:increment` 19.808, `text:number-lines` 19.839, `text:number-position` 19.840, `text:offset` 19.842, `text:restart-on-page` 19.858 and `text:style-name` 19.874.21.

The `<text:linenumbering-configuration>` element has the following child element: `<text:linenumbering-separator>` 16.29.2.

16.29.2 <text:linenumbering-separator>

The `<text:linenumbering-separator>` element contains the text that is displayed as a separator. A separator is text that is displayed instead of a line number for lines where no number is displayed.

The `<text:linenumbering-separator>` element is usable within the following element: `<text:linenumbering-configuration>` 16.29.1.

The `<text:linenumbering-separator>` element has the following attribute: `text:increment` 19.808.

The `<text:linenumbering-separator>` element has no child elements.

The `<text:linenumbering-separator>` element has character data content.

16.29.3 <text:notes-configuration>

A `<text:notes-configuration>` element specifies values for each note class used in a document. If there is no note configuration element, an implementation-defined default note configuration is used.

The `<text:notes-configuration>` element is usable within the following elements: `<office:styles>` 3.15.2 and `<style:section-properties>` 17.11.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:notes-configuration> element has the following attributes: style:num-format 19.500, style:num-letter-sync 19.501, style:num-prefix 19.502, style:num-suffix 19.503, text:citation-body-style-name 19.768, text:citation-style-name 19.769, text:default-style-name 19.794, text:footnotes-position 19.804, text:master-page-name 19.833, text:note-class 19.837, text:start-numbering-at 19.869 and text:start-value 19.868.5.

The <text:notes-configuration> element has the following child elements: <text:note-continuation-notice-backward> 16.29.5 and <text:note-continuation-notice-forward> 16.29.4.

16.29.4 <text:note-continuation-notice-forward>

The <text:note-continuation-notice-forward> elements specifies the text that is displayed at the end of a footnote that is continued on the next page

The <text:note-continuation-notice-forward> element is usable within the following element: <text:notes-configuration> 16.29.3.

The <text:note-continuation-notice-forward> element has no attributes.

The <text:note-continuation-notice-forward> element has no child elements.

The <text:note-continuation-notice-forward> element has character data content.

16.29.5 <text:note-continuation-notice-backward>

The <text:note-continuation-notice-backward> elements specifies the text that is displayed before continued text.

The <text:note-continuation-notice-backward> element is usable within the following element: <text:notes-configuration> 16.29.3.

The <text:note-continuation-notice-backward> element has no attributes.

The <text:note-continuation-notice-backward> element has no child elements.

The <text:note-continuation-notice-backward> element has character data content.

16.29.6 <text:bibliography-configuration>

The <text:bibliography-configuration> element specifies how bibliography entries are displayed in-line, and how they are displayed in a bibliography index.

The <text:bibliography-configuration> element is usable within the following element: <office:styles> 3.15.2.

The <text:bibliography-configuration> element has the following attributes: fo:country 19.234.2, fo:language 19.236.3, fo:script 19.242.3, style:rfc-language-tag 19.512, text:numbered-entries 19.841, text:prefix 19.848, text:sort-algorithm 19.865, text:sort-by-position 19.867 and text:suffix 19.876.

The <text:bibliography-configuration> element has the following child element: <text:sort-key> 16.29.7.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.29.7 <text:sort-key>

The <text:sort-key> element specifies a single sort key if bibliography entries are not displayed in document order.

The <text:sort-key> element is usable within the following element: <text:bibliography-configuration> 16.29.6.

The <text:sort-key> element has the following attributes: text:key 19.820 and text:sort-ascending 19.866.

The <text:sort-key> element has no child elements.

16.30 <text:list-style>

The <text:list-style> element contains a set of style elements for each list level, which are called *list level styles*. There are three different list level style elements, depending on whether a list level is to have a list label containing the list numbering, a bullet, or an image.

If a list style is applied to a list but does not contain a list level specification for a specific level, the list level style of the next lower level is used. If no specific list level style has been defined, an implementation-dependent default style is used.

<text:list-style> elements may occur in the <office:automatic-styles> 3.15.3 and <office:styles> 3.15.2 elements, but they may also occur within the <style:graphic-properties> 17.21.elements of graphic styles.

Including a list style element into a graphic style has the same semantics as adding a style:list-style-name attribute (19.496) to the style that references a list style that is declared outside a graphic style.

Note: The inclusion of a list style element is needed in cases where a common graphic style should be associated with an automatic list style.

List styles contained in a graphic style can be referenced by other graphic styles using the style:list-style-name attribute. Their names are not displayed in the user interface, even if the graphic style that contains it is a common style.

The <text:list-style> element is usable within the following elements: <office:automatic-styles> 3.15.3, <office:styles> 3.15.2 and <style:graphic-properties> 17.21.

The <text:list-style> element has the following attributes: style:display-name 19.472, style:name 19.498.2 and text:consecutive-numbering 19.779.

The <text:list-style> element has the following child elements: <text:list-level-style-bullet> 16.31, <text:list-level-style-image> 16.33 and <text:list-level-style-number> 16.32.

16.31 <text:list-level-style-bullet>

A <text:list-level-style-bullet> element specifies a list style where list items are preceded by bullets.

The <text:list-level-style-bullet> element is usable within the following element: <text:list-style> 16.30.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <text:list-level-style-bullet> element has the following attributes: style:num-prefix 19.502, style:num-suffix 19.503, text:bullet-char 19.760, text:bullet-relative-size 19.761, text:level 19.828 and text:style-name 19.874.24.

The <text:list-level-style-bullet> element has the following child elements: <style:list-level-properties> 17.19 and <style:text-properties> 16.27.28.

16.32 <text:list-level-style-number>

A <text:list-level-style-number> specifies a list style where list items are preceded by numbers.

The <text:list-level-style-number> element is usable within the following element: <text:list-style> 16.30.

The <text:list-level-style-number> element has the following attributes: style:num-format 19.500, style:num-letter-sync 19.501, style:num-prefix 19.502, style:num-suffix 19.503, text:display-levels 19.797, text:level 19.828, text:start-value 19.868.4 and text:style-name 19.874.23.

The <text:list-level-style-number> element has the following child elements: <style:list-level-properties> 17.19 and <style:text-properties> 16.27.28.

16.33 <text:list-level-style-image>

A <text:list-level-style-image> specifies a list style where list items are preceded by images. This element can be an [XLink] and can only be contained in list style elements.

The <text:list-level-style-image> element is usable within the following element: <text:list-style> 16.30.

The <text:list-level-style-image> element has the following attributes: text:level 19.828, xlink:actuate 19.909, xlink:href 19.910.35, xlink:show 19.911 and xlink:type 19.913.

The <text:list-level-style-image> element has the following child elements: <office:binary-data> 10.4.5 and <style:list-level-properties> 17.19.

16.34 <text:outline-style>

The <text:outline-style> element contains the elements that specify a style for each outline level.

An outline style is a list style that is applied to all headings within a text document where the heading's paragraph style does not define a list style to use itself.

The <text:outline-style> element is usable within the following element: <office:styles> 3.15.2.

The <text:outline-style> element has the following attribute: style:name 19.498.2.

The <text:outline-style> element has the following child element: <text:outline-level-style> 16.35.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.35 <text:outline-level-style>

The <text:outline-level-style> element specifies a style for each outline level.

The <text:outline-level-style> element is usable within the following element: <text:outline-style> 16.34.

The <text:outline-level-style> element has the following attributes: style:num-format 19.500, style:num-letter-sync 19.501, style:num-prefix 19.502, style:num-suffix 19.503, text:display-levels 19.797, text:level 19.828, text:start-value 19.868.7 and text:style-name 19.874.28.

The <text:outline-level-style> element has the following child elements: <style:list-level-properties> 17.19 and <style:text-properties> 16.27.28.

16.36 Table Styles

16.36.1 Table Styles

Table styles are <style:style> elements that have the family table.

16.36.2 Table Column Styles

Table column styles are <style:style> elements that have the family table-column.

16.36.3 Table Row Styles

Table row styles are <style:style> elements that have the family table-row.

16.36.4 Table Cell Styles

Table cell styles are <style:style> elements that have the family table-cell.

In addition to table cell properties, table cell styles may define paragraph and text properties. These are applied to paragraphs contained in a table cell unless they are overwritten by paragraph styles that are specified by the paragraph elements themselves.

16.37 Graphic Styles

Graphic styles are <style:style> elements that have the family graphic.

In addition to graphic properties, graphic styles may define paragraph and text properties. These are applied to paragraphs contained in drawing objects unless they are overwritten by paragraph styles that are specified by the paragraph elements themselves.

16.38 Presentation Styles

Presentation styles are <style:style> elements that have the family presentation.

In addition to graphic properties, presentation styles may define paragraph and text properties. These are applied to paragraphs contained in drawing objects unless they are overwritten by paragraph styles that are specified by the paragraph elements themselves.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.39 Drawing Page Style

A drawing page style is a <style:style> element with family drawing-page.

Within drawing and presentation documents, drawing page styles can be used to change the background of a draw page. If a background is set with the help of a drawing page style, it overrides the background of the master page that is assigned to the draw page, but not the shapes that are on the master page.

Within presentation documents, the draw page style may contain presentation formatting properties.

16.40 Enhanced Graphic Style Elements

16.40.1 <draw:gradient>

The <draw:gradient> element defines a gradient for filling a drawing object.

The <draw:gradient> element is usable within the following element: <office:styles> 3.15.2.

The <draw:gradient> element has the following attributes: draw:angle 19.112, draw:border 19.114, draw:cx 19.129, draw:cy 19.130, draw:display-name 19.133.3, draw:end-color 19.141, draw:end-intensity 19.143, draw:name 19.197.12, draw:start-color 19.214, draw:start-intensity 19.216 and draw:style 19.218.2.

The <draw:gradient> element has no child elements.

16.40.2 <svg:linearGradient>

The <svg:linearGradient> element as specified in §13.2 of [SVG] can used in documents in OpenDocument format subject to the following rules:

- The gradient shall have a name. It is specified by the draw:name attribute.
- Only the svg:gradientTransform, svg:x1, svg:y1, svg:x2, svg:y2 and svg:spreadMethod attributes are evaluated.
- The gradient shall be calculated as having a svg:gradientUnits attribute of objectBoundingBox.
- The only child element that is evaluated is <svg:stop>.
- For <svg:stop>, only the svg:offset, svg:stop-color and svg:stop-opacity attributes are evaluated.

The <svg:linearGradient> element is usable within the following element: <office:styles> 3.15.2.

The <svg:linearGradient> element has the following attributes: draw:display-name 19.133.8, draw:name 19.197.29, svg:gradientTransform 19.536, svg:gradientUnits 19.537, svg:spreadMethod 19.553, svg:x1 19.574.2, svg:x2 19.575.2, svg:y1 19.578.2 and svg:y2 19.579.2.

The <svg:linearGradient> element has the following child element: <svg:stop> 16.40.4.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.40.3 <svg:radialGradient>

The <svg:radialGradient> element as specified in §13.2 of [SVG] can used in documents in OpenDocument format subject to the following rules:

- The gradient shall have a name. It is specified by the draw:name attribute.
- For <svg:radialGradient>, only the svg:gradientTransform, svg:cx, svg:cy, svg:r, svg:fx, svg:fy and svg:spreadMethod attributes are evaluated.
- The gradient shall be calculated as having a svg:gradientUnits attribute of objectBoundingBox.
- The only child element that is evaluated is <svg:stop>.
- For <svg:stop>, only the svg:offset, svg:stop-color and svg:stop-opacity attributes are evaluated.

The <svg:radialGradient> element is usable within the following element: <office:styles> 3.15.2.

The <svg:radialGradient> element has the following attributes: draw:display-name 19.133.9, draw:name 19.197.30, svg:cx 19.524.4, svg:cy 19.525.4, svg:fx 19.534, svg:fy 19.535, svg:gradientTransform 19.536, svg:gradientUnits 19.537, svg:r 19.549.3 and svg:spreadMethod 19.553.

The <svg:radialGradient> element has the following child element: <svg:stop> 16.40.4.

16.40.4 <svg:stop>

See §13.2.4 of [SVG].

The <svg:stop> element is usable within the following elements: <svg:linearGradient> 16.40.2 and <svg:radialGradient> 16.40.3.

The <svg:stop> element has the following attributes: svg:offset 19.543, svg:stop-color 19.556 and svg:stop-opacity 19.557.

The <svg:stop> element has no child elements.

16.40.5 <draw:hatch>

The <draw:hatch> element defines a hatch for filling graphic objects. A hatch is a simple pattern of straight lines that is repeated in the fill area.

The <draw:hatch> element is usable within the following element: <office:styles> 3.15.2.

The <draw:hatch> element has the following attributes: draw:color 19.122.2, draw:display-name 19.133.4, draw:distance 19.134.2, draw:name 19.197.13, draw:rotation 19.209 and draw:style 19.218.3.

The <draw:hatch> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.40.6 <draw:fill-image>

The <draw:fill-image> element specifies a link to a bitmap resource. Fill image are not available as automatic styles.

The <draw:fill-image> element is usable within the following element: <office:styles> 3.15.2.

The <draw:fill-image> element has the following attributes: draw:display-name 19.133.2, draw:name 19.197.9, svg:height 19.539.7, svg:width 19.571.9, xlink:actuate 19.909, xlink:href 19.910.13, xlink:show 19.911 and xlink:type 19.913.

The <draw:fill-image> element has no child elements.

16.40.7 <draw:opacity>

The <draw:opacity> element specifies an opacity gradient for a graphic object. An opacity gradient interpolates opacity. Opacity gradients are not available as automatic styles.

The <draw:opacity> element is usable within the following element: <office:styles> 3.15.2.

The <draw:opacity> element has the following attributes: draw:angle 19.112, draw:border 19.114, draw:cx 19.129, draw:cy 19.130, draw:display-name 19.133.6, draw:end 19.139, draw:name 19.197.18, draw:start 19.212 and draw:style 19.218.4.

The <draw:opacity> element has no child elements.

16.40.8 <draw:marker>

The <draw:marker> element represents a marker, which is used to draw polygons at the start or end point of a stroke depending on whether it is referenced by a draw:marker-start or draw:marker-end attribute.

Marker geometry is defined by a svg:d attribute.

Note: The marker geometry could be imagined as an arrow whose vertex points upwards.

When the marker is painted, its geometry is first mapped to the stroke start or end point as follows:

If a marker is referenced by a draw:marker-start attribute, the marker geometry is scaled so that its width equals the width specified by draw:marker-start-width attribute. If the marker is referenced by a draw:marker-end attribute, the marker geometry is scaled so that its width equals the width specified by draw:marker-end-width attribute. The aspect ratio of the geometry is in both cases kept.

The geometry is horizontally centered. It is vertically positioned relative to an offset value which is specified by a draw:marker-start-center attribute for markers referenced by a draw:marker-start attribute, and by the draw:marker-end-center attribute for markers referenced by a draw:marker-end attribute. The attribute value true defines an offset of 0.5 and the attribute value false defines an offset of 0.3, which is also the default value. The offset specifies the marker's vertical position in a range from 0.0 to 1.0, where the value 0.0 means the geometry's bottom bound is aligned to the X axis of the local coordinate system of the marker geometry, and where the value 1.0 means the top bound to be aligned to the X axis of the local coordinate system of the marker geometry.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If the marker referenced by a draw:marker-start attribute, the marker geometry is then rotated so that the Y axis is aligned with the direction of the stroke in the start/end point direction. It is painted to the stroke so that the origin of the coordinate system of the mapped marker geometry is positioned at the start point's position.

If the marker is referenced by a draw:marker-end attribute, the marker geometry is then rotated so that the X axis is aligned with the direction of the stroke in the end/start point direction. It is pointed to the stroke so that the origin of the coordinate system of the mapped marker geometry is positioned at the end point's position.

Markers are not available as automatic styles.

The <draw:marker> element is usable within the following element: <office:styles> 3.15.2.

The <draw:marker> element has the following attributes: draw:display-name 19.133.5, draw:name 19.197.16, svg:d 19.526 and svg:viewBox 19.570.

The <draw:marker> element has no child elements.

16.40.9 <draw:stroke-dash>

The <draw:stroke-dash> element represents a dash style that can be used to render strokes of shapes. Dash styles are not available as automatic styles.

The <draw:stroke-dash> element is usable within the following element: <office:styles> 3.15.2.

The <draw:stroke-dash> element has the following attributes: draw:display-name 19.133.7, draw:distance 19.134.3, draw:dots1 19.135, draw:dots1-length 19.136, draw:dots2 19.137, draw:dots2-length 19.138, draw:name 19.197.27 and draw:style 19.218.5.

The <draw:stroke-dash> element has no child elements.

16.41 <style:presentation-page-layout>

The <style:presentation-page-layout> element is a container <presentation:placeholder> elements. These placeholders are used as templates for creating new presentation objects and to mark the size and position of an object if the presentation page layout of a drawing page is changed.

The <style:presentation-page-layout> element is usable within the following element: <office:styles> 3.15.2.

The <style:presentation-page-layout> element has the following attributes: style:display-name 19.472 and style:name 19.498.2.

The <style:presentation-page-layout> element has the following child element: <presentation:placeholder> 16.42.

16.42 <presentation:placeholder>

The <presentation:placeholder> element specifies a placeholder for presentation objects.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <presentation:placeholder> element is usable within the following element: <style:presentation-page-layout> 16.41.

The <presentation:placeholder> element has the following attributes: presentation:object 19.403, svg:height 19.539.10, svg:width 19.571.12, svg:x 19.573.8 and svg:y 19.577.8.

The <presentation:placeholder> element has no child elements.

16.43 Chart Styles

Chart styles are <style:style> elements that have the family chart.

There are two style inheritance models at work with chart styles. The first model, is standard style inheritance as described in <style:style>. 16.2 The second model is inheritance between elements representing parts of a chart.

If an attribute is not specified with a chart style on a <chart:data-point> element, the specification of that attribute on its parent <chart:series> element is used. If the attribute is not specified on the parent <chart:series> element, then the specification of that attribute on its ancestor <chart:plot-area> element is used.

Chart styles may define paragraph and text properties. These are applied to paragraphs contained in chart elements unless they are over-ridden by paragraph styles that are specified by the paragraph elements themselves.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

17 Formatting Elements

17.1 General

A document can contain multiple style elements. Formatting properties are attributes and child elements of formatting properties elements, which are described in this chapter, and which are child elements of style elements. This container relationship means:

- Formatting properties can be addressed by [CSS2] or [XSLT] stylesheets regardless of the style type.
- Styles may contain additional information that is not defined by formatting properties.

17.2 <style:page-layout-properties>

The `<style:page-layout-properties>` element acts as a container for attributes and elements that define a page layout.

The `<style:page-layout-properties>` element is usable within the following elements: `<style:default-page-layout>` 16.8 and `<style:page-layout>` 16.5.

The `<style:page-layout-properties>` element has the following attributes: `fo:background-color` 20.175, `fo:border` 20.176.2, `fo:border-bottom` 20.176.3, `fo:border-left` 20.176.4, `fo:border-right` 20.176.5, `fo:border-top` 20.176.6, `fo:margin` 20.198, `fo:margin-bottom` 20.199, `fo:margin-left` 20.200, `fo:margin-right` 20.201, `fo:margin-top` 20.202, `fo:padding` 20.210, `fo:padding-bottom` 20.211, `fo:padding-left` 20.212, `fo:padding-right` 20.213, `fo:padding-top` 20.214, `fo:page-height` 20.208, `fo:page-width` 20.209, `style:border-line-width` 20.241, `style:border-line-width-bottom` 20.242, `style:border-line-width-left` 20.243, `style:border-line-width-right` 20.244, `style:border-line-width-top` 20.245, `style:first-page-number` 20.258, `style:footnote-max-height` 20.288, `style:layout-grid-base-height` 20.296, `style:layout-grid-base-width` 20.297, `style:layout-grid-color` 20.298, `style:layout-grid-display` 20.299, `style:layout-grid-lines` 20.300, `style:layout-grid-mode` 20.301, `style:layout-grid-print` 20.302, `style:layout-grid-ruby-below` 20.303, `style:layout-grid-ruby-height` 20.304, `style:layout-grid-snap-to` 20.305, `style:layout-grid-standard-mode` 20.306, `style:num-format` 20.314, `style:num-letter-sync` 20.315, `style:num-prefix` 20.316, `style:num-suffix` 20.317, `style:paper-tray-name` 20.321, `style:print` 20.322, `style:print-orientation` 20.325, `style:print-page-order` 20.324, `style:register-truth-ref-style-name` 20.329, `style:scale-to` 20.344, `style:scale-to-pages` 20.345, `style:shadow` 20.349, `style:table-centering` 20.353 and `style:writing-mode` 20.394.3.

The `<style:page-layout-properties>` element has the following child elements: `<style:background-image>` 17.3, `<style:columns>` 17.12 and `<style:footnote-sep>` 17.4.

17.3 <style:background-image>

The `<style:background-image>` element specifies an image as a background.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If the <style:background-image> element is empty and if there is no color specified by an fo:background-color element in the same formatting properties element, the background color is set to transparent.

Note: The fo:background-color property also sets a background attribute.

The <style:background-image> element is usable within the following elements: <style:graphic-properties> 17.21, <style:header-footer-properties> 17.5, <style:page-layout-properties> 17.2, <style:paragraph-properties> 17.6, <style:section-properties> 17.11, <style:table-cell-properties> 17.18, <style:table-properties> 17.15 and <style:table-row-properties> 17.17.

The <style:background-image> element has the following attributes: draw:opacity 19.202, style:filter-name 19.477, style:position 19.508.2, style:repeat 19.511, xlink:actuate 19.909, xlink:href 19.910.28, xlink:show 19.911 and xlink:type 19.913.

The <style:background-image> element has the following child element: <office:binary-data> 10.4.5.

17.4 <style:footnote-sep>

The <style:footnote-sep> element specifies the line that separates a footnote area from a body text area on a page.

The <style:footnote-sep> element is usable within the following element: <style:page-layout-properties> 17.2.

The <style:footnote-sep> element has the following attributes: style:adjustment 19.461, style:color 19.467, style:distance-after-sep 19.475, style:distance-before-sep 19.474, style:line-style 19.493, style:rel-width 19.510.4 and style:width 19.518.3.

The <style:footnote-sep> element has no child elements.

17.5 <style:header-footer-properties>

The <style:header-footer-properties> element specifies formatting properties for both headers and footers.

The <style:header-footer-properties> element is usable within the following elements: <style:footer-style> 16.7 and <style:header-style> 16.6.

The <style:header-footer-properties> element has the following attributes: fo:background-color 20.175, fo:border 20.176.2, fo:border-bottom 20.176.3, fo:border-left 20.176.4, fo:border-right 20.176.5, fo:border-top 20.176.6, fo:margin 20.198, fo:margin-bottom 20.199, fo:margin-left 20.200, fo:margin-right 20.201, fo:margin-top 20.202, fo:min-height 20.205.2, fo:padding 20.210, fo:padding-bottom 20.211, fo:padding-left 20.212, fo:padding-right 20.213, fo:padding-top 20.214, style:border-line-width 20.241, style:border-line-width-bottom 20.242, style:border-line-width-left 20.243, style:border-line-width-right 20.244, style:border-line-width-top 20.245, style:dynamic-spacing 20.256, style:shadow 20.349 and svg:height 20.397.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <style:header-footer-properties> element has the following child element: <style:background-image> 17.3.

17.6 <style:paragraph-properties>

The <style:paragraph-properties> element specifies formatting properties for paragraphs.

The <style:paragraph-properties> element is usable within the following elements: <style:default-style> 16.4 and <style:style> 16.2.

The <style:paragraph-properties> element has the following attributes: fo:background-color 20.175, fo:border 20.176.2, fo:border-bottom 20.176.3, fo:border-left 20.176.4, fo:border-right 20.176.5, fo:border-top 20.176.6, fo:break-after 20.177, fo:break-before 20.178, fo:hyphenation-keep 20.189, fo:hyphenation-ladder-count 20.190, fo:keep-together 20.193, fo:keep-with-next 20.194, fo:line-height 20.197, fo:margin 20.198, fo:margin-bottom 20.199, fo:margin-left 20.200, fo:margin-right 20.201, fo:margin-top 20.202, fo:orphans 20.207, fo:padding 20.210, fo:padding-bottom 20.211, fo:padding-left 20.212, fo:padding-right 20.213, fo:padding-top 20.214, fo:text-align 20.216.1, fo:text-align-last 20.217, fo:text-indent 20.218, fo:widows 20.221, style:auto-text-indent 20.239, style:background-transparency 20.240, style:border-line-width 20.241, style:border-line-width-bottom 20.242, style:border-line-width-left 20.243, style:border-line-width-right 20.244, style:border-line-width-top 20.245, style:font-independent-line-spacing 20.268, style:join-border 20.292, style:justify-single-word 20.293, style:line-break 20.307, style:line-height-at-least 20.309, style:line-spacing 20.310, style:page-number 20.320, style:punctuation-wrap 20.327, style:register-true 20.328, style:shadow 20.349, style:snap-to-layout-grid 20.351, style:tab-stop-distance 20.352, style:text-autospace 20.355, style:vertical-align 20.386.1, style:writing-mode 20.394.4, style:writing-mode-automatic 20.395, text:line-number 20.420 and text:number-lines 20.424.

The <style:paragraph-properties> element has the following child elements: <style:background-image> 17.3, <style:drop-cap> 17.9 and <style:tab-stops> 17.7.

17.7 <style:tab-stops>

The <style:tab-stops> element is a container for <style:tab-stop> elements.

The <style:tab-stops> element is usable within the following element: <style:paragraph-properties> 17.6.

The <style:tab-stops> element has no attributes.

The <style:tab-stops> element has the following child element: <style:tab-stop> 17.8.

17.8 <style:tab-stop>

The <style:tab-stop> element defines a tab stop.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <style:tab-stop> element is usable within the following element: <style:tab-stops> 17.7.

The <style:tab-stop> element has the following attributes: style:char 19.465, style:leader-color 19.484, style:leader-style 19.485, style:leader-text 19.486, style:leader-text-style 19.487, style:leader-type 19.488, style:leader-width 19.489, style:position 19.508.3, style:type 19.515.3.

The <style:tab-stop> element has no child elements.

17.9 <style:drop-cap>

The <style:drop-cap> element specifies if the first character or more of a paragraph is displayed in a larger font, that spans multiple lines.

The <style:drop-cap> element is usable within the following element: <style:paragraph-properties> 17.6.

The <style:drop-cap> element has the following attributes: style:distance 19.473, style:length 19.492, style:lines 19.494 and style:style-name 19.514.

The <style:drop-cap> element has no child elements.

17.10 <style:ruby-properties>

The <style:ruby-properties> element specifies formatting properties for ruby elements.

The <style:ruby-properties> element is usable within the following elements: <style:default-style> 16.4 and <style:style> 16.2.

The <style:ruby-properties> element has the following attributes: style:ruby-align 20.341 and style:ruby-position 20.342.

The <style:ruby-properties> element has no child elements.

17.11 <style:section-properties>

The <style:section-properties> element defined the formatting properties used by section styles.

The <style:section-properties> element is usable within the following elements: <style:default-style> 16.4 and <style:style> 16.2.

The <style:section-properties> element has the following attributes: fo:background-color 20.175, fo:margin-left 20.200, fo:margin-right 20.201, style:editable 20.257, style:protect 20.326.3, style:writing-mode 20.394.5 and text:dont-balance-text-columns 20.418.

The <style:section-properties> element has the following child elements: <style:background-image> 17.3, <style:columns> 17.12 and <text:notes-configuration> 16.29.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

17.12 <style:columns>

The <style:columns> element specifies the formatting properties of columns by its attributes and its child elements. If it does not contain any column formatting properties, all columns are assigned the same width.

The <style:columns> element is usable within the following elements: <style:graphic-properties> 17.21, <style:page-layout-properties> 17.2 and <style:section-properties> 17.11.

The <style:columns> element has the following attributes: fo:column-count 19.232 and fo:column-gap 19.233.

The <style:columns> element has the following child elements: <style:column> 17.13 and <style:column-sep> 17.14.

17.13 <style:column>

The <style:column> element specifies formatting properties for a column.

The <style:column> element is usable within the following element: <style:columns> 17.12.

The <style:column> element has the following attributes: fo:end-indent 19.235, fo:space-after 19.243, fo:space-before 19.244, fo:start-indent 19.245 and style:rel-width 19.510.3.

The <style:column> element has no child elements.

17.14 <style:column-sep>

The <style:column-sep> element specifies a separator line between columns.

The <style:column-sep> element is usable within the following element: <style:columns> 17.12.

The <style:column-sep> element has the following attributes: style:color 19.467, style:height 19.482, style:style 19.513, style:vertical-align 19.516 and style:width 19.518.2.

The <style:column-sep> element has no child elements.

17.15 <style:table-properties>

The <style:table-properties> element specifies formatting properties for tables.

The <style:table-properties> element is usable within the following elements: <style:default-style> 16.4 and <style:style> 16.2.

The <style:table-properties> element has the following attributes: fo:background-color 20.175, fo:break-after 20.177, fo:break-before 20.178, fo:keep-with-next 20.194, fo:margin 20.198, fo:margin-bottom 20.199, fo:margin-left 20.200, fo:margin-right 20.201, fo:margin-top 20.202, style:may-break-between-rows 20.311, style:page-number 20.320, style:rel-width 20.332.2, style:shadow 20.349,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

style:width 20.389, style:writing-mode 20.394.7, table:align 20.404, table:border-model 20.405 and table:display 20.406.

The <style:table-properties> element has the following child element: <style:background-image> 17.3.

17.16 <style:table-column-properties>

The <style:table-column-properties> element specifies formatting properties for table columns.

The <style:table-column-properties> element is usable within the following elements: <style:default-style> 16.4 and <style:style> 16.2.

The <style:table-column-properties> element has the following attributes: fo:break-after 20.177, fo:break-before 20.178, style:column-width 20.247, style:rel-column-width 20.330 and style:use-optimal-column-width 20.383.

The <style:table-column-properties> element has no child elements.

17.17 <style:table-row-properties>

The <style:table-row-properties> element specifies formatting properties for table rows.

The <style:table-row-properties> element is usable within the following elements: <style:default-style> 16.4 and <style:style> 16.2.

The <style:table-row-properties> element has the following attributes: fo:background-color 20.175, fo:break-after 20.177, fo:break-before 20.178, fo:keep-together 20.193, style:min-row-height 20.312, style:row-height 20.340 and style:use-optimal-row-height 20.384.

The <style:table-row-properties> element has the following child element: <style:background-image> 17.3.

17.18 <style:table-cell-properties>

The <style:table-cell-properties> element specifies formatting properties for cells.

The <style:table-cell-properties> element is usable within the following elements: <style:default-style> 16.4 and <style:style> 16.2.

The <style:table-cell-properties> element has the following attributes: fo:background-color 20.175, fo:border 20.176.2, fo:border-bottom 20.176.3, fo:border-left 20.176.4, fo:border-right 20.176.5, fo:border-top 20.176.6, fo:padding 20.210, fo:padding-bottom 20.211, fo:padding-left 20.212, fo:padding-right 20.213, fo:padding-top 20.214, fo:wrap-option 20.223, style:border-line-width 20.241, style:border-line-width-bottom 20.242, style:border-line-width-left 20.243, style:border-line-width-right 20.244, style:border-line-width-top 20.245, style:cell-protect 20.246, style:decimal-places 20.250, style:diagonal-bl-tr 20.251, style:diagonal-bl-tr-widths 20.252, style:diagonal-tl-br 20.253, style:diagonal-tl-br-widths 20.254, style:direction 20.255, style:glyph-orientation-vertical 20.289, style:print-content 20.323.3, style:repeat-content 20.334, style:rotation-

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

align 20.338, style:rotation-angle 20.339, style:shadow 20.349, style:shrink-to-fit 20.350, style:text-align-source 20.354, style:vertical-align 20.386.2 and style:writing-mode 20.394.6.

The <style:table-cell-properties> element has the following child element: <style:background-image> 17.3.

17.19 <style:list-level-properties>

The <style:list-level-properties> element specifies formatting properties for a list level.

The <style:list-level-properties> element is usable within the following elements: <text:list-level-style-bullet> 16.31, <text:list-level-style-image> 16.33, <text:list-level-style-number> 16.32 and <text:outline-level-style> 16.35.

The <style:list-level-properties> element has the following attributes: fo:height 20.187, fo:text-align 20.216.2, fo:width 20.222, style:font-name 20.269, style:vertical-pos 20.387, style:vertical-rel 20.388, svg:y 20.402.2, text:list-level-position-and-space-mode 20.421, text:min-label-distance 20.422, text:min-label-width 20.423 and text:space-before 20.425.

The <style:list-level-properties> element has the following child element: <style:list-level-label-alignment> 17.20.

17.20 <style:list-level-label-alignment>

The <style:list-level-label-alignment> element specifies the position and spacing of a list label and its list item.

The element will be evaluated only if the text:list-level-position-and-space-mode attribute has the value label-alignment.

The fo:text-indent and fo:margin-left attributes specify the indent and margin for the text lines of a list item. The text lines of a list item contains the list level properties specific content and the text of the paragraph inside the list item. The value fo:text-indent + fo:margin-left specifies the indent of the first text line of the list item. This position is also the alignment position for the list label, because the value of text:min-label-width is treated as 0. 19.246, 20.421

The fo:text-indent and fo:margin-left attributes are evaluated only for paragraphs inside list items whose paragraph styles do not specify them. If one of the two properties, or both, are specified by the paragraph style, the text indent and/or left margin are taken from the paragraph style. In this case the paragraph style's properties are used to determine the indent and margin for the text lines and thus also the alignment position.

The <style:list-level-label-alignment> element is usable within the following element: <style:list-level-properties> 17.19.

The <style:list-level-label-alignment> element has the following attributes: fo:margin-left 19.237, fo:text-indent 19.246, text:label-followed-by 19.827 and text:list-tab-stop-position 19.830.

The <style:list-level-label-alignment> element has no child elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

17.21 <style:graphic-properties>

The <style:graphic-properties> element specifies formatting properties for chart, draw, graphic, and frame elements.

The <style:graphic-properties> element is usable within the following elements: <style:default-style> 16.4 and <style:style> 16.2.

The <style:graphic-properties> element has the following attributes: dr3d:ambient-color 20.67, dr3d:backface-culling 20.69, dr3d:back-scale 20.68, dr3d:close-back 20.70, dr3d:close-front 20.71, dr3d:depth 20.72, dr3d:diffuse-color 20.73, dr3d:edge-rounding 20.74, dr3d:edge-rounding-mode 20.75, dr3d:emissive-color 20.76, dr3d:end-angle 20.77, dr3d:horizontal-segments 20.78, dr3d:lighting-mode 20.79, dr3d:normals-direction 20.80, dr3d:normals-kind 20.81, dr3d:shadow 20.82, dr3d:shininess 20.83, dr3d:specular-color 20.84, dr3d:texture-filter 20.85, dr3d:texture-generation-mode-x 20.88, dr3d:texture-generation-mode-y 20.89, dr3d:texture-kind 20.86, dr3d:texture-mode 20.87, dr3d:vertical-segments 20.90, draw:auto-grow-height 20.91, draw:auto-grow-width 20.92, draw:blue 20.94, draw:caption-angle 20.95, draw:caption-angle-type 20.96, draw:caption-escape 20.97, draw:caption-escape-direction 20.98, draw:caption-fit-line-length 20.99, draw:caption-gap 20.100, draw:caption-line-length 20.101, draw:caption-type 20.102, draw:color-inversion 20.103, draw:color-mode 20.104, draw:contrast 20.105, draw:decimal-places 20.106, draw:draw-aspect 20.107, draw:end-guide 20.108, draw:end-line-spacing-horizontal 20.109, draw:end-line-spacing-vertical 20.110, draw:fill 20.111, draw:fill-color 20.112, draw:fill-gradient-name 20.113, draw:fill-hatch-name 20.114, draw:fill-hatch-solid 20.115, draw:fill-image-height 20.116, draw:fill-image-name 20.117, draw:fill-image-ref-point 20.118, draw:fill-image-ref-point-x 20.119, draw:fill-image-ref-point-y 20.120, draw:fill-image-width 20.121, draw:fit-to-contour 20.122, draw:fit-to-size 20.123, draw:frame-display-border 20.124, draw:frame-display-scrollbar 20.126, draw:frame-margin-horizontal 20.125, draw:frame-margin-vertical 20.127, draw:gamma 20.128, draw:gradient-step-count 20.130, draw:green 20.129, draw:guide-distance 20.131, draw:guide-overhang 20.132, draw:image-opacity 20.133, draw:line-distance 20.134, draw:luminance 20.135, draw:marker-end 20.136, draw:marker-end-center 20.137, draw:marker-end-width 20.138, draw:marker-start 20.139, draw:marker-start-center 20.140, draw:marker-start-width 20.141, draw:measure-align 20.142, draw:measure-vertical-align 20.143, draw:ole-draw-aspect 20.144, draw:opacity 20.145, draw:opacity-name 20.146, draw:parallel 20.147, draw:placing 20.148, draw:red 20.149, draw:secondary-fill-color 20.150, draw:shadow 20.151, draw:shadow-color 20.152, draw:shadow-offset-x 20.153, draw:shadow-offset-y 20.154, draw:shadow-opacity 20.155, draw:show-unit 20.156, draw:start-guide 20.157, draw:start-line-spacing-horizontal 20.158, draw:start-line-spacing-vertical 20.159, draw:stroke 20.160, draw:stroke-dash 20.161, draw:stroke-dash-names 20.162, draw:stroke-linejoin 20.163, draw:symbol-color 20.165, draw:textarea-horizontal-align 20.166, draw:textarea-vertical-align 20.167, draw:tile-repeat-offset 20.168, draw:unit 20.173, draw:visible-area-height 20.169, draw:visible-area-left 20.170, draw:visible-area-top 20.171, draw:visible-area-width 20.172, draw:wrap-influence-on-position 20.174, fo:background-color 20.175, fo:border 20.176.2, fo:border-bottom 20.176.3, fo:border-left 20.176.4, fo:border-right 20.176.5, fo:border-top 20.176.6, fo:clip 20.179, fo:margin 20.198, fo:margin-bottom 20.199, fo:margin-left 20.200, fo:margin-right 20.201, fo:margin-top 20.202, fo:max-height 20.203, fo:max-width 20.204,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

fo:min-height 20.205.1, fo:min-width 20.206, fo:padding 20.210, fo:padding-bottom 20.211, fo:padding-left 20.212, fo:padding-right 20.213, fo:padding-top 20.214, fo:wrap-option 20.223, style:background-transparency 20.240, style:border-line-width 20.241, style:border-line-width-bottom 20.242, style:border-line-width-left 20.243, style:border-line-width-right 20.244, style:border-line-width-top 20.245, style:editable 20.257, style:flow-with-text 20.259, style:horizontal-pos 20.290, style:horizontal-rel 20.291, style:mirror 20.313, style:number-wrapped-paragraphs 20.318, style:overflow-behavior 20.319, style:print-content 20.323.2, style:protect 20.326.2, style:rel-height 20.331, style:rel-width 20.332.1, style:repeat 20.333, style:run-through 20.343, style:shadow 20.349, style:shrink-to-fit 20.350, style:vertical-pos 20.387, style:vertical-rel 20.388, style:wrap 20.390, style:wrap-contour 20.391, style:wrap-contour-mode 20.392, style:wrap-dynamic-threshold 20.393, style:writing-mode 20.394.2, svg:fill-rule 20.396, svg:height 20.397.1, svg:stroke-color 20.398, svg:stroke-linecap 20.164, svg:stroke-opacity 20.399, svg:stroke-width 20.400, svg:width 20.403, svg:x 20.401, svg:y 20.402.1, text:anchor-page-number 20.407, text:anchor-type 20.408, text:animation 20.409, text:animation-delay 20.410, text:animation-direction 20.411, text:animation-repeat 20.412, text:animation-start-inside 20.413, text:animation-steps 20.414 and text:animation-stop-inside 20.415.

The <style:graphic-properties> element has the following child elements: <style:background-image> 17.3, <style:columns> 17.12 and <text:list-style> 16.30.

17.22 <style:chart-properties>

The <style:chart-properties> element specifies formatting properties for charts.

The <style:chart-properties> element is usable within the following elements: <style:default-style> 16.4 and <style:style> 16.2.

The <style:chart-properties> element has the following attributes: chart:angle-offset 20.2, chart:auto-position 20.3, chart:auto-size 20.4, chart:axis-label-position 20.5, chart:axis-position 20.6, chart:connect-bars 20.7, chart:data-label-number 20.8, chart:data-label-symbol 20.9, chart:data-label-text 20.10, chart:deep 20.11, chart:display-label 20.12, chart:error-category 20.13, chart:error-lower-indicator 20.14, chart:error-lower-limit 20.15, chart:error-lower-range 20.16, chart:error-margin 20.17, chart:error-percentage 20.18, chart:error-upper-indicator 20.19, chart:error-upper-limit 20.20, chart:error-upper-range 20.21, chart:gap-width 20.22, chart:group-bars-per-axis 20.23, chart:hole-size 20.24, chart:include-hidden-cells 20.25, chart:interpolation 20.26, chart:interval-major 20.27, chart:interval-minor-divisor 20.28, chart:japanese-candle-stick 20.29, chart:label-arrangement 20.30, chart:label-position 20.31, chart:label-position-negative 20.32, chart:lines 20.33, chart:link-data-style-to-source 20.34, chart:logarithmic 20.35, chart:maximum 20.36, chart:mean-value 20.37, chart:minimum 20.38, chart:origin 20.39, chart:overlap 20.40, chart:percentage 20.42, chart:pie-offset 20.41, chart:regression-type 20.43, chart:reverse-direction 20.44, chart:right-angled-axes 20.45, chart:scale-text 20.46, chart:series-source 20.47, chart:solid-type 20.49, chart:sort-by-x-values 20.48, chart:spline-order 20.50, chart:spline-resolution 20.51, chart:stacked 20.52, chart:symbol-height 20.53, chart:symbol-name 20.54, chart:symbol-type 20.55, chart:symbol-

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

width 20.56, chart:text-overlap 20.57, chart:three-dimensional 20.58, chart:tick-mark-position 20.63, chart:tick-marks-major-inner 20.59, chart:tick-marks-major-outer 20.60, chart:tick-marks-minor-inner 20.61, chart:tick-marks-minor-outer 20.62, chart:treat-empty-cells 20.64, chart:vertical 20.65, chart:visible 20.66, style:direction 20.255, style:rotation-angle 20.339 and text:line-break 20.419.

The <style:chart-properties> element has the following child elements: <chart:label-separator> 17.24 and <chart:symbol-image> 17.23.

17.23 <chart:symbol-image>

The <chart:symbol-image> element specifies an image to be used for a data point in a chart.

This element should be used only together with a chart:symbol-type attribute and only when that attribute has the value image.

The <chart:symbol-image> element is usable within the following element: <style:chart-properties> 17.22.

The <chart:symbol-image> element has the following attribute: xlink:href 19.910.4.

The <chart:symbol-image> element has no child elements.

17.24 <chart:label-separator>

The <chart:label-separator> element specifies text that is used for separating different parts of a textual data label. These parts can be the value as number, the value as a percentage (20.8), and the label text (20.10).

If the <chart:label-separator> element is omitted, the default value is a space character " " (U+0020, SPACE).

This element should be used within chart styles that are applied to <chart:data-label>, <chart:data-point>, <chart:series> or <chart:plot-area> elements.

If a separator is not specified by this element in a chart style applied to a <chart:data-label> element, the separator specified with a chart style applied to a parent element is used.

The <chart:label-separator> element is usable within the following element: <style:chart-properties> 17.22.

The <chart:label-separator> element has no attributes.

The <chart:label-separator> element has the following child element: <text:p> 5.1.3.

17.25 <style:drawing-page-properties>

The <style:drawing-page-properties> element specifies formatting that can be applied to a <draw:page> element.

The <style:drawing-page-properties> element is usable within the following elements: <style:default-style> 16.4 and <style:style> 16.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The <style:drawing-page-properties> element has the following attributes: draw:background-size 20.93, draw:fill 20.111, draw:fill-color 20.112, draw:fill-gradient-name 20.113, draw:fill-hatch-name 20.114, draw:fill-hatch-solid 20.115, draw:fill-image-height 20.116, draw:fill-image-name 20.117, draw:fill-image-ref-point 20.118, draw:fill-image-ref-point-x 20.119, draw:fill-image-ref-point-y 20.120, draw:fill-image-width 20.121, draw:gradient-step-count 20.130, draw:opacity 20.145, draw:opacity-name 20.146, draw:secondary-fill-color 20.150, draw:tile-repeat-offset 20.168, presentation:background-objects-visible 20.224, presentation:background-visible 20.225, presentation:display-date-time 20.226, presentation:display-footer 20.227, presentation:display-header 20.228, presentation:display-page-number 20.229, presentation:duration 20.230, presentation:transition-speed 20.231, presentation:transition-style 20.232, presentation:transition-type 20.233, presentation:visibility 20.234, smil:direction 20.235, smil:fadeColor 20.236, smil:subtype 20.237, smil:type 20.238, style:repeat 20.333 and svg:fill-rule 20.396.

The <style:drawing-page-properties> element has the following child element: <presentation:sound> 10.8.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

18 Datatypes

18.1 Introduction

The values of attributes and elements have datatypes. This specification defines datatypes for values of elements and attributes of OpenDocument documents.

Note: This specification and the schema make reference to other specifications for some datatype definitions. Some datatypes introduced here may be specializations of other datatypes defined here or in other specifications.

18.2 W3C Schema Datatypes

The following [xmlschema-2] datatypes are used in this specification:

- string
- date
- time
- dateTime
- decimal
- duration
- int
- integer
- nonNegativeInteger
- positiveInteger
- double
- long
- short
- base64Binary
- ID
- IDREF
- IDREFS
- NCName

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

18.3 Other Datatypes

18.3.1 angle

An angle, as defined in §4.1 of [SVG]. An angle is a double value that may be followed immediately by one of the following angle unit identifiers: `deg` (degrees), `grad` (gradiants) or `rad` (radians). If no unit identifier is specified, the value is assumed to be in degrees.

Note: OpenDocument v1.1 did not support angle specifications that contain an angle unit identifier. Angle unit identifiers should be omitted for compatibility with OpenDocument v1.1.

18.3.2 anyIRI

An IRI-reference as defined in [RFC3987], expressed in an [xmlschema-2] anyURI.

Note: The procedure for resolution of anyIRI values that are not IRI values is undefined.

18.3.3 boolean

A Boolean value may have either of the values `true` or `false`.

18.3.4 cellAddress

A cell address as specified in 9.2.1.

18.3.5 cellRangeAddress

A cell range address as specified in 9.2.3.

18.3.6 cellRangeAddressList

A cell range address list as specified in 9.2.5.

18.3.7 character

A character value is a string with only one character.

18.3.8 clipShape

A clip shape as defined in §7.20.1 of [XSL]. Offsets shall not be specified using the units `em` and `px`.

18.3.9 color

A RGB color in conformance with §5.9.11 of [XSL], that is a RGB color in notation “#rrggbb”, where rr, gg and bb are 8-bit hexadecimal digits.

18.3.10 coordinate

A coordinate represents a length in a coordinate system. It specifies the distance from the origin of the coordinate system along the relevant axis.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

18.3.11 countryCode

A country code is a value that conforms to ISO 3166 ([ISO3166-1], [ISO3166-2], [ISO3166-3], or their successors, and further parts).

See §2.2.4 Region Subtag of [RFC5646], or its successors.

18.3.12 CURIE

A CURIE, as described in §7 of [RDFa].

18.3.13 CURIEs

A list of CURIEs, as described in §7 of [RDFa], separated by whitespaces.

18.3.14 dateOrDateTime

A dateOrDateTime value is either an [xmlschema-2] date value or an [xmlschema-2] dateTime value.

18.3.15 distance

The length between two points.

18.3.16 language

A language is a natural language identifier as defined by [RFC5646], or its successor. The lexical space is the same as the [xmlschema-2] language data type.

Note 1: The language datatype is the same as the [xmlschema-2] language datatype, except that its value range is not restricted to values of [RFC3066], but follows the syntax of the `xml:lang` attribute. See §2.12 of [XML1.0].

18.3.17 languageCode

A language code is a value that conforms to ISO 639 ([ISO639-1], [ISO639-2], [ISO639-3] or their successors, and further parts).

See §2.2.1 Primary Language Subtag of [RFC5646], or its successors.

18.3.18 length

A (positive or negative) length, consisting of magnitude and unit, in conformance with the Units of Measure defined in §5.9.13 of [XSL].

18.3.19 namespacedToken

A namespaced token is an [xmlschema-2] QName that matches the definition of PrefixedName in §4 of [xml-names].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

18.3.20 nonNegativeLength

A measurement with a value that shall be zero or positive.

18.3.21 nonNegativePixelLength

A non-negative measurement that shall have the unit `px` (pixels).

18.3.22 pathData

Path data as described in §8.3 of [SVG]. Attribute values of this data type shall match the BNF grammar for SVG path data in §8.3.9 of [SVG].

18.3.23 percent

(Positive or negative) percentage values in conformance with §5.9.11 of [XSL].

18.3.24 point3D

A 3D point. The syntax of a 3D point is the same as that of a `vector3D`, except that each coordinate is shall be followed by a unit.

18.3.25 points

A sequence of points. Each point consists of two integer coordinates separated by a comma “,” (U+002C, COMMA). The points are separated by white space.

18.3.26 positiveLength

A measurement with a value that shall be positive.

18.3.27 relativeLength

A relative length is a positive integer, followed by a ”*” (U+002A, ASTERISK) character.

18.3.28 safeCURIE

A safe CURIE, as described in §7 of [RDFa].

18.3.29 scriptCode

A script code conforming to [ISO15924], or its successors. See §2.2.3 Script Subtag of [RFC5646], or its successors.

18.3.30 signedZeroToHundredPercent

Percentage values in the range [-100%,100%] in conformance with §5.9.11 of [XSL].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

18.3.31 styleName

A NCName as specified in [xmlschema-2] that is the name of a style.

18.3.32 styleNameRef

A NCName as specified in [xmlschema-2] that is the name of a referenced style, or an empty value.

18.3.33 styleNameRefs

A white space separated list of NCNames as specified in [xmlschema-2] that are the names of a styles.

18.3.34 targetFrameName

The name of a target frame in conformance with §6.16 of [HTML4].

18.3.35 textEncoding

A character encoding in the notation described in the §4.3.3 of [XML1.0], or the value `x-symbol`. The value is `x-symbol` means that the character encoding is not enumerated by §4.3.3 of [XML1.0].

18.3.36 timeOrDateTime

A timeOrDateTime value is either an [xmlschema-2] time or an [xmlschema-2] dateTime value.

18.3.37 URIorSafeCURIE

An IRI or a safe CURIE, as described in §7 of [RDFa].

18.3.38 valueType

A list of value types.,

18.3.39 variableName

A string specifying the name of a variable

18.3.40 vector3D

A 3-element vector that is represented by floating point x, y, z coordinates. The format of a vector3D value is whitespace separated tokens in the order x, y, and z, and that expression starts with "(" (LEFT PARENTHESIS U+0028) and ends with ")" (RIGHT PARENTHESIS U+0029). If this value represents a normal, then it should be normalized.

18.3.41 zeroToHundredPercent

Percentage values in the range [0%,100%] in conformance with §5.9.11 of [XSL].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19 General Attributes

19.1 General

Attributes for elements defined by OpenDocument are divided between those used by structural elements (19) versus those used by `<style:*-properties>` elements (20).

Attributes have *default values* defined by this standard. When any element appears in a document instance without such an attribute, consumers should behave as if the attribute is present with the defined default value.

19.2 anim:color-interpolation

The `anim:color-interpolation` attribute specifies the color space that is used for color interpolation.

The defined values for the `anim:color-interpolation` attribute are:

- `hsl`: HSL (hue, saturation, lightness) color model.
- `rgb`: RGB (red, green, blue) color model.

The default value for this attribute is `rgb`.

The `anim:color-interpolation` attribute is usable with the following element: `<anim:animateColor>` 15.2.6.

The values of the `anim:color-interpolation` attribute are `rgb` or `hsl`.

19.3 anim:color-interpolation-direction

The `anim:color-interpolation-direction` attribute specifies the direction that is used for color interpolation. This is only valid for the HSL color space.

The defined values for the `anim:color-interpolation-direction` attribute are:

- `clockwise`: color interpolation proceeds in a clockwise direction.
- `counterclockwise`: color interpolation proceeds in a counterclockwise direction.

The default value for this attribute is `clockwise`.

The `anim:color-interpolation-direction` attribute is usable with the following element: `<anim:animateColor>` 15.2.6.

The values of the `anim:color-interpolation-direction` attribute are `clockwise` or `counter-clockwise`.

19.4 anim:audio-level

The `anim:audio-level` attribute specifies the audio volume during a playback.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined value range for the anim:audio-level attribute is a rational number between 0 (inaudible) and 1 (system volume), inclusive.

The anim:audio-level attribute is usable with the following element: <anim:audio> 15.5.

The anim:audio-level attribute has the data type double 18.2.

19.5 anim:command

The anim:command attribute specifies an animation command.

The defined values for the anim:command attribute are:

- custom: the command is user defined.
- verb: the command targets an OLE2 shape. The parameter verb is the verb number executed at the OLE2 shape.
- play: the command targets a media shape and starts its playback. The parameter media-time defines the playback start time in seconds. If this parameter is not set, playback starts at the last position.
- toggle-pause: the command targets a media shape and toggles its playback state from play to paused or from paused to play.
- stop: the command targets a media shape and stops its playback.
- stop-audio: the command has no target and stops all running audio playback.

If the value of the anim:command attribute is custom, then there shall be a <anim:param> child element whose anim:name attribute and anim:value attribute values are user defined.

If the value of the anim:command attribute is verb, then there shall be a <anim:param> child element whose anim:name attribute value is verb and whose anim:value attribute value contains the verb number.

If the value of the anim:command attribute is play, then there shall be a <anim:param> child element whose anim:name attribute value is play and whose anim:value attribute value contains a value expressed in seconds.

The anim:command attribute is usable with the following element: <anim:command> 15.6.1.

The anim:command attribute has the data type string 18.2.

19.6 anim:formula

The anim:formula attribute specifies a formula used in an animation function.

The following is the minimum supported grammar:

```
formula::= additive_expression

identifier::= '$' | 'pi' | 'e' | 'x' | 'y' | 'width' | 'height'
function::= 'abs'|'sqrt'|'sin'|'cos'|'tan'|'atan'|'acos'|'asin'|'exp'|'log'
binary_function::= 'min'|'max'
basic_expression::= number
    | identifier
    | unary_function S* '(' S* additive_expression S* ')'
```


Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

```
    | binary_function S* '(' S* additive_expression S* ','
    S*additive_expression S* ')'
    | '(' S* additive_expression S* ')'

unary_expression::= '-' S* basic_expression | basic_expression
multiplicative_expression::= unary_expression ( ( S* '*' S* unary_expression )
    | ( S* '/' S* unary_expression ) )*
additive_expression::= multiplicative_expression ( ( S* '+' S*
multiplicative_expression )
    | ( S* '-' S* multiplicative_expression ) )*
number::= sign? integer | sign? Floating-point-constant
floating-point-constant::= fractional-constant exponent? | integer exponent
fractional-constant::= integer? '.' integer | integer '.'
exponent::= ( 'e' | 'E' ) sign? Integer
sign::= '+' | '-'
integer::= [0-9]+
S::= (#x20 | #x9)
```

The defined identifiers for the `anim:formula` attribute are:

- `"$"` (U+0024, DOLLAR SIGN): The identifier ”$” is replaced by a value between 0 and 1 (inclusive) that represents a proportional offset into an animation element's duration.
- `pi`: The Pi constant.

When the `anim:formula` attribute appears on a descendant element of `<office:presentation>`, it may use the following additional identifiers:

- `e`: the Euler constant.
- `x`: the animated elements left edge in screen space where 0 is the left edge of the screen and 1 is the right edge.
- `y`: the animated elements top edge in screen space, where 0 is the top edge of the screen and 1 is the bottom edge.
- `width`: the animated elements width in screen space, where 0 is no width and 1 is the screen's width.
- `height`: the animated elements height in screen space, where 0 is no height and 1 is the screen's height.

If an `anim:formula` attribute is given, it overrides the `smil:values`, `smil:to`, `smil:from` and `smil:by` attributes as specified in 15.3.2.

The `anim:formula` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3 and `<anim:transitionFilter>` 15.2.7.

The `anim:formula` attribute has the data type `string` 18.2.

19.7 anim:id (deprecated)

The `anim:id` attribute specifies an identifier to an animation element.

OpenDocument consumers shall ignore an `anim:id` attribute if it occurs on an element with an `xml:id` attribute value.

When consuming OpenDocument v1.0 and v1.1 documents, OpenDocument consumers should process `anim:id` attributes as they were `xml:id` attributes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

OpenDocument producers may write anim:id attributes for elements in addition to an xml:id attribute.

The value of an anim:id attribute shall equal the value of an xml:id attribute on the same element.

The anim:id attribute is deprecated in favor of xml:id. 19.914

The anim:id attribute is usable with the following elements: <anim:audio> 15.5, <anim:command> 15.6.1, <anim:iterate> 15.4.4, <anim:par> 15.4.2 and <anim:seq> 15.4.3.

The anim:id attribute has the data type NCName 18.2.

19.8 anim:iterate-interval

The anim:iterate-interval attribute specifies the time interval between effects that are children of <anim:iterate> elements.

The anim:iterate-interval attribute is usable with the following element: <anim:iterate> 15.4.4.

The anim:iterate-interval attribute has the data type duration 18.2.

19.9 anim:iterate-type

The anim:iterate-type attribute of a <anim:iterate> element specifies the iteration of child elements.

The defined values for the anim:iterate-type attribute are:

- by-letter: the target shape or paragraph is iterated by letters.
- by-paragraph: the target shape is iterated by paragraphs.
- by-word: the target shape or paragraph is iterated by words.

The anim:iterate-type attribute is usable with the following element: <anim:iterate> 15.4.4.

The anim:iterate-type attribute has the data type string 18.2.

19.10 anim:name

The anim:name attribute specifies the name of a parameter for an <anim:command> element.

The anim:name attribute is usable with the following element: <anim:param> 15.6.2.

The anim:name attribute has the data type string 18.2.

19.11 anim:sub-item

The anim:sub-item attribute specifies components of a target element for application of animation effects.

The defined values for the anim:sub-item attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `background`: animates only a shape's background and not its text.
- `text`: animates only the text of a shape.
- `whole`: animates both a shape and its text.

The `anim:sub-item` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3, `<anim:command>` 15.6.1, `<anim:iterate>` 15.4.4, `<anim:set>` 15.2.4 and `<anim:transitionFilter>` 15.2.7.

The `anim:sub-item` attribute has the data type `string` 18.2.

19.12 anim:value

The `anim:value` attribute specifies the value of a parameter for an `<anim:command>` element.

The `anim:value` attribute is usable with the following element: `<anim:param>` 15.6.2.

The `anim:value` attribute has the data type `string` 18.2.

19.13 chart:attached-axis

The `chart:attached-axis` attribute specifies an axis to be used with a series. The value shall be the name of an axis as defined with the `chart:name` attribute on a `<chart:axis>` element.

The `chart:attached-axis` attribute is usable with the following element: `<chart:series>` 11.11.

The `chart:attached-axis` attribute has the data type `string` 18.2.

19.14 chart:automatic-content

The `chart:automatic-content` attribute specifies if an equation to be displayed should be calculated automatically or if text given within a `<text:p>` element should be used instead.

If no `<text:p>` element is provided, the `chart:automatic-content` attribute is assumed to be `true`.

The defined values for the `chart:automatic-content` attribute are:

- `false`: the text within a `<text:p>` element is displayed.
- `true`: an equation is calculated and displayed automatically.

The default value for this attribute is `true`.

The `chart:automatic-content` attribute is usable with the following element: `<chart:equation>` 11.18.

The `chart:automatic-content` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.15 chart:class

19.15.1 <chart:chart>, <chart:series>

The `chart:class` attribute specifies a chart type. The value is a namespaced token. The values for the predefined chart types are defined within the chart namespace (urn:oasis:names:tc:opendocument:xmlns:chart:1.0).

The term *line attributes* is used in defining `chart:class` values to refer to the attributes of the `<style:graphic-properties>` element within a chart style: `draw:stroke`, `svg:stroke-color`, `svg:stroke-width`, `svg:stroke-opacity`, `draw:stroke-dash` and `draw:stroke-linejoin`.

The term *fill attributes* is used in defining `chart:class` values to refer to the attributes of the `<style:graphic-properties>` element within a chart style: `draw:fill`, `draw:fill-color`, `draw:fill-gradient-name`, `draw:gradient-step-count`, `draw:fill-hatch-name`, `draw:fill-hatch-solid`, `draw:fill-image-name`, `style:repeat`, `draw:fill-image-height`, `draw:fill-image-width`, `draw:fill-image-ref-point`, `draw:fill-image-ref-point-x`, `draw:fill-image-ref-point-y`, `draw:tile-repeat-offset`, `draw:opacity` and `draw:opacity-name`.

The defined values for the `chart:class` attribute are:

- `chart:area` –The values given by a `chart:values-cell-range-address` attribute on a `<chart:series>` element are interpreted as y-coordinates within a Cartesian coordinate system with horizontal x-axis and vertical y-axis. The accessory x-coordinates are generated from the positions in the y-value sequence starting with 1.0. The first y value gets an x value 1.0. The second y value is associated with an x value of 2.0 and so forth. The `<chart:categories>` element can be used to define labels for the x-axis.

  Where `chart:three-dimensional`="`true`" a left handed three-dimensional Cartesian coordinate system is used with horizontal x-axis and vertical y-axis (prior to any 3D scene transformations).

  Where `chart:deep`="`true`" the z-coordinates are generated from the order of the series elements starting with 1.0. The first series has an associated z-coordinate of 1.0. The second series has a z-coordinate 2.0 and so forth. The series names are used as labels at the z-axis.

  The area in the xy-pane between the data points and the x-axis is filled (chart:origin 20.39).

  Where `chart:stacked`="`true`" the area between a series and the previous series is filled. The filling is done as indicated by the fill attributes of the series. A border is drawn as specified by the line attributes of the series.

- `chart:bar` – The values given by a `chart:values-cell-range-address` attribute on a `<chart:series>` element are interpreted as y-coordinates within a Cartesian coordinate system with horizontal x-axis and vertical y-axis. The accessory x-coordinates are generated from the positions in the y-value sequence starting with 1.0. The first y value gets an x value 1.0. The second y value is associated with an x value of 2.0 and so forth. The `<chart:categories>` element> can be used to define labels for the x-axis. Where `chart:three-dimensional`="`true`" a left handed three-dimensional Cartesian coordinate system is used with horizontal x-axis and vertical y-axis (prior to any 3D scene transformations).

  Where `chart:deep`="`true`" the z-coordinates are generated from the order of the series elements starting with 1.0. The first series has an associated z-coordinate of 1.0. The second series has a z-coordinate 2.0 and so forth. The series names are used as labels at the z-axis.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Bars are displayed for each data point starting at the x-axis and ending at the indicated y-coordinate (see chart:origin for more details). In case of chart:stacked="true" the bar starts at the previous series instead of the x-axis. The width and exact position of the bars along the x-axis is influenced by the attributes chart:gap-width, chart:overlap, chart:group-bars-per-axis, chart:stacked and chart:percentage. In case of chart:three-dimensional="false" the bars are simple rectangles.

Where chart:three-dimensional="true" the shape of the bars are defined by a chart:solid-type attribute. A chart:vertical attribute indicates whether the positions of x- and y-axis should be swapped, resulting in a horizontal y-axis and vertical x-axis. The bars are filled as indicated by the fill attributes of the series and points. A border is drawn as specified by the line attributes.

- chart:bubble – Circles(bubbles) with different sizes are displayed in a Cartesian coordinate system with horizontal x-axis and vertical y-axis. The values given by a chart:values-cell-range-address attribute on a <chart:series> element are interpreted as relative bubble area. The values for the y-coordinates are given by the first <chart:domain> element. The values for the x-coordinates are given by the second <chart:domain> element. The bubbles are filled as indicated by the fill attributes of the series and points. A border is drawn as specified by the line attributes.

- chart:circle – The values given by a chart:values-cell-range-address attribute on a <chart:series> element are displayed as pie chart. For a value sequence a circle is divided into sectors, the angle of a sector represents the relative weight of a value. Only one series can be displayed with this chart type. By default, the segments are arranged counter clockwise starting at 12 o'clock. To arrange the segments in clockwise order the attribute chart:reverse-direction at the y-axis is set to true. The chart:angle-offset attribute is used to rotate the pie. The <chart:categories> element at the x-axis can be used to define categories for the data points. The segments are filled as indicated by the fill attributes of the series and points. A border is drawn as specified by the line attributes.

- chart:filled-radar – The values given by a chart:values-cell-range-address attribute on a <chart:series> element are interpreted as radius-coordinates within a counter clockwise polar coordinate system. The angle axis starts at 12 o'clock. The axis element with chart:dimension="y" is interpreted as radius axis. The axis element with chart:dimension="x" is interpreted as angle axis. The <chart:categories> element can be used to define labels for the x-axis. The x-coordinates are generated from the positions in the value sequence starting with 1.0. First value gets an x value 1.0. The second value is associated with an x value of 2.0 and so forth.

  The area surrounded by the data points is filled as indicated by the fill attributes of the series. In case of chart:stacked="true" the area between a series and the previous series is filled instead. A border is drawn as specified by the line attributes.

- chart:gantt – The values given by a chart:values-cell-range-address attribute of two <chart:series> (marked as being of type chart:gantt) are interpreted together to form the start and end values (in this order) in a gantt chart. Start and end values are displayed at the y-axis in a Cartesian coordinate system with horizontal x-axis and vertical y-axis. The accessory x-coordinates are generated from the positions in the y-value sequence starting with 1.0. The first y value gets an x value 1.0. The second y value is associated with an x value of 2.0 and so forth. The <chart:categories> element can be used to define labels for the x-axis.

  For each x-coordinate, a bar is displayed, starting at the start value and ending at the end value. The fill and line attributes of the series and points specify how the bars are to be displayed. If the end value is greater than or equal to the start value the style of the first series, shall be used. If the end value is smaller than the start value, the styles of the second series shall be used.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `chart:line` – The values given by a `chart:values-cell-range-address` attribute on a `<chart:series>` element are interpreted as y-coordinates within a Cartesian coordinate system with horizontal x-axis and vertical y-axis.

  The accessory x-coordinates are generated from the positions in the y-value sequence starting with 1.0. The first y value gets an x value 1.0. The second y value is associated with an x value of 2.0 and so forth. The `<chart:categories>` element can be used to define labels for the x-axis.

  Where `chart:three-dimensional`="`true`" a left handed three-dimensional Cartesian coordinate system is used with horizontal x-axis and vertical y-axis (prior to any 3D scene transformations).

  Where `chart:deep`="`true`" the z-coordinates are generated from the order of the series elements starting with 1.0. The first series has an associated z-coordinate of 1.0. The second series has a z-coordinate 2.0 and so forth. The series names are used as labels at the z-axis.

  Where `chart:three-dimensional`="`false`" the data points are connected with a line as specified by the line attributes of the series. By default a solid line is drawn. If symbols should be used for the data points this shall be specified with the `chart:symbol-type` attribute. The fill attributes of the series and data points specify how the symbols are filled. By default. the symbols are filled solid with the same color as the connecting line. In case no line color is given but a fill color, the line uses the fill color.

  Where `chart:three-dimensional`="`true`" no symbols are shown. The data points are connected with a line that is extruded in z direction. The extruded line is filled as specified by the fill attributes of the series. A border is drawn as specified by the line attributes.

  The attribute `chart:interpolation` within the chart style at the plot-area specifies which type of interpolation is used while connecting the points with lines.

- `chart:radar` – The values given by a `chart:values-cell-range-address` attribute on a `<chart:series>` element are interpreted as radius-coordinates within a counter clockwise polar coordinate system. The angle axis starts at 12 o'clock. The axis element with `chart:dimension`="`y`" is interpreted as radius axis. The axis element with `chart:dimension`="`x`" is interpreted as angle axis. The `<chart:categories>` element can be used to define labels for the x-axis. The x-coordinates are generated from the positions in the value sequence starting with 1.0. First value gets an x value 1.0. The second value is associated with an x value of 2.0 and so forth.

  The data points are connected with a line as specified by the line attributes of the series. By default a solid line is drawn. If symbols should be used for the data points this shall be specified with the `chart:symbol-type` attribute. The fill attributes of the series and data points specify how the symbols are filled. By default, the symbols are filled solid with the same color as the connecting line. In case no line color is given but a fill color, the line uses the fill color.

- `chart:ring` – The values given by a `chart:values-cell-range-address` attribute on a `<chart:series>` element are displayed as one ring in a donut chart. For a given value sequence, the ring is divided into sectors, the angle of a sector represents the relative weight of a value.

  By default, segments are arranged counter clockwise starting at 12 o'clock. To arrange the segments in clockwise order the attribute `chart:reverse-direction` at the y-axis is set to "`true`". The `chart:angle-offset` attribute is used to rotate the donut.

  By default, the first series of class ring forms the inner ring and the last series forms the outermost ring. To arrange the the rings in opposite order the attribute `chart:reverse-`

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

direction is set to "true" at the x-axis. The attribute chart:hole-size is used to influence the inner hole size.

The <chart:categories> element at the x-axis can be used to define categories for the data points. The segments are filled as specified by the fill attributes of the series and points. A border is drawn around a segment as specified by the line attributes.

- chart:scatter – The values given by a chart:values-cell-range-address attribute on a <chart:series> element are interpreted as y-coordinates within a Cartesian coordinate system with horizontal x-axis and vertical y-axis. The values for the x-coordinates are given by the first <chart:domain> element.

  Where chart:three-dimensional="true" a left handed three-dimensional Cartesian coordinate system is used with horizontal x-axis and vertical y-axis (prior to any 3D scene transformations).

  Where chart:deep="true" the z-coordinates are generated from the order of the series elements starting with 1.0. The first series has an associated z-coordinate of 1.0. The second series has a z-coordinate 2.0 and so forth. The series names are used as labels at the z-axis.

  Where chart:three-dimensional="false" the data points are connected with a line as specified by the line attributes of the series. By default a solid line is drawn. If symbols should be used for the data points this shall be specified with the chart:symbol-type attribute.

  The fill attributes of the series and data points specify how the symbols are filled. By default the symbols are filled solid with the same color as the connecting line. In case no line color is given but a fill color, the line uses the fill color.

  Where chart:three-dimensional="true" no symbols are shown. The data points are connected with a line that is extruded in z direction. The extruded line is filled as specified by the fill attributes of the series. A border is drawn as specified by the line attributes.

  The attribute chart:interpolation within the chart style at the plot-area specifies which type of interpolation is used while connecting the points with lines.

- chart:stock – The values given by a chart:values-cell-range-address attribute on up to four <chart:series> (marked as being of type chart:stock) are interpreted together to form the opening, minimum, maximum and closing (in this order) values of a stock symbol displayed at the y scale in a Cartesian coordinate system with horizontal x-axis and vertical y-axis. If only three series are given, the values are interpreted as minimum, maximum and closing values (in this order). The accessory x-coordinates are generated from the positions in the y-value sequence starting with 1.0. The first y value gets an x value 1.0. The second y value is associated with an x value of 2.0 and so forth. The <chart:categories> element can be used to define labels for the x-axis.

  For each x-coordinate, the minimum and maximum y-values are connected with a line. The line style is specified with element <chart:stock-range-line>. The chart:japanese-candle-stick attribute specifies the display of opening and closing values in a stock chart. In case of chart:japanese-candle-stick="false" opening and closing values are displayed as left and right tick-lines in the same style as the line connecting minimum and maximum value. This is the default. Only in case of chart:japanese-candle-stick="true" a bar is drawn from opening to closing value. The styles to use for those bars are defined with elements <chart:stock-gain-marker> and <chart:stock-loss-marker>.

- chart:surface – Depending on the size of the range specified by chart:values-cell-range-address attribute of the first <chart:series> element one of two types of surfaces is rendered:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- If the chart:values-cell-range-address attribute of the first <chart:series> element specifies a range with more than one row and more than one column, the first version of a surface chart is rendered:

  The value in the ith column and jth row of the cell range given by the chart:values-cell-range-address attribute of the <chart:series> element (marked as being of type chart:surface) is the altitude corresponding to the x-value i and the y-value j unless <chart:domain> elements are contained in the <chart:series> element.

  If chart:three-dimensional="true" a surface chart is displayed in a right-handed three-dimensional Cartesian coordinate system with horizontal x-axis (from left to right), a perspective y-axis running from the front to the right rear and a vertical z-axis (prior to any 3D scene transformation). The altitude values are displayed on the z-axis in this case. The surface is displayed as specified by the line and fill attributes of the first series. Furthermore the <chart:data-point> elements of the series can be used to specify differing fill and line styles for the different altitude intervals. The surface within the first major interval (starting at lower values) is displayed with the line and fill attributes of the first data-point, within the second major interval the surface is displayed with the line and fill attributes of the second data-point and so on.

  Where chart:three-dimensional="false" a contour plot is displayed in a 2 dimensional Cartesian coordinate system with horizontal x-axis and vertical y-axis. An axis element with chart:dimension="z" is used to define the range and segmentation of the displayed altitude values. Contour lines are drawn along lines of equal altitude specified by the major interval of the z-axis. The area between the contour lines can be filled. The line and fill style is specified by the line and fill attributes of the series. Furthermore the <chart:data-point> elements of the series can be used to specify differing line and fill attributes for the different altitude intervals. The contour line and area belonging to the first major interval is displayed with the line and fill attributes of the first data-point, the contour line and area belonging to the second interval is displayed as specified by the line and fill attributes of the second data-point and so on.

  In both cases two <chart:domain> elements may be used to specify the y-values and x-values to be used (19.593.5). In this case the jth value of the table:cell-range-address attribute of the first <chart:domain> element specifies the y-values used for the values in the jth row of the cell range given by the chart:values-cell-range-address attribute of the <chart:series> element and the ith value of the table:cell-range-address attribute of the second <chart:domain> element specifies the x-values used for the values in the ith column.

  The attribute chart:deep shall be false. Multiple <chart:series> elements of type chart:surface will result in multiple surfaces being rendered.

- If the chart:values-cell-range-address attribute of the first <chart:series> element specifies a range with a single row or with a single column the second version of a surface chart is rendered:

  The values given by a chart:values-cell-range-address attribute on multiple <chart:series> elements (marked as being of type chart:surface) are interpreted as altitudes at specific grid locations.

  Where chart:three-dimensional="true" a surface chart is displayed in a left handed three-dimensional Cartesian coordinate system with horizontal x-axis and vertical y-axis (prior to any 3D scene transformation). The altitude values are displayed on the y-axis in this case. The attribute chart:deep shall be true. The accessory x-coordinates are generated from the positions in the altitude -value sequence starting with 1.0. The first altitude value in each series gets an x value 1.0. The second altitude value is associated with an x value of 2.0 and so forth. The <chart:categories> element can

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

be used to define labels for the x-axis. The z-coordinates are generated from the order of the series elements starting with 1.0. The first series marked as being of type surface gets an associated z-coordinate of 1.0. The second series marked as being of type surface gets a z-coordinate 2.0 and so forth. The series names are used as labels at the z-axis. The surface is displayed as specified by the line and fill attributes of the first series. Furthermore the `<chart:data-point>` elements of the first series can be used to specify differing fill and line styles for the different altitude intervals. The surface within the first major interval (starting at lower values) is displayed with the line and fill attributes of the first data-point, within the second major interval the surface is displayed with the line and fill attributes of the second data-point and so on.

Where `chart:three-dimensional="false"` a contour plot is displayed in a 2 dimensional Cartesian coordinate system with horizontal x-axis and vertical y-axis. The x-coordinates are generated from the positions in the altitude -value sequence starting with 1.0. The `<chart:categories>` element can be used to define labels for the x-axis. The y-coordinates are generated from the order of the series elements starting with 1.0. The series names are used as labels at the y-axis. A third axis element with `chart:dimension="z"` is used to define the range and segmentation of the displayed altitude values. Contour lines are drawn along lines of equal altitude specified by the major interval of the z-axis. The area between the contour lines can be filled. The line and fill style is specified by the line and fill attributes of the first series. Furthermore the `<chart:data-point>` elements of the first series can be used to specify differing line and fill attributes for the different altitude intervals. The contour line and area belonging to the first major interval is displayed with the line and fill attributes of the first data-point, the contour line and area belonging to the second interval is displayed as specified by the line and fill attributes of the second data-point and so on.

Additional chart types may be supported by using a different namespace.

A `chart:class` attribute for a `<chart:series>` element overrides the `chart:class` attribute for the entire chart.

Note: The following table shows examples for the pre-defined chart types. Those charts that use one or two data series use two data series with the values 1;2;3;4 and 1;4;9;16 and the labels a;b;c;d. Those chart types that use more than two data series (stock and bubble) use the data series 1;2;3;4 and multiples thereof. The radar chart uses two data series with five data points.



Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product



chart:ring



chart:scatter



chart:radar



chart:bar



chart:stock



chart:bubble



chart:surface



chart:gantt

The `chart:class` attribute is usable with the following elements: `<chart:chart>` 11.1 and `<chart:series>` 11.11.

The `chart:class` attribute has the data type `namespacedToken` 18.3.19.

19.15.2 <chart:grid>

The `chart:class` attribute of a `<chart:grid>` element specifies whether major or minor tick marks are used on a grid.

The defined values for the `chart:class` attribute are:

- `major`: major tick marks are extended to grid lines.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `minor`: minor tick marks are extended to grid lines.

For a `<chart:grid>` 11.10 element the default value for this attribute is `major`.

The `chart:class` attribute is usable with the following element: `<chart:grid>` 11.10.

The values of the `chart:class` attribute are `major` or `minor`.

19.16 chart:column-mapping (deprecated)

The `chart:column-mapping` attribute is deprecated. It specifies a list of indexes of series. The numbers define a reordering of data that comes from a container document that provides the data for the chart. The numbering begins with 1. A list of ascending numbers beginning with 1 has no effect. To exchange two series, their numbers shall be exchanged in the list.

The `chart:column-mapping` and `chart:row-mapping` 19.26 attributes shall not be used simultaneously.

Note: Instead of using the deprecated `chart:column-mapping` attribute, `<chart:series>` elements may be reordered and and specific cell ranges may be assigned to them using the `chart:values-cell-range-address` attribute.

The `chart:column-mapping` attribute is usable with the following element: `<chart:chart>` 11.1.

The `chart:column-mapping` attribute has the data type `string` 18.2.

19.17 chart:data-source-has-labels (deprecated)

The `chart:data-source-has-labels` attribute specifies whether a chart's source range (as given within `table:cell-range-address` attribute on a `<chart:plot-area>` element) contain labels.

The defined values for the `chart:data-source-has-labels` attribute are:

- `both`: first row and column of a chart's source range both contain labels.
- `column`: first column of a chart's source range contains labels.
- `none`: neither the first row nor the first column of a chart's source range contains labels.
- `row`: first row of a chart's source range contains labels.

The default value for this attribute is `none`.

The `chart:data-source-has-labels` attribute is usable with the following element: `<chart:plot-area>` 11.4.

The values of the `chart:data-source-has-labels` attribute are `none`, `row`, `column` or `both`.

19.18 chart:dimension

The `chart:dimension` attribute specifies a dimension in a coordinate system.

For charts with less than three axes the `chart:dimension` attribute may appear with values for the x-axis and y-axis only.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the chart:dimension attribute are:

- x: dimension represented by the x-axis of a chart.
- y: dimension represented by the y-axis of a chart.
- z: dimension represented by the z-axis of a chart.

The chart:dimension attribute is usable with the following elements: <chart:axis> 11.8 and <chart:error-indicator> 11.16.

The values of the chart:dimension attribute are x, y or z.

19.19 chart:display-equation

The chart:display-equation attribute specifies whether the equation itself should be displayed or not. It is only evaluated if the value of the chart:automatic-content attribute is true.

The defined values for the chart:display-equation attribute are:

- false: the equation is not displayed.
- true: the equation is displayed.

The default value for this attribute is true.

The chart:display-equation attribute is usable with the following element: <chart:equation> 11.18.

The chart:display-equation attribute has the data type boolean 18.3.3.

19.20 chart:display-r-square

The chart:display-r-square attribute specifies whether an R-square value should be displayed or not. It is only evaluated if the value of the chart:automatic-content attribute is true.

The defined values for the chart:display-r-square attribute are:

- false: R-square value is not displayed.
- true: R-square value is displayed.

The default value for this attribute is false.

The chart:display-r-square attribute is usable with the following element: <chart:equation> 11.18.

The chart:display-r-square attribute has the data type boolean 18.3.3.

19.21 chart:label-cell-address

The chart:label-cell-address attribute specifies a cell range list that contains the name for a series.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `chart:label-cell-address` attribute is usable with the following element: `<chart:series>` 11.11.

The `chart:label-cell-address` attribute has the data type `cellRangeAddressList` 18.3.6.

19.22 chart:legend-align

The `chart:legend-align` attribute specifies the alignment of a legend with the plot area.

The defined values for the `chart:legend-align` attribute are:

- `center`: legend is aligned at the center of the plot-area.
- `end`: legend is aligned at the end of the plot-area (which is right or bottom).
- `start`: legend is aligned at the beginning of the plot-area (which is left or top).

Note: This attribute can be used when the `chart:legend-position` attribute has one of the following values: start, end, top, bottom.

The `chart:legend-align` attribute is usable with the following element: `<chart:legend>` 11.3.

The values of the `chart:legend-align` attribute are `start`, `center` or `end`.

19.23 chart:legend-position

The `chart:legend-position` attribute specifies the placement of a legend.

The defined values for the `chart:legend-position` attribute to specify the location of a legend in one of the corners of a chart outside the plot area are:

- `bottom-end`: place legend in the bottom right corner.
- `bottom-start`: place the legend in the bottom left corner.
- `top-end`: place legend in the top right corner.
- `top-start`: place legend in the top left corner.

The defined values for the `chart:legend-position` attribute to specify the location of a legend next to the plot area are:

- `bottom`: place legend below the plot area.
- `end`: place legend on the right side of the plot area.
- `start`: place legend on the left side of the plot area.
- `top`: place legend above the plot area.

The legend position can also be given in absolute coordinates with `svg:x` and `svg:y` attributes, as with any drawing object. If both absolute coordinates and the legend-position attribute are given, the legend-position attribute shall be used.

The `chart:legend-position` attribute is usable with the following element: `<chart:legend>` 11.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The values of the chart:legend-position attribute are start, end, top, bottom, top-start, bottom-start, top-end or bottom-end.

19.24 chart:name

The chart:name attribute specifies a name for an axis.

Note: The value of a chart:name attribute can be used to reference an axis.

The chart:name attribute is usable with the following element: <chart:axis> 11.8.

The chart:name attribute has the data type string 18.2.

19.25 chart:repeated

The chart:repeated attribute specifies how many consecutive data points have the same style.

The chart:repeated attribute is usable with the following element: <chart:data-point> 11.13.

The chart:repeated attribute has the data type positiveInteger 18.2.

19.26 chart:row-mapping (deprecated)

The chart:row-mapping attribute specifies a list of indexes of series. The numbers define a reordering of data that comes from a container document that provides the data for the chart. The numbering begins with 1. A list of ascending numbers beginning with 1 has no effect. To exchange two series, their numbers shall be exchanged in the list.

The chart:row-mapping and chart:column-mapping 19.16 attributes shall not be used simultaneously.

Note: Instead of using the deprecated chart:row-mapping attribute, <chart:series> elements may be reordered and and specific cell ranges may be assigned to them using the chart:values-cell-range-address attribute.

The chart:row-mapping attribute is usable with the following element: <chart:chart> 11.1.

The chart:row-mapping attribute has the data type string 18.2.

19.27 chart:style-name

The chart:style-name attribute references a chart style by its name.19.498

The chart:style-name attribute is usable with the following elements: <chart:axis> 11.8, <chart:chart> 11.1, <chart:data-label> 11.14, <chart:data-point> 11.13, <chart:equation> 11.18, <chart:error-indicator> 11.16, <chart:floor> 11.7, <chart:footer> 11.2.3, <chart:grid> 11.10, <chart:legend> 11.3, <chart:mean-value> 11.15, <chart:plot-area> 11.4, <chart:regression-curve> 11.17, <chart:series> 11.11, <chart:stock-gain-marker> 11.19, <chart:stock-loss-marker> 11.20, <chart:stock-range-line> 11.21, <chart:subtitle> 11.2.2, <chart:title> 11.2.1 and <chart:wall> 11.6.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The chart:style-name attribute has the data type styleNameRef 18.3.32.

19.28 chart:values-cell-range-address

The chart:values-cell-range-address attribute specifies a cell range that contains the values for a data series.

The chart:values-cell-range-address attribute is usable with the following element: <chart:series> 11.11.

The chart:values-cell-range-address attribute has the data type cellRangeAddressList 18.3.6.

19.29 config:name

The config:name attribute specifies a name of an application setting, an application setting sequence, or an application setting container.

For <config:config-item-set> elements that are children of <office:settings> elements, the name shall begin with a namespace prefix followed by a ":" (U+003A, COLON). The XML namespace bound to the prefix identifies the implementation that defines the name of a setting.

The config:name attribute is usable with the following elements: <config:config-item> 3.10.3, <config:config-item-map-entry> 3.10.5, <config:config-item-map-indexed> 3.10.4, <config:config-item-map-named> 3.10.6 and <config:config-item-set> 3.10.2.

The config:name attribute has the data type string 18.2.

19.30 config:type

The config:type attribute specifies a data type for a setting.

The defined values for the config:type attribute are:

- base64Binary: 18.2
- boolean: 18.3.3
- datetime: 18.2
- double: 18.2
- int: 18.2
- long: 18.2 .
- short: 18.2
- string: 18.2

The config:type attribute is usable with the following element: <config:config-item> 3.10.3.

The values of the config:type attribute are boolean, short, int, long, double, string, datetime or base64Binary.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.31 db:additional-column-statement

The `db:additional-column-statement` attribute specifies the auto-increment keyword of an SQL create statement and any start value.

Note: The auto increment keyword, optional start value and the format of the string specifying them are database specific.

The `db:additional-column-statement` attribute is usable with the following element: `<db:auto-increment>` 12.10.

The `db:additional-column-statement` attribute has the data type `string` 18.2.

19.32 db:append-table-alias-name

The `db:append-table-alias-name` attribute specifies that a table alias name should be appended when creating an SQL query.

The defined values for the `db:append-table-alias-name` attribute are:

- `false`: table alias name is not appended to a query when creating an SQL query.
- `true`: table alias name is appended to a query when creating an SQL query.

The default value for this attribute is `true`.

The `db:append-table-alias-name` attribute is usable with the following element: `<db:application-connection-settings>` 12.15.

The `db:append-table-alias-name` attribute has the data type `boolean` 18.3.3.

19.33 db:apply-command

The `db:apply-command` attribute specifies whether an SQL clause specified by a `db:command` attribute should be appended to an underlying statement.

The defined values for the `db:apply-command` attribute are:

- `false`: an SQL clause specified by a `db:command` will not be appended to an underlying statement.
- `true`: an SQL clause specified by a `db:command` attribute will be appended to an underlying statement.

The default value for this attribute is `false`.

The `db:apply-command` attribute is usable with the following elements: `<db:filter-statement>` 12.30 and `<db:order-statement>` 12.29.

The `db:apply-command` attribute has the data type `boolean` 18.3.3.

19.34 db:as-template

The `db:as-template` attribute specifies that a document is used as a template for a table structure to be created inside a database.

The defined values for the `db:as-template` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `false`: document is not used as a template.
- `true`: document is used as a template.

The `db:as-template` attribute is usable with the following element: `<db:component>` 12.25.5.

The `db:as-template` attribute has the data type `boolean` 18.3.3.

19.35 db:base-dn

The `db:base-dn` attribute specifies a base DN for data that is retrieved using LDAP. [RFC4514]

The `db:base-dn` attribute is usable with the following element: `<db:driver-settings>` 12.9.

The `db:base-dn` attribute has the data type `string` 18.2.

19.36 db:boolean-comparison-mode

The `db:boolean-comparison-mode` attribute specifies a comparison mode used for Boolean values in SQL SELECT statements.

The defined values for the `db:boolean-comparison-mode` attribute are:

- `equal-boolean`: “= TRUE" will be used for true and “= FALSE" for false.
- `equal-integer`: “= 1" will be used for true and “= 0" for false.
- `equal-use-only-zero`: “NOT ($value = 0 or $value IS NULL)" will be used for true and “= 0" for false.
- `is-boolean`: “IS TRUE" will be used for true and “IS FALSE" for false.

The default value for this attribute is `equal-integer`.

The `db:boolean-comparison-mode` attribute is usable with the following element: `<db:application-connection-settings>` 12.15.

The values of the `db:boolean-comparison-mode` attribute are `equal-integer`, `is-boolean`, `equal-boolean` or `equal-use-only-zero`.

19.37 db:catalog-name

The `db:catalog-name` attribute specifies the catalog part of a full qualified SQL table name or index name.

The `db:catalog-name` attribute is usable with the following elements: `<db:index>` 12.46, `<db:table-definition>` 12.38, `<db:table-representation>` 12.33 and `<db:update-table>` 12.31.

The `db:catalog-name` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.38 db:command

The db:command attribute specifies an SQL select, order or filter clause that is used as part of a SELECT statement.

The db:command attribute is usable with the following elements: <db:filter-statement> 12.30, <db:order-statement> 12.29 and <db:query> 12.28.

The db:command attribute has the data type string 18.2.

19.39 db:data-source-setting-is-list

The db:data-source-setting-is-list attribute specifies whether a <db:data-source-setting> element contains a list of <db:data-source-setting-value> elements.

The defined values for the db:data-source-setting-is-list attribute are:

- false: <db:data-source-settings> element should not contain a list of <db:data-source-setting-value> elements.
- true: <db:data-source-settings> element should contain a list of <db:data-source-setting-value> elements.

The db:data-source-setting-is-list attribute is usable with the following element: <db:data-source-setting> 12.23.

The db:data-source-setting-is-list attribute has the data type boolean 18.3.3.

19.40 db:data-source-setting-name

The db:data-source-setting-name attribute specifies a name for a <db:data-source-setting> element.

The db:data-source-setting-name attribute is usable with the following element: <db:data-source-setting> 12.23.

The db:data-source-setting-name attribute has the data type string 18.2.

19.41 db:data-source-setting-type

The db:data-source-setting-type attribute specifies a data type for a data-source-setting value.

The defined values for the db:data-source-setting-type attribute are:

- boolean: 18.3.3
- double: 18.2
- int: 18.2
- long: defined by [SQL].
- string: 18.2

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The db:data-source-setting-type attribute is usable with the following element: <db:data-source-setting> 12.23.

The values of the db:data-source-setting-type attribute are boolean, short, int, long, double or string.

19.42 db:data-type

The db:data-type attribute specifies an SQL data type for a column.

The values accepted by db:data-type are defined by [SQL].

The db:data-type attribute is usable with the following element: <db:column-definition> 12.40.

The values of the db:data-type attribute are bit, boolean, tinyint, smallint, integer, bigint, float, real, double, numeric, decimal, char, varchar, longvarchar, date, time, timestmp, binary, varbinary, longvarbinary, sqlnull, other, object, distinct, struct, array, blob, clob or ref.

19.43 db:database-name

The db:database-name attribute specifies the database for a connection if the database type supports multiple logical databases per server.

The db:database-name attribute is usable with the following element: <db:server-database> 12.6.

The db:database-name attribute has the data type string 18.2.

19.44 db:decimal

The db:decimal attribute specifies a decimal separator for numeric fields.

The default value for this attribute is "." (U+002E, FULL STOP).

The db:decimal attribute is usable with the following element: <db:delimiter> 12.11.

The db:decimal attribute has the data type string 18.2.

19.45 db:default-cell-style-name

The db:default-cell-style-name attribute specifies a default cell style. This style is applied to all cells in a column.

The db:default-cell-style-name attribute is usable with the following element: <db:column> 12.35.

The db:default-cell-style-name attribute has the data type styleNameRef 18.3.32.

19.46 db:default-row-style-name

The db:default-row-style-name attribute specifies a default row style. This style is applied to all rows in a table.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The db:default-row-style-name attribute is usable with the following elements: <db:query> 12.28 and <db:table-representation> 12.33.

The db:default-row-style-name attribute has the data type styleNameRef 18.3.32.

19.47 db:delete-rule

The db:delete-rule attribute specifies a rule that is applied for deleting records from a table. It is used only with foreign keys.

The defined values for the db:delete-rule attribute are:

- cascade: when the primary key is deleted, rows that imported that key are deleted.
- no-action: indicates that if the primary key has been imported, it cannot be deleted.
- restrict: a primary key shall not be deleted if it has been imported by another table as a foreign key.
- set-default: when the primary key is deleted, the foreign key (imported key) is set to the default value.
- set-null: when the primary key is deleted, the foreign key (imported key) is changed to NULL.

The default value for this attribute is no-action.

The db:delete-rule attribute is usable with the following element: <db:key> 12.42.

The values of the db:delete-rule attribute are cascade, restrict, set-null, no-action or set-default.

19.48 db:description

The db:description attribute specifies a description of a database object.

The db:description attribute is usable with the following elements: <db:column> 12.35, <db:component> 12.25.5, <db:component-collection> 12.25.4, <db:query> 12.28, <db:query-collection> 12.27 and <db:table-representation> 12.33.

The db:description attribute has the data type string 18.2.

19.49 db:enable-sql92-check

The db:enable-sql92-check attribute specifies whether the names of tables, views, columns, and queries may contain characters defined by the [SQL] feature F392.

The defined values for the db:enable-sql92-check attribute are:

- false: consumers should permit characters defined by the [SQL] feature F392 for new or changed names of tables, views, columns, and queries.
- true: consumers should not permit characters defined by the [SQL] feature F392 for new or changed names of tables, views, columns, and queries.

The default value for this attribute is false.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The db:enable-sql92-check attribute is usable with the following element: <db:application-connection-settings> 12.15.

The db:enable-sql92-check attribute has the data type boolean 18.3.3.

19.50 db:encoding

The db:encoding attribute specifies a text encoding for string data.

The default value for this attribute is utf-8.

The db:encoding attribute is usable with the following element: <db:character-set> 12.12.

The db:encoding attribute has the data type textEncoding 18.3.35.

19.51 db:escape-processing

The db:escape-processing attribute specifies whether escape processing for a query is used or not.

The defined values for the db:escape-processing attribute are:

- false: consumer should pass a query statement to the database driver without interpreting it itself.
- true: consumer may pass a query statement to a database driver after interpreting it itself.

The default value for this attribute is true.

The db:escape-processing attribute is usable with the following element: <db:query> 12.28.

The db:escape-processing attribute has the data type boolean 18.3.3.

19.52 db:extension

The db:extension attribute of a <db:file-based-database> element specifies a file name extension for files which are used as tables.

The db:extension attribute is usable with the following element: <db:file-based-database> 12.5.

The db:extension attribute has the data type string 18.2.

19.53 db:field

The db:field attribute specifies a separator for database fields.

The default value for this attribute is ";" (U+003B, SEMICOLON).

The db:field attribute is usable with the following element: <db:delimiter> 12.11.

The db:field attribute has the data type string 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.54 db:hostname

The db:hostname attribute specifies the name of a server for a server-based database.

The db:hostname attribute is usable with the following element: <db:server-database> 12.6.

The db:hostname attribute has the data type string 18.2.

19.55 db:ignore-driver-privileges

The db:ignore-driver-privileges attribute specifies whether privileges returned by a database driver should be ignored.

The defined values for the db:ignore-driver-privileges attribute are:

- false: privileges returned by a database driver should not be ignored.
- true: privileges returned by a database driver should be ignored.

The default value for this attribute is true.

The db:ignore-driver-privileges attribute is usable with the following element: <db:application-connection-settings> 12.15.

The db:ignore-driver-privileges attribute has the data type boolean 18.3.3.

19.56 db:is-ascending

The db:is-ascending attribute specifies that a column is to be sorted in ascending order.

The defined values for the db:is-ascending attribute are:

- false: column is not sorted in ascending order.
- true: column is sorted in ascending order.

The db:is-ascending attribute is usable with the following element: <db:index-column> 12.48.

The db:is-ascending attribute has the data type boolean 18.3.3.

19.57 db:is-autoincrement

The db:is-autoincrement attribute specifies whether a column is automatically numbered.

The defined values for the db:is-autoincrement attribute are:

- false: column is not automatically numbered.
- true: column is automatically numbered.

The db:is-autoincrement attribute is usable with the following element: <db:column-definition> 12.40.

The db:is-autoincrement attribute has the data type boolean 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.58 db:is-clustered

The `db:is-clustered` attribute specifies that an index is clustered.

The defined values for the `db:is-clustered` attribute are:

- `false`: index is not clustered.
- `true`: index is clustered.

The `db:is-clustered` attribute is usable with the following element: `<db:index>` 12.46.

The `db:is-clustered` attribute has the data type `boolean` 18.3.3.

19.59 db:is-empty-allowed

The `db:is-empty-allowed` attribute specifies whether a column may contain empty values.

The defined values for the `db:is-empty-allowed` attribute are:

- `false`: column may not contain empty values.
- `true`: column may contain empty values.

The `db:is-empty-allowed` attribute is usable with the following element: `<db:column-definition>` 12.40.

The `db:is-empty-allowed` attribute has the data type `boolean` 18.3.3.

19.60 db:is-first-row-header-line

The `db:is-first-row-header-line` attribute specifies whether the first row in a text file, which is interpreted as table of a file-based database, is used to define the columns of a table.

The defined values for the `db:is-first-row-header-line` attribute are:

- `false`: first row of text file does not define columns of a table.
- `true`: first row of text file does define columns of a table.

The default value for this attribute is `true`.

The `db:is-first-row-header-line` attribute is usable with the following elements: `<db:driver-settings>` 12.9 and `<db:table-setting>` 12.14.

The `db:is-first-row-header-line` attribute has the data type `boolean` 18.3.3.

19.61 db:login-timeout

The `db:login-timeout` attribute indicates a default time-out to be used when establishing a connection for this data source. If the attribute is not present, then default time-out is specified by the database server.

The `db:login-timeout` attribute is usable with the following element: `<db:login>` 12.8.

The `db:login-timeout` attribute has the data type `positiveInteger` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.62 db:is-nullable

The `db:is-nullable` attribute specifies the nullability of values in a column.

The defined values for the `db:is-nullable` attribute are:

- `no-nulls`: null values should not appear in a column.
- `nullable`: null values may appear in a column.

The `db:is-nullable` attribute is usable with the following element: `<db:column-definition>` 12.40.

The values of the `db:is-nullable` attribute are `no-nulls` or `nullable`.

19.63 db:is-password-required

The `db:is-password-required` attribute specifies if a password is always necessary when establishing a connection for a data source.

The defined values for the `db:is-password-required` attribute are:

- `false`: password should not be required for a connection to data source.
- `true`: password should be required for a connection to data source.

The default value for this attribute is `false`.

The `db:is-password-required` attribute is usable with the following element: `<db:login>` 12.8.

The `db:is-password-required` attribute has the data type `boolean` 18.3.3.

19.64 db:is-unique

The `db:is-unique` attribute specifies an index shall have unique values.

The defined values for the `db:is-unique` attribute are:

- `false`: index should not require unique values.
- `true`: index shall have unique values.

The `db:is-unique` attribute is usable with the following element: `<db:index>` 12.46.

The `db:is-unique` attribute has the data type `boolean` 18.3.3.

19.65 db:precision

The `db:precision` attribute specifies a column's number of decimal digits.

The `db:precision` attribute is usable with the following element: `<db:column-definition>` 12.40.

The `db:precision` attribute has the data type `positiveInteger` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.66 db:is-table-name-length-limited

The `db:is-table-name-length-limited` attribute specifies whether table names are limited to eight characters or fewer characters.

The defined values for the `db:is-table-name-length-limited` attribute are:

- `false`: tables names may exceed eight characters in length.
- `true`: table names shall not be greater than eight characters in length.

The default value for this attribute is `true`.

The `db:is-table-name-length-limited` attribute is usable with the following element: `<db:application-connection-settings>` 12.15.

The `db:is-table-name-length-limited` attribute has the data type `boolean` 18.3.3.

19.67 db:local-socket

The `db:local-socket` attribute specifies local socket on which a server database is running and accepting connections. The server's local socket filename is used for connecting to a server database when it is running locally.

If `db:local-socket` is present but empty, consumers should use the default local socket for the database type in question.

The `db:local-socket` attribute is usable with the following element: `<db:server-database>` 12.6.

The `db:local-socket` attribute has the data type `string` 18.2.

19.68 db:max-row-count

The `db:max-row-count` attribute specifies the maximum number of rows that should be returned in a result set.

The `db:max-row-count` attribute is usable with the following element: `<db:application-connection-settings>` 12.15.

The `db:max-row-count` attribute has the data type `integer` 18.2.

19.69 db:media-type

The `db:media-type` attribute of a `<db:file-based-database>` element specifies the type of the file(s) that comprise a database. If the database consists of multiple files of different types which all are required for it to be operational, this attribute specifies the type of the file l to by the `xlink:href` attribute on the `<db:file-based-database>` element.

The `db:media-type` attribute is usable with the following element: `<db:file-based-database>` 12.5.

The `db:media-type` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.70 db:name

19.70.1 General

The `db:name` attribute specifies a name of a database or component of a database.

19.70.2 <db:column>

The `db:name` attribute value specifies the name of a column.

The `db:name` attribute is usable with the following element: `<db:column>` 12.35.

The `db:name` attribute has the data type `string` 18.2.

19.70.3 <db:column-definition>

The `db:name` attribute specifies the name of a column.

The `db:name` attribute is usable with the following element: `<db:column-definition>` 12.40.

The `db:name` attribute has the data type `string` 18.2.

19.70.4 <db:component>

The `db:name` attribute specifies the name of a database component.

The `db:name` attribute is usable with the following element: `<db:component>` 12.25.5.

The `db:name` attribute has the data type `string` 18.2.

19.70.5 <db:component-collection>

The `db:name` attribute specifies the name of a collection of `<db:component>` and `<db:component-collection>` elements.

The `db:name` attribute is usable with the following element: `<db:component-collection>` 12.25.4.

The `db:name` attribute has the data type `string` 18.2.

19.70.6 <db:index>

The `db:name` attribute value specifies the name of an index.

The `db:name` attribute is usable with the following element: `<db:index>` 12.46.

The `db:name` attribute has the data type `string` 18.2.

19.70.7 <db:index-column>

The `db:name` attribute value specifies the name of an index column.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The db:name attribute is usable with the following element: <db:index-column> 12.48.

The db:name attribute has the data type string 18.2.

19.70.8 <db:key>

The db:name attribute value specifies the name of a key. If the key is not a primary key, the db:name attribute with a value shall appear on the <db:key> element.

The db:name attribute is usable with the following element: <db:key> 12.42.

The db:name attribute has the data type string 18.2.

19.70.9 <db:key-column>

The db:name attribute specifies the name of a <db:key-column> element.

The db:name attribute is usable with the following element: <db:key-column> 12.44.

The db:name attribute has the data type string 18.2.

19.70.10 <db:query>

The db:name attribute specifies the name of a <db:query> element.

The db:name attribute is usable with the following element: <db:query> 12.28.

The db:name attribute has the data type string 18.2.

19.70.11 <db:query-collection>

The db:name attribute specifies the name of a collection of <db:query> and <db:query-collection> elements.

The db:name attribute is usable with the following element: <db:query-collection> 12.27.

The db:name attribute has the data type string 18.2.

19.70.12 <db:table-definition>

The db:name attribute specifies the name of a schema for a table.

The db:name attribute is usable with the following element: <db:table-definition> 12.38.

The db:name attribute has the data type string 18.2.

19.70.13 <db:table-representation>

The db:name attribute value specifies the name of a table. Fully identifying a table in a database may require values from the db:catalog-name and db:schema-name attributes.

The db:name attribute is usable with the following element: <db:table-representation> 12.33.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The db:name attribute has the data type string 18.2.

19.70.14 <db:update-table>

The db:name attribute specifies the name of a <db:update-table> element.

The db:name attribute is usable with the following element: <db:update-table> 12.31.

The db:name attribute has the data type string 18.2.

19.71 db:parameter-name-substitution

The db:parameter-name-substitution attribute specifies that parameter names shall be replaced with a "?" (U+003F, QUESTION MARK).

The defined values for the db:parameter-name-substitution attribute are:

- false: parameters names may be replaced by a "?".
- true: parameters names shall be replaced by a "?".

The default value for this attribute is true.

The db:parameter-name-substitution attribute is usable with the following element: <db:driver-settings> 12.9.

The db:parameter-name-substitution attribute has the data type boolean 18.3.3.

19.72 db:port

The db:port attribute specifies the port on which a server database is accepting connections. If no port is present, consumers should use the default port for the database type in question.

The db:port attribute is usable with the following element: <db:server-database> 12.6.

The db:port attribute has the data type positiveInteger 18.2.

19.73 db:referenced-table-name

The db:referenced-table-name attribute specifies the name of a referenced table. It is only used with foreign keys.

The db:referenced-table-name attribute is usable with the following element: <db:key> 12.42.

The db:referenced-table-name attribute has the data type string 18.2.

19.74 db:related-column-name

The db:related-column-name attribute specifies the name of a reference column out of the referenced table. It is used only with foreign keys.

The db:related-column-name attribute is usable with the following element: <db:key-column> 12.44.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The db:related-column-name attribute has the data type string 18.2.

19.75 db:row-retrieving-statement

The db:row-retrieving-statement attribute specifies an SQL statement, which is executed to retrieve auto generated values after inserting a new row.

The db:row-retrieving-statement attribute is usable with the following element: <db:auto-increment> 12.10.

The db:row-retrieving-statement attribute has the data type string 18.2.

19.76 db:scale

The db:scale attribute specifies a column's number of digits to the right of the decimal point.

The db:scale attribute is usable with the following element: <db:column-definition> 12.40.

The db:scale attribute has the data type positiveInteger 18.2.

19.77 db:schema-name

The db:schema-name attribute specifies the name of a schema.

The db:schema-name attribute is usable with the following elements: <db:table-definition> 12.38, <db:table-representation> 12.33 and <db:update-table> 12.31.

The db:schema-name attribute has the data type string 18.2.

19.78 db:show-deleted

The db:show-deleted attribute specifies that deleted records should be included in result sets.

The defined values for the db:show-deleted attribute are:

- false: deleted records not included in result sets.
- true: deleted records included in result sets.

The default value for this attribute is false.

The db:show-deleted attribute is usable with the following elements: <db:driver-settings> 12.9 and <db:table-setting> 12.14.

The db:show-deleted attribute has the data type boolean 18.3.3.

19.79 db:string

The db:string attribute specifies a separator for strings.

The default value for this attribute is "." (U+002E, FULL STOP).

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The db:string attribute is usable with the following element: <db:delimiter> 12.11.

The db:string attribute has the data type string 18.2.

19.80 db:style-name

19.80.1 General

The db:style-name attribute specifies a style name of a style family for the element upon which it appears.

19.80.2 <db:column>

The db:style-name attribute value specifies the name of a style of the family table-column.

The db:style-name attribute is usable with the following element: <db:column> 12.35.

The db:style-name attribute has the data type styleNameRef 18.3.32.

19.80.3 <db:query>

The db:style-name attribute value specifies the name of a style of the family table.

The db:style-name attribute is usable with the following element: <db:query> 12.28.

The db:style-name attribute has the data type styleNameRef 18.3.32.

19.80.4 <db:table-representation>

The db:style-name attribute value specifies the name of a style of the family table.

The db:style-name attribute is usable with the following element: <db:table-representation> 12.33.

The db:style-name attribute has the data type styleNameRef 18.3.32.

19.81 db:suppress-version-columns

The db:suppress-version-columns attribute specifies that version columns, columns that are used for versioning row content, should be suppressed.

The defined values for the db:suppress-version-columns attribute are:

- false: version columns are not suppressed.
- true: version columns should be suppressed.

The default value for this attribute is true.

The db:suppress-version-columns attribute is usable with the following element: <db:application-connection-settings> 12.15.

The db:suppress-version-columns attribute has the data type boolean 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.82 db:system-driver-settings

The `db:system-driver-settings` attribute specifies system specific options for a connection.

The `db:system-driver-settings` attribute is usable with the following element: `<db:driver-settings>` 12.9.

The `db:system-driver-settings` attribute has the data type `string` 18.2.

19.83 db:thousand

The `db:thousand` attribute specifies a thousand separator of numeric fields.

The default value for this attribute is "," (U+002C, COMMA).

The `db:thousand` attribute is usable with the following element: `<db:delimiter>` 12.11.

The `db:thousand` attribute has the data type `string` 18.2.

19.84 db:title

The `db:title` attribute specifies a human-readable title of an object.

The `db:title` attribute is usable with the following elements: `<db:column>` 12.35, `<db:component>` 12.25.5, `<db:component-collection>` 12.25.4, `<db:query>` 12.28, `<db:query-collection>` 12.27 and `<db:table-representation>` 12.33.

The `db:title` attribute has the data type `string` 18.2.

19.85 db:type

19.85.1 General

The `db:type` attribute specifies a type for keys, databases, or tables, depending upon the element where it occurs.

19.85.2 <db:key>

The `db:type` attribute specifies the type of a key.

The defined values for the `db:type` attribute are:

- `foreign`: a foreign key is a tuple of values in a database record that points to a key of a record in another table.
- `primary`: a primary key is a tuple of values that can be used to identify a row in a table.
- `unique`: a unique key specifies that the value of the key is unique but may be the NULL value.

The `db:type` attribute is usable with the following element: `<db:key>` 12.42.

The values of the `db:type` attribute are `primary`, `unique` or `foreign`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.85.3 <db:server-database>

The `db:type` attribute specifies the type of a database.

The `db:type` attribute is usable with the following element: `<db:server-database>` 12.6.
The `db:type` attribute has the data type `namespacedToken` 18.3.19.

19.85.4 <db:table-definition>

The `db:type` attribute specifies the type of a table.

The defined values for the `db:type` attribute are:

- `system table`: a table used by a database for administration.
- `table`: a table.
- `view`: a table that is a view of another table.
- Implementation-defined values

The `db:type` attribute is usable with the following element: `<db:table-definition>` 12.38.
The `db:type` attribute has the data type `string` 18.2.

19.86 db:type-name

The `db:type-name` attribute specifies a database dependent type name of a database column.

The `db:type-name` attribute is usable with the following element: `<db:column-definition>` 12.40.
The `db:type-name` attribute has the data type `string` 18.2.

19.87 db:update-rule

The `db:update-rule` attribute specifies a rule that is applied for updating records in a table. It is only used for foreign keys.

The defined values for the `db:update-rule` attribute are:

- `cascade`: when the primary key is updated, the foreign key (imported key) is changed to the same value.
- `restrict`: a primary key shall not be updated if it has been imported by another table as a foreign key.
- `no-action`: if the primary key has been imported, it cannot be updated.
- `set-default`: when the primary key is updated, the foreign key (imported key) is set to the default value.
- `set-null`: when the primary key is updated, the foreign key (imported key) is changed to NULL.

The default value for this attribute is `no-action`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The db:update-rule attribute is usable with the following element: <db:key> 12.42.

The values of the db:update-rule attribute are cascade, restrict, set-null, no-action or set-default.

19.88 db:use-catalog

The db:use-catalog attribute specifies that a catalog name should be used to reference a table in SQL statements.

The defined values for the db:use-catalog attribute are:

- false: catalog name is not use to reference a table in SQL statements.
- true: catalog name should be used to reference a table in SQL statements.

The default value for this attribute is false.

The db:use-catalog attribute is usable with the following element: <db:application-connection-settings> 12.15.

The db:use-catalog attribute has the data type boolean 18.3.3.

19.89 db:use-system-user

The db:use-system-user attribute specifies that the name of a user as logged in to the client operating system is used.

If db:use-system-user and db:user-name attributes are omitted and the server requires a user name, the user is prompted to enter a name.

The defined values for the db:use-system-user attribute are:

- false: name of user logged into client operating system is not used for login.
- true: name of user logged into client operating system is used for login.

The db:use-system-user attribute is usable with the following element: <db:login> 12.8.

The db:use-system-user attribute has the data type boolean 18.3.3.

19.90 db:user-name

The db:user-name attribute specifies a user name for authentication upon creating a connection to a database.

If db:user-name and db:use-system-user attributes are omitted and the server requires a user name, the user is prompted to enter a name.

The db:user-name attribute is usable with the following element: <db:login> 12.8.

The db:user-name attribute has the data type string 18.2.

19.91 db:visible

The db:visible attribute specifies whether a column appears in a table grid view.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the db:visible attribute are:

- false: column does not appear in a table grid view.
- true: column appears in a table grid view.

The default value for this attribute is true.

The db:visible attribute is usable with the following element: <db:column> 12.35.
The db:visible attribute has the data type boolean 18.3.3.

19.92 dr3d:ambient-color

The dr3d:ambient-color attribute specifies a color for ambient light.

Note: Ambient light is light that seems to come from all directions.

The dr3d:ambient-color attribute, along with dr3d:diffuse-color, dr3d:emissive-color, and dr3d:specular-color specifies the four colors that define the color of a material.

The dr3d:ambient-color attribute is usable with the following elements: <chart:plot-area> 11.4 and <dr3d:scene> 10.5.2.
The dr3d:ambient-color attribute has the data type color 18.3.9.

19.93 dr3d:center

The dr3d:center attribute specifies the center of a sphere in a three-dimensional space.

The dr3d:center attribute is usable with the following element: <dr3d:sphere> 10.5.5.
The dr3d:center attribute has the data type vector3D 18.3.40.

19.94 dr3d:diffuse-color

The dr3d:diffuse-color attribute specifies the base color that a light is emitting.

The dr3d:diffuse-color attribute is usable with the following element: <dr3d:light> 10.5.3.
The dr3d:diffuse-color attribute has the data type color 18.3.9.

19.95 dr3d:direction

The dr3d:direction attribute specifies the direction in which light is emitted.

The dr3d:direction attribute is usable with the following element: <dr3d:light> 10.5.3.
The dr3d:direction attribute has the data type vector3D 18.3.40.

19.96 dr3d:distance

The dr3d:distance attribute specifies the distance between a camera and an object.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The dr3d:distance attribute is usable with the following elements: <chart:plot-area> 11.4 and <dr3d:scene> 10.5.2.

The dr3d:distance attribute has the data type length 18.3.18.

19.97 dr3d:enabled

The dr3d:enabled attribute specifies if a light is enabled. If a light is not enabled, it does not emit any light.

The defined values for the dr3d:enabled attribute are:

- false: light is not enabled.
- true: light is enabled.

The dr3d:enabled attribute is usable with the following element: <dr3d:light> 10.5.3.

The dr3d:enabled attribute has the data type boolean 18.3.3.

19.98 dr3d:focal-length

The dr3d:focal-length attribute specifies the focal length of a virtual camera in a scene.

The dr3d:focal-length attribute is usable with the following elements: <chart:plot-area> 11.4 and <dr3d:scene> 10.5.2.

The dr3d:focal-length attribute has the data type length 18.3.18.

19.99 dr3d:lighting-mode

19.99.1 General

The dr3d:lighting-mode attribute specifies the use of lighting in three-dimensional scenes

Note: The dr3d:lighting-mode attribute is also defined for 3D objects. 20.79

19.99.2 <chart:plot-area>

The dr3d:lighting-mode attribute specifies whether lighting is used in a three-dimensional chart.

The defined values for the dr3d:lighting-mode attribute are:

- false: lighting is not used.
- true: lighting is used.

The dr3d:lighting-mode attribute is usable with the following element: <chart:plot-area> 11.4.

The dr3d:lighting-mode attribute has the data type boolean 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.99.3 <dr3d:scene>

The dr3d:lighting-mode attribute specifies whether lighting is used in a three-dimensional scene.

The defined values for the dr3d:lighting-mode attribute are:

- false: lighting is not used.
- true: lighting is used.

The dr3d:lighting-mode attribute is usable with the following element: <dr3d:scene> 10.5.2.

The dr3d:lighting-mode attribute has the data type boolean 18.3.3.

19.100 dr3d:max-edge

The dr3d:max-edge attribute specifies the maximum x, y and z coordinate values for a cube.

The dr3d:max-edge attribute is usable with the following element: <dr3d:cube> 10.5.4.

The dr3d:max-edge attribute has the data type vector3D 18.3.40.

19.101 dr3d:min-edge

The dr3d:min-edge attribute specifies the minimum x, y and z coordinate values for a cube.

The dr3d:min-edge attribute is usable with the following element: <dr3d:cube> 10.5.4.

The dr3d:min-edge attribute has the data type vector3D 18.3.40.

19.102 dr3d:projection

The dr3d:projection attribute specifies a projection mode.

The defined values for the dr3d:projection attribute are:

- parallel: distance from the center of projection to the projection plane is infinite.
- perspective: distance from the center of projection to the projection plane is finite.

For a <draw:enhanced-geometry> 10.6.2 element the default value for this attribute is parallel.

The dr3d:projection attribute is usable with the following elements: <chart:plot-area> 11.4, <dr3d:scene> 10.5.2 and <draw:enhanced-geometry> 10.6.2.

The values of the dr3d:projection attribute are parallel or perspective.

19.103 dr3d:shade-mode

The dr3d:shade-mode attribute specifies how lighting is calculated for rendered surfaces.

The defined values for the dr3d:shade-mode attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `draft`: surfaces are not lit and drawn as wireframe only.
- `flat`: lighting is calculated by one surface normal.
- `gouraud`: lighting is calculated by interpolating the color calculated with the surface normals at each edge.
- `phong`: lighting is calculated by interpolating the surface normals over the surface.

For a `<draw:enhanced-geometry>` 10.6.2 element the default value for this attribute is `flat`.

The `dr3d:shade-mode` attribute is usable with the following elements: `<chart:plot-area>` 11.4, `<dr3d:scene>` 10.5.2 and `<draw:enhanced-geometry>` 10.6.2.

The values of the `dr3d:shade-mode` attribute are `flat`, `phong`, `gouraud` or `draft`.

19.104 dr3d:shadow-slant

The `dr3d:shadow-slant` attribute specifies an angle from a three-dimensional scene to a virtual paper on which a shadow is cast.

The `dr3d:shadow-slant` attribute is usable with the following elements: `<chart:plot-area>` 11.4 and `<dr3d:scene>` 10.5.2.

The `dr3d:shadow-slant` attribute has the data type `angle` 18.3.1.

19.105 dr3d:size

The `dr3d:size` attribute specifies the size of a sphere in a three-dimensional space.

The `dr3d:size` attribute is usable with the following element: `<dr3d:sphere>` 10.5.5.

The `dr3d:size` attribute has the data type `vector3D` 18.3.40.

19.106 dr3d:specular

The `dr3d:specular` attribute specifies whether a light causes a specular reflection on objects. consumers may evaluate this attribute only for the first light in a scene.

The defined values for the `dr3d:specular` attribute are:

- `false`: light does not cause specular reflection.
- `true`: light does cause specular reflection.

The `dr3d:specular` attribute is usable with the following element: `<dr3d:light>` 10.5.3.

The `dr3d:specular` attribute has the data type `boolean` 18.3.3.

19.107 dr3d:transform

The `dr3d:transform` attribute specifies a list of transform definitions, which are applied in the order provided. The individual transform definitions are separated by white space.

The defined transforms are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `matrix(<a> <b> <c> <d> <e> <f> <g> <h> <i> <j> <k> <l>)`: specifies a transformation in the form of a transformation matrix of twelve values. The values describe a standard 4x3 homogeneous transformation matrix in column-major order, where the right column (<j>, <k>, <l>) describes the translation.
- `rotatex(<rotate-angle>)`: specifies a rotation by `<rotate-angle>` degrees along the x-axis.
- `rotatey(<rotate-angle>)`: specifies a rotation by `<rotate-angle>` degrees along the y-axis.
- `rotatez(<rotate-angle>)`: specifies a rotation by `<rotate-angle>` degrees along the z-axis.
- `scale(<sx> <sy> <sz>)`: specifies a scale operation by *sx*, *sy* and *sz*.
- `translate(<tx> <ty> <tz>)`: specifies a translation by *tx*, *ty* and *tz*.

The `dr3d:transform` attribute is usable with the following elements: `<chart:plot-area>` 11.4, `<dr3d:cube>` 10.5.4, `<dr3d:extrude>` 10.5.6, `<dr3d:rotate>` 10.5.7, `<dr3d:scene>` 10.5.2 and `<dr3d:sphere>` 10.5.5.

The `dr3d:transform` attribute has the data type `string` 18.2.

19.108 dr3d:vpn

The `dr3d:vpn` attribute specifies a pointer towards projected objects.

With the `dr3d:vrp` and `dr3d:vup` attributes, the `dr3d:vpn` attribute specifies a viewing volume.

The `dr3d:vpn` attribute is usable with the following elements: `<chart:plot-area>` 11.4 and `<dr3d:scene>` 10.5.2.

The `dr3d:vpn` attribute has the data type `vector3D` 18.3.40.

19.109 dr3d:vrp

The `dr3d:vrp` attribute specifies an origin.

With the `dr3d:vpn` and `dr3d:vup` attributes, the `dr3d:vrp` attribute specifies a viewing volume.

The `dr3d:vrp` attribute is usable with the following elements: `<chart:plot-area>` 11.4 and `<dr3d:scene>` 10.5.2.

The `dr3d:vrp` attribute has the data type `vector3D` 18.3.40.

19.110 dr3d:vup

The `dr3d:vup` attribute specifies an up vector.

With the `dr3d:vpn` and `dr3d:vrp` attributes, the `dr3d:vup` attribute specifies a viewing volume.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The dr3d:vup attribute is usable with the following elements: <chart:plot-area> 11.4 and <dr3d:scene> 10.5.2.

The dr3d:vup attribute has the data type vector3D 18.3.40.

19.111 draw:align

The draw:align attribute specifies the shape edge where a glue point is positioned.

The defined values for the draw:align attribute are:

- bottom-left: The position of the glue point is specified relative to the bottom-left corner of the shape's bounding box.
- bottom-right: The position of the glue point is specified relative to the bottom-right corner of the shape's bounding box.
- center: The position of the glue point is specified relative to the center of the shape's bounding box.
- right: The position of the glue point is specified relative to the right of the shape's bounding box.
- top: The position of the glue point is specified relative to the top of the shape's bounding box.
- top-right: The position of the glue point is specified relative to the top-right corner of the shape's bounding box.
- top-left: The position of the glue point is specified relative to the top-left corner of the shape's bounding box.

The draw:align attribute is usable with the following element: <draw:glue-point> 10.3.16.

The values of the draw:align attribute are top-left, top, top-right, left, center, right, bottom-left or bottom-right.

19.112 draw:angle

The draw:angle attribute specifies an angle that rotates the axis at which the gradient values are interpolated. This attribute is ignored for radial style gradients.

The draw:angle attribute is usable with the following elements: <draw:gradient> 16.40.1 and <draw:opacity> 16.40.7.

The draw:angle attribute has the data type angle 18.3.1.

19.113 draw:archive

The draw:archive attribute is equivalent to the archive attribute of an <applet> element in HTML. See. §13.4 of [HTML4].

The draw:archive attribute is usable with the following element: <draw:applet> 10.4.7.

The draw:archive attribute has the data type string 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.114 draw:border

The `draw:border` attribute specifies a percentage value that is used to scale a border area which is filled by a solid color.

For linear, square, rectangle, radial and elliptical gradients the start color is used. For axial gradients, the end color is used.

The `draw:border` attribute is usable with the following elements: `<draw:gradient>` 16.40.1 and `<draw:opacity>` 16.40.7.

The `draw:border` attribute has the data type `percent` 18.3.23.

19.115 draw:caption-id

The `draw:caption-id` attribute establishes a relationship between a drawing shape and its caption. It takes a value of type IDREF. The value for the `draw:caption-id` attribute is the target ID assigned to the `<draw:text-box>` element (see 10.4.3) that contains the caption.

Note: When a caption is assigned to a drawing shape, an id shall be assigned to the element containing the text used to caption a drawing shape. Removing the caption should result in removing the `draw:caption-id` attribute of the drawing shape that was being captioned.

The `draw:caption-id` attribute is usable with the following elements: `<dr3d:scene>` 10.5.2, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:connector>` 10.3.10, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:g>` 10.3.15, `<draw:line>` 10.3.3, `<draw:measure>` 10.3.12, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2 and `<draw:regular-polygon>` 10.3.6.

The `draw:caption-id` attribute has the data type `IDREF` 18.2.

19.116 draw:caption-point-x

The `draw:caption-point-x` attribute, along with the `draw:caption-point-y` specifies the position of a point that is captioned. A set of lines are rendered to that point from the caption area.

The `draw:caption-point-x` attribute is usable with the following elements: `<draw:caption>` 10.3.11 and `<office:annotation>` 14.1.

The `draw:caption-point-x` attribute has the data type `coordinate` 18.3.10.

19.117 draw:caption-point-y

The `draw:caption-point-y` attribute, along with the `draw:caption-point-x` specifies the position of a point that is captioned. A set of lines are rendered to that point from the caption area.

The `draw:caption-point-y` attribute is usable with the following elements: `<draw:caption>` 10.3.11 and `<office:annotation>` 14.1.

The `draw:caption-point-y` attribute has the data type `coordinate` 18.3.10.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.118 draw:chain-next-name

The `draw:chain-next-name` attribute specifies a name that is used to chain text boxes together for cases where the content of a text box exceeds its capacity. The content flows into the next text box in the chain. The value of this attribute is the name of the next text box in the chain.

The `draw:chain-next-name` attribute is usable with the following element: `<draw:text-box>` 10.4.3.

The `draw:chain-next-name` attribute has the data type `string` 18.2.

19.119 draw:class-id

The `draw:class-id` attribute specifies the OLE class id of an object.

The `draw:class-id` attribute is usable with the following element: `<draw:object-ole>` 10.4.6.3.

The `draw:class-id` attribute has the data type `string` 18.2.

19.120 draw:class-names

The `draw:class-names` attribute specifies a white space separated list of styles with the family value of graphic. The referenced styles are applied in the order they are contained in the list.

If both `draw:style-name` and `draw:class-names` are present, the style referenced by the `draw:style-name` attribute is applied before the styles referenced by the `draw:class-names` attribute.

The `draw:class-names` attribute is usable with the following elements: `<dr3d:cube>` 10.5.4, `<dr3d:extrude>` 10.5.6, `<dr3d:rotate>` 10.5.7, `<dr3d:scene>` 10.5.2, `<dr3d:sphere>` 10.5.5, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:connector>` 10.3.10, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:g>` 10.3.15, `<draw:line>` 10.3.3, `<draw:measure>` 10.3.12, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2, `<draw:regular-polygon>` 10.3.6 and `<office:annotation>` 14.1.

The `draw:class-names` attribute has the data type `styleNameRefs` 18.3.33.

19.121 draw:code

The `draw:code` attribute is equivalent to the code attribute of an `<applet>` element in HTML. See. §13.4 of [HTML4].

The `draw:code` attribute is usable with the following element: `<draw:applet>` 10.4.7.

The `draw:code` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.122 draw:color

19.122.1 General

The `draw:color` attribute specifies different colors depending upon the element where it appears.

19.122.2 <draw:hatch>

The `draw:color` attribute specifies the color of hatch lines.

The `draw:color` attribute is usable with the following element: `<draw:hatch>` 16.40.5.
The `draw:color` attribute has the data type `color` 18.3.9.

19.122.3 <presentation:dim>

The `draw:color` attribute specifies the color of that is used to fill a shape when the shape is dimmed.

The `draw:color` attribute is usable with the following element: `<presentation:dim>` 10.8.7.
The `draw:color` attribute has the data type `color` 18.3.9.

19.123 draw:concave

The `draw:concave` attribute specifies whether a regular polygon is convex or concave. For a concave regular polygon the `draw:sharpness` attribute shall be specified in addition to the `draw:concave` attribute.

The defined values for the `draw:concave` attribute are:

- `false`: polygon is convex.
- `true`: polygon is concave.

The `draw:concave` attribute is usable with the following element: `<draw:regular-polygon>` 10.3.6.
The values of the `draw:concave` attribute are `false` or `true`.

19.124 draw:concentric-gradient-fill-allowed

The `draw:concentric-gradient-fill-allowed` attribute specifies the rendering of a shape with a concentric gradient that uses a custom shape path.

The defined values for the `draw:concentric-gradient-fill-allowed` attribute are:

- `false`: the rendering of a shape with a concentric gradient that does not use a custom shape path.
- `true`: the rendering of a shape with a concentric gradient that does use a custom shape path.

The default value for this attribute is `false`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:concentric-gradient-fill-allowed attribute is usable with the following element: <draw:enhanced-geometry> 10.6.2.

The draw:concentric-gradient-fill-allowed attribute has the data type boolean 18.3.3.

19.125 draw:control

The draw:control attribute specifies a control within a form that is linked to the control shape by its ID.

The draw:control attribute is usable with the following element: <draw:control> 10.3.13.

The draw:control attribute has the data type IDREF 18.2.

19.126 draw:copy-of

The draw:copy-of attribute specifies that a frame displays the contents of another frame. This does not effect style and position information. The style and position information of the frame with the draw:copy-of attribute is used to render the copied contents.

Note: Multiple frames can be set to display the exact same underlying data: for instance for a company logo, that shall appear somewhere on every page, without being part of a header or footer.

The draw:copy-of attribute is usable with the following element: <draw:frame> 10.4.2.

The draw:copy-of attribute has the data type string 18.2.

19.127 draw:corner-radius

The draw:corner-radius attribute specifies the radius of the circle used to round off the corners of a caption <draw:caption>, rectangle <draw:rect>, or a text-box <draw:text-box>.

The svg:rx and svg:ry attributes can also be used to round off the corners of a rectangle <draw:rect>.

If svg:rx and/or svg:ry and draw:corner-radius attributes are present on an element, the svg:rx and svg:ry attributes control the rounding applied to the shape defined by the element. If one or both of svg:rx and svg:ry attributes are present, any draw:corner-radius attribute is ignored.

The draw:corner-radius attribute is usable with the following elements: <draw:caption> 10.3.11, <draw:rect> 10.3.2, <draw:text-box> 10.4.3 and <office:annotation> 14.1.

The draw:corner-radius attribute has the data type nonNegativeLength 18.3.20.

19.128 draw:corners

The draw:corners attribute specifies the number of polygon corners on a polygon shape.

The draw:corners attribute is usable with the following element: <draw:regular-polygon> 10.3.6.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:corners attribute has the data type positiveInteger 18.2.

19.129 draw:cx

The draw:cx attribute, along with the draw:cy attribute, specifies the center of the geometry that is used for a gradient, if the gradient style is ellipsoid, radial, rectangular, or square.

The draw:cx attribute is usable with the following elements: <draw:gradient> 16.40.1 and <draw:opacity> 16.40.7.

The draw:cx attribute has the data type percent 18.3.23.

19.130 draw:cy

The draw:cy attribute, along with the draw:cx attribute, specifies the center of the geometry that is used for a gradient, if the gradient style is ellipsoid, radial, rectangular, or square.

The draw:cy attribute is usable with the following elements: <draw:gradient> 16.40.1 and <draw:opacity> 16.40.7.

The draw:cy attribute has the data type percent 18.3.23.

19.131 draw:data

The draw:data attribute specifies rendering engine specific data for a custom shape. This attribute is only evaluated if a rendering engine is specified by the draw:engine attribute.

The draw:data attribute is usable with the following element: <draw:custom-shape> 10.6.1.

The draw:data attribute has the data type string 18.2.

19.132 draw:display

The draw:display attribute specifies the visibility of drawing objects contained in a layer for display or printing.

The defined values for the draw:display attribute are:

- always: drawing objects are visible on screen and in printed output.
- none: drawing objects are not visible on screen or in printed output.
- printer: drawing objects are visible in printed output but not on screen.
- screen: drawing objects are visible on screen but not in printed output.

The default value for this attribute is always.

The draw:display attribute is usable with the following element: <draw:layer> 10.2.3.

The values of the draw:display attribute are always, screen, printer or none.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.133 draw:display-name

19.133.1 General

The `draw:display-name` attribute specifies a name as it should appear in the user interface. If this attribute is not present, the display name is the same as the internal name.

19.133.2 <draw:fill-image>

The `draw:display-name` attribute specifies the name of a fill image.

The `draw:display-name` attribute is usable with the following element: `<draw:fill-image>` 16.40.6.

The `draw:display-name` attribute has the data type `string` 18.2.

19.133.3 <draw:gradient>

The `draw:display-name` attribute specifies the name of a gradient.

The `draw:display-name` attribute is usable with the following element: `<draw:gradient>` 16.40.1.

The `draw:display-name` attribute has the data type `string` 18.2.

19.133.4 <draw:hatch>

The `draw:display-name` attribute specifies the name of a hatch style.

The `draw:display-name` attribute is usable with the following element: `<draw:hatch>` 16.40.5.

The `draw:display-name` attribute has the data type `string` 18.2.

19.133.5 <draw:marker>

The `draw:display-name` attribute specifies the name of a marker.

The `draw:display-name` attribute is usable with the following element: `<draw:marker>` 16.40.8.

The `draw:display-name` attribute has the data type `string` 18.2.

19.133.6 <draw:opacity>

The `draw:display-name` attribute specifies the name of an opacity gradient.

The `draw:display-name` attribute is usable with the following element: `<draw:opacity>` 16.40.7.

The `draw:display-name` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.133.7 <draw:stroke-dash>

The `draw:display-name` attribute specifies the name of a dash style.

The `draw:display-name` attribute is usable with the following element: `<draw:stroke-dash>` 16.40.9.

The `draw:display-name` attribute has the data type `string` 18.2.

19.133.8 <svg:linearGradient>

The `draw:display-name` attribute specifies the name of a gradient.

The `draw:display-name` attribute is usable with the following element: `<svg:linearGradient>` 16.40.2.

The `draw:display-name` attribute has the data type `string` 18.2.

19.133.9 <svg:radialGradient>

The `draw:display-name` attribute specifies the name of a gradient.

The `draw:display-name` attribute is usable with the following element: `<svg:radialGradient>` 16.40.3.

The `draw:display-name` attribute has the data type `string` 18.2.

19.134 draw:distance

19.134.1 General

The `draw:distance` attribute specifies distances.

19.134.2 <draw:hatch>

The `draw:distance` attribute specifies the distance between two hatch lines.

The `draw:distance` attribute is usable with the following element: `<draw:hatch>` 16.40.5.

The `draw:distance` attribute has the data type `length` 18.3.18.

19.134.3 <draw:stroke-dash>

The `draw:distance` attribute specifies the distance between the dashes of a stroke.

The value of the attribute may be an absolute length or a percentage value. Percentage values are relative to the width of the stroke as defined by the `svg:stroke-width` attribute. 20.400

The `draw:distance` attribute is usable with the following element: `<draw:stroke-dash>` 16.40.9.

The values of the `draw:distance` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.135 draw:dots1

The `draw:dots1` attribute specifies the number of dashes for the first sequence in an alternating sequence of dots.

The `draw:dots1` attribute is usable with the following element: `<draw:stroke-dash>` 16.40.9.

The `draw:dots1` attribute has the data type `integer` 18.2.

19.136 draw:dots1-length

The `draw:dots1-length` attributes specifies the length of the dashes in the sequence specified by `draw:dots1`.

The value of the attribute may be an absolute length or a percentage value. Percentage values are relative to the width of the stroke as defined by the `svg:stroke-width` attribute. 20.400

The `draw:dots1-length` attribute is usable with the following element: `<draw:stroke-dash>` 16.40.9.

The values of the `draw:dots1-length` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

19.137 draw:dots2

The `draw:dots2` attribute specifies the number of dashes for the second sequence in an alternating sequence of dots.

The `draw:dots2` attribute is usable with the following element: `<draw:stroke-dash>` 16.40.9.

The `draw:dots2` attribute has the data type `integer` 18.2.

19.138 draw:dots2-length

The `draw:dots2-length` attributes specifies the length of the dashes in the sequence specified by `draw:dots2`.

The value of the attribute may be an absolute length or a percentage value. Percentage values relative to the width of the stroke as defined by the `svg:stroke-width` attribute. 20.400

The `draw:dots2-length` attribute is usable with the following element: `<draw:stroke-dash>` 16.40.9.

The values of the `draw:dots2-length` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

19.139 draw:end

The `draw:end` attributes specifies the end value for the `<draw:opacity>` element, which interpolates between the value of this attribute and `draw:start`. The defined value range for the `draw:end` attribute is 0% to 100%, where 0% is transparent and 100% is opaque.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:end attribute is usable with the following element: <draw:opacity> 16.40.7.

The draw:end attribute has the data type zeroToHundredPercent 18.3.41.

19.140 draw:end-angle

The draw:end-angle attribute specifies the end angle of a arc, cut, or section for circles where the draw:kind attribute value is arc, cut, or section.

The draw:end-angle attribute is usable with the following elements: <draw:circle> 10.3.8 and <draw:ellipse> 10.3.9.

The draw:end-angle attribute has the data type angle 18.3.1.

19.141 draw:end-color

The draw:end-color attribute specifies the end value for the <draw:gradient> element, which interpolates between the value of this attribute and draw:start-color.

The draw:end-color attribute is usable with the following element: <draw:gradient> 16.40.1.

The draw:end-color attribute has the data type color 18.3.9.

19.142 draw:end-glue-point

The draw:end-glue-point attribute identifies the glue point in a shape where a connector ends by its number. See 10.3.16. Glue point numbers are defined by the draw:id attributes of the glue point elements <draw:glue-point>. See 19.187.

If the connector is not connected to a shape, this attribute is ignored.

The draw:end-glue-point attribute is usable with the following element: <draw:connector> 10.3.10.

The draw:end-glue-point attribute has the data type nonNegativeInteger 18.2.

19.143 draw:end-intensity

The draw:end-intensity attribute specifies the intensity of the gradient's end color as a percentage value. If it is not specified, the color is used at 100% intensity. The defined value range for the draw:end-intensity attribute is 0% to 100%,

The draw:end-intensity attribute is usable with the following element: <draw:gradient> 16.40.1.

The draw:end-intensity attribute has the data type zeroToHundredPercent 18.3.41.

19.144 draw:end-shape

The draw:end-shape attribute specifies a drawing shape to which the end of a connector is connected by its ID.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:end-shape attribute is usable with the following element: <draw:connector> 10.3.10.

The draw:end-shape attribute has the data type IDREF 18.2.

19.145 draw:enhanced-path

The draw:enhanced-path attribute specifies a path that is the outline of a shape.

The syntax of a value for a draw:enhanced-path attribute is defined as:

- Commands are expressed as one character.
- Commands are followed by parameters.
- Commands and parameters are delimited by white space characters. Parameters may also be delimited by comma “,” (U+002C, COMMA) characters.
- White space and commas may be eliminated if they are not necessary to identify individual commands or parameters.
- If a command is repeated multiple times, all repeated command characters except the first one may be omitted.
- The decimal delimiter is the ”.” (U+002E, FULL STOP) character.

A parameter in the value of a draw:enhanced-path attribute may be:

- An integer value.
- An integer value preceded by a “$” (U+0024, DOLLAR SIGN) character. Such a value is an index to a draw:modifiers attribute on the element where the draw:enhanced-path attribute appears. The corresponding modifier value is used as a parameter value.
- A floating point value.
- A formula name, preceded by a “?” (U+003F, QUESTION MARK) character. The result of the value of the draw:formula attribute of the <draw:equation> child element of the <draw:enhanced-geometry> element on which the draw:enhanced-path attribute appears is used as the parameter value.

The syntax used in Table 10 for parameters is:

- (): grouping of parameters.
- +: 1 or more of the given parameter(s) shall be present.

The following commands are defined:

Table 10 - Enhanced path commands

Command	***Name***	***Parameters***	***Description***
A	arcto	(x1 y1 x2 y2 x3 y3 x y) +	(x1, y1) and (x2, y2) is defining the bounding box of a ellipse. A line is then drawn from the current point to the start angle of the arc that is specified by the radial vector of point (x3, y3) and then counter clockwise to the end-angle that is specified by point (x4, y4).

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Command	*Name*	*Parameters*	*Description*
B	arc	(x1 y1 x2 y2 x3 y3 x y) +	The same as the “A” command, except that a implied moveto to the starting point is done.
C	curveto	(x1 y1 x2 y2 x y) +	Draws a cubic Bézier curve from the current point to (x,y) using (x1,y1) as the control point at the beginning of the curve and (x2,y2) as the control point at the end of the curve.
F	nofill	(none)	Specifies that the current set of sub-paths will not be filled.
L	lineto	(x y) +	Draws a line from the current point to (x, y). If followed by multiple coordinate pairs, they are all interpreted as lineto.
M	moveto	(x y) +	Start a new sub-path at the given (x,y) coordinate. If a moveto is followed by multiple pairs of coordinates, they are treated as lineto.
N	endpath	(none)	Ends the current set of sub-paths. The sub-paths will be filled by using the “even-odd” filling rule. Other following subpaths will be filled independently.
Q	quadratic-curveto	(x1 y1 x y)+	Draws a quadratic Bézier curve from the current point to (x, y) using (x1, y1) as the control point. (x, y) becomes the new current point at the end of the command.
S	nostroke	(none)	Specifies that the current set of sub-paths will not be stroked.
T	angle-ellipseto	(x y w h t0 t1) +	Draws a segment of an ellipse. The ellipse is specified by the center(x, y), the size(w, h) and the start-angle t0 in degrees and end-angle t1 in degrees.
U	angle-ellipse	(x y w h t0 t1) +	The same as the “T” command, except that a implied moveto to the starting point is done.
V	clockwisearc	(x1 y1 x2 y2 x3 y3 x y)+	The same as the “A” command, except that a implied moveto to the starting point is done and the arc is drawn clockwise.
W	clockwisearcto	(x1 y1 x2 y2 x3 y3 x y) +	The same as the “A” command except, that the arc is drawn clockwise.
X	elliptical-quatrantx	(x y) +	Draws a quarter ellipse, whose initial segment is tangential to the x-axis from the current point to (x, y). For each additional quarter ellipse command, the axis to which the segment is tangential to switches from x to y and from y to x.
Y	elliptical-quadranty	(x y) +	Draws a quarter ellipse, whose initial segment is tangential to the y-axis from the current

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Command	Name	Parameters	Description
			point to (x, y). For each additional quarter ellipse command, the axis to which the segment is tangential to switches from y to x and from x to y
Z	closepath	(none)	Close the current sub-path by drawing a straight line from the current point to current sub-path's initial point.

Note: The value of the `draw:enhanced-path` attribute is based upon [SVG] §8.3.

The `draw:enhanced-path` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:enhanced-path` attribute has the data type `string` 18.2.

19.146 draw:engine

The `draw:engine` attribute specifies the name of a specific rendering engine that can be used to render a custom shape.

The value of the `draw:engine` attribute shall not influence the geometry of a shape.

The `draw:engine` attribute is usable with the following element: `<draw:custom-shape>` 10.6.1.

The `draw:engine` attribute has the data type `namespacedToken` 18.3.19.

19.147 draw:escape-direction

The `draw:escape-direction` attribute specifies the direction in which a connection line leaves a drawing object if a connector connects to a glue point.

The defined values for the `draw:escape-direction` attribute are:

- `auto`: the connection line may leave in all four directions from a drawing object.
- `down`: the connection line leave down from a drawing object.
- `horizontal`: the connection line may leave to the left or to the right of a drawing object.
- `left`: the connection line leaves to the left of a drawing object.
- `right`: the connection line leaves to the right of a drawing object.
- `up`: the connection line leaves up from a drawing object.
- `vertical`: the connection line may leave up or down from a drawing object.

The `draw:escape-direction` attribute is usable with the following element: `<draw:glue-point>` 10.3.16.

The values of the `draw:escape-direction` attribute are `auto`, `left`, `right`, `up`, `down`, `horizontal` or `vertical`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.148 draw:extrusion

The `draw:extrusion` attribute specifies if an extrusion is displayed.

The defined values for the `draw:extrusion` attribute are:

- `false`: extrusion is not displayed.
- `true`: extrusion is displayed.

The default value for this attribute is `false`.

The `draw:extrusion` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion` attribute has the data type `boolean` 18.3.3.

19.149 draw:extrusion-allowed

The `draw:extrusion-allowed` attribute specifies whether a shape can be rendered as extrusion object.

The defined values for the `draw:extrusion-allowed` attribute are:

- `false`: shape is cannot be rendered as an extrusion object.
- `true`: shape can be rendered as an extrusion object.

The default value for this attribute is `false`.

The `draw:extrusion-allowed` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-allowed` attribute has the data type `boolean` 18.3.3.

19.150 draw:extrusion-brightness

The `draw:extrusion-brightness` attribute specifies the brightness of a scene.

The default value for this attribute is `33%`.

The `draw:extrusion-brightness` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-brightness` attribute has the data type `zeroToHundredPercent` 18.3.41.

19.151 draw:extrusion-color

The `draw:extrusion-color` attribute specifies if an extrusion color is used. The extrusion color is defined by the `draw:secondary-fill-color` attribute specified in a custom shape's graphic style.

The defined values for the `draw:extrusion-color` attribute are:

- `false`: extrusion color is not used.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: extrusion color is used.

The default value for this attribute is `false`.

The `draw:extrusion-color` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-color` attribute has the data type `boolean` 18.3.3.

19.152 draw:extrusion-depth

The `draw:extrusion-depth` attribute specifies the depth of an extrusion. It takes two white space separated values. The first value specifies the depth of the extrusion in units, the second value specifies the fraction of the extrusion that lies before a shape. The second value shall be in the range [0,1]. A value of 0 is the default.

The default value for this attribute is `36pt 0`.

The `draw:extrusion-depth` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-depth` attribute has two white space separated values. The first value is of type `length` 18.3.18. The second value is of type `double` 18.2.

19.153 draw:extrusion-diffusion

The `draw:extrusion-diffusion` attribute specifies the amount of diffusion reflected by a shape.

The default value for this attribute is `0%`.

The `draw:extrusion-diffusion` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-diffusion` attribute has the data type `percent` 18.3.23.

19.154 draw:extrusion-first-light-direction

The `draw:extrusion-first-light-direction` attribute specifies the direction of the first light.

The default value for this attribute is `(5 0 1)`.

The `draw:extrusion-first-light-direction` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-first-light-direction` attribute has the data type `vector3D` 18.3.40.

19.155 draw:extrusion-first-light-harsh

The `draw:extrusion-first-light-harsh` attribute specifies if the first light is harsh.

The defined values for the `draw:extrusion-first-light-harsh` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `false`: the light is not harsh. The means by which the light is softened is implementation-defined.
- `true`: the light is harsh. The light is an undiffused point source.

The default value for this attribute is `true`.

The `draw:extrusion-first-light-harsh` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-first-light-harsh` attribute has the data type `boolean` 18.3.3.

19.156 draw:extrusion-first-light-level

The `draw:extrusion-first-light-level` attribute specifies the intensity of the first light.

The default value for this attribute is `66%`.

The `draw:extrusion-first-light-level` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-first-light-level` attribute has the data type `zeroToHundredPercent` 18.3.41.

19.157 draw:extrusion-light-face

The `draw:extrusion-light-face` attribute specifies if the front face of an extrusion responds to lighting changes.

The defined values for the `draw:extrusion-light-face` attribute are:

- `false`: front face of extrusion does not respond to lighting changes.
- `true`: front face of extrusion responds to lighting changes.

The default value for this attribute is `true`.

The `draw:extrusion-light-face` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-light-face` attribute has the data type `boolean` 18.3.3.

19.158 draw:extrusion-metal

The `draw:extrusion-metal` attribute specifies the shading of an extruded shape.

The defined values for the `draw:extrusion-metal` attribute are:

- `false`: the specular color for the shading of an extruded shape is white.
- `true`: the specular color for the shading of an extruded shape is gray (red green and blue value of 200) instead of white and 15% is added to the specularity.

The default value for this attribute is `false`.

The `draw:extrusion-metal` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:extrusion-metal attribute has the data type boolean 18.3.3.

19.159 draw:extrusion-number-of-line-segments

The draw:extrusion-number-of-line-segments attribute specifies the number of line segments that should be used to display curved surfaces.

The default value for this attribute is 30.

The draw:extrusion-number-of-line-segments attribute is usable with the following element: <draw:enhanced-geometry> 10.6.2.

The draw:extrusion-number-of-line-segments attribute has the data type integer 18.2.

19.160 draw:extrusion-origin

The draw:extrusion-origin attribute specifies the point of origin of a shape within its bounding box in shape size fractions. The value of the draw:extrusion-origin attribute consists of two parameters separated by white space.

The first parameter represents the horizontal origin of a shape.

The defined values for the first parameter of the draw:extrusion-origin attribute are:

- -0.5: represents the left side of the shape.
- 0: represents the center of the shape.
- 0.5: represents the right side of the shape.

The second parameter represents the vertical origin of a shape.

The defined values for the second parameter of the draw:extrusion-origin attribute are:

- -0.5: represents the top side of the shape.
- 0: represents the center of the shape.
- 0.5: represents the bottom side of the shape.

The default value for this attribute is 0.5 -0.5.

The draw:extrusion-origin attribute is usable with the following element: <draw:enhanced-geometry> 10.6.2.

The draw:extrusion-origin attribute has two white space separated values. The first value is a value of type double 18.2 in the range [-0.5,0.5]. The second value is a value of type double 18.2 in the range [-0.5,0.5].

19.161 draw:extrusion-rotation-angle

The draw:extrusion-rotation-angle attribute specifies rotation about an x-axis and y-axis. The values are separated by a white space. The first angle specifies rotation on the x-axis and the second angle specifies rotation on the y-axis. z-axis is specified by the draw:transform attribute on the <draw:custom-shape> element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The order of the rotation is: z-axis, y-axis and then x-axis.

The default value for this attribute is `0 0`.

The `draw:extrusion-rotation-angle` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-rotation-angle` attribute has two white space separated values. The first value is of type `angle` 18.3.1. The second value is of type `angle` 18.3.1.

19.162 draw:extrusion-rotation-center

The `draw:extrusion-rotation-center` attribute specifies the position of a rotation center in shape size fractions. If the `draw:extrusion-rotation-center` attribute is omitted, the geometric center of the shape is used as the rotation center.

The `draw:extrusion-rotation-center` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-rotation-center` attribute has the data type `vector3D` 18.3.40.

19.163 draw:extrusion-second-light-direction

The `draw:extrusion-second-light-direction` attribute specifies the direction of a second light.

The default value for this attribute is `(-5 0 1)`.

The `draw:extrusion-second-light-direction` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-second-light-direction` attribute has the data type `vector3D` 18.3.40.

19.164 draw:extrusion-second-light-harsh

The `draw:extrusion-second-light-harsh` attribute specifies if a second light is harsh.

The defined values for the `draw:extrusion-second-light-harsh` attribute are:

- `false`: the light is not harsh. The means by which the light is softened is implementation-defined.
- `true`: the light is harsh. The light is an undiffused point source.

The default value for this attribute is `true`.

The `draw:extrusion-second-light-harsh` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-second-light-harsh` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.165 draw:extrusion-second-light-level

The `draw:extrusion-second-light-level` attribute specifies the intensity of a second light.

The default value for this attribute is `66%`.

The `draw:extrusion-second-light-level` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-second-light-level` attribute has the data type `zeroToHundredPercent` 18.3.41.

19.166 draw:extrusion-shininess

The `draw:extrusion-shininess` attribute specifies the reflectivity of a mirror.

The default value for this attribute is `50%`.

The `draw:extrusion-shininess` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-shininess` attribute has the data type `zeroToHundredPercent` 18.3.41.

19.167 draw:extrusion-skew

The `draw:extrusion-skew` attribute specifies the skew amount and skew angle of an extrusion. Skew settings are only applied if the `dr3d:projection` attribute on the same element has the value `parallel`.

The attribute value is a white space separated number and angle. The first value defines the skew amount in percent, the second value defines the skew angle.

The default value for this attribute is `50 45`.

The `draw:extrusion-skew` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-skew` attribute has two white space separated values. The first value is of type `double` 18.2. The second value is of type `angle` 18.3.1.

19.168 draw:extrusion-specularity

The `draw:extrusion-specularity` attribute specifies the specularity of an extrusion object.

The default value for this attribute is `0%`.

The `draw:extrusion-specularity` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-specularity` attribute has the data type `zeroToHundredPercent` 18.3.41.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.169 draw:extrusion-viewpoint

The `draw:extrusion-viewpoint` attribute specifies the viewpoint of an observer as an 3D point.

The default value for this attribute is `3.5cm -3.5cm 25cm`.

The `draw:extrusion-viewpoint` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:extrusion-viewpoint` attribute has the data type `point3D` 18.3.24.

19.170 draw:filter-name

The `draw:filter-name` attribute specifies the implementation-dependent filter name that has been used to load an image into the document.

The `draw:filter-name` attribute is usable with the following element: `<draw:image>` 10.4.4.

The `draw:filter-name` attribute has the data type `string` 18.2.

19.171 draw:formula

The `draw:formula` attribute specifies an equation that should be used to evaluate a value. A formula can make use of other formulas or modifier values by function and or modifier reference.

The value of a `draw:formula` attribute can have one of the following parameters:

- A "?" (U+003F, QUESTION MARK) is used to mark the beginning of a formula name. The result of the `<draw:equation>` element's `draw:formula` attribute whose `draw:name` attribute is the formula name used as the value.
- If ”$” (U+0024) precedes a integer value, the value is an index to a `draw:modifiers` attribute. The corresponding modifier value is used as value.

```
formula::=additive_expression

identifier::= 'pi' | 'left' | 'top' | 'right' | 'bottom' | 'xstretch'
    | 'ystretch' | 'hasstroke' | 'hasfill' | 'width' | 'height' | 'logwidth'
    | 'logheight'
unary_function::= 'abs' | 'sqrt' | 'sin' | 'cos' | 'tan' | 'atan'
binary_function::= 'min' | 'max' | 'atan2'
ternary_function::= 'if'
basic_expression::= number
    | identifier
    | function_reference
    | modifier_reference
    | unary_function S* '(' S* additive_expression S* ')'
    | binary_function S* '(' S* additive_expression S* ',' S*
        additive_expression S* ')'
    | ternary_function S* '(' S* additive_expression S* ',' S*
        additive_expression S* ',' S* additive_expression S* ')'
    | '(' S* additive_expression S* ')'
unary_expression::= '-' S* basic_expression | basic_expression
multiplicative_expression::= unary_expression  ( ( S* '*' S* unary_expression )
    | ( S* '/' S* unary_expression ) )*
additive_expression::= multiplicative_expression
    ( ( S* '+' S* multiplicative_expression )
```


Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

```
    | ( S* '-' S* multiplicative_expression ) )*
number::= sign? Integer | sign? Floating-point-constant
function_reference::= "?" name
modifier_reference::= "$" integer
floating-point-constant::= fractional-constant exponent? | integer exponent
fractional-constant::= integer? '.' integer | integer '.'
exponent::= ( 'e' | 'E' ) sign? Integer
sign::= '+' | '-'
name::= [^#x20#x9]+
integer::= [0-9]+
S::= (#x20 | #x9)
```

Table 11 - Enhanced geometry equation identifiers

Identifier	***Description***
bottom	The bottom position the `svg:viewBox` attribute is used.
hasfill	If the shape has a fill style, a value of 1 is used.If the shape has a fill style, a value of 1 is used. If the shape has no fill style, a value of 0 is used.
hasstroke	If the shape has a line style, a value of 1 is used. If the shape has a line style, a value of 1 is used. If the shape has no line style, a value of 0 is used.
height	The height of the `svg:viewBox` attribute is used.
left	The left position of the `svg:viewBox` attribute is used.
logheight	The height of the `svg:viewBox` attribute in 1/100th mm is used.
logwidth	The width of the `svg:viewBox` attribute in 1/100th mm is used.
right	The right position the `svg:viewBox` attribute is used.
top	The top position the `svg:viewBox` attribute is used.
width	The width of the `svg:viewBox` attribute is used.
xstretch	The value of the `draw:path-stretchpoint-x` attribute is used.
ystretch	The value of the `draw:path-stretchpoint-y` attribute is used.

Table 12 - Functions Used in `draw:formula`

Function	***Description***
abs(n)	returns the absolute value of n
sqrt(n)	returns the positive square root of n
sin(n)	returns the trigonometric sine of n, where n is an angle specified in degrees
cos(n)	returns the trigonometric cosine of n, where n is an angle

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

	specified in degrees
tan(n)	returns the trigonometric tangent of n, where n is an angle specified in degrees
atan(n)	returns the arc tangent of n in degrees
min(x,y)	returns the smaller of two values
max(x,y)	returns the greater of two values
atan2(x,y)	returns the angle in degrees of the vector (x,y) with the x-axis
if(c,x,y)	conditional testing: if c is greater than zero then the result of evaluating x is returned, otherwise the result of evaluating y is returned.

The `draw:formula` attribute is usable with the following element: `<draw:equation>` 10.2.5.

The `draw:formula` attribute has the data type `string` 18.2.

19.172 draw:frame-name

The `draw:frame-name` attribute specifies the name of a frame. The name of a frame can be used as a target by hyperlinks.

The `draw:frame-name` attribute is usable with the following element: `<draw:floating-frame>` 10.4.10.

The `draw:frame-name` attribute has the data type `string` 18.2.

19.173 draw:glue-point-leaving-directions

The `draw:glue-point-leaving-directions` attribute specifies a comma “,” (U+002C, COMMA) separated list of angles. The angles are listed in the same order as the glue-points specified in the `draw:glue-points` attribute. 19.175

The `draw:glue-point-leaving-directions` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:glue-point-leaving-directions` attribute has the data type `string` 18.2.

19.174 draw:glue-point-type

The `draw:glue-point-type` attribute specifies a glue-point type. If the `draw:glue-points` attribute has a value, this attribute is ignored.

The defined values for the `draw:glue-point-type` attribute are:

- `none`: there are no glue points, including default glue points.
- `rectangle`: the middle of each side of the shape bound rectangle specifies a object specific glue point
- `segments`: a connector will connect with each point of the `draw:enhanced-path` attribute.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The default value for this attribute is `none`.

The `draw:glue-point-type` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The values of the `draw:glue-point-type` attribute are `none`, `segments` or `rectangle`.

19.175 draw:glue-points

The `draw:glue-points` attribute specifies a list of object defined glue points. Unlike the user defined glue points which are defined by the `<draw:glue-point>` sub-element, the position of an object defined glue point can be defined using equations and modifiers.

The first parameter specifies the horizontal position of the glue point.

The second parameter specifies the vertical position of the glue point.

Each parameter can be a float, or it can also have one of the following enhancements:

- A “?” (U+003F, QUESTION MARK) is used to mark the beginning of a formula name. The result of the `<draw:equation>` element's `draw:formula` attribute whose `draw:name` attribute is the formula name that is used as the value.
- If “$” (U+0024, DOLLAR SIGN) precedes a integer value, the value is an index to a `draw:modifiers` attribute. The corresponding modifier value is used as parameter value.

The value of a `draw:glue-points` attribute is formally defined as:

```
gluepoints::= gluepointsequence?
gluepointsequence::= gluepoint ( ' '+ gluepointsequence )*
glue-point::= position ' '+ position
position::= formula | modifier | number
formula::= '?' name
modifier::= '$' integer
number::= sign? float | sign? integer
float::= fractional exponent? | integer exponent
fractional::= integer? '.' integer | integer '.'
exponent::= ( 'e' | 'E' ) sign? integer
sign::= '+'| '-'
integer::= [0-9]+
name ::= [^ ]+
```

The `draw:glue-points` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:glue-points` attribute has the data type `string` 18.2.

19.176 draw:handle-mirror-horizontal

The `draw:handle-mirror-horizontal` attribute specifies if the y position of a handle is mirrored.

The defined values for the `draw:handle-mirror-horizontal` attribute are:

- `false`: the y position of a handle is not mirrored.
- `true`: the y position of a handle is mirrored.

The default value for this attribute is `false`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:handle-mirror-horizontal attribute is usable with the following element: <draw:handle> 10.6.3.

The draw:handle-mirror-horizontal attribute has the data type boolean 18.3.3.

19.177 draw:handle-mirror-vertical

The draw:handle-mirror-vertical attribute specifies if the x position of a handle is mirrored.

The defined values for the draw:handle-mirror-vertical attribute are:

- false: the x position of a handle is not mirrored.
- true: the x position of a handle is mirrored.

The default value for this attribute is false.

The draw:handle-mirror-vertical attribute is usable with the following element: <draw:handle> 10.6.3.

The draw:handle-mirror-vertical attribute has the data type boolean 18.3.3.

19.178 draw:handle-polar

The draw:handle-polar attribute specifies that a handle is a polar handle. The syntax for this attribute is the same as for the draw:handle-position attribute. The first parameter specifies the horizontal center position, the vertical center position is specified by the second parameter. If this attribute is set, the draw:handle-range-x-minimum, draw:handle-range-x-maximum, draw:handle-range-y-minimum and draw:handle-range-y-maximum attributes are ignored, and the draw:handle-radius-range-minimum and draw:handle-radius-range-maximum attributes are used.

The draw:handle-polar attribute is usable with the following element: <draw:handle> 10.6.3.

The draw:handle-polar attribute has the data type string 18.2.

19.179 draw:handle-position

The draw:handle-position attribute specifies the position of a handle and consists of two values.

Each value can be a float or it can have one of the following enhancements:

- A “?” (U+003F, QUESTION MARK) is used to mark the beginning of a formula name. The result of the <draw:equation> element's draw:formula attribute whose draw:name attribute is the formula name that is used as the value.
- If “$” (U+0024, DOLLAR SIGN) precedes a integer value, the value is an index to a draw:modifiers attribute. The corresponding modifier value is used as parameter value.
- Instead of a number a value can also be one of the following constants:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Table 13 - Handle position constants

Constant	***Description***
bottom	The bottom coordinate of the view box as specified by the `svg:viewBox` attribute is used.
hasfill	If the shape has a fill style, a value of 1 is used.
hasstroke	If the shape has a line style, a value of 1 is used.
height	The view box height as specified by the `svg:viewBox` attribute is used.
logheight	The view box height in 1/100th mm as specified by the `svg:viewBox` attribute is used.
logwidth	The view box width in 1/100th mm as specified by the `svg:viewBox` attribute is used.
left	The left coordinate of the view box as specified by the `svg:viewBox` attribute is used.
right	The right coordinate of the view box as specified by the `svg:viewBox` attribute is used.
top	The top coordinate of the view box as specified by the `svg:viewBox` attribute is used.
width	The view box width as specified by the `svg:viewBox` attribute is used.
xstretch	The value of the `draw:path-stretchpoint-x` attribute is used.
ystretch	The value of the `draw:path-stretchpoint-y` attribute is used.

If the `draw:handle-polar` attribute is not set, the first parameter of the `draw:handle-position` attribute specifies the horizontal handle position, the vertical handle position is described by the second parameter. If the `draw:handle-polar` attribute is set, then a handle is a polar handle and the first parameter of the `draw:handle-position` attribute specifies the angle (as defined in 18.3.1), the handle radius is specified by the second parameter.

The value of a `draw:handle-position` attribute is formally defined as:

```
handleposition ::= position ' '+ position
position::= formula | modifier | constant | number
formula::= '?' name
modifier::= '$' integer
constant::= 'left' | 'top' | 'right' | 'bottom' |
'xstretch' | 'ystretch' | 'hasstroke' | 'hasfill ' |
'width' | 'height' | 'logwidth' | 'logheight'
number::=sign? float | sign? integer
float::= fractional exponent? | integer exponent
fractional::= integer? '.' integer | integer '.'
exponent::= ( 'e' | 'E' ) sign? integer
sign::= '+'| '-'
integer::= [0-9]+
name ::= [^ ]+
```


Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:handle-position attribute is usable with the following element: <draw:handle> 10.6.3.

The draw:handle-position attribute has the data type string 18.2.

19.180 draw:handle-radius-range-maximum

The draw:handle-radius-range-maximum attribute specifies the maximum radius range for a polar handle. The syntax for the value of the draw:handle-radius-range-maximum attribute is the same as the draw:handle-position attribute, except that only the first parameter is used. 19.179

The draw:handle-radius-range-maximum attribute is usable with the following element: <draw:handle> 10.6.3.

The draw:handle-radius-range-maximum attribute has the data type string 18.2.

19.181 draw:handle-radius-range-minimum

The draw:handle-radius-range-minimum attribute specifies the minimum radius range for a polar handle. The syntax for the value of the draw:handle-radius-range-minimum attribute is the same as the draw:handle-position attribute, except that only the first parameter is used. 19.179

The draw:handle-radius-range-minimum attribute is usable with the following element: <draw:handle> 10.6.3.

The draw:handle-radius-range-minimum attribute has the data type string 18.2.

19.182 draw:handle-range-x-maximum

The draw:handle-range-x-maximum attribute specifies the horizontal maximum value of the range for movement of a handle. The syntax for the value of the draw:handle-range-x-maximum attribute is the same as the draw:handle-position attribute, except that only the first parameter is used. 19.179

The draw:handle-range-x-maximum attribute is usable with the following element: <draw:handle> 10.6.3.

The draw:handle-range-x-maximum attribute has the data type string 18.2.

19.183 draw:handle-range-x-minimum

The draw:handle-range-x-minimum attribute specifies the horizontal minimum value of the range of movement of a handle. The syntax for the value of the draw:handle-range-x-minimum attribute is the same as the draw:handle-position attribute, except that only the first parameter is used. 19.179

The draw:handle-range-x-minimum attribute is usable with the following element: <draw:handle> 10.6.3.

The draw:handle-range-x-minimum attribute has the data type string 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.184 draw:handle-range-y-maximum

The `draw:handle-range-y-maximum` attribute specifies the vertical maximum value of the range for movement of a handle. The syntax for the value of the `draw:handle-range-y-maximum` attribute is the same as the `draw:handle-position` attribute, except that only the first parameter is used. 19.179

The `draw:handle-range-y-maximum` attribute is usable with the following element: `<draw:handle>` 10.6.3.

The `draw:handle-range-y-maximum` attribute has the data type `string` 18.2.

19.185 draw:handle-range-y-minimum

The `draw:handle-range-y-minimum` attribute specifies the vertical minimum value of the range of movement of a handle. The syntax for the value of the `draw:handle-range-y-minimum` attribute is the same as the `draw:handle-position` attribute, except that only the first parameter is used. 19.179

The `draw:handle-range-y-minimum` attribute is usable with the following element: `<draw:handle>` 10.6.3.

The `draw:handle-range-y-minimum` attribute has the data type `string` 18.2.

19.186 draw:handle-switched

The `draw:handle-switched` attribute specifies if handle directions are swapped if shape height exceeds shape width.

The defined values for the `draw:handle-switched` attribute are:

- `false`: handle directions are not switched if a shape's height exceeds its width.
- `true`: handle directions are switched if a shape's height exceeds it width.

The default value for this attribute is `false`.

The `draw:handle-switched` attribute is usable with the following element: `<draw:handle>` 10.6.3.

The `draw:handle-switched` attribute has the data type `boolean` 18.3.3.

19.187 draw:id

19.187.1 General

The `draw:id` attribute specifies an identifier for an element.

19.187.2 <draw:glue-point>

The `draw:id` attribute specifies an identifier for a glue point. See 10.3.16. The ids 0 to 3 are reserved for the 4 standard glue points of drawing objects. The glue points are numbered clockwise, starting at the top left corner edge of the shape.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `draw:id` attribute is usable with the following element: `<draw:glue-point>` 10.3.16.

The `draw:id` attribute has the data type `nonNegativeInteger` 18.2.

19.187.3 <dr3d:cube>, <dr3d:extrude>, <dr3d:rotate>, <dr3d:scene>, <dr3d:sphere>, <draw:caption>, <draw:circle>, <draw:connector>, <draw:control>, <draw:custom-shape>, <draw:ellipse>, <draw:frame>, <draw:g>, <draw:line>, <draw:measure>, <draw:page>, <draw:page-thumbnail>, <draw:path>, <draw:polygon>, <draw:polyline>, <draw:rect>, <draw:regular-polygon> and <office:annotation>

The `draw:id` attribute specifies identifiers for draw elements other than `<draw:glue-point>`.

OpenDocument consumers shall ignore a `draw:id` attribute if it occurs on a draw element with an `xml:id` attribute value.

When consuming OpenDocument v1.0 and v1.1 documents, OpenDocument consumers should process `draw:id` attributes as they were `xml:id` attributes.

OpenDocument producers may write `draw:id` attributes for any draw element in addition to an `xml:id` attribute.

The value of a `draw:id` attribute shall equal the value of an `xml:id` attribute on the same element.

The `draw:id` attribute is deprecated in favor of `xml:id`. 19.914

The `draw:id` attribute is usable with the following elements: `<dr3d:cube>` 10.5.4, `<dr3d:extrude>` 10.5.6, `<dr3d:rotate>` 10.5.7, `<dr3d:scene>` 10.5.2, `<dr3d:sphere>` 10.5.5, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:connector>` 10.3.10, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:g>` 10.3.15, `<draw:line>` 10.3.3, `<draw:measure>` 10.3.12, `<draw:page>` 10.2.4, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2, `<draw:regular-polygon>` 10.3.6 and `<office:annotation>` 14.1.

The `draw:id` attribute has the data type `NCName` 18.2.

19.188 draw:kind

The `draw:kind` attribute specifies the appearance of a circle.

The defined values for the `draw:kind` attribute are:

- `arc`: specifies a circle or ellipse arc, like .
- `cut`: specifies a circle or ellipse with a cut, like .
- `full`: specifies a full circle or ellipse, like .
- `section`: specifies a section of a circle or ellipse, like .

The default value for this attribute is `full`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `draw:kind` attribute is usable with the following elements: `<draw:circle>` 10.3.8 and `<draw:ellipse>` 10.3.9.

The values of the `draw:kind` attribute are `full`, `section`, `cut` or `arc`.

19.189 draw:layer

The `draw:layer` attribute specifies the name of a layer in the layer-set of a document.

Note: The effect of this attribute is to assign a shape to a particular layer.

The `draw:layer` attribute is usable with the following elements: `<dr3d:cube>` 10.5.4, `<dr3d:extrude>` 10.5.6, `<dr3d:rotate>` 10.5.7, `<dr3d:scene>` 10.5.2, `<dr3d:sphere>` 10.5.5, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:connector>` 10.3.10, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:line>` 10.3.3, `<draw:measure>` 10.3.12, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2, `<draw:regular-polygon>` 10.3.6 and `<office:annotation>` 14.1.

The `draw:layer` attribute has the data type `string` 18.2.

19.190 draw:line-skew

The `draw:line-skew` attribute specifies a list of offsets for the placements of connector lines if the connector is of type `standard`. The offsets are relative to the default position of the connector, that is, the position the lines get if the `draw:line-skew` attribute is not present. The offsets are applied in the order from the connector's start to its end shape. The first offset is applied to the line that follows the line that is connected to the start shape. The last line to which an offset is applied is the line that precedes the line that is connected to the end shape.

For the application of the offsets the connector lines are interpreted as vectors from their start to the their end point. Positive values move a line to the right, while negative values move it to the left.

The `draw:line-skew` attribute is usable with the following element: `<draw:connector>` 10.3.10.

The values of the `draw:line-skew` attribute are one, two or three white space separated values of type `length` 18.3.18.

19.191 draw:mime-type

The `draw:mime-type` attribute specifies the MIME type of the media-type which a plugin processes. Valid values for this attribute are those defined in accordance with §3.7 of [RFC2616], or registered in accordance with [RFC4288].

Note: Additional information on MIME media types can be found at [MIMETYPES].

The `draw:mime-type` attribute is usable with the following element: `<draw:plugin>` 10.4.8.

The `draw:mime-type` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.192 draw:mirror-horizontal

The `draw:mirror-horizontal` attribute specifies if the horizontal geometry of a shape is to be mirrored.

The defined values for the `draw:mirror-horizontal` attribute are:

- `false`: horizontal geometry of a shape is not mirrored.
- `true`: horizontal geometry of a shape is mirrored.

The default value for this attribute is `false`.

The `draw:mirror-horizontal` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:mirror-horizontal` attribute has the data type `boolean` 18.3.3.

19.193 draw:mirror-vertical

The `draw:mirror-vertical` attribute specifies if the vertical geometry of a shape is to be mirrored.

The defined values for the `draw:mirror-vertical` attribute are:

- `false`: vertical geometry of a shape is not mirrored.
- `true`: vertical geometry of a shape is mirrored.

The default value for this attribute is `false`.

The `draw:mirror-vertical` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:mirror-vertical` attribute has the data type `boolean` 18.3.3.

19.194 draw:master-page-name

The `draw:master-page-name` attribute specifies the name of a master page assigned to a drawing page.

The `draw:master-page-name` attribute is usable with the following element: `<draw:page>` 10.2.4.

The `draw:master-page-name` attribute has the data type `styleNameRef` 18.3.32.

19.195 draw:may-script

The `draw:may-script` attribute specifies whether an applet can be modified by scripts.

The defined values for the `draw:may-script` attribute are:

- `false`: applet cannot be modified by scripts.
- `true`: applet can be modified by scripts.

The default value for this attribute is `false`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:may-script attribute is usable with the following element: <draw:applet> 10.4.7.

The draw:may-script attribute has the data type boolean 18.3.3.

19.196 draw:modifiers

The draw:modifiers attribute contains list of modifier values.

The value of a draw:modifiers attribute is formally defined as:

```
modifiers::= numbersequence?
numbersequence::= number ( ' '+ numbersequence )*
number::= sign? float | sign? integer
float::= fractional exponent? | integer exponent
fractional::= integer? '.' integer | integer '.'
exponent::= ( 'e' | 'E' ) sign? integer
sign::= '+'| '-'
integer::= [0-9]+
```

The draw:modifiers attribute is usable with the following element: <draw:enhanced-geometry> 10.6.2.

The draw:modifiers attribute has the data type string 18.2.

19.197 draw:name

19.197.1 General

The draw:name attribute specifies names that are used for referencing graphical elements.

19.197.2 <draw:caption>

The draw:name attribute specifies a name by which a <draw:caption> element can be referenced.

The draw:name attribute is usable with the following element: <draw:caption> 10.3.11.

The draw:name attribute has the data type string 18.2.

19.197.3 <draw:circle>

The draw:name attribute specifies a name by which a <draw:circle> element can be referenced.

The draw:name attribute is usable with the following element: <draw:circle> 10.3.8.

The draw:name attribute has the data type string 18.2.

19.197.4 <draw:connector>

The draw:name attribute specifies a name by which a <draw:connector> element can be referenced.

The draw:name attribute is usable with the following element: <draw:connector> 10.3.10.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:name attribute has the data type string 18.2.

19.197.5 <draw:control>

The draw:name attribute specifies a name by which a <draw:control> element can be referenced.

The draw:name attribute is usable with the following element: <draw:control> 10.3.13.

The draw:name attribute has the data type string 18.2.

19.197.6 <draw:custom-shape>

The draw:name attribute specifies a name by which a <draw:custom-shape> element can be referenced.

The draw:name attribute is usable with the following element: <draw:custom-shape> 10.6.1.

The draw:name attribute has the data type string 18.2.

19.197.7 <draw:ellipse>

The draw:name attribute specifies a name by which a <draw:ellipse> element can be referenced.

The draw:name attribute is usable with the following element: <draw:ellipse> 10.3.9.

The draw:name attribute has the data type string 18.2.

19.197.8 <draw:equation>

The draw:name attribute specifies a name by which a <draw:equation> element can be referenced.

The draw:name attribute is usable with the following element: <draw:equation> 10.2.5.

The draw:name attribute has the data type string 18.2.

19.197.9 <draw:fill-image>

The draw:name attribute specifies a name by which a <draw:fill-image> element can be referenced.

The draw:name attribute is usable with the following element: <draw:fill-image> 16.40.6.

The draw:name attribute has the data type styleName 18.3.31.

19.197.10 <draw:frame>

The draw:name attribute specifies a name by which a <draw:frame> element can be referenced.

The draw:name attribute is usable with the following element: <draw:frame> 10.4.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:name attribute has the data type string 18.2.

19.197.11 <draw:g>

The draw:name attribute specifies a name by which a <draw:g> element can be referenced.

The draw:name attribute is usable with the following element: <draw:g> 10.3.15.

The draw:name attribute has the data type string 18.2.

19.197.12 <draw:gradient>

The draw:name attribute specifies a name by which a <draw:gradient> element can be referenced.

The draw:name attribute is usable with the following element: <draw:gradient> 16.40.1.

The draw:name attribute has the data type styleName 18.3.31.

19.197.13 <draw:hatch>

The draw:name attribute specifies a name by which a <draw:hatch> element can be referenced.

The draw:name attribute is usable with the following element: <draw:hatch> 16.40.5.

The draw:name attribute has the data type styleName 18.3.31.

19.197.14 <draw:layer>

The draw:name attribute specifies a name by which a <draw:layer> element can be referenced.

The draw:name attribute is usable with the following element: <draw:layer> 10.2.3.

The draw:name attribute has the data type string 18.2.

19.197.15 <draw:line>

The draw:name attribute specifies a name by which a <draw:line> element can be referenced.

The draw:name attribute is usable with the following element: <draw:line> 10.3.3.

The draw:name attribute has the data type string 18.2.

19.197.16 <draw:marker>

The draw:name attribute specifies a name by which a <draw:marker> element can be referenced.

The draw:name attribute is usable with the following element: <draw:marker> 16.40.8.

The draw:name attribute has the data type styleName 18.3.31.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.197.17 <draw:measure>

The `draw:name` attribute specifies a name by which a `<draw:measure>` element can be referenced.

The `draw:name` attribute is usable with the following element: `<draw:measure>` 10.3.12.

The `draw:name` attribute has the data type `string` 18.2.

19.197.18 <draw:opacity>

The `draw:name` attribute specifies a name by which a `<draw:opacity>` element can be referenced.

The `draw:name` attribute is usable with the following element: `<draw:opacity>` 16.40.7.

The `draw:name` attribute has the data type `styleName` 18.3.31.

19.197.19 <draw:page>

The `draw:name` attribute specifies a name by which a `<draw:page>` element can be referenced. The name shall be unique within the document instance. If the attribute is not present, a consumer may generate a unique name.

The `draw:name` attribute is usable with the following element: `<draw:page>` 10.2.4.

The `draw:name` attribute has the data type `string` 18.2.

19.197.20 <draw:page-thumbnail>

The `draw:name` attribute specifies a name by which a `<draw:page-thumbnail>` element can be referenced.

The `draw:name` attribute is usable with the following element: `<draw:page-thumbnail>` 10.3.14.

The `draw:name` attribute has the data type `string` 18.2.

19.197.21 <draw:param>

The `draw:name` attribute specifies the name of a runtime parameter.

The `draw:name` attribute is usable with the following element: `<draw:param>` 10.4.9.

The `draw:name` attribute has the data type `string` 18.2.

19.197.22 <draw:path>

The `draw:name` attribute specifies a name by which a `<draw:path>` element can be referenced.

The `draw:name` attribute is usable with the following element: `<draw:path>` 10.3.7.

The `draw:name` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.197.23 <draw:polygon>

The draw:name attribute specifies a name by which a <draw:polygon> element can be referenced.

The draw:name attribute is usable with the following element: <draw:polygon> 10.3.5.

The draw:name attribute has the data type string 18.2.

19.197.24 <draw:polyline>

The draw:name attribute specifies a name by which a <draw:polyline> element can be referenced.

The draw:name attribute is usable with the following element: <draw:polyline> 10.3.4.

The draw:name attribute has the data type string 18.2.

19.197.25 <draw:rect>

The draw:name attribute specifies a name by which a <draw:rect> element can be referenced.

The draw:name attribute is usable with the following element: <draw:rect> 10.3.2.

The draw:name attribute has the data type string 18.2.

19.197.26 <draw:regular-polygon>

The draw:name attribute specifies a name by which a <draw:regular-polygon> element can be referenced.

The draw:name attribute is usable with the following element: <draw:regular-polygon> 10.3.6.

The draw:name attribute has the data type string 18.2.

19.197.27 <draw:stroke-dash>

The draw:name attribute specifies a name by which a <draw:stroke-dash> element can be referenced.

The draw:name attribute is usable with the following element: <draw:stroke-dash> 16.40.9.

The draw:name attribute has the data type styleName 18.3.31.

19.197.28 <office:annotation> (deprecated)

The draw:name attribute specifies a name for an <office:annotation> element.

The draw:name attribute has been deprecated in favor of the office:name attribute.

The draw:name attribute is usable with the following element: <office:annotation> 14.1.

The draw:name attribute has the data type string 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.197.29 <svg:linearGradient>

The `draw:name` attribute specifies a name by which a `<svg:linearGradient>` element can be referenced.

SVG gradients are referenced by the name assigned to them by use of the `draw:fill-gradient-name` attribute within a graphic style. SVG gradients cannot be referenced by a `draw:opacity-name` attribute. The result of referencing a SVG gradient with a `draw:fill-gradient-name` attribute and an opacity gradient with a `draw:opacity-name` attribute at the same time is unspecified.

The `draw:name` attribute is usable with the following element: `<svg:linearGradient>` 16.40.2.

The `draw:name` attribute has the data type `styleName` 18.3.31.

19.197.30 <svg:radialGradient>

The `draw:name` attribute specifies a name by which a `<svg:radialGradient>` element can be referenced.

SVG gradients are referenced by the name assigned to them by use of the `draw:fill-gradient-name` attribute within a graphic style. SVG gradients cannot be referenced by a `draw:opacity-name` attribute. The result of referencing a SVG gradient with a `draw:fill-gradient-name` attribute and an opacity gradient with a `draw:opacity-name` attribute at the same time is unspecified.

The `draw:name` attribute is usable with the following element: `<svg:radialGradient>` 16.40.3.

The `draw:name` attribute has the data type `styleName` 18.3.31.

19.198 draw:nav-order

The `draw:nav-order` attribute defines a navigation sequence for the graphical elements included in a `<draw:page>` element. Its value is a sequence of IDREFs. It shall include all graphic elements in the page that are not contained within a `<draw:g>` element. Any `<draw:g>` elements are included in that list as a single graphical element.

The value of this attribute is the ordering of graphics as set by the document author.

Note: The ordering within any `<draw:g>` element is set by the value of its `draw:z-index` attribute. 19.231

The `draw:nav-order` attribute is usable with the following element: `<draw:page>` 10.2.4.

The `draw:nav-order` attribute has the data type `IDREFS` 18.2.

19.199 draw:nohref

The `draw:nohref` attribute specifies that an image map element and its associated area are inactive.

The `draw:nohref` attribute is usable with the following elements: `<draw:area-circle>` 10.4.13.4, `<draw:area-polygon>` 10.4.13.5 and `<draw:area-rectangle>` 10.4.13.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The only value of the draw:nohref attribute is nohref.

19.200 draw:notify-on-update-of-ranges

The draw:notify-on-update-of-ranges attribute specifies that a <draw:object> will be notified if content within a given ranges changes.

The defined values for the draw:notify-on-update-of-ranges attribute are:

- a list of cell ranges.
- a table name.

If a table name is specified, the <draw:object> element is notified if any of the table's cells change.

The draw:notify-on-update-of-ranges attribute is usable with the following element: <draw:object> 10.4.6.2.

The values of the draw:notify-on-update-of-ranges attribute are a value of type cellRangeAddressList 18.3.6 or a value of type string 18.2.

19.201 draw:object

The draw:object attribute is equivalent to the object attribute of an <applet> element in HTML. See. §13.4 of [HTML4].

The draw:object attribute is usable with the following element: <draw:applet> 10.4.7.

The draw:object attribute has the data type string 18.2.

19.202 draw:opacity

The draw:opacity attribute specifies the opacity for an image or graphic object. The defined value range for the draw:opacity attribute is 0% to 100%, where 0% is fully transparent and 100% is fully opaque.

Use of the draw:opacity attribute disables any transparency effect and set the opacity for the fill area of a graphic object.

The draw:opacity attribute is usable with the following element: <style:background-image> 17.3.

The draw:opacity attribute has the data type zeroToHundredPercent 18.3.41.

19.203 draw:page-number

The draw:page-number attribute specifies the number of a page that is displayed as a thumbnail. For thumbnails on notes pages, the value of this attribute is fixed to the drawing page of a notes page. For thumbnails on handout master pages, the value of this attribute is the order in which the pages are previewed on the handout.

The draw:page-number attribute is usable with the following element: <draw:page-thumbnail> 10.3.14.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:page-number attribute has the data type positiveInteger 18.2.

19.204 draw:path-stretchpoint-x

The draw:path-stretchpoint-x attribute specifies that a drawing shape is stretched horizontally.

If specified, and if the x/y aspect ratio of the svg:viewBox is lower than the x/y aspect ratio of the shape size then the whole path is stretched horizontally at draw:path-stretchpoint-x.

Stretching is done by:

1) intersecting the path vertically at draw:path-stretchpoint-x.

2) moving the right path fragments to the right border of the drawing shape, using its original aspect ratio.The left path fragment remains unmodified at the left border of drawing the shape

The draw:path-stretchpoint-x attribute is usable with the following element: <draw:enhanced-geometry> 10.6.2.

The draw:path-stretchpoint-x attribute has the data type double 18.2.

19.205 draw:path-stretchpoint-y

The draw:path-stretchpoint-y attribute specifies that a drawing shape is stretched vertically.If the x/y aspect ratio of the svg:viewBox is greater than the x/y aspect ratio of the shape size then the whole path is stretched vertically at draw:path-stretchpoint-y.

Stretching is done by:

1) intersecting the path horizontally at draw:path-stretchpoint-y.

2) moving the bottom path fragments to the bottom border of the drawing shape, using its original aspect ratio.

The top path fragment remains unmodified at the top border of drawing the shape

The draw:path-stretchpoint-y attribute is usable with the following element: <draw:enhanced-geometry> 10.6.2.

The draw:path-stretchpoint-y attribute has the data type double 18.2.

19.206 draw:points

The draw:points attribute stores a sequence of points, which are connected by straight lines. Each point consists of two coordinates. The coordinates are separated by a comma “,” (U+002C, COMMA) and the points are separated by white spaces. The coordinates are relative to the coordinate system established by the svg:viewBox attribute.

The draw:points attribute is usable with the following elements: <draw:area-polygon> 10.4.13.5, <draw:contour-polygon> 10.4.11.2, <draw:polygon> 10.3.5 and <draw:polyline> 10.3.4.

The draw:points attribute has the data type points 18.3.25.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.207 draw:protected

The `draw:protected` attribute specifies if drawing objects in a layer are protected from modification.

The defined values for the `draw:protected` attribute are:

- `false`: objects in a layer are not protected from modification.
- `true`: objects in a layer are protected from modification.

The default value for this attribute is `false`.

The `draw:protected` attribute is usable with the following element: `<draw:layer>` 10.2.3.

The `draw:protected` attribute has the data type `boolean` 18.3.3.

19.208 draw:recreate-on-edit

The `draw:recreate-on-edit` attribute specifies if the contour of an image or object should be recreated automatically if the image or object is edited.

The defined values for the `draw:recreate-on-edit` attribute are:

- `false`: the contour of an image or object is not recreated automatically if the image or object is edited.
- `true`: the contour of an image or object is recreated automatically if the image or object is edited.

The `draw:recreate-on-edit` attribute is usable with the following elements: `<draw:contour-path>` 10.4.11.3 and `<draw:contour-polygon>` 10.4.11.2.

The `draw:recreate-on-edit` attribute has the data type `boolean` 18.3.3.

19.209 draw:rotation

The `draw:rotation` attribute specifies the rotation angle of a hatch axis. The direction is clockwise, 0 degrees is the vertical axis.

The `draw:rotation` attribute is usable with the following element: `<draw:hatch>` 16.40.5.

The `draw:rotation` attribute has the data type `angle` 18.3.1.

19.210 draw:shape-id

The `draw:shape-id` attribute identifies the shape to which an effect defined by a presentation shape effect element is applied.

The `draw:shape-id` attribute is usable with the following elements: `<presentation:dim>` 10.8.7, `<presentation:hide-shape>` 10.8.5, `<presentation:hide-text>` 10.8.6, `<presentation:play>` 10.8.8, `<presentation:show-shape>` 10.8.3 and `<presentation:show-text>` 10.8.4.

The `draw:shape-id` attribute has the data type `IDREF` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.211 draw:sharpness

The `draw:sharpness` attribute specifies the radius of the ellipse on which inner polygon corners are located. The value is a percentage, where 0% means that all corners are located on a single ellipse, while 100% means that the inner corners are located at the center point of the polygon. If *r* is the radius of the polygon, and *s* is the sharpness, the inner corners a located on a ellipse that's radius is *r(100-s)/100*.

Note: This attribute is only meaningful only with a `draw:concave` attribute with the value `true`.

The `draw:sharpness` attribute is usable with the following element: `<draw:regular-polygon>` 10.3.6.

The `draw:sharpness` attribute has the data type `percent` 18.3.23.

19.212 draw:start

The `draw:start` attribute specifies the start value for the `<draw:opacity>` element, which interpolates between the value of this attribute and `draw:end`. The defined value range for the `draw:start` attribute is 0% to 100%, where 0% is transparent and 100% is opaque.

The `draw:start` attribute is usable with the following element: `<draw:opacity>` 16.40.7.

The `draw:start` attribute has the data type `zeroToHundredPercent` 18.3.41.

19.213 draw:start-angle

The `draw:start-angle` attribute specifies the start angle of a section, cut, or arc for circles where the `draw:kind` attribute value is `section`, `cut` or `arc`.

The `draw:start-angle` attribute is usable with the following elements: `<draw:circle>` 10.3.8 and `<draw:ellipse>` 10.3.9.

The `draw:start-angle` attribute has the data type `angle` 18.3.1.

19.214 draw:start-color

The `draw:start-color` attributes specifies the start value for the `<draw:gradient>` element, which interpolates between the value of this attribute and `draw:end-color`.

The `draw:start-color` attribute is usable with the following element: `<draw:gradient>` 16.40.1.

The `draw:start-color` attribute has the data type `color` 18.3.9.

19.215 draw:start-glue-point

The `draw:start-glue-point` attribute identifies the glue point in a shape where a connector starts by its number. See 10.3.16. Glue point numbers are defined by the `draw:id` attributes of the glue point elements `<draw:glue-point>`. See 19.187.

If the connector is not connected to a shape, this attribute is ignored.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:start-glue-point attribute is usable with the following element: <draw:connector> 10.3.10.

The draw:start-glue-point attribute has the data type nonNegativeInteger 18.2.

19.216 draw:start-intensity

The draw:start-intensity attribute specifies the intensity of the gradient's start color as a percentage value. If it is not specified, the color is used at 100% intensity. The defined value range for the draw:start-intensity attribute is 0% to 100%.

The draw:start-intensity attribute is usable with the following element: <draw:gradient> 16.40.1.

The draw:start-intensity attribute has the data type zeroToHundredPercent 18.3.41.

19.217 draw:start-shape

The draw:start-shape attribute specifies a drawing shape to which the start of a connector is connected by its ID.

The draw:start-shape attribute is usable with the following element: <draw:connector> 10.3.10.

The draw:start-shape attribute has the data type IDREF 18.2.

19.218 draw:style

19.218.1 General

The draw:style attribute specifies the rendering of graphic objects.

19.218.2 <draw:gradient>

The draw:style attribute specifies a rendering for a gradient.

The defined values for the draw:style attribute are:

- axial: defines a bi-linear gradient that is also known as reflected gradient or mirrored linear gradient. It is created as a linear gradient that is mirrored (or reflected) along its axis.
- ellipsoid: defines a gradient where the colors are blend along the radius from the center of an ellipsoid as defined with the draw:cx and draw:cy attributes. The length of the semi major-axis is the width of the filled area and the length of the semi-minor axis is the height of the filled area. The area outside the ellipse is filled with the end color.
- Linear: defines a gradient where the colors blend along the linear axis of the gradient. The axis of the gradient is specified with the draw:angle attribute clockwise to the vertical axis.
- radial: defines a gradient where the colors are blend along the radius from the center of a circle as defined with the draw:cx and draw:cy attributes. The outside of the circle is filled with the end color.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `rectangle`: defines a gradient that produces a rectangular blend from the center of the rectangle to the shortest of the 4 borders. The center of the rectangle is defined with the attributes `draw:cx` and `draw:cy`. The width of the rectangle is the width of the filled area, the height of the rectangle is the height of the filled area. The outside of the square is filled with the end color.
- `square`: defines a gradient that produces a square blend, imitating the visual perspective in a corridor or the aerial view of a pyramid. Also known as "box gradient" and "pyramidal gradient". The center of the square is defined with the `draw:cx` and `draw:cy` attributes. The width and height of the square is the minimum value of either the width or the height of the filled area. The outside of the square is filled with the end color.

The `draw:style` attribute is usable with the following element: `<draw:gradient>` 16.40.1. The values of the `draw:style` attribute are `linear`, `axial`, `radial`, `ellipsoid`, `square` or `rectangular`.

19.218.3 <draw:hatch>

The `draw:style` attribute specifies a rendering for a hatch.

The defined values for the `draw:style` attribute are:

- `double`: defines a hatch that is made of a set of parallel lines along the axis of the hatch and a set of parallel lines perpendicular to the axis of the hatch.
- `single`: defines a hatch that is made of parallel lines along the axis of the hatch.
- `triple`: defines a hatch that is made of a set of parallel lines along the axis of the hatch, a set of parallel lines perpendicular to the axis of the hatch and a set of lines along 45 degree clockwise to the axis of the hatch.

The `draw:style` attribute is usable with the following element: `<draw:hatch>` 16.40.5. The values of the `draw:style` attribute are `single`, `double` or `triple`.

19.218.4 <draw:opacity>

The `draw:style` attribute specifies the transparency of a graphic object.

The defined values for the `draw:style` attribute are:

- `axial`: 19.218.2
- `ellipsoid`: 19.218.2
- `linear`: 19.218.2
- `rectangle`: 19.218.2
- `square`: 19.218.2

The transparency of an object is blended in contrast to the blending of colors described for `draw:style` on `<draw:gradient>`.

The `draw:style` attribute is usable with the following element: `<draw:opacity>` 16.40.7.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The values of the draw:style attribute are linear, axial, radial, ellipsoid, square or rectangular.

19.218.5 <draw:stroke-dash>

The draw:style attribute specifies a rendering for a stroke-dash.

The defined values for the draw:style attribute are:

- rect: dash has a rectangular shape.
- round: dash has a round shape.

The draw:style attribute is usable with the following element: <draw:stroke-dash> 16.40.9.

The values of the draw:style attribute are rect or round.

19.219 draw:style-name

19.219.1 General

The draw:style-name attribute specifies the name of a <style:style> element whose family varies depending upon the element where it appears.

19.219.2 <dr3d:cube>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <dr3d:cube> 10.5.4.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.3 <dr3d:extrude>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <dr3d:extrude> 10.5.6.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.4 <dr3d:rotate>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <dr3d:rotate> 10.5.7.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.219.5 <dr3d:scene>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <dr3d:scene> 10.5.2.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.6 <dr3d:sphere>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <dr3d:sphere> 10.5.5.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.7 <draw:caption>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <draw:caption> 10.3.11.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.8 <draw:circle>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <draw:circle> 10.3.8.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.9 <draw:connector>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <draw:connector> 10.3.10.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.10 <draw:control>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <draw:control> 10.3.13.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.11 <draw:custom-shape>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <draw:custom-shape> 10.6.1.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.12 <draw:ellipse>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <draw:ellipse> 10.3.9.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.13 <draw:frame>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <draw:frame> 10.4.2.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.14 <draw:g>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <draw:g> 10.3.15.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.15 <draw:line>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

The draw:style-name attribute is usable with the following element: <draw:line> 10.3.3.

The draw:style-name attribute has the data type styleNameRef 18.3.32.

19.219.16 <draw:measure>

The draw:style-name attribute specifies the name of a <style:style> element that defines a style with the family value of graphic.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `draw:style-name` attribute is usable with the following element: `<draw:measure>` 10.3.12.

The `draw:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.219.17 <draw:page>

The `draw:style-name` attribute specifies the name of a `<style:style>` element that defines a style with the family value of `drawing-page`.

The `draw:style-name` attribute is usable with the following element: `<draw:page>` 10.2.4.

The `draw:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.219.18 <draw:page-thumbnail>

The `draw:style-name` attribute specifies the name of a `<style:style>` element that defines a style with the family value of `graphic`.

The `draw:style-name` attribute is usable with the following element: `<draw:page-thumbnail>` 10.3.14.

The `draw:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.219.19 <draw:path>

The `draw:style-name` attribute specifies the name of a `<style:style>` element that defines a style with the family value of `graphic`.

The `draw:style-name` attribute is usable with the following element: `<draw:path>` 10.3.7.

The `draw:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.219.20 <draw:polygon>

The `draw:style-name` attribute specifies the name of a `<style:style>` element that defines a style with the family value of `graphic`.

The `draw:style-name` attribute is usable with the following element: `<draw:polygon>` 10.3.5.

The `draw:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.219.21 <draw:polyline>

The `draw:style-name` attribute specifies the name of a `<style:style>` element that defines a style with the family value of `graphic`.

The `draw:style-name` attribute is usable with the following element: `<draw:polyline>` 10.3.4.

The `draw:style-name` attribute has the data type `styleNameRef` 18.3.32.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.219.22 <draw:rect>

The `draw:style-name` attribute specifies the name of a `<style:style>` element that defines a style with the family value of `graphic`.

The `draw:style-name` attribute is usable with the following element: `<draw:rect>` 10.3.2.

The `draw:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.219.23 <draw:regular-polygon>

The `draw:style-name` attribute specifies the name of a `<style:style>` element that defines a style with the family value of `graphic`.

The `draw:style-name` attribute is usable with the following element: `<draw:regular-polygon>` 10.3.6.

The `draw:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.219.24 <office:annotation>

The `draw:style-name` attribute specifies the name of a `<style:style>` element that defines a style with the family value of `graphic`.

The `draw:style-name` attribute is usable with the following element: `<office:annotation>` 14.1.

The `draw:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.219.25 <presentation:notes>

The `draw:style-name` attribute specifies the name of a `<style:style>` element that defines a style with the family value of `drawing-page`.

The `draw:style-name` attribute is usable with the following element: `<presentation:notes>` 16.17.

The `draw:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.219.26 <style:handout-master>

The `draw:style-name` attribute specifies the name of a `<style:style>` element that defines a style with the family value of `drawing-page`.

The `draw:style-name` attribute is usable with the following element: `<style:handout-master>` 10.2.1.

The `draw:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.219.27 <style:master-page>

The `draw:style-name` attribute specifies the name of a `<style:style>` element that defines a style with the family value of `drawing-page`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

In drawing and presentation documents, additional drawing page attributes may be assigned to a drawing page using the `draw:style-name` attribute.

The `draw:style-name` attribute is usable with the following element: `<style:master-page>` 16.9.

The `draw:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.220 draw:text-areas

The `draw:text-areas` attribute specifies up to two text areas. If the attribute specifies one text area, this text area is used to position and align the text. If the attribute specifies two text areas, the second text area is used if a style that is assigned to the text has a `style:writing-mode` attribute with value `tb-rl` or `tb`. Otherwise, the first text area is used. If the draw:text-areas attribute is omitted, the entire area of the shape is used to position and align the text.

An area consists of four parameters:

The first parameter specifies the left side of a text area.

The second parameter specifies the top side of a text area.

The third parameter specifies the right side of a text area.

The fourth parameter specifies the bottom side of a text area.

A parameter can also have one of the following enhancements:

- A “?” (U+003F, QUESTION MARK) is used to mark the beginning of a formula name. The result of the `<draw:equation>` element's `draw:formula` attribute whose `draw:name` attribute is the formula name that is used as the value.
- If “$” (U+0024, DOLLAR SIGN) precedes a integer value, the value is an index to a `draw:modifiers` attribute. The corresponding modifier value is used as parameter value.

The value of a `draw:text-areas` attribute is formally defined as:

```
textareas::= textareasequence
textareasequence ::= textarea ( ' '+ textarea )?
textarea::= position ' '+ position ' '+ position ' '+ position
position::= formula | modifier | number
formula::= '?' name
modifier::= '$' integer
number::= sign? float | sign? integer
float::= fractional exponent? | integer exponent
fractional::= integer? '.' integer | integer '.'
exponent::= ( 'e' | 'E' ) sign? integer
sign::= '+'| '-'
integer::= [0-9]+
name ::= [^ ]+
```

The `draw:text-areas` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.

The `draw:text-areas` attribute has the data type `string` 18.2.

19.221 draw:text-path

The `draw:text-path` attribute specifies if text is displayed on a text path.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the draw:text-path attribute are:

- false: text is not displayed on a text path.
- true: text is displayed on a text path.

The default value for this attribute is false.

The draw:text-path attribute is usable with the following element: <draw:enhanced-geometry> 10.6.2.

The draw:text-path attribute has the data type boolean 18.3.3.

19.222 draw:text-path-allowed

The draw:text-path-allowed attribute specifies whether the user interface of a consumer that supports the draw:text-path attribute should allow modification of the value of the draw:text-path attribute.

The defined values for the draw:text-path-allowed attribute are:

- false: the value of the draw:text-path attribute should not be modifiable by the user interface.
- true: the value of the draw:text-path attribute should be modifiable by the user interface.

The default value for this attribute is false.

The draw:text-path-allowed attribute is usable with the following element: <draw:enhanced-geometry> 10.6.2.

The draw:text-path-allowed attribute has the data type boolean 18.3.3.

19.223 draw:text-path-mode

The draw:text-path-mode attribute specifies how text is drawn on a path.

The defined values for the draw:text-path-mode attribute are:

- normal: text is drawn along the path without scaling;
- path: text is fitted to a path;
- shape: text is fitted to the bounding box of a shape.

The default value for this attribute is normal.

The draw:text-path-mode attribute is usable with the following element: <draw:enhanced-geometry> 10.6.2.

The values of the draw:text-path-mode attribute are normal, path or shape.

19.224 draw:text-path-same-letter-heights

The draw:text-path-same-letter-heights attribute specifies if all letters in a custom shape have the same height.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the draw:text-path-same-letter-heights attribute are:

- false: letters in a custom shape may not have the same height.
- true: letters in a custom shape have the same height.

The default value for this attribute is false.

The draw:text-path-same-letter-heights attribute is usable with the following element: <draw:enhanced-geometry> 10.6.2.

The draw:text-path-same-letter-heights attribute has the data type boolean 18.3.3.

19.225 draw:text-path-scale

The draw:text-path-scale attribute specifies the scaling of a text path.

The defined values for the draw:text-path-scale attribute are:

- path: text scaling is determined by the length of the path from the draw:enhanced-path attribute.
- shape: text scaling is determined by the width of a shape.

The default value for this attribute is path.

The draw:text-path-scale attribute is usable with the following element: <draw:enhanced-geometry> 10.6.2.

The values of the draw:text-path-scale attribute are path or shape.

19.226 draw:text-rotate-angle

The draw:text-rotate-angle attribute specifies the angle by which text within a custom shape is rotated in addition to the rotation included in the shape's draw:transform attribute.

The default value for this attribute is 0.

The draw:text-rotate-angle attribute is usable with the following element: <draw:enhanced-geometry> 10.6.2.

The draw:text-rotate-angle attribute has the data type angle 18.3.1.

19.227 draw:text-style-name

The draw:text-style-name attribute specifies a style for formatting of text in a shape.

The value of this attribute is the name of a <style:style> element with a family value of paragraph.

The draw:text-style-name attribute is usable with the following elements: <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6 and <office:annotation> 14.1.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:text-style-name attribute has the data type styleNameRef 18.3.32.

19.228 draw:transform

The draw:transform attribute specifies a list of transformations that can be applied to a drawing shape.

The value of this attribute is a list of transform definitions, which are applied to the drawing shape in the order in which they are listed. The transform definitions in the list shall be separated by a white space and/or a comma "," (U+002C, COMMA). Unless otherwise stated, the parameters of the transform definitions are double values (18.2)

The defined transforms are:

- matrix(*<a> <b> <c> <d> <e> <f>*), specifies a transformation in the form of a transformation matrix of six values. "The values describe a standard 3x2 homogeneous transformation matrix in column-major order, where the right column (*<e>*, *<f>*) describes the translation.
- rotate(*<rotate-angle>*), specifies a rotation by *<rotate-angle>* degrees about the origin of the shapes coordinate system.
- scale(*<sx>* [*<sy>*]), specifies a scale operation by *sx* and *sy*. If *<sy>* is not provided, it is assumed to be equal to *<sx>*.
- skewX(*<skew-angle>*), specifies a skew transformation by *<rotate-angle>* degrees along the x-axis.
- skewY(*<skew-angle>*), specifies a skew transformation by *<rotate-angle>* degrees along the y-axis.
- translate(*<tx>* [*<ty>*]), specifies a translation by *tx* and *ty,* where tx and ty are lengths (18.3.18). If *ty* is not provided, it is assumed to be zero.

The draw:transform attribute is usable with the following elements: <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6 and <office:annotation> 14.1.

The draw:transform attribute has the data type string 18.2.

19.229 draw:type

19.229.1 General

The draw:type attribute specifies a drawing type.

19.229.2 <draw:connector>

The draw:type attribute specifies the line or series of lines that connect two glue points.

The defined values for the draw:type attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `curve`: a curve connector draws a single curved line between the two glue points of connected objects
- `line`: a line connector draws one straight line between the two glue points of connected objects
- `lines`: a lines connector leaves two connecting objects with straight lines and connects them with a straight (not necessarily perpendicular) line
- `standard`: a standard connector escapes two connecting objects with straight lines and connects them with one or more straight perpendicular lines that do not intersect the connected shapes' bounding boxes

For a `<draw:connector>` 10.3.10 element the default value for this attribute is `standard`.

The `draw:type` attribute is usable with the following element: `<draw:connector>` 10.3.10.
The values of the `draw:type` attribute are `standard`, `lines`, `line` or `curve`.

19.229.3 <draw:enhanced-geometry>

The `draw:type` attribute specifies the name of a shape type that is rendering engine dependent.

The defined values for the `draw:type` attribute are:

- `non-primitive`: no shape type is available.
- a value of type string: a rendering engine specific name of a shape.

The value of this attribute shall not influence the geometry of the shape.

Note: The shape type can be used to offer specialized user interfaces for classes of shapes, like for arrows, smileys, etc.

For a `<draw:enhanced-geometry>` 10.6.2 element the default value for this attribute is `non-primitive`.

The `draw:type` attribute is usable with the following element: `<draw:enhanced-geometry>` 10.6.2.
The values of the `draw:type` attribute are `non-primitive` or a value of type `string` 18.2.

19.230 draw:value

The `draw:value` attribute specifies the value of a runtime parameter specified by a `draw:name` attribute.

The `draw:value` attribute is usable with the following element: `<draw:param>` 10.4.9.
The `draw:value` attribute has the data type `string` 18.2.

19.231 draw:z-index

The `draw:z-index` attribute defines a rendering order for shapes in a document instance. Shapes are rendered in the order in which they appear in the document in the absence of this attribute.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:z-index attribute is usable with the following elements: <dr3d:cube> 10.5.4, <dr3d:extrude> 10.5.6, <dr3d:rotate> 10.5.7, <dr3d:scene> 10.5.2, <dr3d:sphere> 10.5.5, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6 and <office:annotation> 14.1.

The draw:z-index attribute has the data type nonNegativeInteger 18.2.

19.232 fo:column-count

The fo:column-count attribute specifies the number of columns in a section.

The fo:column-count attribute is usable with the following element: <style:columns> 17.12.

The fo:column-count attribute has the data type positiveInteger 18.2.

19.233 fo:column-gap

The fo:column-gap attribute specifies the gap between columns for <style:columns> elements that do not contain individual <style:column> elements.

Note: This attribute has the same name as an [XSL] property but it is attached to a different element.

In the OpenDocument XSL compatible namespace, the fo:column-gap attribute does not support inherit and percentage values.

The fo:column-gap attribute is usable with the following element: <style:columns> 17.12.

The fo:column-gap attribute has the data type length 18.3.18.

19.234 fo:country

19.234.1 <text:alphabetical-index-source>

The fo:country attribute specifies the country code used for sorting an alphabetical index.

The fo:country attribute is usable with the following element: <text:alphabetical-index-source> 8.8.2.

The fo:country attribute has the data type countryCode 18.3.11.

19.234.2 <text:bibliography-configuration>

The fo:country attribute specifies the country code used for sorting a bibliographic index.

The fo:country attribute is usable with the following element: <text:bibliography-configuration> 16.29.6.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `fo:country` attribute has the data type `countryCode` 18.3.11.

19.235 fo:end-indent

The `fo:end-indent` attribute specifies the right space of a column. Together with the `fo:start-indent` attribute of an immediately adjacent and following column, it establishes the gap between the columns. 19.245

See §7.10.8 of [XSL].

In the OpenDocument XSL compatible namespace, the `fo:end-indent` attribute does not support `inherit` and `percentage` values.

The default value for this attribute is `0cm`.

The `fo:end-indent` attribute is usable with the following element: `<style:column>` 17.13.

The `fo:end-indent` attribute has the data type `length` 18.3.18.

19.236 fo:language

19.236.1 General

See §7.9.2 of [XSL]. Compared to the XSL language attribute, the value range of this attribute is extended to additional parts of ISO 639.

This attribute may be ignored if it is not specified together with a `fo:country` attribute.

In the OpenDocument XSL compatible namespace, the `fo:language` attribute does not support `inherit` and `none` values.

19.236.2 <text:alphabetical-index-source>

The `fo:language` attribute specifies the language code used for sorting an alphabetical index.

The `fo:language` attribute is usable with the following element: `<text:alphabetical-index-source>` 8.8.2.

The `fo:language` attribute has the data type `languageCode` 18.3.17.

19.236.3 <text:bibliography-configuration>

The `fo:language` attribute specifies the language code used for sorting a bibliographic index.

The `fo:language` attribute is usable with the following element: `<text:bibliography-configuration>` 16.29.6.

The `fo:language` attribute has the data type `languageCode` 18.3.17.

19.237 fo:margin-left

See §7.10.3 of [XSL].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The fo:margin-left attribute specifies the left margins for the text lines of a list item. The attribute has the same meaning as the formatting property attribute fo:margin-left. 20.200 Its value is only considered for paragraphs inside a list item those paragraph styles do not specify a fo:text-indent attribute or a fo:margin-left attribute.

The fo:margin-left attribute is usable with the following element: <style:list-level-label-alignment> 17.20.

The fo:margin-left attribute has the data type length 18.3.18.

19.238 fo:max-height

See §7.14.6 of [XSL].

The fo:max-height attribute specifies the maximum height of a text box when the minimum height has been set using the fo:min-height attribute. When this maximum value is reached, the text box stops increasing in height. The units of measure for this attribute shall match those used for the corresponding fo:min-height attribute.

If the anchor for the text box is in a table cell, a percentage value is relative to the size of the surrounding table cell. If the anchor for the text box is in a text box, a percentage value is relative to the size of the surrounding text box. In other cases, percentage values are relative to the width or height of the page or window.

In the OpenDocument XSL compatible namespace, the fo:max-height attribute does not support the none value.

The fo:max-height attribute is usable with the following element: <draw:text-box> 10.4.3.

The values of the fo:max-height attribute are a value of type length 18.3.18 or a value of type percent 18.3.23.

19.239 fo:max-width

See §7.14.7 of [XSL].

The fo:max-width attribute specifies the maximum width of a text box when the minimum width have been set using the fo:min-width attribute. When this maximum value is reached, the text box stops increasing in width. The units of measure for this attribute shall match those used for the corresponding fo:min-width attribute.

If the anchor for the text box is in a table cell, a percentage value is relative to the size of the surrounding table cell. If the anchor for the text box is in a text box, a percentage value is relative to the size of the surrounding text box. In other cases, percentage values are relative to the width or height of the page or window.

The fo:max-width attribute is usable with the following element: <draw:text-box> 10.4.3.

The values of the fo:max-width attribute are a value of type length 18.3.18 or a value of type percent 18.3.23.

19.240 fo:min-height

See §7.14.8 of [XSL].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If set, it overrides the height or width of a text box specified by the `svg:height` attribute of the surrounding `<draw:frame>` element.

If the anchor for a text box is in a table cell, a percentage value is relative to the surrounding table box. If the anchor for the text box is in a text box, a percentage value is relative to the surrounding text box. In other cases, percentage values are relative to the height of the page or window.

The `fo:min-height` attribute is usable with the following element: `<draw:text-box>` 10.4.3.

The values of the `fo:min-height` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

19.241 fo:min-width

See §7.14.9 of [XSL].

If set, it overrides the width of a text box specified by the `svg:width` attribute of the surrounding `<draw:frame>` element.

If the anchor for a text box is in a table cell, a percentage value is relative to the surrounding table box. If the anchor for a text box is in a text box, a percentage value is relative to the surrounding text box. In other cases, percentage values are relative to the height of the page or window.

The `fo:min-width` attribute is usable with the following element: `<draw:text-box>` 10.4.3.

The values of the `fo:min-width` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

19.242 fo:script

19.242.1 General

See §7.9.3 of [XSL]. The attribute should be used only if necessary according to the rules of §2.2.3 of [RFC5646], or its successors.

It may be ignored if it is not specified together with a `fo:language` attribute.

In the OpenDocument XSL compatible namespace, the `fo:script` attribute does not support `inherit` and `none` values.

19.242.2 <text:alphabetical-index-source>

The `fo:script` attribute specifies the script code used for sorting an alphabetical index. The attribute should be used only if necessary according to the rules of §2.2.3 of [RFC5646], or its successors.

The `fo:script` attribute is usable with the following element: `<text:alphabetical-index-source>` 8.8.2.

The `fo:script` attribute has the data type `scriptCode` 18.3.29.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.242.3 <text:bibliography-configuration>

The `fo:script` attribute specifies the script code used for sorting a bibliographic index. The attribute should be used only if necessary according to the rules of §2.2.3 of [RFC5646], or its successors.

The `fo:script` attribute is usable with the following element: `<text:bibliography-configuration>` 16.29.6.

The `fo:script` attribute has the data type `scriptCode` 18.3.29.

19.243 fo:space-after

See §7.10.6 of [XSL].

The default value for this attribute is `0cm`.

The `fo:space-after` attribute is usable with the following element: `<style:column>` 17.13.

The `fo:space-after` attribute has the data type `length` 18.3.18.

19.244 fo:space-before

See §7.10.5 of [XSL].

The default value for this attribute is `0cm`.

The `fo:space-before` attribute is usable with the following element: `<style:column>` 17.13.

The `fo:space-before` attribute has the data type `length` 18.3.18.

19.245 fo:start-indent

See §7.10.7 of [XSL].

The default value for this attribute is `0cm`.

The `fo:start-indent` attribute is usable with the following element: `<style:column>` 17.13.

The `fo:start-indent` attribute has the data type `length` 18.3.18.

19.246 fo:text-indent

The `fo:text-indent` attribute specifies the indent for the text lines of a list item. The attribute has the same meaning as the formatting property attribute `fo:text-indent`. See 20.218 It is used for paragraphs inside list items whose paragraph styles do not specify an `fo:text-indent` or `fo:margin-left` attribute.

The value `fo:text-indent` + `fo:margin-left` specifies the indent of the first text line of the list item. This position is also the alignment position for the list label, because the value of `text:min-label-width` is treated as 0.

The `fo:text-indent` attribute is usable with the following element: `<style:list-level-label-alignment>` 17.20.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `fo:text-indent` attribute has the data type `length` 18.3.18.

19.247 form:allow-deletes

The `form:allow-deletes` attribute specifies whether data records can be deleted by a form. It applies only if a form is data-aware.

The defined values for the `form:allow-deletes` attribute are:

- `false`: records cannot be deleted by a form.
- `true`: records can be deleted by a form.

The default value for this attribute is `true`.

The `form:allow-deletes` attribute is usable with the following element: `<form:form>` 13.3.

The `form:allow-deletes` attribute has the data type `boolean` 18.3.3.

19.248 form:allow-inserts

The `form:allow-inserts` attribute specifies whether new data records can be inserted by a form. It applies only if the form is data-aware.

The defined values for the `form:allow-inserts` attribute are:

- `false`: records cannot be inserted by a form.
- `true`: records can be inserted by a form.

The default value for this attribute is `true`.

The `form:allow-inserts` attribute is usable with the following element: `<form:form>` 13.3.

The `form:allow-inserts` attribute has the data type `boolean` 18.3.3.

19.249 form:allow-updates

The `form:allow-updates` attribute specifies whether data records in the form can be updated. It applies only if the form is data-aware.

The defined values for the `form:allow-updates` attribute are:

- `false`: records cannot be updated by a form.
- `true`: records can be updated by a form.

The default value for this attribute is `true`.

The `form:allow-updates` attribute is usable with the following element: `<form:form>` 13.3.

The `form:allow-updates` attribute has the data type `boolean` 18.3.3.

19.250 form:apply-design-mode

The `form:apply-design-mode` attribute specifies whether forms are presented in editable or non-editable state.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `false`: forms in document presented in completed state
- `true`: forms in document presented in editable state

The default value for this attribute is `true`.

The `form:apply-design-mode` attribute is usable with the following element: `<office:forms>` 13.2.

The `form:apply-design-mode` attribute has the data type `boolean` 18.3.3.

19.251 form:apply-filter

The `form:apply-filter` attribute specifies whether the filter clause specified by the `form:filter` attribute is applied to the SQL command constituting the form's result set. 19.273

The defined values for the `form:apply-filter` attribute are:

- `false`: the filter clause specified by the `form:filter` attribute is not applied to the SQL command constituting the form's result set.
- `true`: the filter clause specified by the `form:filter` attribute is applied to the SQL command constituting the form's result set.

The default value for this attribute is `false`.

The `form:apply-filter` attribute is usable with the following element: `<form:form>` 13.3.

The `form:apply-filter` attribute has the data type `boolean` 18.3.3.

19.252 form:auto-complete

The `form:auto-complete` attribute specifies whether, when the user enters text in the combobox that matches the beginning of a list item in the combobox, the consumer completes the text with the matched item.

The defined values for the `form:auto-complete` attribute are:

- `false`: completion of text is not enabled.
- `true`: completion of text is enabled.

The `form:auto-complete` attribute is usable with the following element: `<form:combobox>` 13.5.11.

The `form:auto-complete` attribute has the data type `boolean` 18.3.3.

19.253 form:automatic-focus

The `form:automatic-focus` attribute specifies whether the consumer loading the document should set the focus to a form control.

The defined values for the `form:automatic-focus` attribute are:

- `false`: the consumer does not set the focus to a form control, but to the document view. In this case, the user can start editing the document content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: the consumer sets the focus to a form control after loading the document. In this case, the user can immediately start editing the form control content.

Note: Which form control is chosen to be focused is not defined. It may be the first control in the logical order defined by the `<office:forms>` elements and its sub elements, it may be the top-most form control of the document view, or any other control.

The default value for this attribute is `false`.

The `form:automatic-focus` attribute is usable with the following element: `<office:forms>` 13.2.

The `form:automatic-focus` attribute has the data type `boolean` 18.3.3.

19.254 form:bound-column

The `form:bound-column` attribute specifies the column values of the list source result set that are used to fill the data field values.

The `form:list-source` and `form:list-source-type` attributes together define an SQL command to execute against the database to which the control's form is bound. The result set of the execution of this SQL command is the list source result set.

The `form:bound-column` attribute is usable with the following element: `<form:listbox>` 13.5.13.

The `form:bound-column` attribute has the data type `string` 18.2.

19.255 form:button-type

The `form:button-type` attribute specifies the type of a button.

The defined values for the `form:button-type` attribute are:

- `push`: pressing the button does not perform any action by default. A user can add scripts to a button and the script will run when the button is pressed.
- `reset`: pressing the button resets every control in the form to its default value.
- `submit`: pressing the button submits the form.
- `url`: pressing the button loads the IRI that is specified in the `xlink:href` attribute.

The default value for this attribute is `push`.

The `form:button-type` attribute is usable with the following elements: `<form:button>` 13.5.15 and `<form:image>` 13.5.16.

The values of the `form:button-type` attribute are `submit`, `reset`, `push` or `url`.

19.256 form:command

The `form:command` attribute specifies a command to execute on a data source.

The value is interpreted differently, depending to the value of the `form:command-type` attribute of the form.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The form:command attribute is usable with the following element: <form:form> 13.3.

The form:command attribute has the data type string 18.2.

19.257 form:command-type

The form:command-type attribute specifies the type of command to execute on a data source.

The defined values of the form:command-type attribute are:

- command: the command contains an SQL statement. The form executes the SQL statement.
- query: the command contains the name of query. The form retrieves the query and executes its SQL statement.
- table: the command contains a table name. The form executes an SQL statement that retrieves all of the data in the table.

Note: The attribute value query is only meaningful if the form:datasource attribute specifies a data source name or an database front-end document. .

The default value for this attribute is command.

The form:command-type attribute is usable with the following element: <form:form> 13.3.

The values of the form:command-type attribute are table, query or command.

19.258 form:control-implementation

The form:control-implementation attribute specifies a \rendition or implementation of a control that should be created. If the consumer supports the form element this attribute is used with, but does not support the specific concrete rendition or implementation, the consumer shall ignore the form:control-implementation attribute and use its own rendition of the form element.

The form:control-implementation attribute is usable with the following elements: <form:button> 13.5.15, <form:checkbox> 13.5.17, <form:column> 13.5.23, <form:combobox> 13.5.11, <form:date> 13.5.8, <form:file> 13.5.5, <form:fixed-text> 13.5.10, <form:form> 13.3, <form:formatted-text> 13.5.6, <form:frame> 13.5.19, <form:generic-control> 13.5.25, <form:grid> 13.5.22, <form:hidden> 13.5.21, <form:image> 13.5.16, <form:image-frame> 13.5.20, <form:listbox> 13.5.13, <form:number> 13.5.7, <form:password> 13.5.4, <form:radio> 13.5.18, <form:text> 13.5.2, <form:textarea> 13.5.3, <form:time> 13.5.9 and <form:value-range> 13.5.24.

The form:control-implementation attribute has the data type namespacedToken 18.3.19.

19.259 form:convert-empty-to-null

The form:convert-empty-to-null attribute specifies whether empty current values are treated as NULL.

The defined values for the form:convert-empty-to-null attribute are:

- false: an empty string in the control is treated as an empty string.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: an empty string in the control is treated as a NULL value.

The default value for this attribute is `false`.

The `form:convert-empty-to-null` attribute is usable with the following elements: `<form:combobox>` 13.5.11, `<form:date>` 13.5.8, `<form:formatted-text>` 13.5.6, `<form:number>` 13.5.7, `<form:password>` 13.5.4, `<form:text>` 13.5.2, `<form:textarea>` 13.5.3 and `<form:time>` 13.5.9.

The `form:convert-empty-to-null` attribute has the data type `boolean` 18.3.3.

19.260 form:current-selected

The `form:current-selected` attribute specifies the state of a radio button or option element.

The defined values for the `form:current-selected` attribute are:

- `false`: radio button or option element is not selected.
- `true`: radio button or option element is selected.

The default value for this attribute is `false`.

The `form:current-selected` attribute is usable with the following elements: `<form:option>` 13.5.14 and `<form:radio>` 13.5.18.

The `form:current-selected` attribute has the data type `boolean` 18.3.3.

19.261 form:current-state

The `form:current-state` attribute specifies the state of a check box control.

The defined values for the `form:current-state` attribute are:

- `checked`: The check box is checked. The value of the control is submitted with the form.
- `unchecked`: The check box is not checked.
- `unknown`: This value is available only if the `form:is-tristate` attribute for a `<form:checkbox>` element is true. It indicates that a check box control is neither checked nor unchecked.

The `form:current-state` attribute is usable with the following element: `<form:checkbox>` 13.5.17.

The values of the `form:current-state` attribute are `unchecked`, `checked` or `unknown`.

19.262 form:current-value

The `form:current-value` attribute specifies the current status of an input control. It overrides the value of a `form:value` attribute, if one is present.

The defined value types for `form:current-value` attribute values are:

- `<form:combobox>` 13.5.11: `string`.
- `<form:date>` 13.5.8: `date`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- <form:file> 13.5.5: string.
- <form:formatted-text> 13.5.6: string.
- <form:number> 13.5.7: double.
- <form:text> 13.5.2: string.
- <form:textarea> 13.5.3: string.
- <form:time> 13.5.9: time.

The form:current-value attribute is usable with the following elements: <form:combobox> 13.5.11, <form:date> 13.5.8, <form:file> 13.5.5, <form:formatted-text> 13.5.6, <form:number> 13.5.7, <form:text> 13.5.2, <form:textarea> 13.5.3 and <form:time> 13.5.9.

The form:current-value attribute has the data type string 18.2.

19.263 form:data-field

The form:data-field attribute specifies the name of a column in the result set defined by a (data-aware) form. A control interchanges content with its column when:

- the current row of a form changes, the control is initialized with the value from its column.
- the user changes the content of a control, this changed value is written back to its column.

Note: consumers may delay this write-back, for instance until the control loses the focus, instead of updating the column value with every change in the control.

The form:data-field attribute is usable with the following elements: <form:checkbox> 13.5.17, <form:combobox> 13.5.11, <form:date> 13.5.8, <form:formatted-text> 13.5.6, <form:image-frame> 13.5.20, <form:listbox> 13.5.13, <form:number> 13.5.7, <form:radio> 13.5.18, <form:text> 13.5.2, <form:textarea> 13.5.3 and <form:time> 13.5.9.

The form:data-field attribute has the data type string 18.2.

19.264 form:datasource

The form:datasource attribute specifies the name of a data source to use for a form.

The defined values for the form:datasource attribute are:

- An IRI specifying a database connection.
- A data source name that an consumer can use to establish a database connection.
- The IRI of an OpenDocument database front-end document.

Note: The data source name is a programmatic name for a database front end document which allows it to reference data sources regardless of their real location. The mapping from data source names to specific instances of database front end documents is implementation-defined.

The form:datasource attribute is usable with the following element: <form:form> 13.3.

The values of the form:datasource attribute are a value of type anyIRI 18.3.2 or a value of type string 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.265 form:default-button

The `form:default-button` attribute specifies whether a button is the default button on a form. If a user clicks the default button or presses Return while an input control is focused, the consumer takes the same action.

If multiple buttons with `form:default-button` attributes with values of true are present in a form, it is implementation-defined which button is the default for the form.

The defined values for the `form:default-button` attribute are:

- `false`: button is not the default button for a form.
- `true`: button is the default button for a form.

The default value for this attribute is `false`.

The `form:default-button` attribute is usable with the following element: `<form:button>` 13.5.15.

The `form:default-button` attribute has the data type `boolean` 18.3.3.

19.266 form:delay-for-repeat

The `form:delay-for-repeat` attribute specifies a time-out to be used before a pressed mouse button results in repeating an action. The `form:delay-for-repeat` attribute is ignored unless a `form:repeat` attribute is present, and evaluates to `true`.

The default value for this attribute is `PT0.050S`.

The `form:delay-for-repeat` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:date>` 13.5.8, `<form:formatted-text>` 13.5.6, `<form:number>` 13.5.7, `<form:time>` 13.5.9 and `<form:value-range>` 13.5.24.

The `form:delay-for-repeat` attribute has the data type `duration` 18.2.

19.267 form:detail-fields

The `form:detail-fields` attribute specifies the names of the columns in contained forms that are related to columns in the containing form. The columns are used as parameters in the command for the contained form to retrieve the details from its containing form.

This attribute contains a comma “,” (U+002C, COMMA) separated list of field names.

The `form:detail-fields` attribute is usable with the following element: `<form:form>` 13.3.

The `form:detail-fields` attribute has the data type `string` 18.2.

19.268 form:disabled

The `form:disabled` attribute specifies whether a control can accept user input.

Controls that are disabled are not included in the tabbing navigation sequence and cannot be focused.

The defined values for the `form:disabled` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `false`: a control cannot accept user input.
- `true`: a control can accept user input.

The default value for this attribute is `false`.

The `form:disabled` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:checkbox>` 13.5.17, `<form:combobox>` 13.5.11, `<form:date>` 13.5.8, `<form:file>` 13.5.5, `<form:fixed-text>` 13.5.10, `<form:formatted-text>` 13.5.6, `<form:frame>` 13.5.19, `<form:grid>` 13.5.22, `<form:image>` 13.5.16, `<form:image-frame>` 13.5.20, `<form:listbox>` 13.5.13, `<form:number>` 13.5.7, `<form:password>` 13.5.4, `<form:radio>` 13.5.18, `<form:text>` 13.5.2, `<form:textarea>` 13.5.3, `<form:time>` 13.5.9 and `<form:value-range>` 13.5.24.

The `form:disabled` attribute has the data type `boolean` 18.3.3.

19.269 form:dropdown

The `form:dropdown` attribute specifies whether a list in a `<form:combobox>` or `<form:listbox>` element is always visible or is only visible when the user clicks the drop-down button.

The defined values for the `form:dropdown` attribute are:

- `false`: list is visible only when a user selects a drop-down button.
- `true`: list is always visible.

The default value for this attribute is `false`.

The `form:dropdown` attribute is usable with the following elements: `<form:combobox>` 13.5.11 and `<form:listbox>` 13.5.13.

The `form:dropdown` attribute has the data type `boolean` 18.3.3.

19.270 form:echo-char

The `form:echo-char` attribute specifies the character that a form uses to mask text that a user inputs in a password control.

The default value for this attribute is "*" (U+002A, ASTERISK).

The `form:echo-char` attribute is usable with the following element: `<form:password>` 13.5.4.

The `form:echo-char` attribute has the data type `character` 18.3.7.

19.271 form:enctype

The `form:enctype` attribute, when the value of the `form:method` attribute is `post`, specifies the content type used to submit the form to the server. Other MIME types may be acceptable. See §17.3.4 of [HTML4].

The default value for this attribute is `application/x-www-form-urlencoded`.

The `form:enctype` attribute is usable with the following element: `<form:form>` 13.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The form:enctype attribute has the data type string 18.2.

19.272 form:escape-processing

The form:escape-processing attribute, when the value of the form:command-type attribute is command, specifies whether the consumer processes the command before passing it to a database driver.

The defined values for the form:escape-processing attribute are:

- false: consumer does not process commands before passing them to a database driver.
- true: consumer does process commands before passing them to a database driver.

The default value for this attribute is true.

The form:escape-processing attribute is usable with the following element: <form:form> 13.3.

The form:escape-processing attribute has the data type boolean 18.3.3.

19.273 form:filter

The form:filter attribute specifies a filter for the SQL clause determined by the form:command-type and form:command attributes. If that SQL statement contains a filter (WHERE clause), the filter specified by the attribute value is conjunctively added to the existing filter.

The filter is only applied if the form:apply-filter attribute has the value true. 19.251.

Note: This allows OpenDocument consumers to toggle a filter on and off without losing the content of the form:filter attribute.

The form:filter attribute is usable with the following element: <form:form> 13.3.

The form:filter attribute has the data type string 18.2.

19.274 form:focus-on-click

The form:focus-on-click attribute specifies if a <form:button> element is given the focus in a form when the form button control for that element is operated.

The defined values for the form:focus-on-click attribute are:

- false: element not given focus.
- true: element given focus.

The form:focus-on-click attribute is usable with the following element: <form:button> 13.5.15.

The form:focus-on-click attribute has the data type boolean 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.275 form:for

The `form:for` attribute specifies a comma "," (U+002C, COMMA) separated list of `xml:id`s of control elements that are the targets of the elements where this attribute appears.

The `form:for` attribute is usable with the following elements: `<form:fixed-text>` 13.5.10 and `<form:frame>` 13.5.19.

The `form:for` attribute has the data type `string` 18.2.

19.276 form:id

The `form:id` attribute specifies an identifier for a control element.

OpenDocument consumers shall ignore a `form:id` attribute if it occurs on an element with an `xml:id` attribute value.

When consuming OpenDocument v1.0 and v1.1 documents, OpenDocument consumers should process `form:id` attributes as they were `xml:id` attributes.

OpenDocument producers may write `form:id` attributes for elements in addition to an `xml:id` attribute.

The value of a `form:id` attribute shall equal the value of an `xml:id` attribute on the same element.

The `form:id` attribute is deprecated in favor of `xml:id`. 19.914

The `form:id` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:checkbox>` 13.5.17, `<form:combobox>` 13.5.11, `<form:date>` 13.5.8, `<form:file>` 13.5.5, `<form:fixed-text>` 13.5.10, `<form:formatted-text>` 13.5.6, `<form:frame>` 13.5.19, `<form:generic-control>` 13.5.25, `<form:grid>` 13.5.22, `<form:hidden>` 13.5.21, `<form:image>` 13.5.16, `<form:image-frame>` 13.5.20, `<form:listbox>` 13.5.13, `<form:number>` 13.5.7, `<form:password>` 13.5.4, `<form:radio>` 13.5.18, `<form:text>` 13.5.2, `<form:textarea>` 13.5.3, `<form:time>` 13.5.9 and `<form:value-range>` 13.5.24.

The `form:id` attribute has the data type `NCName` 18.2.

19.277 form:ignore-result

The `form:ignore-result` attribute specifies whether to discard all results that are retrieved from an underlying data source.

The defined values for the `form:ignore-result` attribute are:

- `false`: data from query of data source not discarded.
- `true`: data from query of data source is discarded. Only new data can be inserted into a data source.

The default value for this attribute is `false`.

The `form:ignore-result` attribute is usable with the following element: `<form:form>` 13.3.

The `form:ignore-result` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.278 form:image-align

The `form:image-align` attribute specifies which border (`start`, `end`) or axis (`center`) of an image and a text are to be aligned.

The defined values for the `form:image-align` attribute are:

- `center`: image and text are centered.
- `end`: image and text are aligned on the end of the image.
- `start`: image and text are aligned on the start of the image.

If a `form:image-align` attribute is not present, it is assumed to be `center`.

The default value for this attribute is `center`.

The `form:image-align` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:checkbox>` 13.5.17 and `<form:radio>` 13.5.18.

The values of the `form:image-align` attribute are `start`, `center` or `end`.

19.279 form:image-data

The `form:image-data` attribute specifies the location of a file containing image data.

The `form:image-data` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:image>` 13.5.16 and `<form:image-frame>` 13.5.20.

The `form:image-data` attribute has the data type `anyIRI` 18.3.2.

19.280 form:image-position

If the `form:image-position` attribute specifies the location of an image relative to the text of a control.

The defined values for the `form:image-position` attribute are:

- `bottom`: image is placed below the text.
- `center`: image centered relative to the text.
- `end`: image is placed after the text.
- `start`: image is placed before the text.
- `top`: image is placed above the text.

The default value for this attribute is `center`.

The `form:image-position` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:checkbox>` 13.5.17 and `<form:radio>` 13.5.18.

The values of the `form:image-position` attribute are `center`, `start`, `end`, `top` or `bottom`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.281 form:is-tristate

The `form:is-tristate` attribute specifies a check box can have the values of `checked`, `unchecked` and `unknown`.

The defined values for the `form:is-tristate` attribute are:

- `false`: a check box can only have the values of checked and unchecked.
- `true`: a check box can have the values of checked, unchecked and unknown.

The default value for this attribute is `false`.

The `form:is-tristate` attribute is usable with the following element: `<form:checkbox>` 13.5.17.

The `form:is-tristate` attribute has the data type `boolean` 18.3.3.

19.282 form:label

The `form:label` attribute specifies the text for a control.

The `form:label` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:checkbox>` 13.5.17, `<form:column>` 13.5.23, `<form:fixed-text>` 13.5.10, `<form:frame>` 13.5.19, `<form:item>` 13.5.12, `<form:option>` 13.5.14 and `<form:radio>` 13.5.18.

The `form:label` attribute has the data type `string` 18.2.

19.283 form:linked-cell

The `form:linked-cell` attribute specifies a table cell to which the form control content should be linked. Linking means that the cell value and control content are equal at all times.

The table cell to link the control to can be specified as a `cellAddress`, or as a named cell range. In the latter case, if the named range contains more than one cell, the cell in the first row and first column of the range is linked to the form control.

If the attribute value matches the name of a named range as well as a cell address, it is interpreted as the name of a named range.

The `form:linked-cell` attribute is usable with the following elements: `<form:checkbox>` 13.5.17, `<form:combobox>` 13.5.11, `<form:date>` 13.5.8, `<form:file>` 13.5.5, `<form:formatted-text>` 13.5.6, `<form:listbox>` 13.5.13, `<form:number>` 13.5.7, `<form:password>` 13.5.4, `<form:radio>` 13.5.18, `<form:text>` 13.5.2, `<form:textarea>` 13.5.3, `<form:time>` 13.5.9 and `<form:value-range>` 13.5.24.

The values of the `form:linked-cell` attribute are a value of type `cellAddress` 18.3.4 or a value of type `string` 18.2.

19.284 form:list-linkage-type

The `form:list-linkage-type` attribute specifies how a control defined by a `<form:listbox>` elements interacts with a linked table cell.

The defined values for the `form:list-linkage-type` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `selection`: The text selected in the control is propagated to its linked cell. If text is entered into a cell linked to a `<form:listbox>` element, the list item whose label matches the cell text is selected, or all items are deselected if no such item exists.
- `selection-indices`: If a list item is selected in the control, its index value on a 1-based index is propagated to its its linked cell. If the value in the linked cell changes, the control should select the list item with the index described by the cell value, or deselect all items if the cell value cannot be interpreted as integer value, or does not specify a valid list index item.

The `form:list-linkage-type` attribute is usable with the following element: `<form:listbox>` 13.5.13.

The values of the `form:list-linkage-type` attribute are `selection` or `selection-indices`.

19.285 form:list-source

The `form:list-source` attribute specifies a source for the list entries in a list or combo box.

Obtaining those list entries is may be a multi-step process. The process depends upon the value of the `form:list-source-type` attribute on the same element.

If the `form:list-source-type` attribute has the value `value-list`, the content of the `form:list-source` attribute is ignored.

In all other cases, the content of the `form:list-source` attribute is resolved relative to a database connection or database front-end document. The `<form:form>` element containing the control defines this database connection or document by its `form:datasource` attribute.

For retrieving the list entries depending on the `form:list-source-type` attribute, the following algorithms are to be used:

If the `form:list-source-type` attribute has the value `table-fields`, the `form:list-source` attribute specifies the name of a database table. The names of the columns of this table, in the order as returned by the database driver, are used as list entries.

For all other values of `form:list-source-type`, the value of the `form:list-source` attribute is used to create a result set. For this, the first step is to transform the value of the `form:list-source` attribute into an SQL command as follows:

- `sql`, `sql-pass-through`: The SQL command is the content of the `form:list-source` attribute.
- `query`: The `form:list-source` attribute specifies the name of a query object in the database, whose underlying SQL command is to be used.
- `table`: The `form:list-source` attribute specifies the name of a database table, and the SQL command is the default SQL command to select all data from that table. This is "SELECT * FROM <table_name>", but consumers may find it necessary to add escape characters to a table name, if required by the database driver.

In a next step, the obtained SQL command is executed against the database. If the `form:list-source-type` attribute has the value `sql-pass-through` or `query`, and if the `db:escape-processing` attribute of the referred query has the value `false`, then the SQL command shall be passed directly to the database driver, without being interpreted and modified or normalized by the consumer.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

This execution produces a two-dimensional homogeneous result set, whose first-column-values form the entry list to be used.

The `form:list-source` attribute is usable with the following elements: `<form:combobox>` 13.5.11 and `<form:listbox>` 13.5.13.

The `form:list-source` attribute has the data type `string` 18.2.

19.286 form:list-source-type

The `form:list-source-type` attribute specifies how to populate the entry list in a combo box or list box control.

The defined values for the `form:list-source-type` attribute are:

- `query`: evaluated against the database front-end document or database connection defined by the `<form:form>` element which the control belongs to. The `form:list-source` attribute defines that evaluation. 19.285
- `sql`: evaluated against the database front-end document or database connection defined by the `<form:form>` element which the control belongs to. The `form:list-source` attribute defines that evaluation. 19.285
- `sql-pass-through`: evaluated against the database front-end document or database connection defined by the `<form:form>` element which the control belongs to. The `form:list-source` attribute defines that evaluation. 19.285
- `table`: evaluated against the database front-end document or database connection defined by the `<form:form>` element which the control belongs to. The `form:list-source` attribute defines that evaluation. 19.285
- `table-fields`: evaluated against the database front-end document or database connection defined by the `<form:form>` element which the control belongs to. The `form:list-source` attribute defines that evaluation. 19.285
- `value-list`: entry list populated by values specified by the `form:value` attributes of `<form:option>` child elements. This value is applicable to list boxes only.

The `form:list-source-type` attribute is usable with the following elements: `<form:combobox>` 13.5.11 and `<form:listbox>` 13.5.13.

The values of the `form:list-source-type` attribute are `table`, `query`, `sql`, `sql-pass-through`, `value-list` or `table-fields`.

19.287 form:master-fields

The `form:master-fields` attribute specifies the names of the columns in the result set represented by a parent form. Each time the parent form changes the current row, the nested form queries the database again based on the values of the master fields.

The attribute contains a comma “,” (U+002C, COMMA) separated list of field names.

The `form:master-fields` attribute is usable with the following element: `<form:form>` 13.3.

The `form:master-fields` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.288 form:max-length

The `form:max-length` attribute specifies the maximum number of characters that a user can enter in an input control.

The `form:max-length` attribute is usable with the following elements: `<form:combobox>` 13.5.11, `<form:date>` 13.5.8, `<form:file>` 13.5.5, `<form:formatted-text>` 13.5.6, `<form:number>` 13.5.7, `<form:password>` 13.5.4, `<form:text>` 13.5.2, `<form:textarea>` 13.5.3 and `<form:time>` 13.5.9.

The `form:max-length` attribute has the data type `nonNegativeInteger` 18.2.

19.289 form:max-value

19.289.1 General

The `form:max-value` attribute specifies the maximum value that a user can enter.

19.289.2 <form:date>

The value type of the `form:max-value` attribute is `date`.

The `form:max-value` attribute is usable with the following element: `<form:date>` 13.5.8.

The `form:max-value` attribute has the data type `date` 18.2.

19.289.3 <form:formatted-text>

The value type of the `form:max-value` attribute is `string`.

The `form:max-value` attribute is usable with the following element: `<form:formatted-text>` 13.5.6.

The `form:max-value` attribute has the data type `string` 18.2.

19.289.4 <form:number> and <form:value-range>

The value type of the `form:max-value` attribute is `double`.

The `form:max-value` attribute is usable with the following elements: `<form:number>` 13.5.7 and `<form:value-range>` 13.5.24.

The `form:max-value` attribute has the data type `double` 18.2.

19.289.5 <form:time>

The value type of the `form:max-value` attribute is `time`.

The `form:max-value` attribute is usable with the following element: `<form:time>` 13.5.9.

The `form:max-value` attribute has the data type `time` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.290 form:min-value

19.290.1 General

The `form:min-value` attribute specifies the minimum value that a user can enter.

19.290.2 <form:date>

The value type of the `form:min-value` attribute is `date`.

The `form:min-value` attribute is usable with the following element: `<form:date>` 13.5.8.
The `form:min-value` attribute has the data type `date` 18.2.

19.290.3 <form:formatted-text>

The value type of the `form:min-value` attribute is `string`.

The `form:min-value` attribute is usable with the following element: `<form:formatted-text>` 13.5.6.
The `form:min-value` attribute has the data type `string` 18.2.

19.290.4 <form:number> and <form:value-range>

The value type of the `form:min-value` attribute is `double`.

The `form:min-value` attribute is usable with the following elements: `<form:number>` 13.5.7 and `<form:value-range>` 13.5.24.
The `form:min-value` attribute has the data type `double` 18.2.

19.290.5 <form:time>

The value type of the `form:min-value` attribute is `time`.

The `form:min-value` attribute is usable with the following element: `<form:time>` 13.5.9.
The `form:min-value` attribute has the data type `time` 18.2.

19.291 form:method

The `form:method` attribute specifies the HTTP method used to submit data in a form to a server.

The defined values for the `form:list-source-type` attribute are:

- `get`: HTTP get method.
- `post`: HTTP post method.
- a value of type string

These values are not case sensitive.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The default value for this attribute is `get`.

The `form:method` attribute is usable with the following element: `<form:form>` 13.3.

The values of the `form:method` attribute are `get`, `post` or a value of type `string` 18.2.

19.292 form:multi-line

The `form:multi-line` attribute specifies whether a label is displayed on multiple lines.

The defined values for the `form:multi-line` attribute are:

- `false`: label is not displayed over multiple lines.
- `true`: label is displayed over multiple lines.

The default value for this attribute is `false`.

The `form:multi-line` attribute is usable with the following element: `<form:fixed-text>` 13.5.10.

The `form:multi-line` attribute has the data type `boolean` 18.3.3.

19.293 form:multiple

The `form:multiple` attribute specifies whether a user can select multiple items from a list box.

The defined values for the `form:multiple` attribute are:

- `false`: multiple items cannot be selected from a list box.
- `true`: multiple items can be selected from a list box.

The default value for this attribute is `false`.

The `form:multiple` attribute is usable with the following element: `<form:listbox>` 13.5.13.

The `form:multiple` attribute has the data type `boolean` 18.3.3.

19.294 form:name

The `form:name` attribute specifies the name of a form or control element.

Note: This may be used to give a form or control element an identity, which is can be used for scripting or for submitting the content of controls.

The `form:name` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:checkbox>` 13.5.17, `<form:column>` 13.5.23, `<form:combobox>` 13.5.11, `<form:date>` 13.5.8, `<form:file>` 13.5.5, `<form:fixed-text>` 13.5.10, `<form:form>` 13.3, `<form:formatted-text>` 13.5.6, `<form:frame>` 13.5.19, `<form:generic-control>` 13.5.25, `<form:grid>` 13.5.22, `<form:hidden>` 13.5.21, `<form:image>` 13.5.16, `<form:image-frame>` 13.5.20, `<form:listbox>` 13.5.13, `<form:number>` 13.5.7, `<form:password>` 13.5.4, `<form:radio>` 13.5.18, `<form:text>` 13.5.2, `<form:textarea>` 13.5.3, `<form:time>` 13.5.9 and `<form:value-range>` 13.5.24.

The `form:name` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.295 form:navigation-mode

The `form:navigation-mode` attribute specifies methods for navigation of a database aware form.

The defined values of the `form:navigation-mode` attribute are:

- `current`: An user interface is provided and the navigation is performed on the current form.
- `none`: a user interface is not provided, but the form may be navigated using the TAB and SHIFT/TAB keys on the keyboard.
- `parent`: a user interface is provided and the navigation is performed on the parent form of the current form.

The `form:navigation-mode` attribute is usable with the following element: `<form:form>` 13.3.

The values of the `form:navigation-mode` attribute are `none`, `current` or `parent`.

19.296 form:order

The `form:order` attribute specifies a sort criteria for a command.

The `form:order` attribute is usable with the following element: `<form:form>` 13.3.

The `form:order` attribute has the data type `string` 18.2.

19.297 form:orientation

The `form:orientation` attribute specifies the orientation of a control,

The defined values for the `form:orientation` attribute are:

- `horizontal`: control is oriented horizontally.
- `vertical`: control is oriented vertically.

The `form:orientation` attribute is usable with the following element: `<form:value-range>` 13.5.24.

The values of the `form:orientation` attribute are `horizontal` or `vertical`.

19.298 form:page-step-size

The `form:page-step-size` attribute specifies the preferred major value change offered through a UI (if applicable for the control used).

The value of a `form:page-step-size` attribute shall be positive.

The `form:page-step-size` attribute is usable with the following element: `<form:value-range>` 13.5.24.

The `form:page-step-size` attribute has the data type `positiveInteger` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.299 form:printable

The `form:printable` attribute specifies whether a control is printed when a user prints a document in which the control is contained.

The defined values for the `form:printable` attribute are:

- `false`: control not printed when a document containing the control is printed.
- `true`: control printed when a document containing the control is printed.

The default value for this attribute is `true`.

The `form:printable` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:checkbox>` 13.5.17, `<form:combobox>` 13.5.11, `<form:date>` 13.5.8, `<form:file>` 13.5.5, `<form:fixed-text>` 13.5.10, `<form:formatted-text>` 13.5.6, `<form:frame>` 13.5.19, `<form:grid>` 13.5.22, `<form:image>` 13.5.16, `<form:image-frame>` 13.5.20, `<form:listbox>` 13.5.13, `<form:number>` 13.5.7, `<form:password>` 13.5.4, `<form:radio>` 13.5.18, `<form:text>` 13.5.2, `<form:textarea>` 13.5.3, `<form:time>` 13.5.9 and `<form:value-range>` 13.5.24.

The `form:printable` attribute has the data type `boolean` 18.3.3.

19.300 form:property-name

The `form:property-name` attribute specifies the name of a property element. The name is unique within all `<form:property>` and `<form:list-property>` child elements of a <form:properties> element.

The `form:property-name` attribute is usable with the following elements: `<form:list-property>` 13.9 and `<form:property>` 13.8.

The `form:property-name` attribute has the data type `string` 18.2.

19.301 form:readonly

The `form:readonly` attribute specifies whether a user can modify the value of a control.

Read-only controls are included in a tabbing navigation sequence.

The defined values for the `form:readonly` attribute are:

- `false`: a user cannot modify the value of a control.
- `true`: a user can modify the value of a control.

The default value for this attribute is `false`.

The `form:readonly` attribute is usable with the following elements: `<form:combobox>` 13.5.11, `<form:date>` 13.5.8, `<form:file>` 13.5.5, `<form:formatted-text>` 13.5.6, `<form:image-frame>` 13.5.20, `<form:number>` 13.5.7, `<form:text>` 13.5.2, `<form:textarea>` 13.5.3 and `<form:time>` 13.5.9.

The `form:readonly` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.302 form:repeat

The `form:repeat` attribute specifies whether a form control, or a part of a form control repeats a defined action in response a continuous action by a user.

The defined values for the `form:repeat` attribute are:

- `false`: continuous action results in one defined action.
- `true`: continuous action results in repeating the defined action.

Note: Pressing and holding any key is an example of continuing a single act.

The `form:repeat` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:date>` 13.5.8, `<form:formatted-text>` 13.5.6, `<form:number>` 13.5.7, `<form:time>` 13.5.9 and `<form:value-range>` 13.5.24.

The `form:repeat` attribute has the data type `boolean` 18.3.3.

19.303 form:selected

The `form:selected` attribute specifies the default state of a radio button or option. A control initializes to the default state specified by this attribute.

In a group of radio buttons that share the same name, only one radio button can have a `form:selected` attribute set to true.

The defined values for the `form:selected` attribute are:

- `false`: not the default state of a radio button or option.
- `true`: default state of a radio button or option.

The default value for this attribute is `false`.

The `form:selected` attribute is usable with the following elements: `<form:option>` 13.5.14 and `<form:radio>` 13.5.18.

The `form:selected` attribute has the data type `boolean` 18.3.3.

19.304 form:size

The `form:size` attribute specifies the number of rows that are visible at a time in a combo box list or a list box list.

The `form:size` attribute is usable with the following elements: `<form:combobox>` 13.5.11 and `<form:listbox>` 13.5.13.

The `form:size` attribute has the data type `nonNegativeInteger` 18.2.

19.305 form:source-cell-range

The `form:source-cell-range` attribute specifies a rectangular cell range, whose content should be synchronized with a form controls item list. The form control reacts to changes in the cell range, that is, it adjusts its item list as cell range's content changes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Specify a cell range using cellRangeAddress or as a name of a named cell range. Display the left most columns of a range if the range contains more columns than a form control can display.

The `form:source-cell-range` attribute is usable with the following elements: `<form:combobox>` 13.5.11 and `<form:listbox>` 13.5.13.

The values of the `form:source-cell-range` attribute are a value of type `cellRangeAddress` 18.3.5 or a value of type `string` 18.2.

19.306 form:spin-button

The `form:spin-button` attribute specifies whether a form control for input has spin buttons. Spin buttons are used to increment or decrement all or part of an input value.

The defined values for the `form:spin-button` attribute are:

- `false`: form control does not have spin buttons.
- `true`: form control has spin buttons.

The default value for this attribute is `false`.

The `form:spin-button` attribute is usable with the following elements: `<form:date>` 13.5.8, `<form:formatted-text>` 13.5.6, `<form:number>` 13.5.7 and `<form:time>` 13.5.9.

The `form:spin-button` attribute has the data type `boolean` 18.3.3.

19.307 form:state

The `form:state` attribute specifies the default state of a check box control. A check box control initializes to the default state specified by this attribute.

The defined values for the `form:state` attribute are:

- `checked`: default state of a check box control.
- `unchecked`: check box control has no default state.
- `unknown`: state of check box control is not known.

The default value for this attribute is `unchecked`.

The `form:state` attribute is usable with the following element: `<form:checkbox>` 13.5.17.

The values of the `form:state` attribute are `unchecked`, `checked` or `unknown`.

19.308 form:step-size

The `form:step-size` attribute specifies the preferred minor value change offered through a UI (if applicable for the control used).

The value of a `form:step-size` attribute shall be positive.

The default value for this attribute is `1`.

The `form:step-size` attribute is usable with the following element: `<form:value-range>` 13.5.24.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `form:step-size` attribute has the data type `positiveInteger` 18.2.

19.309 form:tab-cycle

The `form:tab-cycle` attribute specifies how the consumer responds when the user presses the TAB key in the controls in a form. The behavior of the consumer depends on whether the form is bound to a data source.

The defined values for the `form:tab-cycle` attribute are:

- `current`: If a user presses the TAB key in the last control of the form, the focus moves to the first control specified in the tab order of the same form. If the form is data aware (13.1), then the current row of the result set subject to the form is not changed.
- `page`: If a user presses the TAB key in the last control of a form, the focus moves to the first control specified in the tab order for the next form.
- `records`: If a user presses the TAB key in the last control of the form, the focus moves to the first control specified in the tab order of the same form. If the form is data aware (13.1), then the current row of the result set subject to the form moves to the next row.

The `form:tab-cycle` attribute is usable with the following element: `<form:form>` 13.3.

The values of the `form:tab-cycle` attribute are `records`, `current` or `page`.

19.310 form:tab-index

The `form:tab-index` attribute specifies the tabbing navigation order of controls within a form. Tabbing order is the order of focus on controls when a user navigates the form using the TAB key on the keyboard. Elements within other elements can be included in a tabbing order. Values do not have to be sequential and they do not have to begin with a particular value.

The rules of tab navigation are:

1) Controls that have the `form:disabled` attribute set to true are not included in the navigation, independent of their `form:tab-index` value.
2) Controls that have the same values for the `form:tab-index` attribute are navigated in order of their position in the form.
3) The navigation starts with the controls with lowest non-zero `form:tab-index` value.
4) When the controls with a certain `form:tab-index` value have been navigated, navigation continues with the controls with the next highest value.
5) After the controls with the highest value have been navigated, navigation continues with the controls that do not contain the `form:tab-index` attribute or contain the attribute with a value of 0.

The default value for this attribute is `0`.

The `form:tab-index` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:checkbox>` 13.5.17, `<form:combobox>` 13.5.11, `<form:date>` 13.5.8, `<form:file>` 13.5.5, `<form:formatted-text>` 13.5.6, `<form:grid>` 13.5.22, `<form:image>` 13.5.16, `<form:listbox>` 13.5.13, `<form:number>` 13.5.7, `<form:password>` 13.5.4, `<form:radio>` 13.5.18, `<form:text>` 13.5.2, `<form:textarea>` 13.5.3, `<form:time>` 13.5.9 and `<form:value-range>` 13.5.24.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The form:tab-index attribute has the data type nonNegativeInteger 18.2.

19.311 form:tab-stop

The form:tab-stop attribute specifies whether a control is included in the tabbing navigation order.

The defined values for the form:tab-stop attribute are:

- false: control is not included in tabbing navigation order.
- true: control is included in tabbing navigation order.

The default value for this attribute is true.

The form:tab-stop attribute is usable with the following elements: <form:button> 13.5.15, <form:checkbox> 13.5.17, <form:combobox> 13.5.11, <form:date> 13.5.8, <form:file> 13.5.5, <form:formatted-text> 13.5.6, <form:grid> 13.5.22, <form:image> 13.5.16, <form:listbox> 13.5.13, <form:number> 13.5.7, <form:password> 13.5.4, <form:radio> 13.5.18, <form:text> 13.5.2, <form:textarea> 13.5.3, <form:time> 13.5.9 and <form:value-range> 13.5.24.

The form:tab-stop attribute has the data type boolean 18.3.3.

19.312 form:text-style-name

The form:text-style-name attribute specifies paragraph style that is applied to all controls for a column. Unlike other paragraph styles, this style may reference a data style.

The form:text-style-name attribute is usable with the following element: <form:column> 13.5.23.

The form:text-style-name attribute has the data type styleNameRef 18.3.32.

19.313 form:title

The form:title attribute contains additional information about a control. The value of the attribute may be used as a "tool tip" (a short message that appears when the pointing device pauses over the form element). Audio user agents may speak the title information in a similar context.

The form:title attribute is usable with the following elements: <form:button> 13.5.15, <form:checkbox> 13.5.17, <form:combobox> 13.5.11, <form:date> 13.5.8, <form:file> 13.5.5, <form:fixed-text> 13.5.10, <form:formatted-text> 13.5.6, <form:frame> 13.5.19, <form:grid> 13.5.22, <form:image> 13.5.16, <form:image-frame> 13.5.20, <form:listbox> 13.5.13, <form:number> 13.5.7, <form:password> 13.5.4, <form:radio> 13.5.18, <form:text> 13.5.2, <form:textarea> 13.5.3, <form:time> 13.5.9 and <form:value-range> 13.5.24.

The form:title attribute has the data type string 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.314 form:toggle

The `form:toggle` attribute specifies whether a form button control acts as push button or as toggle button.

Note: A toggle button is similar to a check box (in fact, it could be considered a different visual representation of a check box), in that operating it once, by either mouse or keyboard, toggles its state between "pressed" and "not pressed".

A push button triggers an action, which happens every time the user operates the button.

The defined values for the `form:toggle` attribute are:

- `false`: form button control acts as push button.
- `true`: form button control acts as a toggle button.

The default value for this attribute is `false`.

The `form:toggle` attribute is usable with the following element: `<form:button>` 13.5.15.
The `form:toggle` attribute has the data type `boolean` 18.3.3.

19.315 form:validation

The `form:validation` attribute specifies whether the text that the user enters is validated during input against the input format associated with the control.

The defined values for the `form:validation` attribute are:

- `true`: invalid content is detected during input.
- `false`: invalid content is not detected during input.

The default value for this attribute is `false`.

The `form:validation` attribute is usable with the following element: `<form:formatted-text>` 13.5.6.
The `form:validation` attribute has the data type `boolean` 18.3.3.

19.316 form:value

19.316.1 General

The `form:value` attribute specifies the default value of an input control.

19.316.2 <form:button>

The value type of the `form:value` attribute is `boolean`.

The `form:value` attribute is usable with the following element: `<form:button>` 13.5.15.
The `form:value` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.316.3 <form:date>

The value type of the `form:value` attribute is `date`.

The `form:value` attribute is usable with the following element: `<form:date>` 13.5.8.
The `form:value` attribute has the data type `date` 18.2.

19.316.4 <form:number> and <form:value-range>

The value type of the `form:value` attribute is `number`.

The `form:value` attribute is usable with the following elements: `<form:number>` 13.5.7 and `<form:value-range>` 13.5.24.
The `form:value` attribute has the data type `double` 18.2.

19.316.5 <form:checkbox>, <form:combobox>, <form:file>, <form:formatted-text>, <form:hidden>, <form:image>, <form:option>, <form:password>, <form:radio>, <form:text>, <form:textarea>

The value type of the `form:value` attribute is `string`.

The `form:value` attribute is usable with the following elements: `<form:checkbox>` 13.5.17, `<form:combobox>` 13.5.11, `<form:file>` 13.5.5, `<form:formatted-text>` 13.5.6, `<form:hidden>` 13.5.21, `<form:image>` 13.5.16, `<form:option>` 13.5.14, `<form:password>` 13.5.4, `<form:radio>` 13.5.18, `<form:text>` 13.5.2 and `<form:textarea>` 13.5.3.
The `form:value` attribute has the data type `string` 18.2.

19.316.6 <form:time>

The value type of the `form:value` attribute is `time`.

The `form:value` attribute is usable with the following element: `<form:time>` 13.5.9.
The `form:value` attribute has the data type `time` 18.2.

19.317 form:visual-effect

The `form:visual-effect` attributes specifies a visual effect to apply to a control.

The defined values for the `form:visual-effect` attribute are:

- `3d`: 3D visual effect.
- `flat`: flat visual effect.

The `form:visual-effect` attribute is usable with the following elements: `<form:checkbox>` 13.5.17 and `<form:radio>` 13.5.18.
The values of the `form:visual-effect` attribute are `flat` or `3d`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.318 form:xforms-list-source

The `form:xforms-list-source` attribute specifies a reference to an `<xforms:bind>` element, and creates a list entry for each node in the node-set defined by that attribute.

The `form:xforms-list-source` attribute is usable with the following element: `<form:listbox>` 13.5.13.

The `form:xforms-list-source` attribute has the data type `string` 18.2.

19.319 form:xforms-submission

The `form:xforms-submission` attribute specifies the name of an `<xforms:submission>` element for a `<form:button>` control.

The `form:xforms-submission` attribute is usable with the following element: `<form:button>` 13.5.15.

The `form:xforms-submission` attribute has the data type `string` 18.2.

19.320 grddl:transformation

The `grddl:transformation` attributes link to a transformation for extracting RDF data from the document. See [GRDDL].

Note: This transformation is intended to be interpreted by consumers that do not support OpenDocument.

The referenced transformations should map OpenDocument elements that are children of the `<office:meta>` element to RDF. They should also extract the RDF triples stored as RDFa attributes in the document content and styles.

Note: Please check the OASIS Open Document Format for Office Applications (OpenDocument) TC's web site for GRDDL transformations provided by the OASIS Open Document Format for Office Applications (OpenDocument) TC.

The `grddl:transformation` attribute is usable with the following elements: `<office:document>` 3.1.2, `<office:document-content>` 3.1.3.2, `<office:document-meta>` 3.1.3.4, `<office:document-settings>` 3.1.3.5 and `<office:document-styles>` 3.1.3.3.

The value of the `grddl:transformation` attribute is a white space separated lists of values of type `anyIRI` 18.3.2, including the empty list.

19.321 meta:cell-count

The `meta:cell-count` attribute specifies the number of table cells that an OpenDocument producer has counted for a document.

The `meta:cell-count` attribute is usable with the following element: `<meta:document-statistic>` 4.3.2.18.

The `meta:cell-count` attribute has the data type `nonNegativeInteger` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.322 meta:character-count

The `meta:character-count` attribute specifies the number of characters that an OpenDocument producer has counted for a document.

The value of the `meta:character-count` attribute is implementation-dependent.

The `meta:character-count` attribute is usable with the following element: `<meta:document-statistic>` 4.3.2.18.

The `meta:character-count` attribute has the data type `nonNegativeInteger` 18.2.

19.323 meta:date

The `meta:date` attribute specifies the date and time when a template was last modified, prior to being used to create the current document.

The `meta:date` attribute is usable with the following element: `<meta:template>` 4.3.2.12.

The `meta:date` attribute has the data type `dateTime` 18.2.

19.324 meta:delay

The `meta:delay` attribute specifies a reload delay.

The `meta:delay` attribute is usable with the following element: `<meta:auto-reload>` 4.3.2.13.

The `meta:delay` attribute has the data type `duration` 18.2.

19.325 meta:draw-count

The `meta:draw-count` attribute specifies the number of drawing-shapes that an OpenDocument producer has counted for a document.

The `meta:draw-count` attribute is usable with the following element: `<meta:document-statistic>` 4.3.2.18.

The `meta:draw-count` attribute has the data type `nonNegativeInteger` 18.2.

19.326 meta:frame-count

The `meta:frame-count` attribute specifies the number of text-boxes that an OpenDocument producer has counted for a document.

The `meta:frame-count` attribute is usable with the following element: `<meta:document-statistic>` 4.3.2.18.

The `meta:frame-count` attribute has the data type `nonNegativeInteger` 18.2.

19.327 meta:image-count

The `meta:image-count` attribute specifies the number of images that an OpenDocument producer has counted for a document.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The meta:image-count attribute is usable with the following element: <meta:document-statistic> 4.3.2.18.

The meta:image-count attribute has the data type nonNegativeInteger 18.2.

19.328 meta:name

The meta:name attribute specifies the name of a metadata element. The name shall be unique within the domain of <meta:user-defined> elements.

The meta:name attribute is usable with the following element: <meta:user-defined> 4.3.3.

The meta:name attribute has the data type string 18.2.

19.329 meta:non-whitespace-character-count

The meta:non-whitespace-character-count attribute specifies the number of non-white space characters that an OpenDocument producer has counted for a document.

The value of the meta:non-whitespace-character-count attribute is implementation-dependent.

The meta:non-whitespace-character-count attribute is usable with the following element: <meta:document-statistic> 4.3.2.18.

The meta:non-whitespace-character-count attribute has the data type nonNegativeInteger 18.2.

19.330 meta:object-count

The meta:object-count attribute specifies the number of embedded objects stored in OpenDocument format that the OpenDocument producer has counted for the document.

The meta:object-count attribute is usable with the following element: <meta:document-statistic> 4.3.2.18.

The meta:object-count attribute has the data type nonNegativeInteger 18.2.

19.331 meta:ole-object-count

The meta:ole-object-count attribute specifies the number of embedded objects stored in a different format than OpenDocument that the OpenDocument producer has counted for the document.

The meta:ole-object-count attribute is usable with the following element: <meta:document-statistic> 4.3.2.18.

The meta:ole-object-count attribute has the data type nonNegativeInteger 18.2.

19.332 meta:page-count

The meta:page-count attribute specifies the number of pages that an OpenDocument producer has calculated for a document.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The value of the meta:page-count attribute is implementation-dependent.

The meta:page-count attribute is usable with the following element: <meta:document-statistic> 4.3.2.18.

The meta:page-count attribute has the data type nonNegativeInteger 18.2.

19.333 meta:paragraph-count

The meta:paragraph-count attribute specifies the number of paragraphs that an OpenDocument producer has counted for a document.

The meta:paragraph-count attribute is usable with the following element: <meta:document-statistic> 4.3.2.18.

The meta:paragraph-count attribute has the data type nonNegativeInteger 18.2.

19.334 meta:row-count

The meta:row-count attribute specifies the number of lines contained in a document instance.

The value of the meta:row-count attribute is implementation-dependent.

The meta:row-count attribute is usable with the following element: <meta:document-statistic> 4.3.2.18.

The meta:row-count attribute has the data type nonNegativeInteger 18.2.

19.335 meta:sentence-count

The meta:sentence-count attribute specifies the number of sentences that an OpenDocument producer has counted for a document.

The value of the meta:sentence-count attribute is implementation-dependent.

The meta:sentence-count attribute is usable with the following element: <meta:document-statistic> 4.3.2.18.

The meta:sentence-count attribute has the data type nonNegativeInteger 18.2.

19.336 meta:syllable-count

The meta:syllable-count attribute specifies the number of syllables that an OpenDocument producer has counted for a document.

The value of the meta:syllable-count attribute is implementation-dependent.

The meta:syllable-count attribute is usable with the following element: <meta:document-statistic> 4.3.2.18.

The meta:syllable-count attribute has the data type nonNegativeInteger 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.337 meta:table-count

The `meta:table-count` attribute specifies the number of `<table:table>` elements contained in a document instance.

The `meta:table-count` attribute is usable with the following element: `<meta:document-statistic>` 4.3.2.18.

The `meta:table-count` attribute has the data type `nonNegativeInteger` 18.2.

19.338 meta:value-type

The `meta:value-type` attribute specifies the type of a metadata element.

The defined values for the `meta:value-type` attribute are:

- `boolean`: 18.3.3
- `date`: 18.2
- `float`: 18.2
- `time`: 18.2
- `string`: 18.2

The default type for meta-data elements is `string`.

The `meta:value-type` attribute is usable with the following element: `<meta:user-defined>` 4.3.3.

The values of the `meta:value-type` attribute are `float`, `date`, `time`, `boolean` or `string`.

19.339 meta:word-count

The `meta:word-count` attribute specifies the number of words that an OpenDocument producer has counted for a document.

The value of the `meta:word-count` attribute is implementation-dependent.

The `meta:word-count` attribute is usable with the following element: `<meta:document-statistic>` 4.3.2.18.

The `meta:word-count` attribute has the data type `nonNegativeInteger` 18.2.

19.340 number:automatic-order

The `number:automatic-order` attribute specifies whether data is ordered to match the default order for the language and country of a data style.

The defined values for the `number:automatic-order` attribute are:

- `false`: data is not ordered to match the default order for the language and country of a data style.
- `true`: data is ordered to match the default order for the language and country of a data style.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The default value for this attribute is `false`.

The `number:automatic-order` attribute is usable with the following elements: `<number:currency-style>` 16.27.7 and `<number:date-style>` 16.27.10.

The `number:automatic-order` attribute has the data type `boolean` 18.3.3.

19.341 number:calendar

The `number:calendar` attribute specifies the calendar system used to extract parts of a date.

The defined values for the `number:calendar` attribute are:

- `buddhist`: Buddhist calendar, identical to Gregorian calendar but offset by -543 years.
- `gengou`: Japanese Gengou calendar, Emperor eras. Identical to Gregorian calendar but with different eras for each emperor. Consumers may implement only the modern eras starting 1868, Meiji, Taisho, Showa and Heisei. Earlier dates are then displayed using the Gregorian calendar [JIS X 0301].
- `gregorian`: Gregorian calendar with cut-off date 1582-10-04, 1582-10-15 following. Dates before cut-off date are calculated in Julian proleptic calendar [ISO8601]., Section 2.4.1.
- `hanja`: Additional Gregorian calendar in Korean locales, uses differently localized day and month names.
- `hanja_yoil`: Legacy alias for `hanja`
- `hijri`: Islamic Hijri lunar calendar (religious, non-civil).
- `jewish`: Jewish lunisolar calendar.
- `ROC`: Taiwanese Minguo calendar, identical to Gregorian calendar offset by -1911 years.

The attribute value may also be a string value. If this attribute is not specified, the default calendar system for the locale of the data style is used.

The `number:calendar` attribute is usable with the following elements: `<number:day>` 16.27.11, `<number:day-of-week>` 16.27.15, `<number:era>` 16.27.14, `<number:month>` 16.27.12, `<number:quarter>` 16.27.17, `<number:week-of-year>` 16.27.16 and `<number:year>` 16.27.13.

The values of the `number:calendar` attribute are `gregorian`, `gengou`, `ROC`, `hanja_yoil`, `hanja`, `hijri`, `jewish`, `buddhist` or a value of type `string` 18.2.

19.342 number:country

The `number:country` attribute specifies a country code for a data style. The country code is used for formatting properties whose evaluation is locale dependent.

If a country is not specified, either the system settings or the setting for the system's country are used, depending on the property whose value should be evaluated.

The `number:country` attribute on a `<number:currency-symbol>` element, specifies the country of a currency symbol.

The `number:country` attribute is usable with the following elements: `<number:boolean-style>` 16.27.23, `<number:currency-style>` 16.27.7, `<number:currency-symbol>`

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

16.27.8, <number:date-style> 16.27.10, <number:number-style> 16.27.2, <number:percentage-style> 16.27.9, <number:text-style> 16.27.25 and <number:time-style> 16.27.18.

The number:country attribute has the data type countryCode 18.3.11.

19.343 number:decimal-places

19.343.1 General

The number:decimal-places attribute specifies the number of decimal places to display.

19.343.2 <number:number>

If the number:decimal-places attribute is not specified, the number of decimal places specified by the default table cell style is used.

The number:decimal-places attribute is usable with the following element: <number:number> 16.27.3.

The number:decimal-places attribute has the data type integer 18.2.

19.343.3 <number:seconds>

If the number:decimal-places attribute is not specified or if the value of the attribute is 0, seconds are not displayed.

For a <number:seconds> 16.27.21 element the default value for this attribute is 0.

The number:decimal-places attribute is usable with the following element: <number:seconds> 16.27.21.

The number:decimal-places attribute has the data type integer 18.2.

19.343.4 <number:scientific-number>

The number:decimal-places attribute specifies the number of decimal places to display.

If the number:decimal-places attribute is not specified, the number of decimal places specified by the default table cell style is used.

The number:decimal-places attribute is usable with the following element: <number:scientific-number> 16.27.5.

The number:decimal-places attribute has the data type integer 18.2.

19.344 number:decimal-replacement

The number:decimal-replacement attribute specifies a replacement text for decimal places if a number style specifies that decimal places are used but the number displayed is an integer.

Note: What replacement text is supported is implementation-dependent.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The number:decimal-replacement attribute is usable with the following element: <number:number> 16.27.3.

The number:decimal-replacement attribute has the data type string 18.2.

19.345 number:denominator-value

The number:denominator-value attribute specifies an integer value that is used as denominator of a fraction. If this attribute is not present, a denominator that is appropriate for displaying the number is used.

Note: The number:denominator-value attribute is used with number:grouping 19.348, number:min-denominator-digits 19.350, number:min-integer-digits 19.352 and number:min-numerator-digits 19.353 to define the display of a floating point number as a fraction.

The number:denominator-value attribute is usable with the following element: <number:fraction> 16.27.6.

The number:denominator-value attribute has the data type integer 18.2.

19.346 number:display-factor

The number:display-factor attribute specifies a factor by which each number is scaled (divided) before displaying.

The default value for this attribute is 1.

The number:display-factor attribute is usable with the following element: <number:number> 16.27.3.

The number:display-factor attribute has the data type double 18.2.

19.347 number:format-source

The number:format-source attribute specifies the source of definitions of the short and long display formats.

The defined values for the number:format-source attribute are:

- fixed: the values short and long of the number:style attribute are defined by this standard.
- language: the meaning of the values long and short of the number:style attribute depend upon the number:language and number:country attributes of the date style. If neither of those attributes are specified, consumers should use their default locale for short and long date and time formats.

The default value for this attribute is fixed.

The number:format-source attribute is usable with the following elements: <number:date-style> 16.27.10 and <number:time-style> 16.27.18.

The values of the number:format-source attribute are fixed or language.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.348 number:grouping

The `number:grouping` attribute specifies whether the integer digits of a number should be grouped using a separator character.

The grouping character that is used and the number of digits that are grouped together depends on the language and country of the style.

The defined values for the `number:grouping` attribute are:

- `false`: integer digits of a number are note grouped using a separator character.
- `true`: integer digits of a number should be grouped by a separator character.

The default value for this attribute is `false`.

The `number:grouping` attribute is usable with the following elements: `<number:fraction>` 16.27.6, `<number:number>` 16.27.3 and `<number:scientific-number>` 16.27.5.

The `number:grouping` attribute has the data type `boolean` 18.3.3.

19.349 number:language

The `number:language` attribute specifies a language code. The country code is used for formatting properties whose evaluation is locale dependent.

If a language code is not specified, either the system settings or the setting for the system's language are used, depending on the property whose value should be evaluated.

The `number:language` attribute is usable with the following elements: `<number:boolean-style>` 16.27.23, `<number:currency-style>` 16.27.7, `<number:currency-symbol>` 16.27.8, `<number:date-style>` 16.27.10, `<number:number-style>` 16.27.2, `<number:percentage-style>` 16.27.9, `<number:text-style>` 16.27.25 and `<number:time-style>` 16.27.18.

The `number:language` attribute has the data type `languageCode` 18.3.17.

19.350 number:min-denominator-digits

The `number:min-denominator-digits` attribute specifies the minimum number of digits to use to display the denominator of a fraction.

The `number:min-denominator-digits` attribute is usable with the following element: `<number:fraction>` 16.27.6.

The `number:min-denominator-digits` attribute has the data type `integer` 18.2.

19.351 number:min-exponent-digits

The `number:min-exponent-digits` attribute specifies the minimum number of digits to use to display an exponent.

The `number:min-exponent-digits` attribute is usable with the following element: `<number:scientific-number>` 16.27.5.

The `number:min-exponent-digits` attribute has the data type `integer` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.352 number:min-integer-digits

The `number:min-integer-digits` attribute specifies the minimum number of integer digits to display in a number, a scientific number, or a fraction.

For a `<number:fraction>` element, if the `number:min-integer-digits` attribute is not present, no integer portion is displayed.

The `number:min-integer-digits` attribute is usable with the following elements: `<number:fraction>` 16.27.6, `<number:number>` 16.27.3 and `<number:scientific-number>` 16.27.5.

The `number:min-integer-digits` attribute has the data type `integer` 18.2.

19.353 number:min-numerator-digits

The `number:min-numerator-digits` attribute specifies the minimum number of digits to use to display the numerator in a fraction.

The `number:min-numerator-digits` attribute is usable with the following element: `<number:fraction>` 16.27.6.

The `number:min-numerator-digits` attribute has the data type `integer` 18.2.

19.354 number:position

The `number:position` attribute specifies the position where text appears.

The index of a position starts with 1 and is counted by digits from right to left in the integer part of a number, starting left from a decimal separator if one exists, or from the last digit of the number. Text is inserted before the digit at the specified position. If the value of `number:position` attribute is greater than the value of `number:min-integer-digits` and greater than the number of integer digits in the number, text is prepended to the number.

The `number:position` attribute is usable with the following element: `<number:embedded-text>` 16.27.4.

The `number:position` attribute has the data type `integer` 18.2.

19.355 number:possessive-form

The `number:possessive-form` attribute specifies whether the month is displayed as a noun or using the possessive form.

The `number:possessive-form` attribute is only applied when a `number:textual` attribute on the same `<number:month>` element has the value of true.

The defined values for the `number:possessive-form` attribute are:

- `false`: the name of the month is displayed in nominative form.
- `true`: the name of the month is displayed in possessive form.

The `number:possessive-form` attribute is usable with the following element: `<number:month>` 16.27.12.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The number:possessive-form attribute has the data type boolean 18.3.3.

19.356 number:rfc-language-tag

The number:rfc-language-tag attribute specifies a language identifier according to the rules of [RFC5646], or its successors.

It shall only be used if its value can not be expressed as a valid combination of the number:language, number:script and number:country attributes.

Producers may add support for consumers that don't support the number:rfc-language-tag attribute by specifying number:language, number:script and number:country attributes with values as close as possible to the actual value of the number:rfc-language-tag attribute. Producers shall not use values for these attributes that contradict the value of the table:rfc-language-tag attribute.

The number:rfc-language-tag attribute is usable with the following elements: <number:boolean-style> 16.27.23, <number:currency-style> 16.27.7, <number:currency-symbol> 16.27.8, <number:date-style> 16.27.10, <number:number-style> 16.27.2, <number:percentage-style> 16.27.9, <number:text-style> 16.27.25 and <number:time-style> 16.27.18.

The number:rfc-language-tag attribute has the data type language 18.3.16.

19.357 number:script

The number:script attribute specifies a script code. The script code is used for formatting properties whose evaluation is locale dependent. The attribute should be used only if necessary according to the rules of §2.2.3 of [RFC5646], or its successors.

The number:script attribute is usable with the following elements: <number:boolean-style> 16.27.23, <number:currency-style> 16.27.7, <number:currency-symbol> 16.27.8, <number:date-style> 16.27.10, <number:number-style> 16.27.2, <number:percentage-style> 16.27.9, <number:text-style> 16.27.25 and <number:time-style> 16.27.18.

The number:script attribute has the data type scriptCode 18.3.29.

19.358 number:style

19.358.1 General

The number:style attribute specifies whether the content of a time element is displayed in short or long format. The value of this attribute can be short or long. The meaning of these values depends on the value of the number:format-source attribute that is attached to a date or time style.

19.358.2 <number:day>

If the value of the number:format-source attribute is fixed the number:style attribute on the same element has the defined values:

- short: the day of month is displayed using one or two digits.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `long`: the day of month is displayed using two digits.

The `number:style` attribute is usable with the following element: `<number:day>` 16.27.11.

The values of the `number:style` attribute are `short` or `long`.

19.358.3 <number:day-of-week>

If the value of the `number:format-source` attribute is `fixed` the `number:style` attribute on the same element has the defined values:

- `short`: abbreviated name of the day is displayed.
- `long`: full name of the day is displayed.

The `number:style` attribute is usable with the following element: `<number:day-of-week>` 16.27.15.

The values of the `number:style` attribute are `short` or `long`.

19.358.4 <number:era>

If the value of the `number:format-source` attribute is `fixed` the `number:style` attribute on the same element has the defined values:

- `short`: abbreviated era name is used.
- `long`: full era name is used.

The `number:style` attribute is usable with the following element: `<number:era>` 16.27.14.

The values of the `number:style` attribute are `short` or `long`.

19.358.5 <number:hours>

If the value of the `number:format-source` attribute is `fixed` the `number:style` attribute on the same element has the defined values:

- `short`: hours are displayed using at least one digit.
- `long`: hours are displayed using at least two digits.

The `number:style` attribute is usable with the following element: `<number:hours>` 16.27.19.

The values of the `number:style` attribute are `short` or `long`.

19.358.6 <number:minutes>

If the value of the `number:format-source` attribute is `fixed` the `number:style` attribute on the same element has the defined values:

- `short`: minutes are displayed using at least one digit.
- `long`: minutes are displayed using at least two digits.

The `number:style` attribute is usable with the following element: `<number:minutes>` 16.27.20.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The values of the number:style attribute are short or long.

19.358.7 <number:month>

If the value of the number:format-source attribute is fixed the number:style attribute on the same element has the defined values:

- short: abbreviated name of the month is displayed or the month is displayed using one or two digits.
- long: full name of the month is displayed or the month is displayed using two digits.

The number:style attribute is usable with the following element: <number:month> 16.27.12.

The values of the number:style attribute are short or long.

19.358.8 <number:quarter>

If the value of the number:format-source attribute is fixed the number:style attribute on the same element has the defined values:

- short: abbreviated name of the quarter is displayed.
- long: full name of the quarter is displayed.

The number:style attribute is usable with the following element: <number:quarter> 16.27.17.

The values of the number:style attribute are short or long.

19.358.9 <number:seconds>

if the value of the number:format-source attribute is fixed the number:style attribute on the same element has the defined values:

- short: seconds are displayed using at least one digit.
- long: seconds are displayed using at least two digits.

The number:style attribute is usable with the following element: <number:seconds> 16.27.21.

The values of the number:style attribute are short or long.

19.358.10 <number:year>

If the value of the number:format-source attribute is fixed the number:style attribute on the same element has the defined values:

- short: year is displayed using two digits.
- long: year is displayed using four digits.

The number:style attribute is usable with the following element: <number:year> 16.27.13.

The values of the number:style attribute are short or long.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.359 number:textual

The number:textual attribute specifies whether the name or number of a month is displayed in the month element of a date.

The defined values for the number:textual element are:

- false: the number of the month is displayed.
- true: the name of the month is displayed.

The name or number of a month is defined by the number:calendar attribute on the same parent element as the number:textual attribute.

The default value for this attribute is false.

The number:textual attribute is usable with the following element: <number:month> 16.27.12.

The number:textual attribute has the data type boolean 18.3.3.

19.360 number:title

The number:title attribute specifies the title of a data style.

The number:title attribute is usable with the following elements: <number:boolean-style> 16.27.23, <number:currency-style> 16.27.7, <number:date-style> 16.27.10, <number:number-style> 16.27.2, <number:percentage-style> 16.27.9, <number:text-style> 16.27.25 and <number:time-style> 16.27.18.

The number:title attribute has the data type string 18.2.

19.361 number:transliteration-country

The number:transliteration-country attribute specifies a country code in conformance with [RFC5646].

If no language/country (locale) combination is specified the locale of the data style is used.

The number:transliteration-country attribute is usable with the following elements: <number:boolean-style> 16.27.23, <number:currency-style> 16.27.7, <number:date-style> 16.27.10, <number:number-style> 16.27.2, <number:percentage-style> 16.27.9, <number:text-style> 16.27.25 and <number:time-style> 16.27.18.

The number:transliteration-country attribute has the data type countryCode 18.3.11.

19.362 number:transliteration-format

The number:transliteration-format attribute specifies which number characters to use.

The value of the number:transliteration-format attribute shall be a decimal "DIGIT ONE" character with numeric value 1 as listed in the Unicode Character Database file UnicodeData.txt with value 'Nd' (Numeric decimal digit) in the General_Category/Numeric_Type property field 6 and value '1' in the Numeric_Value fields 7 and 8, respectively as listed in DerivedNumericValues.txt

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If no format is specified the default ASCII representation of Latin-Indic digits is used, other transliteration attributes present in that case are ignored.

The default value for this attribute is `1`.

The `number:transliteration-format` attribute is usable with the following elements: `<number:boolean-style>` 16.27.23, `<number:currency-style>` 16.27.7, `<number:date-style>` 16.27.10, `<number:number-style>` 16.27.2, `<number:percentage-style>` 16.27.9, `<number:text-style>` 16.27.25 and `<number:time-style>` 16.27.18.

The `number:transliteration-format` attribute has the data type `string` 18.2.

19.363 number:transliteration-language

The `number:transliteration-language` attribute specifies a language code in conformance with [RFC5646].

If no language/country (locale) combination is specified the locale of the data style is used.

The `number:transliteration-language` attribute is usable with the following elements: `<number:boolean-style>` 16.27.23, `<number:currency-style>` 16.27.7, `<number:date-style>` 16.27.10, `<number:number-style>` 16.27.2, `<number:percentage-style>` 16.27.9, `<number:text-style>` 16.27.25 and `<number:time-style>` 16.27.18.

The `number:transliteration-language` attribute has the data type `countryCode` 18.3.11.

19.364 number:transliteration-style

The `number:transliteration-style` attribute specifies the transliteration-format of a number system.

The semantics of the values of the `number:transliteration-style` attribute are locale and implementation-dependent.

The default value for this attribute is `short`.

The `number:transliteration-style` attribute is usable with the following elements: `<number:boolean-style>` 16.27.23, `<number:currency-style>` 16.27.7, `<number:date-style>` 16.27.10, `<number:number-style>` 16.27.2, `<number:percentage-style>` 16.27.9, `<number:text-style>` 16.27.25 and `<number:time-style>` 16.27.18.

The values of the `number:transliteration-style` attribute are `short`, `medium` or `long`.

19.365 number:truncate-on-overflow

The `number:truncate-on-overflow` attribute specifies if a time or duration for which the value to be displayed by the largest time component specified in the style is too large to be displayed using the value range for `<number:hours>` (0 to 23), or `<number:minutes>` or `<number:seconds>` (0 to 59) is truncated or if the value range of this component is extended. The largest time component is those for which a value of "1" represents the longest period of time.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If a value gets truncated, then its value is displayed modulo 24 (for <number:hours>) or modulo 60 (for <number:minutes> and <number:seconds>).

If the value range of a component get extended, then values larger than 23 or 59 are displayed.

The defined values for the number:truncate-on-overflow element are:

- false: the value range of the component is extended.
- true: the value range of the component is not extended.

The default value for this attribute is true.

The number:truncate-on-overflow attribute is usable with the following element: <number:time-style> 16.27.18.

The number:truncate-on-overflow attribute has the data type boolean 18.3.3.

19.366 office:automatic-update

The office:automatic-update attribute specifies if DDE links are automatically updated or only upon user request.

The defined values for the office:automatic-update element are:

- false: DDE links are updated on user request only.
- true: DDE links are updated automatically.

The default value for this attribute is true.

The office:automatic-update attribute is usable with the following elements: <office:dde-source> 14.6.5 and <text:dde-connection-decl> 14.6.3.

The office:automatic-update attribute has the data type boolean 18.3.3.

19.367 office:boolean-value

The office:boolean-value attribute specifies the Boolean value for a table cell (<table:change-track-table-cell>, <table:covered-table-cell> and <table:table-cell>), a text field (<text:expression>, <text:user-defined>, <text:user-field-decl> and <text:variable-set>), or a form property (<form:list-value> and <form:property>).

It specifies a default value for database columns and database column definitions (<db:column> and <db:column-definition>).

For <text:user-defined> elements, this attribute is only evaluated if the the corresponding <meta:user-defined> element has attribute meta:value-type="boolean".

The office:boolean-value attribute is usable with the following elements: <db:column> 12.35, <db:column-definition> 12.40, <form:list-value> 13.10, <form:property> 13.8, <table:change-track-table-cell> 9.9.16, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:expression> 7.4.14, <text:user-defined> 7.5.6, <text:user-field-decl> 7.4.8 and <text:variable-set> 7.4.4.

The office:boolean-value attribute has the data type boolean 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.368 office:conversion-mode

The `office:conversion-mode` attribute specifies the method by which the DDE server converts its data into numbers.

The defined values for the `office:conversion-mode` attribute are:

- `into-default-style-data-style`: numbers are converted into the data style which is set on the default style.
- `into-english-number`: numbers are converted into the English default format.
- `keep-text`: numbers are not converted. They are treated as text.

The default value for this attribute is `into-default-style-data-style`.

The `office:conversion-mode` attribute is usable with the following element: `<office:dde-source>` 14.6.5.

The values of the `office:conversion-mode` attribute are `into-default-style-data-style`, `into-english-number` or `keep-text`.

19.369 office:currency

The `office:currency` attribute specifies the currency for a value of a table cell (`<table:change-track-table-cell>`, `<table:covered-table-cell>` and `<table:table-cell>`), a text field (`<text:expression>`, `<text:user-field-decl>` and `<text:variable-set>`), or a form property (`<form:list-value>` and `<form:property>`).

It specifies a default currency for database columns and database column definitions (`<db:column>` and `<db:column-definition>`).

The `office:currency` attribute is usable with the following elements: `<db:column>` 12.35, `<db:column-definition>` 12.40, `<form:list-value>` 13.10, `<form:property>` 13.8, `<table:change-track-table-cell>` 9.9.16, `<table:covered-table-cell>` 9.1.5, `<table:table-cell>` 9.1.4, `<text:expression>` 7.4.14, `<text:user-field-decl>` 7.4.8 and `<text:variable-set>` 7.4.4.

The `office:currency` attribute has the data type `string` 18.2.

19.370 office:date-value

The `office:date-value` attribute specifies the date or date-time value for a table cell (`<table:change-track-table-cell>`, `<table:covered-table-cell>` and `<table:table-cell>`), a text field (`<text:expression>`, `<text:user-defined>`, `<text:user-field-decl>` and `<text:variable-set>`), or a form property (`<form:list-value>` and `<form:property>`).

It specifies a default value for database columns and database column definitions (`<db:column>` and `<db:column-definition>`).

For `<text:user-defined>` elements, this attribute is only evaluated if the corresponding `<meta:user-defined>` element has attribute `meta:value-type`="`date`".

The `office:date-value` attribute is usable with the following elements: `<db:column>` 12.35, `<db:column-definition>` 12.40, `<form:list-value>` 13.10, `<form:property>` 13.8,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<table:change-track-table-cell> 9.9.16, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:expression> 7.4.14, <text:user-defined> 7.5.6, <text:user-field-decl> 7.4.8 and <text:variable-set> 7.4.4.

The office:date-value attribute has the data type dateOrDateTime 18.3.14.

19.371 office:dde-application

The office:dde-application attribute specifies the name of the target application to use for the DDE connection.

The office:dde-application attribute is usable with the following elements: <office:dde-source> 14.6.5 and <text:dde-connection-decl> 14.6.3.

The office:dde-application attribute has the data type string 18.2.

19.372 office:dde-item

The office:dde-item attribute specifies which information the target application should deliver.

The office:dde-item attribute is usable with the following elements: <office:dde-source> 14.6.5 and <text:dde-connection-decl> 14.6.3.

The office:dde-item attribute has the data type string 18.2.

19.373 office:dde-topic

The office:dde-topic attribute specifies the name of the topic to use for the DDE connection.

The office:dde-topic attribute is usable with the following elements: <office:dde-source> 14.6.5 and <text:dde-connection-decl> 14.6.3.

The office:dde-topic attribute has the data type string 18.2.

19.374 office:display

The office:display attribute specifies whether an annotation is visible.

The office:display attribute is usable with the following element: <office:annotation> 14.1.

The office:display attribute has the data type boolean 18.3.3.

19.375 office:mimetype

The office:mimetype attribute specifies the document type for a document that is contained in a single XML file. Its values are the MIME types that are used for the packaged variant of office documents.

The office:mimetype attribute is usable with the following element: <office:document> 3.1.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `office:mimetype` attribute has the data type `string` 18.2.

19.376 office:name

19.376.1 General

The `office:name` attribute specifies a name. The use of that name is specified for each element on which it appears.

19.376.2 <draw:a>

The `office:name` attribute specifies a name for a link. The name can serve as a target for other hyperlinks. The name does not have to be unique.

The `office:name` attribute is usable with the following element: `<draw:a>` 10.4.12.

The `office:name` attribute has the data type `string` 18.2.

19.376.3 <draw:area-circle>

The `office:name` attribute specifies a name for a shape represented by this element. The name does not have to be unique.

The `office:name` attribute is usable with the following element: `<draw:area-circle>` 10.4.13.4.

The `office:name` attribute has the data type `string` 18.2.

19.376.4 <draw:area-rectangle>

The `office:name` attribute specifies a name for a shape represented by this element. The name does not have to be unique.

The `office:name` attribute is usable with the following element: `<draw:area-rectangle>` 10.4.13.3.

The `office:name` attribute has the data type `string` 18.2.

19.376.5 <draw:area-polygon>

The `office:name` attribute specifies a name for an image map. The name does not have to be unique.

The `office:name` attribute is usable with the following element: `<draw:area-polygon>` 10.4.13.5.

The `office:name` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.376.6 <office:annotation>

The `office:name` attribute specifies a name for an annotation. It is used to match `<office:annotation>` elements with the corresponding `<office:annotation-end>` elements.

The name that appears in the `office:name` attribute of any `<office:annotation>`, `<office:annotation-end>` pair shall be unique to that pair of elements in a document instance.

The `office:name` attribute is usable with the following element: `<office:annotation>` 14.1.

The `office:name` attribute has the data type `string` 18.2.

19.376.7 <office:annotation-end>

The `office:name` attribute specifies a name for an annotation. It is used to match `<office:annotation-end>` elements with the corresponding `<office:annotation>` elements.

The `office:name` attribute is usable with the following element: `<office:annotation-end>` 14.2.

The `office:name` attribute has the data type `string` 18.2.

19.376.8 <office:dde-source>

The `office:name` attribute specifies the name by which a connection can be referred.

The `office:name` attribute is usable with the following element: `<office:dde-source>` 14.6.5.

The `office:name` attribute has the data type `string` 18.2.

19.376.9 <text:a>

The `office:name` attribute specifies a name for a hyperlink. The name serves as a target for other hyperlinks and may not be unique.

Note: This attribute is specified for compatibility with [HTML4] only, where an `<a>` element may serve as a link source and target simultaneously. This attribute should not be used for any purpose other than to represent links that came from a HTML document.

The `office:name` attribute is usable with the following element: `<text:a>` 6.1.8.

The `office:name` attribute has the data type `string` 18.2.

19.376.10 <text:dde-connection-decl>

The `office:name` attribute specifies a name by which a connection can be referenced.

The `office:name` attribute is usable with the following element: `<text:dde-connection-decl>` 14.6.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `office:name` attribute has the data type `string` 18.2.

19.377 office:process-content (deprecated)

The `office:process-content` attribute specifies the processing to be performed on foreign elements.

The defined values of the `office:process-content` attribute are:

- `false`: conforming consumers should not interpret a foreign element's content, but may preserve its content, regardless of the foreign element's ancestor elements.
- `true`: conforming consumers may interpret a foreign element's content without regard to its ancestor elements.

Note: The `office:process-content` attribute has been deprecated in favor of simpler rules regarding the processing of foreign elements. 3.17

19.378 office:server-map

The `office:server-map` attribute specifies that a link returns data to a server side image map. The mouse coordinates of the click position of the graphic shape are appended to the IRI of the link. The coordinates are be used by the server to determine which link to activate within the image map.

The default value for this attribute is `false`.

The `office:server-map` attribute is usable with the following element: `<draw:a>` 10.4.12.

The `office:server-map` attribute has the data type `boolean` 18.3.3.

19.379 office:string-value

The `office:string-value` attribute specifies the string-value for a table cell (`<table:change-track-table-cell>`, `<table:covered-table-cell>` and `<table:table-cell>`), a text field (`<text:expression>`, `<text:user-defined>`, `<text:user-field-decl>` and `<text:variable-set>`), or a form property (`<form:list-value>` and `<form:property>`).

It specifies a default value for database columns and database column definitions (`<db:column>` and `<db:column-definition>`).

For `<text:user-defined>` elements, this attribute is only evaluated if the the corresponding `<meta:user-defined>` element has (default) attribute `meta:value-type="string"`.

The `office:string-value` attribute is usable with the following elements: `<db:column>` 12.35, `<db:column-definition>` 12.40, `<form:list-value>` 13.10, `<form:property>` 13.8, `<table:change-track-table-cell>` 9.9.16, `<table:covered-table-cell>` 9.1.5, `<table:table-cell>` 9.1.4, `<text:expression>` 7.4.14, `<text:user-defined>` 7.5.6, `<text:user-field-decl>` 7.4.8 and `<text:variable-set>` 7.4.4.

The `office:string-value` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.380 office:target-frame

The `office:target-frame` attribute specifies a target frame.

The defined values for the `office:target-frame` attribute are:

- `_blank`: The referenced document is displayed in a new frame.
- `_parent`: The referenced document is displayed in the parent frame of the current frame.
- `_self`: The referenced document replaces the content of the current frame.
- `_top`: The referenced document is displayed in the topmost frame, that is the frame that contains the current frame as a child or descendant but is not contained within another frame.
- A frame name : The referenced document is displayed in the named frame. If the named frame does not exist, a new frame with that name is created.

The default value for this attribute is `_blank`.

The `office:target-frame` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:form>` 13.3 and `<form:image>` 13.5.16.

The `office:target-frame` attribute has the data type `targetFrameName` 18.3.34.

19.381 office:target-frame-name

The `office:target-frame-name` attribute. specifies the name of a target frame.

The defined values for the `office:target-frame-name` attribute are:

- `_blank`: The referenced document is displayed in a new frame.
- `_parent`: The referenced document is displayed in the parent frame of the current frame.
- `_self`: The referenced document replaces the content of the current frame.
- `_top`: The referenced document is displayed in the topmost frame, that is the frame that contains the current frame as a child or descendant but is not contained within another frame.
- A frame name: The referenced document is displayed in the named frame. If the named frame does not exist, a new frame with that name is created.

The `office:target-frame-name` attribute may be used together with an `xlink:show` attribute. In that case, if the value of the attribute is `_blank`, the `xlink:show` attribute value should be `new`. If the value of the attribute is any of the other value options, the value of the `xlink:show` attribute should be `replace`.

The `office:target-frame-name` attribute is usable with the following elements: `<draw:a>` 10.4.12, `<draw:area-circle>` 10.4.13.4, `<draw:area-polygon>` 10.4.13.5, `<draw:area-rectangle>` 10.4.13.3, `<meta:hyperlink-behaviour>` 4.3.2.14 and `<text:a>` 6.1.8.

The `office:target-frame-name` attribute has the data type `targetFrameName` 18.3.34.

19.382 office:time-value

The `office:time-value` attribute specifies the time value for a table cell (`<table:change-track-table-cell>`, `<table:covered-table-cell>` and `<table:table-cell>`), a text

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

field (<text:expression>, <text:user-defined>, <text:user-field-decl> and <text:variable-set>), or a form property (<form:list-value> and <form:property>).

It specifies a default value for database columns and database column definitions (<db:column> and <db:column-definition>).

For <text:user-defined> elements, this attribute is only evaluated if the corresponding <meta:user-defined> element has attribute meta:value-type="time".

The office:time-value attribute is usable with the following elements: <db:column> 12.35, <db:column-definition> 12.40, <form:list-value> 13.10, <form:property> 13.8, <table:change-track-table-cell> 9.9.16, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:expression> 7.4.14, <text:user-defined> 7.5.6, <text:user-field-decl> 7.4.8 and <text:variable-set> 7.4.4.

The office:time-value attribute has the data type duration 18.2.

19.383 office:title

The office:title attribute specifies a short accessible description.

Note: See appendix D for guidelines on using this attribute.

The office:title attribute is usable with the following elements: <draw:a> 10.4.12 and <text:a> 6.1.8.

The office:title attribute has the data type string 18.2.

19.384 office:value

The office:value attribute specifies the currency, float or percentage value for a table cell (<table:change-track-table-cell>, <table:covered-table-cell> and <table:table-cell>), a text field (<text:expression>, <text:user-defined>, <text:user-field-decl> and <text:variable-set>), or a form property (<form:list-value> and <form:property>).

It specifies a default value for database columns and database column definitions (<db:column> and <db:column-definition>).

For <text:user-defined> elements, this attribute is only interpreted if the the corresponding <meta:user-defined> element has attribute meta:value-type="float".

The office:value attribute is usable with the following elements: <db:column> 12.35, <db:column-definition> 12.40, <form:list-value> 13.10, <form:property> 13.8, <table:change-track-table-cell> 9.9.16, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:expression> 7.4.14, <text:user-defined> 7.5.6, <text:user-field-decl> 7.4.8 and <text:variable-set> 7.4.4.

The office:value attribute has the data type double 18.2.

19.385 office:value-type

The office:value-type attribute specifies the value-type of a table cell (<table:change-track-table-cell>, <table:covered-table-cell> and <table:table-cell>), a text field (<text:expression>, <text:user-field-decl>, <text:variable-decl>,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<text:variable-input>and <text:variable-set>), or a form property (<form:list-value> and <form:property>).

It specifies a default value type of database columns and database column definitions (<db:column> and <db:column-definition>).

If the value type is not string, the corresponding Value Attribute(s) (Table 14 - Value attributes) shall contain the value(s) of the element.

Each of these elements has a value type that shall be specified. The defined value types, their respective value attributes, and how the values are encoded are described in Table 14 - Value attributes.

Table 14 - Value attributes

Value Type	*Value Attribute(s)*	*Encoded as...*	*Example*
boolean	office:boolean-value	true or false	"true"
currency	office:value and office:currency	Numeric value and currency symbol	"100" "USD"
date	office:date-value	Date value as specified in §3.2.9 of [xmlschema-2], or date and time value as specified in §3.2.7 of [xmlschema-2]	"2003-04-17"
float	office:value	Numeric value	"12.345"
percentage	office:value	Numeric value	"0.50"
string	office:string-value	Strings	"abc def"
time	office:time-value	Duration, as specified in §3.2.6 of [xmlschema-2]	"PT03H30M00S"
void	none		

If the value type is string and the office:string-value attribute is not present, the element content defines the value.

Note: The OpenDocument concept of field values and value types and their encoding in XML is also modeled on the corresponding XML for table cell attributes.

The office:value-type attribute is usable with the following elements: <db:column> 12.35, <db:column-definition> 12.40, <form:list-property> 13.9, <form:property> 13.8, <table:change-track-table-cell> 9.9.16, <table:covered-table-cell> 9.1.5, <table:table-cell> 9.1.4, <text:expression> 7.4.14, <text:user-field-decl> 7.4.8, <text:variable-decl> 7.4.3, <text:variable-input> 7.4.6 and <text:variable-set> 7.4.4.

The office:value-type attribute has the data type valueType 18.3.38.

19.386 office:version

The office:version attribute identifies the version of the OpenDocument specification that defines the associated element, its schema, its complete content, and its interpretation.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The office:version attribute shall be present in each and every <office:document>, <office:document-content>, <office:document-styles>, <office:document-meta>, and <office:document-settings> element in the XML documents that comprise an OpenDocument 1.2 document. The value of the office:version attribute shall be "1.2".

Note 1: When an office:version-requiring element has office:version="1.1" the element and its content are based on the OpenDocument v1.1 specification [ODF11]. For office:version="1.0" the element and its content are based on the OpenDocument v1.0 specification [ODF10]. When an office:version-requiring element has office:version omitted, the element is based on a version of the OpenDocument specification earlier than v1.2.

Note 2: An OpenDocument 1.2 document that relies solely on features of a previous OpenDocument specification that are upward-compatible with OpenDocument 1.2, can be interpreted correctly under that earlier specification by treating the office:version=""1.2" attribute as omitted or as identifying the earlier version

An OpenDocument 1.2 consumer may process a document that does not provide the office:version attribute or where the value of the office:version attribute is not "1.2" as if it is an OpenDocument 1.2 document. Any elements and attributes that are neither recognized, accepted, nor supported by the consumer, even though identified in XML namespaces defined for use in OpenDocument 1.2 documents, should be treated in accordance with the rules for foreign elements and attributes. 3.17

- Any elements and attributes based on earlier versions of OpenDocument for which the same-named OpenDocument 1.2 features are incompatible need not be accepted. If accepted, an OpenDocument 1.2-incompatible feature should be cast into an equivalent but OpenDocument 1.2-compatible form. See Appendix G, Changes From Previous Specification Versions (Non-Normative), as well as previous specifications and any approved errata for them.
- Any elements and attributes that are neither recognized, accepted, nor supported by the consumer, even though identified in XML namespaces defined for use in OpenDocument 1.2 documents, should be treated in accordance with the rules for foreign elements and attributes. 3.17
- Subsequent processing should be as if the accepted document were exactly the OpenDocument 1.2 document derived in this way

The office:version attribute is usable with the following elements: <office:document> 3.1.2, <office:document-content> 3.1.3.2, <office:document-meta> 3.1.3.4, <office:document-settings> 3.1.3.5 and <office:document-styles> 3.1.3.3.

The only value of the office:version attribute is 1.2.

19.387 presentation:action

The presentation:action attribute specifies the type of action that is executed when an event is triggered.

The defined values for the presentation:action attribute are:

- execute: another application is launched when this event is triggered. The application is specified with the xlink:href attribute on the same <presentation:event-listener> element.
- fade-out: the object that contains this event is faded out when this event is triggered. The attributes presentation:effect, presentation:direction, presentation:speed and presentation:start-scale can be used to set the effect.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `first-page`: the presentation jumps to the first page of the current document.
- `hide`: the object that contains this event is hidden if the event is triggered.
- `last-page`: the presentation jumps to the last page of the current document.
- `last-visited-page`: the presentation jumps to the page that was displayed before the current page.
- `next-page`: the presentation jumps to the next page.
- `none`: no action is performed when this event is triggered.
- `previous-page`: the presentation jumps to the previous page.
- `show`: the target of an IRI is opened when this event is triggered. The IRI is specified with the `xlink:href` attribute on the same `<presentation:event-listener>` element.
- `sound`: an audio effect is started when the effect is triggered. The audio effect is described by a `<presentation:sound>` child element.
- `stop`: if a slide show is active, it will be stopped.
- `verb`: if the object that contains this event supports the execution of [OLE] verbs, the verb with the id set in the `presentation:verb` attribute is executed.

The `presentation:action` attribute is usable with the following element: `<presentation:event-listener>` 10.9.2.

The values of the `presentation:action` attribute are `none`, `previous-page`, `next-page`, `first-page`, `last-page`, `hide`, `stop`, `execute`, `show`, `verb`, `fade-out`, `sound` or `last-visited-page`.

19.388 presentation:animations

The `presentation:animations` attribute enables or disables the playback of animations that are specified within embedded or linked images during a presentation.

The defined values for the `presentation:animations` attribute are:

- `disabled`: image animations cannot be played during a presentation.
- `enabled`: image animations can be played during a presentation.

The default value for this attribute is `enabled`.

The `presentation:animations` attribute is usable with the following element: `<presentation:settings>` 10.9.3.7.

The values of the `presentation:animations` attribute are `enabled` or `disabled`.

19.389 presentation:class

The `presentation:class` attribute classifies presentation shapes by their usage within a draw page.

The defined values for the `presentation:class` attribute are:

- `chart`: presentation charts are standard object shapes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `graphic`: presentation graphics are standard graphic shapes
- `handout`: presentation handouts are placeholder for the drawing page in a handout page
- `notes`: presentation notes are used on notes pages
- `object`: presentation objects are standard object shapes
- `orgchart`: presentation organization charts are standard object shapes.
- `outline`: outlines are standard text shapes
- `page`: presentation pages are used on notes pages
- `subtitle`: subtitles are standard text shapes
- `table`: presentation tables are standard object shapes
- `text`: presentation texts are standard text shapes
- `title`: titles are standard text shapes

The `date-time`, `footer`, `header`, and `page-number` classes can be used only for drawing shapes that are contained in master pages. Depending on the settings of the `<style:master-page>` element, they are displayed automatically on drawing pages that use the master page.

When used with drawing shapes contained in master pages, the defined values for the `presentation:class` attribute are:

- `date-time`: drawing shape is used as a date and/or time shape. Date and Time shapes are standard text shapes.
- `footer`: drawing shape is used as a footer. Footer shapes are standard text shapes.
- `header`: drawing shape is used as a header. Header shapes are standard text shapes.
- `page-number`: drawing shape is used as a page number shape. Page Number shapes are standard text shapes.

The `presentation:class` attribute is usable with the following elements: `<draw:frame>` 10.4.2 and `<draw:page-thumbnail>` 10.3.14.

The values of the `presentation:class` attribute are `title`, `outline`, `subtitle`, `text`, `graphic`, `object`, `chart`, `table`, `orgchart`, `page`, `notes`, `handout`, `header`, `footer`, `date-time` or `page-number`.

19.390 presentation:class-names

The `presentation:class-names` attribute specifies a white space separated list of styles with the family value of `presentation`. The referenced styles are applied in the order they are contained in the list.

If both `presentation:style-name` and `presentation:class-names` are present, the style referenced by the `presentation:style-name` attribute is applied before the styles referenced by the `presentation:class-names` attribute.

The `presentation:class-names` attribute is usable with the following elements: `<dr3d:cube>` 10.5.4, `<dr3d:extrude>` 10.5.6, `<dr3d:rotate>` 10.5.7, `<dr3d:scene>` 10.5.2, `<dr3d:sphere>` 10.5.5, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6 and <office:annotation> 14.1.

The presentation:class-names attribute has the data type styleNameRefs 18.3.33.

19.391 presentation:delay

The presentation:delay attribute specifies the delay before a presentation effect starts after the previous one has finished.

The presentation:delay attribute is usable with the following elements: <presentation:hide-shape> 10.8.5, <presentation:hide-text> 10.8.6, <presentation:show-shape> 10.8.3 and <presentation:show-text> 10.8.4.

The presentation:delay attribute has the data type duration 18.2.

19.392 presentation:direction

The presentation:direction attribute specifies the direction of an effect.

The defined values for the presentation:direction attribute are:

- clockwise: effect moves in a clockwise direction.
- counter-clockwise: effect moves in a counter-clockwise direction.
- from-bottom: effect moves from the bottom of the presentation area.
- from-center: effect moves from the center of the presentation area.
- from-left: effect moves from the left of the presentation area.
- from-right: effect moves from the right of the presentation area.
- from-top: effect moves from the top of the presentation area.
- from-lower-left: effect moves from the lower-left of the presentation area.
- from-lower-right: effect moves from the lower-right of the presentation area.
- from-upper-left: effect moves from the upper-left of the presentation area.
- from-upper-right: effect moves from the upper-right of the presentation area.
- horizontal: effect moves from the bottom of the presentation area.
- none: no presentation effect direction
- path: effect moves from the bottom of the presentation area.
- spiral-inward-left: effect spirals inward from the left of the presentation area.
- spiral-inward-right: effect spirals inward from the right of the presentation area.
- spiral-outward-left: effect spirals outward to the left of the presentation area.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `spiral-outward-right`: effect spirals outward to the right of the presentation area.
- `to-left`: effect moves to the left of the presentation area.
- `to-top`: effect moves to the top of the presentation area.
- `to-right`: effect moves to the right of the presentation area.
- `to-bottom`: effect moves to the bottom of the presentation area.
- `to-center`: effect moves from the center of the presentation area.
- `to-lower-left`: effect moves to the lower-left of the presentation area.
- `to-upper-left`: effect moves to the upper-left of the presentation area.
- `to-lower-right`: effect moves to the lower-right of the presentation area.
- `to-upper-right`: effect moves to the upper-right of the presentation area.
- `vertical`: effect moves vertically in the presentation area.

The default value for this attribute is `none`.

The `presentation:direction` attribute is usable with the following elements: `<presentation:event-listener>` 10.9.2, `<presentation:hide-shape>` 10.8.5, `<presentation:hide-text>` 10.8.6, `<presentation:show-shape>` 10.8.3 and `<presentation:show-text>` 10.8.4.

The values of the `presentation:direction` attribute are `none`, `from-left`, `from-top`, `from-right`, `from-bottom`, `from-center`, `from-upper-left`, `from-upper-right`, `from-lower-left`, `from-lower-right`, `to-left`, `to-top`, `to-right`, `to-bottom`, `to-upper-left`, `to-upper-right`, `to-lower-right`, `to-lower-left`, `path`, `spiral-inward-left`, `spiral-inward-right`, `spiral-outward-left`, `spiral-outward-right`, `vertical`, `horizontal`, `to-center`, `clockwise` or `counter-clockwise`.

19.393 presentation:endless

The `presentation:endless` attribute specifies is a presentation repeats indefinitely or not.

The defined values for the `presentation:endless` attribute are:

- `false`: presentation does not repeat indefinitely.
- `true`: presentation repeats indefinitely.

The default value for this attribute is `false`.

The `presentation:endless` attribute is usable with the following element: `<presentation:settings>` 10.9.3.7.

The `presentation:endless` attribute has the data type `boolean` 18.3.3.

19.394 presentation:effect

The `presentation:effect` attribute specifies the type of an effect.

The defined values for the `presentation:effect` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `appear`: the shape is faded in by just switching its state from invisible to visible.
- `checkerboard`: the shape is faded in or out by drawing or removing checkerboard like blocks that increase in size over time.
- `close`: the shape is drawn or removed line by line, either horizontally or vertically, starting at the edge of the shape.
- `dissolve`: the shape is faded in or out by drawing or removing small blocks in a random fashion.
- `fade`: the shape fades from its visible or hidden state to a hidden or visible state.
- `hide`: the shape is faded out by just switching its state from visible to invisible.
- `laser`: this effect is only available for text shapes; the characters of the text are moved one by one from the top edge of the screen to their final position.
- `lines`: the shape is faded in and out by drawing or removing line by line, either horizontally or vertically, in a random fashion.
- `move`: the shape moves from or to its final position.
- `move-short`: like the move effect, but the moving shape is clipped to its final bounding rectangle during fade.
- `none`: no effect is used.
- `open`: the shape is drawn or removed line by line, either horizontally or vertically, starting at the center of the shape.
- `random`: an effect is chosen at random to fade the shape in or out.
- `rotate`: the shape rotates horizontally or vertically for a short amount of time during this effect.
- `stretch`: the shape is faded in or out by changing its size during this effect.
- `stripes`: the shape is faded in or out by drawing or removing horizontal or vertical stripes that change their size.
- `wavyline`: the shape is faded in and out by drawing or removing small blocks in a snake like fashion.

The default value for this attribute is `none`.

The `presentation:effect` attribute is usable with the following elements: `<presentation:event-listener>` 10.9.2, `<presentation:hide-shape>` 10.8.5, `<presentation:hide-text>` 10.8.6, `<presentation:show-shape>` 10.8.3 and `<presentation:show-text>` 10.8.4.

The values of the `presentation:effect` attribute are `none`, `fade`, `move`, `stripes`, `open`, `close`, `dissolve`, `wavyline`, `random`, `lines`, `laser`, `appear`, `hide`, `move-short`, `checkerboard`, `rotate` or `stretch`.

19.395 presentation:force-manual

The `presentation:force-manual` attribute specifies that the value of the `presentation:transition-type` attribute is set to `manual`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the `presentation:force-manual` attribute are:

- `false`: `presentation:transition-type` attribute is not set to manual.
- `true`: `presentation:transition-type` attribute is set to manual.

The default value for this attribute is `false`.

The `presentation:force-manual` attribute is usable with the following element: `<presentation:settings>` 10.9.3.7.

The `presentation:force-manual` attribute has the data type `boolean` 18.3.3.

19.396 presentation:full-screen

The `presentation:full-screen` attribute specifies whether the presentation is displayed in full screen mode or in a window.

The defined values for the `presentation:full-screen` attribute are:

- `false`: presentation is displayed in a window.
- `true`: presentation is displayed in full screen mode.

The default value for this attribute is `true`.

The `presentation:full-screen` attribute is usable with the following element: `<presentation:settings>` 10.9.3.7.

The `presentation:full-screen` attribute has the data type `boolean` 18.3.3.

19.397 presentation:group-id

The `presentation:group-id` attribute specifies a group id. This id can be used to group animation elements within a user interface, where a group consists of all animation elements that have the same group id.

The `presentation:group-id` attribute is usable with the following elements: `<anim:audio>` 15.5, `<anim:command>` 15.6.1, `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2 and `<anim:seq>` 15.4.3.

The `presentation:group-id` attribute has the data type `string` 18.2.

19.398 presentation:master-element

The `presentation:master-element` attribute specifies the id of an animation element.

Note: Consumer user interfaces may consider animation elements that have a `presentation:master-element` attribute to be a part of the animation element that is referenced, and may therefore exclude them from any lists of defined animations.

The `presentation:master-element` attribute is usable with the following elements: `<anim:audio>` 15.5, `<anim:command>` 15.6.1, `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2 and `<anim:seq>` 15.4.3.

The `presentation:master-element` attribute has the data type `IDREF` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.399 presentation:mouse-as-pen

The `presentation:mouse-as-pen` attribute specifies if a mouse pointer is displayed as a pen or a pointer.

The defined values for the `presentation:mouse-as-pen` attribute are:

- `false`: mouse pointer is used as a pointer.
- `true`: mouse pointer is used for drawing.

The default value for this attribute is `false`.

The `presentation:mouse-as-pen` attribute is usable with the following element: `<presentation:settings>` 10.9.3.7.

The `presentation:mouse-as-pen` attribute has the data type `boolean` 18.3.3.

19.400 presentation:mouse-visible

The `presentation:mouse-visible` attribute specifies whether a mouse pointer is visible during a presentation.

The defined values for the `presentation:mouse-visible` attribute are:

- `false`: mouse not visible during presentation.
- `true`: mouse visible during presentation.

The default value for this attribute is `true`.

The `presentation:mouse-visible` attribute is usable with the following element: `<presentation:settings>` 10.9.3.7.

The `presentation:mouse-visible` attribute has the data type `boolean` 18.3.3.

19.401 presentation:name

The `presentation:name` attribute identifies the element on which it appears inside a presentation.

The `presentation:name` attribute is usable with the following elements: `<presentation:date-time-decl>` 10.9.3.6, `<presentation:footer-decl>` 10.9.3.4, `<presentation:header-decl>` 10.9.3.2 and `<presentation:show>` 10.9.3.8.

The `presentation:name` attribute has the data type `string` 18.2.

19.402 presentation:node-type

The `presentation:node-type` attribute specifies a node type for an animation element.

The defined values for the `presentation:node-type` attribute are:

- `after-previous`: this animation element is the root element of an effect that starts after the previous effect.
- `default`: no node type is defined. This is the default setting.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `interactive-sequence`: this animation element is the root element for a sequence of effects that are started when the user selects an element inside a page.
- `main-sequence`: this animation element is the root element for the main sequence of effects of a page
- `on-click`: this animation element is the root element of an effect that starts with a user click.
- `timing-root`: this animation element is the root element for the animation of a page.
- `with-previous`: this animation element is the root element of an effect that starts with the previous effect.

Note: Click is the action of a computer user moving a cursor or focus to a location on a screen (point) and then pressing a mouse button, usually the left button(click), or other pointing device. A click can be used with any number of input devices varying from mice, touch pads, keyboards, joysticks, scroll buttons, and roller balls.

The default value for this attribute is `default`.

The `presentation:node-type` attribute is usable with the following elements: `<anim:audio>` 15.5, `<anim:command>` 15.6.1, `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2 and `<anim:seq>` 15.4.3.

The values of the `presentation:node-type` attribute are `default`, `on-click`, `with-previous`, `after-previous`, `timing-root`, `main-sequence` or `interactive-sequence`.

19.403 presentation:object

The `presentation:object` attribute specifies the type of object that a `<presentation:placeholder>` element represents.

The defined values for the `presentation:object` attribute are the same as those defined for the `presentation:class` attribute. 19.389

The `presentation:object` attribute is usable with the following element: `<presentation:placeholder>` 16.42.

The values of the `presentation:object` attribute are `title`, `outline`, `subtitle`, `text`, `graphic`, `object`, `chart`, `table`, `orgchart`, `page`, `notes`, `handout`, `header`, `footer`, `date-time` or `page-number`.

19.404 presentation:pages

The `presentation:pages` attribute specifies a comma “,” (U+002C, COMMA) separated list of page names as given by `draw:name` attributes on `<draw:page>` elements. The pages are displayed in the order in which they are listed during a presentation that uses this show. Pages can be included more than once.

The `presentation:pages` attribute is usable with the following element: `<presentation:show>` 10.9.3.8.

The `presentation:pages` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.405 presentation:path-id

The `presentation:path-id` attribute specifies a polygon shape by the value of its `draw:shape-id` attribute. An effect moves along the lines of the specified polygon. The referenced polygon is not visible during the presentation.

The `presentation:path-id` attribute is usable with the following elements: `<presentation:hide-shape>` 10.8.5, `<presentation:hide-text>` 10.8.6, `<presentation:show-shape>` 10.8.3 and `<presentation:show-text>` 10.8.4.

The `presentation:path-id` attribute has the data type `string` 18.2.

19.406 presentation:pause

The `presentation:pause` attribute specifies a time duration for displaying a pause screen before the presentation is played again if the presentation is to be repeated indefinitely. If this attribute is not set or has a value of `P0s`, a pause screen is not displayed in endless mode.

The `presentation:pause` attribute is usable with the following element: `<presentation:settings>` 10.9.3.7.

The `presentation:pause` attribute has the data type `duration` 18.2.

19.407 presentation:placeholder

The `presentation:placeholder` attribute specifies if a shape is a placeholder or a presentation object with content.

The `presentation:placeholder` attribute is usable with the following elements: `<draw:frame>` 10.4.2 and `<draw:page-thumbnail>` 10.3.14.

The `presentation:placeholder` attribute has the data type `boolean` 18.3.3.

19.408 presentation:play-full

The `presentation:play-full` attribute specifies when an effect starts.

The defined values for the `presentation:play-full` attribute are:

- `false`: effect starts after current effect ends.
- `true`: effect starts after the sound specified by its parent `<presentation:sound>` element ends.

The `presentation:play-full` attribute is usable with the following element: `<presentation:sound>` 10.8.2.

The `presentation:play-full` attribute has the data type `boolean` 18.3.3.

19.409 presentation:presentation-page-layout-name

The `presentation:presentation-page-layout-name` attribute references the `style:name` attribute of a `<style:presentation-page-layout>` element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The presentation:presentation-page-layout-name attribute is usable with the following elements: <draw:page> 10.2.4 and <style:handout-master> 10.2.1.

The presentation:presentation-page-layout-name attribute has the data type styleNameRef 18.3.32.

19.410 presentation:preset-class

The presentation:preset-class attribute specifies the class of the preset that was used to create an animation element.

The defined values for the presentation:preset-class attribute are:

- custom: the preset was a user defined one. This is the default setting.
- entrance: the preset was an entrance effect.
- exit: the preset was an exit effect.
- emphasis: the preset was an emphasis effect.
- motion-path: the preset was a motion path.
- ole-action: the preset was an ole action.
- media-call: the preset was a media call.

The default value for this attribute is custom.

The presentation:preset-class attribute is usable with the following elements: <anim:audio> 15.5, <anim:command> 15.6.1, <anim:iterate> 15.4.4, <anim:par> 15.4.2 and <anim:seq> 15.4.3.

The values of the presentation:preset-class attribute are custom, entrance, exit, emphasis, motion-path, ole-action or media-call.

19.411 presentation:preset-id

The presentation:preset-id attribute specifies the name of the preset that was used to create an animation element.

The presentation:preset-id attribute is usable with the following elements: <anim:audio> 15.5, <anim:command> 15.6.1, <anim:iterate> 15.4.4, <anim:par> 15.4.2 and <anim:seq> 15.4.3.

The presentation:preset-id attribute has the data type string 18.2.

19.412 presentation:preset-sub-type

The presentation:preset-sub-type attribute specifies the sub type of the preset that was used to create an animation element.

The presentation:preset-sub-type attribute is usable with the following elements: <anim:audio> 15.5, <anim:command> 15.6.1, <anim:iterate> 15.4.4, <anim:par> 15.4.2 and <anim:seq> 15.4.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `presentation:preset-sub-type` attribute has the data type `string` 18.2.

19.413 presentation:show

The `presentation:show` attribute specifies the name of a `<presentation:show>` element that is used for the presentation. If the `presentation:start-page` attribute is set, it overrides the value of this attribute.

The `presentation:show` attribute is usable with the following element: `<presentation:settings>` 10.9.3.7.

The `presentation:show` attribute has the data type `string` 18.2.

19.414 presentation:show-end-of-presentation-slide

The `presentation:show-end-of-presentation-slide` attribute specifies whether an additional slide should be shown at the end of the presentation, indicating the presentation is finished.

The slide content is not defined within the document, but is implementation-defined.

The defined values for the `presentation:show-end-of-presentation-slide` attribute are:

- `false`: end of presentation slide not shown at end of presentation.
- `true`: end of presentation slide shown at end of presentation.

The default value for this attribute is `true`.

The `presentation:show-end-of-presentation-slide` attribute is usable with the following element: `<presentation:settings>` 10.9.3.7.

The `presentation:show-end-of-presentation-slide` attribute has the data type `boolean` 18.3.3.

19.415 presentation:show-logo

The `presentation:show-logo` attribute specifies whether an implementation-defined logo is shown on a pause screen.

The defined values for the `presentation:show-logo` attribute are:

- `false`: logo not shown on pause screen.
- `true`: logo shown on pause screen.

The default value for this attribute is `false`.

The `presentation:show-logo` attribute is usable with the following element: `<presentation:settings>` 10.9.3.7.

The `presentation:show-logo` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.416 presentation:source

The `presentation:source` attribute specifies whether the current date/time or the fixed content of the field declaration is displayed.

The `presentation:source` attribute is usable with the following element: `<presentation:date-time-decl>` 10.9.3.6.

The values of the `presentation:source` attribute are `fixed` or `current-date`.

19.417 presentation:speed

The `presentation:speed` attribute specifies the speed of an effect.

The defined values for the `presentation:speed` attribute are:

- `fast`: An implementation-defined speed. The `fast` speed should be faster than the speed the implementation chooses for the values `medium` and `slow`.
- `medium`: An implementation-defined speed. The `medium` speed should be faster than the speed the implementation chooses for the value `slow`, and slower than the speed the implementation chooses for the value `fast`.
- `slow`: An implementation-defined speed. The `slow` speed should be slower than the speed the implementation chooses for the values `medium` and `fast`.

The rates specified by these values are implementation-defined.

The default value for this attribute is `medium`.

The `presentation:speed` attribute is usable with the following elements: `<presentation:event-listener>` 10.9.2, `<presentation:hide-shape>` 10.8.5, `<presentation:hide-text>` 10.8.6, `<presentation:play>` 10.8.8, `<presentation:show-shape>` 10.8.3 and `<presentation:show-text>` 10.8.4.

The values of the `presentation:speed` attribute are `slow`, `medium` or `fast`.

19.418 presentation:start-scale

The `presentation:start-scale` attribute specifies the start size of a shape as a percentage of its original size.

The default value for this attribute is `100%`.

The `presentation:start-scale` attribute is usable with the following elements: `<presentation:event-listener>` 10.9.2, `<presentation:hide-shape>` 10.8.5, `<presentation:hide-text>` 10.8.6, `<presentation:show-shape>` 10.8.3 and `<presentation:show-text>` 10.8.4.

The `presentation:start-scale` attribute has the data type `percent` 18.3.23.

19.419 presentation:start-page

The `presentation:start-page` attribute specifies the name of the page on which the presentation starts. If this attribute is set, it overrides the `presentation:show` attribute.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The presentation:start-page attribute is usable with the following element: <presentation:settings> 10.9.3.7.

The presentation:start-page attribute has the data type string 18.2.

19.420 presentation:start-with-navigator

The presentation:start-with-navigator attribute specifies whether a navigator window is initially displayed during a presentation.

The defined values for the presentation:start-with-navigator attribute are:

- false: navigator window not displayed initially during a presentation.
- true: navigator window displayed initially during a presentation.

The default value for this attribute is false.

The presentation:start-with-navigator attribute is usable with the following element: <presentation:settings> 10.9.3.7.

The presentation:start-with-navigator attribute has the data type boolean 18.3.3.

19.421 presentation:stay-on-top

The presentation:stay-on-top attribute specifies whether a presentation window is displayed on top of other windows during a presentation.

The defined values for the presentation:stay-on-top attribute are:

- false: presentation window may not be displayed on top of other windows during a presentation.
- true: presentation window displayed on top of other windows during a presentation.

The default value for this attribute is false.

The presentation:stay-on-top attribute is usable with the following element: <presentation:settings> 10.9.3.7.

The presentation:stay-on-top attribute has the data type boolean 18.3.3.

19.422 presentation:style-name

The presentation:style-name attribute specifies a style for a presentation shape.

The value of the attribute is the name of a <style:style> element that has a family value of presentation. The formatting properties of the specified style and its parent styles are used to format the shape.

The presentation:style-name attribute is usable with the following elements: <dr3d:cube> 10.5.4, <dr3d:extrude> 10.5.6, <dr3d:rotate> 10.5.7, <dr3d:scene> 10.5.2, <dr3d:sphere> 10.5.5, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6 and <office:annotation> 14.1.

The presentation:style-name attribute has the data type styleNameRef 18.3.32.

19.423 presentation:transition-on-click

The presentation:transition-on-click attributes specifies whether a mouse click on a slide during a presentation triggers a transition.

The defined values for the presentation:transition-on-click attribute are:

- disabled: mouse click on a slide during a presentation does not trigger a transition.
- enabled: mouse click on a slide during a presentation triggers a transition.

The default value for this attribute is enabled.

The presentation:transition-on-click attribute is usable with the following element: <presentation:settings> 10.9.3.7.

The values of the presentation:transition-on-click attribute are enabled or disabled.

19.424 presentation:use-date-time-name

The presentation:use-date-time-name attribute specifies the name of the <presentation:date-time-decl> that is used for all <presentation:date-time> elements that are displayed on a page.

The presentation:use-date-time-name attribute is usable with the following elements: <draw:page> 10.2.4, <presentation:notes> 16.17 and <style:handout-master> 10.2.1.

The presentation:use-date-time-name attribute has the data type string 18.2.

19.425 presentation:use-footer-name

The presentation:use-footer-name attribute specifies the name of the <presentation:footer-decl> element that is used for all <presentation:footer> elements that are displayed on a page.

The presentation:use-footer-name attribute is usable with the following elements: <draw:page> 10.2.4, <presentation:notes> 16.17 and <style:handout-master> 10.2.1.

The presentation:use-footer-name attribute has the data type string 18.2.

19.426 presentation:use-header-name

The presentation:use-header-name attribute specifies the name of the <presentation:header-decl> element that is used for all <presentation:header> elements that are displayed on a page.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `presentation:use-header-name` attribute is usable with the following elements: `<draw:page>` 10.2.4, `<presentation:notes>` 16.17 and `<style:handout-master>` 10.2.1.

The `presentation:use-header-name` attribute has the data type `string` 18.2.

19.427 presentation:user-transformed

The `presentation:user-transformed` attribute specifies whether the size and position of the shape is set by the user or is set by the corresponding presentation shape on the master page.

The defined values for the `presentation:user-transformed` attribute are:

- `false`: size and position of shape set by corresponding presentation shape on master page.
- `true`: size and position of shape set by user.

The `presentation:user-transformed` attribute is usable with the following elements: `<draw:frame>` 10.4.2 and `<draw:page-thumbnail>` 10.3.14.

The `presentation:user-transformed` attribute has the data type `boolean` 18.3.3.

19.428 presentation:verb

The `presentation:verb` attribute specifies the [OLE] verb that is executed for event listeners of type `verb` at the object that contains this event.

The `presentation:verb` attribute is usable with the following element: `<presentation:event-listener>` 10.9.2.

The `presentation:verb` attribute has the data type `nonNegativeInteger` 18.2.

19.429 script:event-name

The `script:event-name` attribute specifies the name of an event.

Event names should begin with a namespace prefix followed by a ":" (U+003A, COLON).

Where appropriate, producers should use the event names described in [DOMEvents2]. The corresponding namespace is "http://www.w3.org/2001/xml-events".

Note: Event names defined in [DOMEvents2] are not namespaced. If used in OpenDocument, they should be preceded by a namespace prefix as described above

Table 9 specifies events defined in [DOMEvents2] that have an equivalent event in HTML. The namespace used for these events is "http://www.w3.org/2001/xml-events"". The namespace prefix used in this specification is "dom".

Table 9 Script Events

Value of `script:event-name` Attribute	***Equivalent HTML Event***	***Description of Event***
`dom:change`	`onchange`	Occurs when a control is no longer focused and the value of the control was modified since

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Value of `script:event-name` Attribute	*Equivalent HTML Event*	*Description of Event*
		it was given focus.
`dom:DOMFocusIn`	`onfocus`	Occurs when a control is given focus using the mouse or the TAB key.
`dom:DOMFocusOut`	`onblur`	Occurs when a control is no longer focused as a result of moving the mouse or by tabbing navigation. It may be used with the same elements as `form:on-focus`.
`dom:mousedown`	`onmousedown`	Occurs when a mouse button is pressed on a control.
`dom:mousemove`	`onmousemove`	Occurs when the mouse pointer is moved onto a control.
`dom:mouseover`	`onmouseover`	Occurs when the mouse pointer is moved over the control.
`dom:mouseup`	`onmouseup`	Occurs when a mouse button is released on a control.
`dom:mouseout`	`onmouseout`	Occurs when the mouse pointer is moved away from a control.
`dom:reset`	`onreset`	Occurs when a form is reset.
`dom:submit`	`onsubmit`	Occurs when a form is submitted.

The `script:event-name` attribute is usable with the following elements: `<presentation:event-listener>` 10.9.2 and `<script:event-listener>` 14.4.2.

The `script:event-name` attribute has the data type `string` 18.2.

19.430 script:language

The attribute `script:language` specifies the name of a script. Script language names are implementation-dependent. The names identifying script languages should begin with by a namespace prefix, followed by a ":" (U+003A, COLON) separator. If a namespace prefix is present, the local name of the attribute value is considered to be a name in the XML namespace bound to the namespace prefix.

The `script:language` attribute is usable with the following elements: `<office:script>` 3.13, `<script:event-listener>` 14.4.2 and `<text:script>` 7.7.9.

The `script:language` attribute has the data type `string` 18.2.

19.431 script:macro-name

The `script:macro-name` attribute specifies the name of a macro. The interpretation of the name is script language dependent.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `script:macro-name` attribute is usable with the following element: `<script:event-listener>` 14.4.2.

The `script:macro-name` attribute has the data type `string` 18.2.

19.432 smil:accelerate

See §11.1.2 of [SMIL20].

The defined range range for the `smil:accelerate` attribute is 0 to 1, inclusive. The default value for a `smil:accelerate` attribute is 0.0, meaning no acceleration.

The default value for this attribute is `0.0`.

The `smil:accelerate` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3, `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2, `<anim:seq>` 15.4.3, `<anim:set>` 15.2.4 and `<anim:transitionFilter>` 15.2.7.

The `smil:accelerate` attribute has values of type `decimal` 18.2 in the range [`0`,`1`].

19.433 smil:accumulate

See $3.4.3 of [SMIL20].

The `smil:accumulate` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3, `<anim:set>` 15.2.4 and `<anim:transitionFilter>` 15.2.7.

The values of the `smil:accumulate` attribute are `none` or `sum`.

19.434 smil:additive

See $3.4.3 of [SMIL20].

The `smil:additive` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3, `<anim:set>` 15.2.4 and `<anim:transitionFilter>` 15.2.7.

The values of the `smil:additive` attribute are `replace` or `sum`.

19.435 smil:attributeName

See §3.4.1 of [SMIL20].

The defined values for the `smil:attributeName` attribute are:

- `charColor`: animates the elements char color.
- `charFontName`: animates the elements text font.
- `charHeight`: animates the elements text height.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `charPosture`: animates the elements text posture.
- `charUnderline`: animates the elements text underline.
- `charWeight`: animates the elements text weight.
- `color`: animates the elements color, this animates both fill,line and char color. Values can be RGB or HSL.
- `fillColor`: animates the elements fill color.
- `fillStyle`: animates the elements fill style.
- `height`: animates the elements height, values are given in screen space where 0 is no height and 1 is the same height as the screen.
- `lineColor`: animates the elements line color.
- `lineStyle`: animates the elements line style.
- `opacity`: animates the elements opacity.
- `rotate`: animates the elements rotation, this animates both the shapes and text animation.
- `skewX`: animates the elements horizontal skew.
- `visibility`: animates the elements visibility.
- `width`: animates the elements width, values are given in screen space where 0 is no width and 1 is the same width as the screen.
- `x`: animates the elements x position, values are given in screen space where 0 is the left edge and 1 is the right edge.
- `y`: animates the elements y position, values are given in screen space where 0 is the top and 1 is the bottom.

The `smil:attributeName` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3 and `<anim:set>` 15.2.4.

The `smil:attributeName` attribute has the data type `string` 18.2.

19.436 smil:autoReverse

See §11.1.2 of [SMIL20].

The default value for this attribute is `false`.

The `smil:autoReverse` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3, `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2, `<anim:seq>` 15.4.3, `<anim:set>` 15.2.4 and `<anim:transitionFilter>` 15.2.7.

The `smil:autoReverse` attribute has the data type `boolean` 18.3.3.

19.437 smil:begin

See §10.3.1 of [SMIL20].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The smil:begin attribute is usable with the following elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3, <anim:audio> 15.5, <anim:command> 15.6.1, <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <anim:set> 15.2.4 and <anim:transitionFilter> 15.2.7.

The smil:begin attribute has the data type string 18.2.

19.438 smil:by

See §3.4.4 of [SMIL20].

The smil:by attribute is usable with the following elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3 and <anim:transitionFilter> 15.2.7.

The smil:by attribute has the data type string 18.2.

19.439 smil:calcMode

See §3.4.2 and §3.7.1 of [SMIL20].

For <anim:animate> 15.2.2 and <anim:animateColor> 15.2.6 elements the default value for this attribute is discrete.

For a <anim:animateMotion> 15.2.5 element the default value for this attribute is paced.

The smil:calcMode attribute is usable with the following elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5 and <anim:transitionFilter> 15.2.7.

The values of the smil:calcMode attribute are discrete, linear, paced or spline.

19.440 smil:decelerate

See §11.1.2 of [SMIL20].

The defined range range for the smil:decelerate attribute is 0 to 1, inclusive.

The default value for this attribute is 0.0.

The smil:decelerate attribute is usable with the following elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3, <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <anim:set> 15.2.4 and <anim:transitionFilter> 15.2.7.

The smil:decelerate attribute has values of type decimal 18.2 in the range [0,1].

19.441 smil:direction

See §12.4.1 of [SMIL20].

For a <anim:transitionFilter> 15.2.7 element the default value for this attribute is forward.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `smil:direction` attribute is usable with the following element: `<anim:transitionFilter>` 15.2.7.

The values of the `smil:direction` attribute are `forward` or `reverse`.

19.442 smil:dur

See §10.3.1 of [SMIL20].

The `smil:dur` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3, `<anim:audio>` 15.5, `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2, `<anim:seq>` 15.4.3, `<anim:set>` 15.2.4 and `<anim:transitionFilter>` 15.2.7.

The `smil:dur` attribute has the data type `string` 18.2.

19.443 smil:end

See §10.3.1 of [SMIL20].

The `smil:end` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3, `<anim:audio>` 15.5, `<anim:command>` 15.6.1, `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2, `<anim:seq>` 15.4.3, `<anim:set>` 15.2.4 and `<anim:transitionFilter>` 15.2.7.

The `smil:end` attribute has the data type `string` 18.2.

19.444 smil:endsync

See §10.3.1 of [SMIL20].

The `smil:endsync` attribute is usable with the following elements: `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2 and `<anim:seq>` 15.4.3.

The values of the `smil:endsync` attribute are `first`, `last`, `all`, `media` or a value of type `IDREF` 18.2.

19.445 smil:fadeColor

See §12.5.1 of [SMIL20].

The default value for this attribute is #000000.

The `smil:fadeColor` attribute is usable with the following element: `<anim:transitionFilter>` 15.2.7.

The `smil:fadeColor` attribute has the data type `color` 18.3.9.

19.446 smil:fill

See §10.3.1 of [SMIL20].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The smil:fill attribute is usable with the following elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3, <anim:audio> 15.5, <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <anim:set> 15.2.4 and <anim:transitionFilter> 15.2.7.

The values of the smil:fill attribute are remove, freeze, hold, auto, default or transition.

19.447 smil:fillDefault

See §10.3.1 of [SMIL20].

The smil:fillDefault attribute is usable with the following elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3, <anim:audio> 15.5, <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <anim:set> 15.2.4 and <anim:transitionFilter> 15.2.7.

The values of the smil:fillDefault attribute are remove, freeze, hold, transition, auto or inherit.

19.448 smil:from

See §3.4.4 of [SMIL20].

The smil:from attribute is usable with the following elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3 and <anim:transitionFilter> 15.2.7.

The smil:from attribute has the data type string 18.2.

19.449 smil:keySplines

See $3.7.1 of [SMIL20].

The smil:keySplines attribute is usable with the following elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6 and <anim:animateMotion> 15.2.5.

The smil:keySplines attribute has the data type string 18.2.

19.450 smil:keyTimes

See $3.7.1 of [SMIL20].

The smil:keyTimes attribute is usable with the following elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6 and <anim:animateMotion> 15.2.5.

The smil:keyTimes attribute has the data type string 18.2.

19.451 smil:mode

See §12.5.1 of [SMIL20].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The default value for this attribute is `in`.

The `smil:mode` attribute is usable with the following element: `<anim:transitionFilter>` 15.2.7.

The values of the `smil:mode` attribute are `in` or `out`.

19.452 smil:repeatCount

See §10.3.1 of [SMIL20].

The `smil:repeatCount` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3, `<anim:audio>` 15.5, `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2, `<anim:seq>` 15.4.3, `<anim:set>` 15.2.4 and `<anim:transitionFilter>` 15.2.7.

The values of the `smil:repeatCount` attribute are a non negative value of type `decimal` 18.2 or `indefinite`.

19.453 smil:repeatDur

See §10.3.1 of [SMIL20].

The value of the `smil:repeatDur` attribute can be `indefinite`, or a clock-value as defined in $10.3.1 of SMIL

The `smil:repeatDur` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3, `<anim:audio>` 15.5, `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2, `<anim:seq>` 15.4.3, `<anim:set>` 15.2.4 and `<anim:transitionFilter>` 15.2.7.

The `smil:repeatDur` attribute has the data type `string` 18.2.

19.454 smil:restart

See §10.3.1 of [SMIL20].

The default value for this attribute is `default`.

The `smil:restart` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3, `<anim:audio>` 15.5, `<anim:iterate>` 15.4.4, `<anim:par>` 15.4.2, `<anim:seq>` 15.4.3, `<anim:set>` 15.2.4 and `<anim:transitionFilter>` 15.2.7.

The values of the `smil:restart` attribute are `never`, `always`, `whenNotActive` or `default`.

19.455 smil:restartDefault

See §10.3.1 of [SMIL20].

The default value for this attribute is `inherit`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The smil:restartDefault attribute is usable with the following elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3, <anim:audio> 15.5, <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <anim:set> 15.2.4 and <anim:transitionFilter> 15.2.7.

The values of the smil:restartDefault attribute are never, always, whenNotActive or inherit.

19.456 smil:subtype

See §12.4.1 of [SMIL20].

Note: See §12.8 of [SMIL20] for a list of supported subtypes.

The smil:subtype attribute is usable with the following element: <anim:transitionFilter> 15.2.7.

The smil:subtype attribute has the data type string 18.2.

19.457 smil:targetElement

See §3.4.1 of [SMIL20].

Drawing shapes are specified by their xml:id or draw:id attribute values and paragraphs by their xml:id or text:id attribute values.

If the anim:sub-item attribute of a <anim:iterate> element has the value whole, the iteration includes the drawing shape's background and its text. If the anim:sub-item attribute value is text, only the shape's text is iterated.

The smil:targetElement attribute is usable with the following elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3, <anim:command> 15.6.1, <anim:iterate> 15.4.4, <anim:set> 15.2.4 and <anim:transitionFilter> 15.2.7.

The smil:targetElement attribute has the data type IDREF 18.2.

19.458 smil:to

See §3.4.4 of [SMIL20].

The smil:to attribute is usable with the following elements: <anim:animate> 15.2.2, <anim:animateColor> 15.2.6, <anim:animateMotion> 15.2.5, <anim:animateTransform> 15.2.3, <anim:set> 15.2.4 and <anim:transitionFilter> 15.2.7.

The smil:to attribute has the data type string 18.2.

19.459 smil:type

The [SMIL20] smil:type attribute specifies a transition type or family.

See §12.8 of [SMIL20] for a list of supported types.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If this attribute is present, the attributes `presentation:transition-type` and `presentation:transition-style` attributes should be ignored.

The `smil:type` attribute is usable with the following element: `<anim:transitionFilter>` 15.2.7.

The `smil:type` attribute has the data type `string` 18.2.

19.460 smil:values

See §3.4.2 of [SMIL20].

The `smil:values` attribute is usable with the following elements: `<anim:animate>` 15.2.2, `<anim:animateColor>` 15.2.6, `<anim:animateMotion>` 15.2.5, `<anim:animateTransform>` 15.2.3 and `<anim:transitionFilter>` 15.2.7.

The `smil:values` attribute has the data type `string` 18.2.

19.461 style:adjustment

The `style:adjustment` attribute specifies how a footnote separator line is aligned on a page.

The defined values for the `style:adjustment` attribute are:

- `center`: footnote separator line centered on page.
- `left`: footnote separator line aligned to left on page.
- `right`: footnote separator line aligned to right on page.

The default value for this attribute is `left`.

The `style:adjustment` attribute is usable with the following element: `<style:footnote-sep>` 17.4.

The values of the `style:adjustment` attribute are `left`, `center` or `right`.

19.462 style:apply-style-name

The `style:apply-style-name` attribute specifies the style to apply when the condition specified by the `style:condition` attribute is `true`. If the referenced style is undefined or is an automatic style, an error occurs.

The referenced style shall be defined by the same type of element as the conditional style that contains the condition. If the referenced style element has a `style:family` attribute, its value further shall be equal the value of the `style:family` attribute of the conditional style.

The `style:apply-style-name` attribute is usable with the following element: `<style:map>` 16.3.

The `style:apply-style-name` attribute has the data type `styleNameRef` 18.3.32.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.463 style:auto-update

The `style:auto-update` attribute specifies whether styles are automatically updated when the formatting properties of an object that has the style assigned to it are changed.

The defined values for the `style:auto-update` attribute are:

- `false`: a change to a formatting property is applied for the object where the change was made. If necessary, an new automatic style will be created which is applied to the object where the change was made.
- `true`: a change to a formatting property results in the updating of the common style that is applied to an object. The formatting change is applied to all objects subject to the common style where the change was made.

The default value for this attribute is `false`.

The `style:auto-update` attribute is usable with the following element: `<style:style>` 16.2.

The `style:auto-update` attribute has the data type `boolean` 18.3.3.

19.464 style:base-cell-address

The `style:base-cell-address` attribute specifies as an absolute cell address with a table name the base cell for relative addresses in formulas. This attribute applies only to cell styles where the condition contains a formula.

The `style:base-cell-address` attribute is usable with the following element: `<style:map>` 16.3.

The `style:base-cell-address` attribute has the data type `cellAddress` 18.3.4.

19.465 style:char

The `style:char` attribute specifies the delimiter character for tab stops of type `char`.

The `style:char` attribute is usable with the following element: `<style:tab-stop>` 17.8.

The `style:char` attribute has the data type `character` 18.3.7.

19.466 style:class

The `style:class` attribute specifies a style class name. A style class name is a string and any style may belong to any number of classes. A style may belong to any class of styles.

The `style:class` attribute is usable with the following element: `<style:style>` 16.2.

The `style:class` attribute has the data type `string` 18.2.

19.467 style:color

The `style:color` attribute specifies the color of a column or footnote separator line.

For a `<style:column-sep>` 17.14 element the default value for this attribute is `#000000`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `style:color` attribute is usable with the following elements: `<style:column-sep>` 17.14 and `<style:footnote-sep>` 17.4.

The `style:color` attribute has the data type `color` 18.3.9.

19.468 style:condition

The `style:condition` attribute specifies a condition that triggers a style map.

If a consumer does not recognize a condition, it shall ignore the `<style:map>` element containing the condition.

The defined conditions that may be used by paragraph styles are:

- `footnote()` and `endnote()`: true if the style is applied to a paragraph or heading that is contained in a footnote or endnote.
- `header()` and `footer()`: True if the style is applied to a paragraph or heading that is contained in a page header or footer.
- `list-level()=`*`n`*, where *`n`* is a number: true if the style is applied to a paragraph or heading that is contained in a list on level *`n`*, or to a numbered paragraph on level *`n`*.
- `outline-level()=`*`n`*, where *`n`* is a number: true if the if the style is applied to a heading on level `n`.
- `section()`: true if the style is applied to a paragraph or heading that is contained in a text section.
- `table()` and `table-header()`: true if the style is applied to a paragraph or heading that is contained in a table cell or table header cell.

The defined conditions that may be used by table cell styles are:

- `cell-content()` *`op value`*: where *`op`* is one of the relational operators ”<”, ”>”, ”<=”, ”>=”, ”=” or ”!=”: true if the style is applied to a table cell where the cell's value compared to the value specified in the condition by *`value`* using the relational operator *`op`* evaluates to true.
- `cell-content-is-between(`*`value1`*`, `*`value2`*`)`: true if the style is applied to a table cell whose value is between *`value1`* and *`value2`*.
- `cell-content-is-not-between(`*`value`*`, `*`value`*`)`: true if the style is applied to a table cell whose value is not between *`value1`* and *`value2`*.
- `is-true-formula(`*`expression`*`)`: true if the style is applied to a table cell for which formula evaluates true.

Within table cell style conditions:

- *`value`*, *`value1`* and *`value2`* are a *`numberValue`*, a *`string`* or an *`expression`*.
- *`numberValue`* is a whole or decimal number. The number shall not contain comma “.” (U+002C, COMMA) separators for numbers of 1000 or greater.
- *`string`* comprises one or more characters surrounded by double quotation marks (U+0022 QUOTATION MARK). An embedded quotation mark is escaped by doubling it.
- *`expression`* is an expression.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined condition that may be used by data styles is:

- `value() op n`, where, *op* is one of the relational operators ”<”, ”>”, ”<=”, ”>=”, “=” or ”!=”, and *n* is a number for non-Boolean data styles and `true` or `false` for Boolean data styles: true if the style is applied to a table cell where the cell's value compared to the value specified in the condition by *n* using the relational operator *op* evaluates to true.

The defined conditions for table cell styles and data styles should be preceded by a namespace prefix. If the namespace prefix is missing it defaults to the "urn:oasis:names:tc:opendocument:xmlns:of:1.2" namespace.

The XML namespace name associated with the namespace prefix specifies the syntax and semantics of the expressions and values occurring within the condition. Expressions defined by part 2 of this specification shall not start with an “=” (EQUALS SIGN, U+003D).

Relative cell range addresses that occur in a condition for a table cell style define an offset which shall be interpreted relative to the cell for which a condition is calculated. The offset is the same as the offsets between the table cell addressed by the relative cell range address and the table cell specified by the `style:base-cell-address` attribute.

An OpenDocument Consumer when hosting a formula evaluator make available the host-dependent properties defined by table 12 in 19.644.

The `style:condition` attribute is usable with the following element: `<style:map>` 16.3.

The `style:condition` attribute has the data type `string` 18.2.

19.469 style:data-style-name

19.469.1 General

The `style:data-style-name` attribute specifies the name of a data style.

19.469.2 <presentation:date-time-decl>

The `style:data-style-name` attribute specifies a data style to format a date and time.

The `style:data-style-name` attribute is usable with the following element: `<presentation:date-time-decl>` 10.9.3.6.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.3 <style:style>

The `style:data-style-name` attribute specifies a data style for a `<style:style>` element that defines the styles for table cell styles and chart styles.

The `style:data-style-name` attribute is usable with the following element: `<style:style>` 16.2.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.4 <text:creation-date>

The `style:data-style-name` attribute specifies a data style to format a numeric value.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `style:data-style-name` attribute is usable with the following element: `<text:creation-date>` 7.5.3.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.5 <text:creation-time>

The `style:data-style-name` attribute specifies a data style to format a numeric value.

The `style:data-style-name` attribute is usable with the following element: `<text:creation-time>` 7.5.4.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.6 <text:database-display>

The `style:data-style-name` attribute specifies a data style to format a numeric value.

The `style:data-style-name` attribute is usable with the following element: `<text:database-display>` 7.6.3.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.7 <text:date>

The `style:data-style-name` attribute specifies a data style to format a numeric value.

The `style:data-style-name` attribute is usable with the following element: `<text:date>` 7.3.2.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.8 <text:editing-duration>

The `style:data-style-name` attribute specifies a data style to format a numeric value.

The `style:data-style-name` attribute is usable with the following element: `<text:editing-duration>` 7.5.14.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.9 <text:expression>

The `style:data-style-name` attribute specifies a data style to format a field value. This attribute shall be omitted for fields whose value type is `string`. It shall be present for fields whose value type is not `string`.

The `style:data-style-name` attribute is usable with the following element: `<text:expression>` 7.4.14.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.469.10 <text:meta-field>

The `style:data-style-name` attribute specifies a data style to format a numeric value.

The `style:data-style-name` attribute is usable with the following element: `<text:meta-field>` 7.5.19.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.11 <text:modification-date>

The `style:data-style-name` attribute specifies a data style to format a numeric value.

The `style:data-style-name` attribute is usable with the following element: `<text:modification-date>` 7.5.16.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.12 <text:modification-time>

The `style:data-style-name` attribute specifies a data style to format a numeric value.

The `style:data-style-name` attribute is usable with the following element: `<text:modification-time>` 7.5.15.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.13 <text:print-date>

The `style:data-style-name` attribute specifies a data style to format a numeric value.

The `style:data-style-name` attribute is usable with the following element: `<text:print-date>` 7.5.8.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.14 <text:print-time>

The `style:data-style-name` attribute specifies a data style to format a numeric value.

The `style:data-style-name` attribute is usable with the following element: `<text:print-time>` 7.5.7.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.15 <text:table-formula>

The `style:data-style-name` attribute specifies a data style to format a numeric value.

The `style:data-style-name` attribute is usable with the following element: `<text:table-formula>` 7.7.14.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.469.16 <text:time>

The `style:data-style-name` attribute specifies a data style to format a numeric value.

The `style:data-style-name` attribute is usable with the following element: `<text:time>` 7.3.3.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.17 <text:user-defined>

The `style:data-style-name` attribute specifies a data style to format a field value. This attribute shall be omitted for fields whose value type is `string`. It shall be present for fields whose value type is not `string`.

The `style:data-style-name` attribute is usable with the following element: `<text:user-defined>` 7.5.6.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.18 <text:user-field-get>

The `style:data-style-name` attribute specifies a data style to format a field value. This attribute shall be omitted for fields whose value type is `string`. It shall be present for fields whose value type is not `string`.

The `style:data-style-name` attribute is usable with the following element: `<text:user-field-get>` 7.4.9.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.19 <text:user-field-input>

The `style:data-style-name` attribute specifies a data style to format a field value. This attribute shall be omitted for fields whose value type is `string`. It shall be present for fields whose value type is not `string`.

The `style:data-style-name` attribute is usable with the following element: `<text:user-field-input>` 7.4.10.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.20 <text:variable-get>

The `style:data-style-name` attribute specifies a data style to format a field value. This attribute shall be omitted for fields whose value type is `string`. It shall be present for fields whose value type is not `string`.

The `style:data-style-name` attribute is usable with the following element: `<text:variable-get>` 7.4.5.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.469.21 <text:variable-input>

The `style:data-style-name` attribute specifies a data style to format a field value. This attribute shall be omitted for fields whose value type is `string`. It shall be present for fields whose value type is not `string`.

The `style:data-style-name` attribute is usable with the following element: `<text:variable-input>` 7.4.6.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.469.22 <text:variable-set>

The `style:data-style-name` attribute specifies a data style to format a field value. This attribute shall be omitted for fields whose value type is `string`. It shall be present for fields whose value type is not `string`.

The `style:data-style-name` attribute is usable with the following element: `<text:variable-set>` 7.4.4.

The `style:data-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.470 style:default-outline-level

The `style:default-outline-level` attribute specifies a default outline level for a style with the family `paragraph`.

If the `style:default-outline-level` attribute is present in a paragraph style, and if an this paragraph style is assigned to a paragraph or heading by user action, then the consumer should replace the paragraph or heading with a heading of the specified level, which has the same content and attributes as the original paragraph or heading.

Note: This attribute does not modify the behavior of `<text:p>` or `<text:h>` elements, but only instructs an consumer to create one or the other when assigning a paragraph style as a result of user interface action while the document is edited.

The `style:default-outline-level` attribute value can be empty. If empty, this attribute does not inherit a list style value from a parent style.

The `style:default-outline-level` attribute is usable with the following element: `<style:style>` 16.2.

The values of the `style:default-outline-level` attribute are a value of type `positiveInteger` 18.2 or an empty string.

19.471 style:display

The `style:display` attribute specifies whether the header or footer is displayed or not.

The defined values for the `style:display` attribute are:

- `false`: header or footer is not displayed.
- `true`: header or footer is displayed.

The default value for this attribute is `true`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The style:display attribute is usable with the following elements: <style:footer> 16.11, <style:footer-left> 16.13, <style:header> 16.10 and <style:header-left> 16.12.

The style:display attribute has the data type boolean 18.3.3.

19.472 style:display-name

The style:display-name attribute specifies the name of a style as it should appear in the user interface. If this attribute is not present, the display name is the same as the style name.

The style:display-name attribute is usable with the following elements: <number:boolean-style> 16.27.23, <number:currency-style> 16.27.7, <number:date-style> 16.27.10, <number:number-style> 16.27.2, <number:percentage-style> 16.27.9, <number:text-style> 16.27.25, <number:time-style> 16.27.18, <style:master-page> 16.9, <style:presentation-page-layout> 16.41, <style:style> 16.2 and <text:list-style> 16.30.

The style:display-name attribute has the data type string 18.2.

19.473 style:distance

The style:distance attribute specifies the distance between the last of the characters using the larger font and the first of the remaining characters of each line.

Note: If the leading characters for a paragraph span the line size of a portion of the remaining text of a paragraph, the style:distance attribute specifies the distance between the end of the text written in the larger font and the smaller text of any lines that it spans.

The default value for this attribute is 0cm.

The style:distance attribute is usable with the following element: <style:drop-cap> 17.9.

The style:distance attribute has the data type length 18.3.18.

19.474 style:distance-before-sep

The style:distance-before-sep attribute specifies the space between the body text area and a footnote separator line.

The style:distance-before-sep attribute is usable with the following element: <style:footnote-sep> 17.4.

The style:distance-before-sep attribute has the data type length 18.3.18.

19.475 style:distance-after-sep

The style:distance-after-sep attribute specifies the space between a footnote separator line and the footnote text.

The style:distance-after-sep attribute is usable with the following element: <style:footnote-sep> 17.4.

The style:distance-after-sep attribute has the data type length 18.3.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.476 style:family

The `style:family` attribute specifies the family of a style.

The defined values for the `style:family` attribute are:

- `chart`: family name of styles for charts.
- `drawing-page`: family name of styles for drawing pages.
- `graphic`: family name of styles for graphic elements.
- `paragraph`: family name of styles for paragraphs.
- `presentation`: family name of styles for presentations.
- `ruby`: family name of styles for ruby text.
- `table`: family name of styles for tables.
- `table-cell`: family name of styles for table cells.
- `table-column`: family name of styles for table columns.
- `table-row`: family name of styles for table rows.
- `text`: family name of styles for text.

The `style:family` attribute is usable with the following elements: `<style:default-style>` 16.4 and `<style:style>` 16.2.

The values of the `style:family` attribute are `text`, `paragraph`, `section`, `ruby`, `table`, `table-column`, `table-row`, `table-cell`, `graphic`, `presentation`, `drawing-page` or `chart`.

19.477 style:filter-name

The `style:filter-name` attribute specifies the implementation-dependent filter name that has been used to load an image into the document.

This attribute is attached to a `<style:background-image>` element.

The `style:filter-name` attribute is usable with the following element: `<style:background-image>` 17.3.

The `style:filter-name` attribute has the data type `string` 18.2.

19.478 style:font-adornments

The `style:font-adornments` attributes specifies a characteristic of a font.

Note: A font characteristic includes bold or italic, which when used with a font family name, specifies a font.

The `style:font-adornments` attribute is usable with the following element: `<style:font-face>` 16.21.

The `style:font-adornments` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.479 style:font-charset

The `style:font-charset` attribute specifies whether a font defines glyphs according to the semantics of [UNICODE] or not.

The value of this attributes can be `x-symbol` or a character encoding in the notation described in the §4.3.3 of [XML1.0]. If the value is `x-symbol`, the font does not defines glyphs according to the semantics of [UNICODE]. If the value is one of the encodings or transformations of [UNICODE], the font does define glyphs according to the semantics of [UNICODE]. The use of other values is deprecated.

Note: Fonts for which the attribute has the value `x-symbol` may define glyphs for code points in the private use area of [UNICODE].

The `style:font-charset` attribute is usable with the following element: `<style:font-face>` 16.21.

The `style:font-charset` attribute has the data type `textEncoding` 18.3.35.

19.480 style:font-family-generic

The `style:font-family-generic` attribute specifies a generic font family name.

The defined values for the `style:font-family-generic` attribute are:

- `decorative`: the family of decorative fonts.
- `modern`: the family of modern fonts.
- `roman`: the family roman fonts (with serifs).
- `script`: the family of script fonts.
- `swiss`: the family roman fonts (without serifs).
- `system`: the family system fonts.

The `style:font-family-generic` attribute is usable with the following element: `<style:font-face>` 16.21.

The values of the `style:font-family-generic` attribute are `roman`, `swiss`, `modern`, `decorative`, `script` or `system`.

19.481 style:font-pitch

The `style:font-pitch` attribute specifies whether a font has a fixed or variable width.

The defined values for the `style:font-pitch` attribute are:

- `fixed`: font has a fixed width.
- `variable`: font has a variable width.

The `style:font-pitch` attribute is usable with the following element: `<style:font-face>` 16.21.

The values of the `style:font-pitch` attribute are `fixed` or `variable`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.482 style:height

The `style:height` attribute specifies the height of a column separator line. The value of this attribute is a percentage of the height of the columned area.

The defined value range for the `style:height` attribute is 0% to 100%, inclusive.

The default value for this attribute is `100%`.

The `style:height` attribute is usable with the following element: `<style:column-sep>` 17.14.

The `style:height` attribute has the data type `zeroToHundredPercent` 18.3.41.

19.483 style:leader-char

The `style:leader-char` attribute specifies a leader character.

The `style:leader-char` attribute is usable with the following element: `<text:index-entry-tab-stop>` 8.13.6.

The `style:leader-char` attribute has the data type `character` 18.3.7.

19.484 style:leader-color

The `style:leader-color` attribute specifies the color of a leader line. The value of this attribute is either `font-color` or a color. If the value is `font-color`, the current text color is used for the leader line.

The `style:leader-color` attribute is usable with the following element: `<style:tab-stop>` 17.8.

The values of the `style:leader-color` attribute are `font-color` or a value of type `color` 18.3.9.

19.485 style:leader-style

The `style:leader-style` attribute specifies a style for a leader line.

The defined values for the `style:leader-style` attribute are:

- `none`: tab stop has no leader line.
- `dash`: tab stop has a dashed leader line.
- `dot-dash`: tab stop has a leader line whose repeating pattern is a dot followed by a dash.
- `dot-dot-dash`: tab stop has a leader line whose repeating pattern has two dots followed by a dash.
- `dotted`: tab stop has a dotted leader line.
- `long-dash`: tab stop has a dashed leader line whose dashes are longer than the ones from the dashed line for value dash.
- `solid`: tab stop has a solid leader line.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `wave`: tab stop has a wavy leader line.

Note: The definitions of the values of the `style:leader-style` attribute are based on the text decoration style 'text-underline-style' from [CSS3Text], §9.2.

The `style:leader-style` attribute is usable with the following element: `<style:tab-stop>` 17.8.

The values of the `style:leader-style` attribute are `none`, `solid`, `dotted`, `dash`, `long-dash`, `dot-dash`, `dot-dot-dash` or `wave`.

19.486 style:leader-text

The `style:leader-text` attribute specifies a single Unicode character for use as leader text for tab stops.

An consumer may support only specific characters as textual leaders. If a character that is not supported by a consumer is specified by this attribute, the consumer should display a leader character that it supports instead of the one specified by this attribute.

If both `style:leader-text` and `style:leader-style` attributes are specified, the value of the `style:leader-text` sets the leader text for tab stops.

The default value for this attribute is " " (U+0020, SPACE).

The `style:leader-text` attribute is usable with the following element: `<style:tab-stop>` 17.8.

The `style:leader-text` attribute has the data type `character` 18.3.7.

19.487 style:leader-text-style

The `style:leader-text-style` specifies a text style that is applied to a textual leader. It is not applied to leader lines. If the attribute appears in an automatic style, it may reference either an automatic text style or a common style. If the attribute appears in a common style, it may reference a common style only.

The `style:leader-text-style` attribute is usable with the following element: `<style:tab-stop>` 17.8.

The `style:leader-text-style` attribute has the data type `styleNameRef` 18.3.32.

19.488 style:leader-type

The `style:leader-type` attribute specifies whether a leader line should be drawn, and if so, whether a single or double line will be used.

The defined values for the `style:leader-type` attribute are:

- `double`: a double line is drawn.
- `none`: no line is drawn.
- `single`: a single line is drawn.

The `style:leader-type` attribute is usable with the following element: `<style:tab-stop>` 17.8.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The values of the style:leader-type attribute are none, single or double.

19.489 style:leader-width

The style:leader-width attribute specifies the width of a leader line.

The defined values for the style:leader-width attribute are:

- auto: the width of a leader line should be calculated from the font size of the text where the leader line will appear.
- bold: the width of a leader line should be calculated from the font size of the text where the leader line will appear but is wider than for the value of auto.
- a value of type percent 18.3.23
- a value of type positiveInteger 18.2
- a value of type positiveLength 18.3.26

The line widths referenced by the values medium, normal, thick and thin are implementation-defined.

The style:leader-width attribute is usable with the following element: <style:tab-stop> 17.8.

The values of the style:leader-width attribute are auto, normal, bold, thin, medium, thick, a value of type positiveInteger 18.2, a value of type percent 18.3.23 or a value of type positiveLength 18.3.26.

19.490 style:legend-expansion

The style:legend-expansion attribute specifies the direction in which a legend expands .

The defined values for the style:legend-expansion attribute are:

- balanced: legend expands horizontally and vertically.
- custom: with a style:legend-expansion-aspect-ratio attribute legend expands according to the specified ratio.
- high: legend expands vertically.
- wide: legend expands horizontally.

The style:legend-expansion attribute is usable with the following element: <chart:legend> 11.3.

The values of the style:legend-expansion attribute are wide, high, balanced or custom.

19.491 style:legend-expansion-aspect-ratio

The style:legend-expansion-aspect-ratio attribute specifies the ratio between width and height for a style:legend-expansion attribute with value custom.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The style:legend-expansion-aspect-ratio attribute is usable with the following element: <chart:legend> 11.3.

The style:legend-expansion-aspect-ratio attribute has the data type double 18.2.

19.492 style:length

The style:length attribute specifies the number of characters that are displayed in a larger font.

The defined values for the style:length attribute are:

- word: specifies a set of characters to be displayed in a larger font.
- a value of type positiveInteger 18.2

Note: What will be treated as a “word” by a consumer is locale specific.

The default value for this attribute is 1.

The style:length attribute is usable with the following element: <style:drop-cap> 17.9.

The values of the style:length attribute are word or a value of type positiveInteger 18.2.

19.493 style:line-style

The style:line-style attribute specifies the style of a footnote separator line.

The defined value for the style:line-style attribute is none: no footnote separator line is drawn.

The footnote separator components referenced by the values dash, dot-dash, dot-dot-dash, dotted, long-dash, solid and wave, are implementation-defined.

The style:line-style attribute is usable with the following element: <style:footnote-sep> 17.4.

The values of the style:line-style attribute are none, solid, dotted, dash, long-dash, dot-dash, dot-dot-dash or wave.

19.494 style:lines

The style:lines attribute specifies the number of text lines which a font spans. If the value of this attribute is 1, <style:drop-cap> is disabled.

The default value for this attribute is 1.

The style:lines attribute is usable with the following element: <style:drop-cap> 17.9.

The style:lines attribute has the data type positiveInteger 18.2.

19.495 style:list-level

The style:list-level attribute specifies the list level value of a list style that may be applied to any paragraph style. It does not directly specify the paragraph's list level value, but consumers

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

can change the paragraph's list level value to the specified value when the paragraph style is applied. It is valid only if the `style:list-style-name` attribute is specified and is not empty, and if the `style:family` attribute has the value `paragraph`.

The `style:list-level` attribute is usable with the following element: `<style:style>` 16.2.

The values of the `style:list-level` attribute are a value of type `positiveInteger` 18.2 or an empty string.

19.496 style:list-style-name

The `style:list-style-name` attribute specifies a list style for style families with paragraph formatting properties. This applies to automatic and common styles.

The list style specified by this attribute is applied to headings and paragraphs that are contained in a list, where the list does not specify a list style itself, and the list has no list style specification for any of its parents.

The `style:list-style-name` attribute value can be empty. If empty, this attribute does not inherit a list style value from a parent style.

The `style:list-style-name` attribute is usable with the following element: `<style:style>` 16.2.

The values of the `style:list-style-name` attribute are a value of type `styleName` 18.3.31 or an empty string.

19.497 style:master-page-name

The `style:master-page-name` attribute defines a master page for a paragraph or table style. This applies to automatic and common styles.

If this attribute is associated with a style, a page break is inserted when the style is applied and the specified master page is applied to the resulting page.

This attribute is ignored if it is associated with a paragraph style that is applied to a paragraph within a table.

The `style:master-page-name` attribute is usable with the following element: `<style:style>` 16.2.

The `style:master-page-name` attribute has the data type `styleNameRef` 18.3.32.

19.498 style:name

19.498.1 General

The `style:name` attribute specifies names that reference style mechanisms.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.498.2 <number:boolean-style>, <number:currency-style>, <number:date-style>, <number:number-style>, <number:percentage-style>, <number:text-style>, <number:time-style>, <style:master-page>, <style:page-layout>, <style:presentation-page-layout>, <style:style>, <text:list-style>, <text:outline-style>

The `style:name` attribute specifies the name of a:

- data style - It can be used with all data style elements.
- list style
- master page - Each master page is referenced using the page name. The name specified shall be unique to the document instance.
- outline style - The outline style as a list style can be referenced by the `style:list-style-name` attribute.
- page layout
- style – With the `style:family` attribute, the `style:name` attribute uniquely identifies a style. The `<office:styles>`, `<office:automatic-styles>` and `<office:master-styles>` elements each shall not contain two styles with the same family and the same name.

For automatic styles, the name may be generated by OpenDocument producers. For each style family or style element, producers should generate distinct sets of names for automatic styles stored in the content.xml 3.1.3.2 and styles.xml 3.1.3.3 files. The names should also be distinct from the names used in the `<office:styles>` element inside the styles.xml files.

Note: If the document is produced multiple times, it cannot be assumed that the same name is generated each time.

The `style:name` attribute is usable with the following elements: `<number:boolean-style>` 16.27.23, `<number:currency-style>` 16.27.7, `<number:date-style>` 16.27.10, `<number:number-style>` 16.27.2, `<number:percentage-style>` 16.27.9, `<number:text-style>` 16.27.25, `<number:time-style>` 16.27.18, `<style:master-page>` 16.9, `<style:page-layout>` 16.5, `<style:presentation-page-layout>` 16.41, `<style:style>` 16.2, `<text:list-style>` 16.30 and `<text:outline-style>` 16.34.

The `style:name` attribute has the data type `styleName` 18.3.31.

19.498.3 <style:font-face>

The `style:name` attribute specifies a unique name for a font declaration. This name can be used inside styles as an attribute of the `<style:text-properties>` element) as the value of a `style:font-name` attribute to immediately select a font face declaration.

The `style:name` attribute is usable with the following element: `<style:font-face>` 16.21.

The `style:name` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.499 style:next-style-name

19.499.1 General

The `style:next-style-name` attribute specifies a style to be used with pages and paragraphs.

19.499.2 <style:master-page>

The `style:next-style-name` attribute specifies the name of the master page that is used for the next page if the current page is entirely filled. If the next style name is not specified, the current master page is used for the next page. The value of this attribute shall be the name of a `<style:master-page>` element.

The `style:next-style-name` attribute is usable with the following element: `<style:master-page>` 16.9.

The `style:next-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.499.3 <style:style>

Within styles for paragraphs, `style:next-style-name` attribute specifies the style to be used for the next paragraph if a paragraph break is inserted in the user interface. By default, the current style is used as the next style.

The `style:next-style-name` attribute is usable with the following element: `<style:style>` 16.2.

The `style:next-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.500 style:num-format

The `style:num-format` attribute specifies a numbering sequence.

The defined values for the `style:num-format` attribute are:

- `1`: Hindu-Arabic number sequence starts with 1.
- `a`: number sequence of lowercase Modern Latin basic alphabet characters starts with “a”.
- `A`: number sequence of uppercase Modern Latin basic alphabet characters starts with “A”.
- `i`: number sequence of lowercase Roman numerals starts with “i”.
- `I`: number sequence of uppercase Roman numerals start with “I”.
- a value of type `string` 18.2.
- an empty string: no number sequence displayed.

If no value is given, no number sequence is displayed.

The `style:num-format` attribute is usable with the following elements: `<text:character-count>` 7.5.18.5, `<text:database-row-number>` 7.6.6, `<text:image-count>` 7.5.18.7, `<text:linenumbering-configuration>` 16.29.1, `<text:list-level-style-number>` 16.32, `<text:notes-configuration>` 16.29.3, `<text:object-count>` 7.5.18.8,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<text:outline-level-style> 16.35, <text:page-count> 7.5.18.2, <text:page-number> 7.3.4, <text:page-variable-get> 7.7.1.3, <text:paragraph-count> 7.5.18.3, <text:sequence> 7.4.13, <text:table-count> 7.5.18.6 and <text:word-count> 7.5.18.4.

The values of the style:num-format attribute are 1, i, I, a value of type string 18.2, an empty string, a or A.

19.501 style:num-letter-sync

The style:num-letter-sync attribute specifies whether letter synchronization shall take place. If letters are used in alphabetical order for numbering, there are two ways to process overflows within a digit, as follows:

- false: A new digit is inserted that always has the same value as the following digit. The numbering sequence (for lower case numberings) in that case is a, b, c, ..., z, aa, bb, cc, ..., zz, aaa, ..., and so on.
- true: A new digit is inserted. Its start value is ”a” or ”A”, and it is incremented every time an overflow occurs in the following digit. The numbering sequence (for lower case numberings) in that case is a,b,c, ..., z, aa, ab, ac, ...,az, ba, ..., and so on.

The style:num-letter-sync attribute is usable with the following elements: <text:character-count> 7.5.18.5, <text:database-row-number> 7.6.6, <text:image-count> 7.5.18.7, <text:linenumbering-configuration> 16.29.1, <text:list-level-style-number> 16.32, <text:notes-configuration> 16.29.3, <text:object-count> 7.5.18.8, <text:outline-level-style> 16.35, <text:page-count> 7.5.18.2, <text:page-number> 7.3.4, <text:page-variable-get> 7.7.1.3, <text:paragraph-count> 7.5.18.3, <text:sequence> 7.4.13, <text:table-count> 7.5.18.6 and <text:word-count> 7.5.18.4.

The style:num-letter-sync attribute has the data type boolean 18.3.3.

19.502 style:num-prefix

The style:num-prefix attribute specifies what to display before a number.

If the style:num-prefix and style:num-suffix values do not contain any character that has a Unicode category of Nd, Nl, No, Lu, Ll, Lt, Lm or Lo, an [XSLT] format attribute can be created from the OpenDocument attributes by concatenating the values of the style:num-prefix, style:num-format, and style:num-suffix attributes.

The style:num-prefix attribute can also specify a character before the value of a text:bullet-char attribute.

The style:num-prefix attribute is usable with the following elements: <text:list-level-style-bullet> 16.31, <text:list-level-style-number> 16.32, <text:notes-configuration> 16.29.3 and <text:outline-level-style> 16.35.

The style:num-prefix attribute has the data type string 18.2.

19.503 style:num-suffix

The style:num-prefix and style:num-suffix attributes specify what to display before and after the number.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If the style:num-prefix and style:num-suffix values do not contain any character that has a Unicode category of Nd, Nl, No, Lu, Ll, Lt, Lm or Lo, an [XSLT] format attribute can be created from the OpenDocument attributes by concatenating the values of the style:num-prefix, style:num-format, and style:num-suffix attributes.

The style:num-suffix attribute can also specify a character after the value of a text:bullet-char attribute.

The style:num-suffix attribute is usable with the following elements: <text:list-level-style-bullet> 16.31, <text:list-level-style-number> 16.32, <text:notes-configuration> 16.29.3 and <text:outline-level-style> 16.35.

The style:num-suffix attribute has the data type string 18.2.

19.504 style:page-layout-name

The style:page-layout-name attribute specifies a page layout style that contains sizes, border and orientation attributes.

The style:page-layout-name attribute is usable with the following elements: <presentation:notes> 16.17, <style:handout-master> 10.2.1 and <style:master-page> 16.9.

The style:page-layout-name attribute has the data type styleNameRef 18.3.32.

19.505 style:page-usage

The style:page-usage attribute specifies the type of pages that a page master should generate.

The defined values for the style:page-usage attribute are:

- all: if there are no <style:header-left> or <style:footer-left> elements, the header and footer content is the same for left and right pages.
- left: <style:header-left> or <style:footer-left> elements are ignored.
- mirrored: if there are no <style:header-left> or <style:footer-left> elements, the header and footer content is the same for left and right pages.
- right: <style:header-left> or <style:footer-left> elements are ignored.

The default value for this attribute is all.

The style:page-usage attribute is usable with the following element: <style:page-layout> 16.5.

The values of the style:page-usage attribute are all, left, right or mirrored.

19.506 style:parent-style-name

The style:parent-style-name attribute specifies the name of a parent style. The parent style cannot be an automatic style and shall exist.

If a parent style is not specified, the default style which has the same family as the current style is used.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The style:parent-style-name attribute is usable with the following element: <style:style> 16.2.

The style:parent-style-name attribute has the data type styleNameRef 18.3.32.

19.507 style:percentage-data-style-name

The style:percentage-data-style-name attribute references the name of a percentage data style.

This attribute should be used together with chart:data-label-number attribute when the chart:data-label-number attribute has the value percentage or the value value-and-percentage.

The style:percentage-data-style-name attribute is usable with the following element: <style:style> 16.2.

The style:percentage-data-style-name attribute has the data type styleNameRef 18.3.32.

19.508 style:position

19.508.1 General

This attribute defines a position.

19.508.2 <style:background-image>

The style:position attribute specifies the position of a background image. Its value can be a space separated combination of top, center or bottom for the vertical position and left, center or right for the horizontal position. The vertical and horizontal positions can be specified in any order. If one position is specified, the other position defaults to center.

For a <style:background-image> 17.3 element the default value for this attribute is center.

The style:position attribute is usable with the following element: <style:background-image> 17.3.

The values of the style:position attribute are left, center, right, top, bottom, or two white space separated values, that may appear in any order. One of these values is one of: left, center or right. The other value is one of: top, center or bottom.

19.508.3 <style:tab-stop>

The style:position attribute specifies the position of a tab stop. Depending on the value of the text:relative-tab-stop-position attribute in the <text:table-of-content-source>, <text:illustration-index-source>, <text:object-index-source>, <text:user-index-source> or <text:alphabetical-index-source> parent element, the position of the tab is interpreted as being relative to the left margin or the left indent.

The style:position attribute is usable with the following element: <style:tab-stop> 17.8.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `style:position` attribute has the data type `length` 18.3.18.

19.508.4 <text:index-entry-tab-stop>

The `style:position` attribute specifies the position of a tab stop. If the value of the `style:type` attribute is `left`, then this attribute shall be present. Otherwise, it shall be omitted.

Depending on the value of the `text:relative-tab-stop-position` attribute in the `<text:table-of-content-source>`, `<text:illustration-index-source>`, `<text:object-index-source>`, `<text:user-index-source>` or `<text:alphabetical-index-source>` parent element, the position of the tab is interpreted as being relative to the left margin or the left indent.

The `style:position` attribute is usable with the following element: `<text:index-entry-tab-stop>` 8.13.6.

The `style:position` attribute has the data type `length` 18.3.18.

19.509 style:rel-height

The `style:rel-height` attribute specifies height of a drawing object as a relative value within a frame.

The defined values for the `style:rel-height` attribute are:

- `scale`: the height should be calculated depending on the width, so that the ratio of width and height of the original image or object size is preserved.
- `scale-min`: the height should be calculated as for value `scale`, but the calculated height is a minimum height rather than an absolute one.
- a value of type `percent` 18.3.23.

The interpretation of percentage values depends on the anchor of the drawing object. If the anchor for the drawing object is in a table cell, the percentage value is relative to the surrounding table box. If the anchor for the drawing object is in a text box, the percentage value is relative to the surrounding text box. In other cases, the percentage values is relative to the width of the page or window.

To support consumers that do not support relative width and heights, producers should also provide the height in `svg:height` and `fo:min-height` attributes.

The `style:rel-height` attribute is usable with the following element: `<draw:frame>` 10.4.2.

The values of the `style:rel-height` attribute are a value of type `percent` 18.3.23, `scale` or `scale-min`.

19.510 style:rel-width

19.510.1 General

The `style:rel-width` attribute specifies widths.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.510.2 <draw:frame>

The `style:rel-width` attribute specifies the width of a drawing object as a relative value within a frame.

The defined values for the `style:rel-width` attribute are:

- `scale`:the width should be calculated depending on the height, so that the ratio of width and height of the original image or object size is preserved.
- `scale-min`: the width should be calculated as for value `scale`, but the calculated width is a minimum width rather than an absolute one.
- a value of type `percent` 18.3.23.

The interpretation of percentage values depends on the anchor of the drawing object. If the anchor for the drawing object is in a table cell, the percentage value is relative to the surrounding table box. If the anchor for the drawing object is in a text box, the percentage value is relative to the surrounding text box. In other cases, the percentage values is relative to the width of the page or window.

To support consumers that do not support relative width, producers should also provide the width and heights in the `svg:width` and `fo:min-width` attributes.

The `style:rel-width` attribute is usable with the following element: `<draw:frame>` 10.4.2.

The values of the `style:rel-width` attribute are a value of type `percent` 18.3.23, `scale` or `scale-min`.

19.510.3 <style:column>

The `style:rel-width` attribute specifies the width of a column.

Column widths are specified as relative widths, that is, a number followed by a "*" (U+002A, ASTERISK) character. The total space available for the entire table is distributed among its columns according to its relative width.

The `style:rel-width` attribute is usable with the following element: `<style:column>` 17.13.

The `style:rel-width` attribute has the data type `relativeLength` 18.3.27.

19.510.4 <style:footnote-sep>

The `style:rel-width` attribute specifies the length of the footnote separator line as a percentage of the body text area.

The `style:rel-width` attribute is usable with the following element: `<style:footnote-sep>` 17.4.

The `style:rel-width` attribute has the data type `percent` 18.3.23.

19.511 style:repeat

The `style:repeat` attribute specifies if an image can be repeated or stretched over an area.

The defined values for the `style:repeat` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `no-repeat`: image should not be repeated.
- `repeat`: image should be repeated.
- `stretch`: image should be stretched over an area.

For a `<style:background-image>` 17.3 element the default value for this attribute is `repeat`.

The `style:repeat` attribute is usable with the following element: `<style:background-image>` 17.3.

The values of the `style:repeat` attribute are `no-repeat`, `repeat` or `stretch`.

19.512 style:rfc-language-tag

The `style:rfc-language-tag` attribute specifies a language identifier according to the rules of [RFC5646], or its successors.

It shall only be used if its value can not be expressed as a valid combination of the `fo:language`, `fo:script` and `fo:country` attributes.

Producers may add support for consumers that don't support the `style:rfc-language-tag` attribute by specifying `fo:language`, `fo:script` and `fo:country` attributes with values that are implementation-dependent.

The `style:rfc-language-tag` attribute is usable with the following elements: `<text:alphabetical-index-source>` 8.8.2 and `<text:bibliography-configuration>` 16.29.6.

The `style:rfc-language-tag` attribute has the data type `language` 18.3.16.

19.513 style:style

The `style:style` attribute specifies the line style of a column separator line.

The defined values for the `style:style` attribute are:

- `none`: no separator line.
- `dashed`: dashed separator line.
- `dot-dashed`: separator line whose repeating pattern is a dot followed by a dash.
- `dotted`: dotted separator line.
- `solid`: solid separator line.

The default value for this attribute is `solid`.

The `style:style` attribute is usable with the following element: `<style:column-sep>` 17.14.

The values of the `style:style` attribute are `none`, `solid`, `dotted`, `dashed` or `dot-dashed`.

19.514 style:style-name

The `style:style-name` attribute specifies the text style to apply to characters specified by a `<style:drop-cap>` element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `style:style-name` attribute is usable with the following element: `<style:drop-cap>` 17.9.

The `style:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.515 style:type

19.515.1 General

The `style:type` attribute specifies a tab stop type.

19.515.2 <text:index-entry-tab-stop>

The `style:type` attribute specifies the type of a tab stop. If the value of this attribute is `left`, the `style:position` attribute shall also be present. Otherwise, this attribute shall be omitted.

The defined values for the `style:type` attribute are:

- `left`: text is left aligned with a tab stop.
- `right`: text is right aligned with a tab stop.

The `style:type` attribute is usable with the following element: `<text:index-entry-tab-stop>` 8.13.6.

The values of the `style:type` attribute are `right` or `left`.

19.515.3 <style:tab-stop>

The `style:type` attribute specifies the type of a tab stop.

The defined values for the `style:type` attribute are:

- `center`: text is centered on a tab stop.
- `char`: character appears at a tab stop position.
- `left`: text is left aligned with a tab stop.
- `right`: text is right aligned with a tab stop.

The `style:type` attribute is usable with the following element: `<style:tab-stop>` 17.8.

The values of the `style:type` attribute are `left`, `center`, `right` or `char`.

For a `<style:tab-stop>` 17.8 element the default value for this attribute is `left`.

19.516 style:vertical-align

The `style:vertical-align` attribute specifies how to vertically align a line that is less than 100% of its height within the columned area. The value of this attribute can be either `top`, `middle`, or `bottom`.

The defined values for the `style:vertical-align` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `bottom`: line is aligned with the bottom of a columned area.
- `middle`: line is aligned with the middle of a columned area.
- `top`: line is aligned with the top of a columned area.

For a `<style:column-sep>` 17.14 element the default value for this attribute is `top`.

The `style:vertical-align` attribute is usable with the following element: `<style:column-sep>` 17.14.

The values of the `style:vertical-align` attribute are `top`, `middle` or `bottom`.

19.517 style:volatile

The `style:volatile` attribute specifies whether unused style in a document are retained or discarded by consumers.

The defined values for the `style:volatile` attribute are:

- `false`: consumers should discard the unused styles.
- `true`: consumers should keep unused styles.

The `style:volatile` attribute is usable with the following elements: `<number:boolean-style>` 16.27.23, `<number:currency-style>` 16.27.7, `<number:date-style>` 16.27.10, `<number:number-style>` 16.27.2, `<number:percentage-style>` 16.27.9, `<number:text-style>` 16.27.25 and `<number:time-style>` 16.27.18.

The `style:volatile` attribute has the data type `boolean` 18.3.3.

19.518 style:width

19.518.1 General

The `style:width` attribute specifies a width.

19.518.2 <style:column-sep>

The `style:width` attribute specifies the width of a column separation.

The `style:width` attribute is usable with the following element: `<style:column-sep>` 17.14.

The `style:width` attribute has the data type `length` 18.3.18.

19.518.3 <style:footnote-sep>

The `style:width` attribute width or thickness of a line.

The `style:width` attribute is usable with the following element: `<style:footnote-sep>` 17.4.

The `style:width` attribute has the data type `length` 18.3.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.519 svg:accent-height

See §20.8.3 of [SVG].

The `svg:accent-height` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:accent-height` attribute has the data type `integer` 18.2.

19.520 svg:alphabetic

See §20.8.3 of [SVG].

The `svg:alphabetic` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:alphabetic` attribute has the data type `integer` 18.2.

19.521 svg:ascent

See §20.8.3 of [SVG].

The `svg:ascent` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:ascent` attribute has the data type `integer` 18.2.

19.522 svg:bbox

See §20.8.3 of [SVG].

The `svg:bbox` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:bbox` attribute has the data type `string` 18.2.

19.523 svg:cap-height

See §20.8.3 of [SVG].

The `svg:cap-height` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:cap-height` attribute has the data type `integer` 18.2.

19.524 svg:cx

19.524.1 <draw:area-circle>

The `svg:cx` attribute defines the x-axis coordinate of the center of a circular image map area.

The `svg:cx` attribute is usable with the following element: `<draw:area-circle>` 10.4.13.4.

The `svg:cx` attribute has the data type `coordinate` 18.3.10.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.524.2 <draw:circle>

See §9.3 of [SVG].

The `svg:cx` attribute is usable with the following element: `<draw:circle>` 10.3.8.
The `svg:cx` attribute has the data type `coordinate` 18.3.10.

19.524.3 <draw:ellipse>

See §9.4 of [SVG].

The `svg:cx` attribute is usable with the following element: `<draw:ellipse>` 10.3.9.
The `svg:cx` attribute has the data type `coordinate` 18.3.10.

19.524.4 <svg:radialGradient>

See §13.3.2 of [SVG].

For a `<svg:radialGradient>` 16.40.3 element the default value for this attribute is `50%`.

The `svg:cx` attribute is usable with the following element: `<svg:radialGradient>` 16.40.3.
The values of the `svg:cx` attribute are a value of type `coordinate` 18.3.10 or a value of type `percent` 18.3.23.

19.525 svg:cy

19.525.1 <draw:area-circle>

The `svg:cy` attribute defines the y-axis coordinate of the center of a circular image map area.

The `svg:cy` attribute is usable with the following element: `<draw:area-circle>` 10.4.13.4.
The `svg:cy` attribute has the data type `coordinate` 18.3.10.

19.525.2 <draw:circle>

See §9.3 of [SVG].

The `svg:cy` attribute is usable with the following element: `<draw:circle>` 10.3.8.
The `svg:cy` attribute has the data type `coordinate` 18.3.10.

19.525.3 <draw:ellipse>

See §9.4 of [SVG].

The `svg:cy` attribute is usable with the following element: `<draw:ellipse>` 10.3.9.
The `svg:cy` attribute has the data type `coordinate` 18.3.10.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.525.4 <svg:radialGradient>

See §13.3.2 of [SVG].

For a `<svg:radialGradient>` 16.40.3 element the default value for this attribute is `50%`.

The `svg:cy` attribute is usable with the following element: `<svg:radialGradient>` 16.40.3.

The values of the `svg:cy` attribute are a value of type `coordinate` 18.3.10 or a value of type `percent` 18.3.23.

19.526 svg:d

See §8 of [SVG].

The `svg:d` attribute is usable with the following elements: `<dr3d:extrude>` 10.5.6, `<dr3d:rotate>` 10.5.7, `<draw:connector>` 10.3.10, `<draw:contour-path>` 10.4.11.3, `<draw:marker>` 16.40.8 and `<draw:path>` 10.3.7.

The `svg:d` attribute has the data type `pathData` 18.3.22.

19.527 svg:descent

See §20.8.3 of [SVG].

The `svg:descent` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:descent` attribute has the data type `integer` 18.2.

19.528 svg:font-family

See §20.8.3 of [SVG].

The `svg:font-family` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:font-family` attribute has the data type `string` 18.2.

19.529 svg:font-size

See §20.8.3 of [SVG].

The `svg:font-size` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:font-size` attribute has the data type `positiveLength` 18.3.26.

19.530 svg:font-stretch

See §20.8.3 of [SVG].

The `svg:font-stretch` attribute is usable with the following element: `<style:font-face>` 16.21.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The values of the svg:font-stretch attribute are normal, ultra-condensed, extra-condensed, condensed, semi-condensed, semi-expanded, expanded, extra-expanded or ultra-expanded.

19.531 svg:font-style

See §20.8.3 of [SVG].

The svg:font-style attribute is usable with the following element: <style:font-face> 16.21.

The values of the svg:font-style attribute are normal, italic or oblique.

19.532 svg:font-variant

See §20.8.3 of [SVG].

The svg:font-variant attribute is usable with the following element: <style:font-face> 16.21.

The values of the svg:font-variant attribute are normal or small-caps.

19.533 svg:font-weight

See §20.8.3 of [SVG].

The svg:font-weight attribute is usable with the following element: <style:font-face> 16.21.

The values of the svg:font-weight attribute are normal, bold, 100, 200, 300, 400, 500, 600, 700, 800 or 900.

19.534 svg:fx

See §13.2.3 of [SVG].

The svg:fx attribute is usable with the following element: <svg:radialGradient> 16.40.3.

The values of the svg:fx attribute are a value of type coordinate 18.3.10 or a value of type percent 18.3.23.

19.535 svg:fy

See §13.2.3 of [SVG].

The svg:fy attribute is usable with the following element: <svg:radialGradient> 16.40.3.

The values of the svg:fy attribute are a value of type coordinate 18.3.10 or a value of type percent 18.3.23.

19.536 svg:gradientTransform

See §13.2.2 and §13.2.3 of [SVG].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `svg:gradientTransform` attribute is usable with the following elements: `<svg:linearGradient>` 16.40.2 and `<svg:radialGradient>` 16.40.3.

The `svg:gradientTransform` attribute has the data type `string` 18.2.

19.537 svg:gradientUnits

See §13.2.2 and §13.2.3 of [SVG].

The default value for this attribute is `objectBoundingBox`.

The `svg:gradientUnits` attribute is usable with the following elements: `<svg:linearGradient>` 16.40.2 and `<svg:radialGradient>` 16.40.3.

The only value of the `svg:gradientUnits` attribute is `objectBoundingBox`.

19.538 svg:hanging

See §20.8.3 of [SVG].

The `svg:hanging` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:hanging` attribute has the data type `integer` 18.2.

19.539 svg:height

19.539.1 <chart:chart>

The `svg:height` attribute defines the height of the entire chart. If it is omitted, the size of the chart is determined by the size of the window in which the chart is displayed.

The `svg:height` attribute is usable with the following element: `<chart:chart>` 11.1.

The `svg:height` attribute has the data type `length` 18.3.18.

19.539.2 <chart:plot-area>

The `svg:height` attribute defines the height of the plot-area.

The `svg:height` attribute is usable with the following element: `<chart:plot-area>` 11.4.

The `svg:height` attribute has the data type `length` 18.3.18.

19.539.3 <dr3d:scene>

See 19.539.8.

The `svg:height` attribute is usable with the following element: `<dr3d:scene>` 10.5.2.

The `svg:height` attribute has the data type `length` 18.3.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.539.4 <draw:area-polygon>

The svg:height attribute defines the height of a polygonal image map area's bounding box.

The svg:height attribute is usable with the following element: <draw:area-polygon> 10.4.13.5.

The svg:height attribute has the data type length 18.3.18.

19.539.5 <draw:area-rectangle>

The svg:height attribute defines the height of a rectangular image map area.

The svg:height attribute is usable with the following element: <draw:area-rectangle> 10.4.13.3.

The svg:height attribute has the data type length 18.3.18.

19.539.6 <draw:contour-polygon>, <draw:contour-path>

The svg:height attribute defines the height of a contour's bounding box.

The svg:height attribute is usable with the following elements: <draw:contour-path> 10.4.11.3 and <draw:contour-polygon> 10.4.11.2.

The svg:height attribute has the data type length 18.3.18.

19.539.7 <draw:fill-image>

The svg:height attribute may be used to specify the height of a linked image. Its value is overridden by the height of the linked image resource.

Note: This attribute can be used to estimate the size of a fill image without loading the image data.

The svg:height attribute is usable with the following element: <draw:fill-image> 16.40.6.

The svg:height attribute has the data type length 18.3.18.

19.539.8 <draw:caption>, <draw:custom-shape>, <draw:circle>, <draw:control>, <draw:ellipse>, <draw:frame>, <draw:rect>, <draw:page-thumbnail>, <draw:path>, <draw:polygon>, <draw:polyline>, <draw:regular-polygon>

See §5.1.2 of [SVG]. For drawing shapes that have a non rectangular shape, the length refers to the drawing shape's bounding box.

If the svg:width and svg:height attributes specify different values for a <draw:circle> element, the radius of the circle is derived from the smaller of the two values, and the circle is centered within the bounding box.

The svg:height attribute is usable with the following elements: <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:page-thumbnail> 10.3.14,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2 and <draw:regular-polygon> 10.3.6.

The svg:height attribute has the data type length 18.3.18.

19.539.9 <office:annotation>

The svg:height attribute specifies the height of the rectangular which displays the annotation. Its meaning is the same as for a <draw:caption> element. See 19.571.10.

The svg:height attribute is usable with the following element: <office:annotation> 14.1.

The svg:height attribute has the data type length 18.3.18.

19.539.10 <presentation:placeholder>

See 19.571.10. Percentage values are relative to the height of the drawing page.

The svg:height attribute is usable with the following element: <presentation:placeholder> 16.42.

The values of the svg:height attribute are a value of type length 18.3.18 or a value of type percent 18.3.23.

19.540 svg:ideographic

See §20.8.3 of [SVG].

The svg:ideographic attribute is usable with the following element: <style:font-face> 16.21.

The svg:ideographic attribute has the data type integer 18.2.

19.541 svg:mathematical

See §20.8.3 of [SVG].

The svg:mathematical attribute is usable with the following element: <style:font-face> 16.21.

The svg:mathematical attribute has the data type integer 18.2.

19.542 svg:name

See §20.8.3 of [SVG].

The svg:name attribute is usable with the following element: <svg:font-face-name> 16.23.

The svg:name attribute has the data type string 18.2.

19.543 svg:offset

See §13.2.4 of [SVG].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `svg:offset` attribute is usable with the following element: `<svg:stop>` 16.40.4.

The values of the `svg:offset` attribute are a value of type `double` 18.2 or a value of type `percent` 18.3.23.

19.544 svg:origin

See §19.2.12 of [SVG].

Note: SVG relies upon the definition of origin in SMIL, see: http://www.w3.org/TR/2001/REC-smil-animation-20010904/#MotionOriginAttribute.

The `svg:origin` attribute is usable with the following element: `<anim:animateMotion>` 15.2.5.

The `svg:origin` attribute has the data type `string` 18.2.

19.545 svg:overline-position

See §20.8.3 of [SVG].

The `svg:overline-position` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:overline-position` attribute has the data type `integer` 18.2.

19.546 svg:overline-thickness

See §20.8.3 of [SVG].

The `svg:overline-thickness` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:overline-thickness` attribute has the data type `integer` 18.2.

19.547 svg:panose-1

See §20.8.3 of [SVG].

The `svg:panose-1` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:panose-1` attribute has the data type `string` 18.2.

19.548 svg:path

See §19.2.12 of [SVG].

The `svg:path` attribute is usable with the following element: `<anim:animateMotion>` 15.2.5.

The `svg:path` attribute has the data type `pathData` 18.3.22.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.549 svg:r

19.549.1 <draw:area-circle>

The svg:r attribute defines the radius of a circular image map area.

The svg:r attribute is usable with the following element: <draw:area-circle> 10.4.13.4.

The svg:r attribute has the data type length 18.3.18.

19.549.2 <draw:circle>

The svg:r attribute defines the radius of a circle. The use of this attribute is defined by §9.3 of [SVG].

Note: If a <draw:circle> element does not have a value for the svg:r attribute, then its svg:x, svg:y, svg:height, and svg:width attributes can be used to define the geometry a circle.

The svg:r attribute is usable with the following element: <draw:circle> 10.3.8.

The svg:r attribute has the data type length 18.3.18.

19.549.3 <svg:radialGradient>

See §13.2.3 of [SVG].

For a <svg:radialGradient> 16.40.3 element the default value for this attribute is 50%.

The svg:r attribute is usable with the following element: <svg:radialGradient> 16.40.3.

The values of the svg:r attribute are a value of type coordinate 18.3.10 or a value of type percent 18.3.23.

19.550 svg:rx

See §9.4 of[SVG].

The svg:rx and svg:ry attributes can be used to round off the corners of a rectangle. The svg:rx attribute specifies the x-axis radius of the ellipse used to round off the corners of a rectangle. The svg:ry attribute specifies the y-axis radius of that ellipse. If only the svg:rx attribute is present then its value will be be used for svg:ry. If only a svg:ry attribute is present then its value will be used for svg:rx.

For use of this attribute with <draw:rect> see §9.2 of [SVG].

For use of this attribute with <draw:ellipse> see §9.4 of [SVG].

The svg:rx attribute is usable with the following elements: <draw:ellipse> 10.3.9 and <draw:rect> 10.3.2.

The svg:rx attribute has the data type nonNegativeLength 18.3.20.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.551 svg:ry

See §9.4 of [SVG].

The `svg:rx` and `svg:ry` attributes can be used to round off the corners of a rectangle. The `svg:rx` attribute specifies the x-axis radius of the ellipse used to round off the corners of a rectangle. The `svg:ry` attribute specifies the y-axis radius of that ellipse. If only the `svg:rx` attribute is present then its value will be be used for `svg:ry`. If only a `svg:ry` attribute is present then its value will be used for `svg:rx`.

The `svg:ry` attribute is usable with the following elements: `<draw:ellipse>` 10.3.9 and `<draw:rect>` 10.3.2.

The `svg:ry` attribute has the data type `nonNegativeLength` 18.3.20.

19.552 svg:slope

See §20.8.3 of [SVG].

The `svg:slope` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:slope` attribute has the data type `integer` 18.2.

19.553 svg:spreadMethod

See §13.2.2 and §13.2.3 of [SVG].

The default value for this attribute is `pad`.

The `svg:spreadMethod` attribute is usable with the following elements: `<svg:linearGradient>` 16.40.2 and `<svg:radialGradient>` 16.40.3.

The values of the `svg:spreadMethod` attribute are `pad`, `reflect` or `repeat`.

19.554 svg:stemh

See §20.8.3 of [SVG].

The `svg:stemh` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:stemh` attribute has the data type `integer` 18.2.

19.555 svg:stemv

See §20.8.3 of [SVG].

The `svg:stemv` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:stemv` attribute has the data type `integer` 18.2.

19.556 svg:stop-color

See §13.2.4 of [SVG].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The svg:stop-color attribute is usable with the following element: <svg:stop> 16.40.4.

The svg:stop-color attribute has the data type color 18.3.9.

19.557 svg:stop-opacity

See §13.2.4 of [SVG].

The svg:stop-opacity attribute is usable with the following element: <svg:stop> 16.40.4.

The svg:stop-opacity attribute has the data type double 18.2.

19.558 svg:strikethrough-position

See §20.8.3 of [SVG].

The svg:strikethrough-position attribute is usable with the following element: <style:font-face> 16.21.

The svg:strikethrough-position attribute has the data type integer 18.2.

19.559 svg:strikethrough-thickness

See §20.8.3 of [SVG].

The svg:strikethrough-thickness attribute is usable with the following element: <style:font-face> 16.21.

The svg:strikethrough-thickness attribute has the data type integer 18.2.

19.560 svg:string

See §20.8.3 of [SVG].

The svg:string attribute is usable with the following element: <svg:font-face-format> 16.26.

The svg:string attribute has the data type string 18.2.

19.561 svg:type

See §19.2.14 of [SVG].

The svg:type attribute is usable with the following element: <anim:animateTransform> 15.2.3.

The values of the svg:type attribute are translate, scale, rotate, skewX or skewY.

19.562 svg:underline-position

See §20.8.3 of [SVG].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `svg:underline-position` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:underline-position` attribute has the data type `integer` 18.2.

19.563 svg:underline-thickness

See §20.8.3 of [SVG].

The `svg:underline-thickness` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:underline-thickness` attribute has the data type `integer` 18.2.

19.564 svg:unicode-range

See §20.8.3 of [SVG].

The `svg:unicode-range` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:unicode-range` attribute has the data type `string` 18.2.

19.565 svg:units-per-em

See §20.8.3 of [SVG].

The `svg:units-per-em` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:units-per-em` attribute has the data type `integer` 18.2.

19.566 svg:v-alphabetic

See §20.8.3 of [SVG].

The `svg:v-alphabetic` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:v-alphabetic` attribute has the data type `integer` 18.2.

19.567 svg:v-hanging

See §20.8.3 of [SVG].

The `svg:v-hanging` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:v-hanging` attribute has the data type `integer` 18.2.

19.568 svg:v-ideographic

See §20.8.3 of [SVG].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `svg:v-ideographic` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:v-ideographic` attribute has the data type `integer` 18.2.

19.569 svg:v-mathematical

See §20.8.3 of [SVG].

The `svg:v-mathematical` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:v-mathematical` attribute has the data type `integer` 18.2.

19.570 svg:viewBox

The `svg:viewBox` attribute establishes a user coordinate system inside the coordinate system of the shape specified by the position and size attributes. This user coordinate system is used by the `draw:points` and `svg:d` attributes, as well as by the attributes of `<draw:enhanced-geometry>` element and its child elements which specify-coordinates.

The syntax for using this attribute is the same as the [SVG] syntax. The value of the attribute are four numbers separated by white spaces, which define the left, top, right, and bottom dimensions of the user coordinate system.

The `svg:viewBox` attribute is usable with the following elements: `<dr3d:extrude>` 10.5.6, `<dr3d:rotate>` 10.5.7, `<draw:area-polygon>` 10.4.13.5, `<draw:connector>` 10.3.10, `<draw:contour-path>` 10.4.11.3, `<draw:contour-polygon>` 10.4.11.2, `<draw:enhanced-geometry>` 10.6.2, `<draw:marker>` 16.40.8, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5 and `<draw:polyline>` 10.3.4.

The values of the `svg:viewBox` attribute are four white space separated values of type `integer` 18.2.

19.571 svg:width

19.571.1 <chart:chart>

The `svg:width` attribute defines the width of a chart. If it is omitted, the size of a chart is determined by the size of the window in which the chart is displayed.

The `svg:width` attribute is usable with the following element: `<chart:chart>` 11.1.

The `svg:width` attribute has the data type `length` 18.3.18.

19.571.2 <chart:floor>

The `svg:width` attribute defines the thickness of a floor.

The `svg:width` attribute is usable with the following element: `<chart:floor>` 11.7.

The `svg:width` attribute has the data type `length` 18.3.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.571.3 <chart:plot-area>

The svg:width attribute defines the width of a plot-area.

The svg:width attribute is usable with the following element: <chart:plot-area> 11.4.

The svg:width attribute has the data type length 18.3.18.

19.571.4 <chart:wall>

The svg:width attribute specifies the thickness of a wall for three-dimensional charts.

The svg:width attribute is usable with the following element: <chart:wall> 11.6.

The svg:width attribute has the data type length 18.3.18.

19.571.5 <dr3d:scene>

See 19.571.10.

The svg:width attribute is usable with the following element: <dr3d:scene> 10.5.2.

The svg:width attribute has the data type length 18.3.18.

19.571.6 <draw:area-polygon>

The svg:width attribute defines the width of a polygonal image map area's bounding box.

The svg:width attribute is usable with the following element: <draw:area-polygon> 10.4.13.5.

The svg:width attribute has the data type length 18.3.18.

19.571.7 <draw:area-rectangle>

The svg:width attribute defines the width of a rectangular image map area.

The svg:width attribute is usable with the following element: <draw:area-rectangle> 10.4.13.3.

The svg:width attribute has the data type length 18.3.18.

19.571.8 <draw:contour-polygon>, <draw:contour-path>

The svg:width attribute defines the width of a contour's bounding box.

The svg:width attribute is usable with the following elements: <draw:contour-path> 10.4.11.3 and <draw:contour-polygon> 10.4.11.2.

The svg:width attribute has the data type length 18.3.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.571.9 <draw:fill-image>

The `svg:width` attribute may be used to specify the width of a linked image. Its value is overridden by the width of the linked image resource.

Note: This attribute can be used to estimate the size of a fill image without loading the image data.

The `svg:width` attribute is usable with the following element: `<draw:fill-image>` 16.40.6.

The `svg:width` attribute has the data type `length` 18.3.18.

19.571.10 <draw:caption>, <draw:custom-shape>, <draw:circle>, <draw:control>, <draw:ellipse>, <draw:frame>, <draw:rect>, <draw:page-thumbnail>, <draw:path>, <draw:polygon>, <draw:polyline>, <draw:regular-polygon>

See §5.1.2 of [SVG]. For drawing shapes that have a non rectangular shape, the length refers to the drawing shape's bounding box.

If the `svg:width` and `svg:height` attributes specify different values for a `<draw:circle>` element, the radius of the circle is derived from the smaller of the two values, and the circle is centered within the bounding box.

The `svg:width` attribute is usable with the following elements: `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2 and `<draw:regular-polygon>` 10.3.6.

The `svg:width` attribute has the data type `length` 18.3.18.

19.571.11 <office:annotation>

The `svg:width` attribute specifies the width of the rectangular which displays the annotation. Its meaning is the same as for a `<draw:caption>` element. See 19.571.10.

The `svg:width` attribute is usable with the following element: `<office:annotation>` 14.1.

The `svg:width` attribute has the data type `length` 18.3.18.

19.571.12 <presentation:placeholder>

See 19.571.10. Percentage values are relative to the width of the drawing page.

The `svg:width` attribute is usable with the following element: `<presentation:placeholder>` 16.42.

The values of the `svg:width` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

19.572 svg:widths

See §20.8.3 of [SVG].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The svg:widths attribute is usable with the following element: <style:font-face> 16.21.

The svg:widths attribute has the data type string 18.2.

19.573 svg:x

19.573.1 <chart:data-label>, <chart:equation>, <chart:footer>, <chart:legend>, <chart:plot-area>, <chart:subtitle>, <chart:title>

The svg:x attribute specifies the horizontal distance of the upper left corner of the given element from the upper left corner of the <chart:chart> element.

The svg:x attribute is usable with the following elements: <chart:data-label> 11.14, <chart:equation> 11.18, <chart:footer> 11.2.3, <chart:legend> 11.3, <chart:plot-area> 11.4, <chart:subtitle> 11.2.2 and <chart:title> 11.2.1.

The svg:x attribute has the data type coordinate 18.3.10.

19.573.2 <draw:area-polygon>

The svg:x attribute defines the x-axis coordinate of a polygonal image map area's bounding box.

The svg:x attribute is usable with the following element: <draw:area-polygon> 10.4.13.5.

The svg:x attribute has the data type coordinate 18.3.10.

19.573.3 <draw:area-rectangle>

The svg:x attribute defines the x-axis coordinate of a rectangular image map area.

The svg:x attribute is usable with the following element: <draw:area-rectangle> 10.4.13.3.

The svg:x attribute has the data type coordinate 18.3.10.

19.573.4 <dr3d:scene>

See 19.573.5.

The svg:x attribute is usable with the following element: <dr3d:scene> 10.5.2.

The svg:x attribute has the data type coordinate 18.3.10.

19.573.5 <draw:caption>, <draw:custom-shape>, <draw:circle>, <draw:control>, <draw:ellipse>, <draw:frame>, <draw:rect>, <draw:page-thumbnail>, <draw:path>, <draw:polygon>, <draw:polyline>, <draw:regular-polygon>

See §5.1.2 of [SVG]. For drawing shapes that have a non rectangular shape, the coordinate refers to the drawing shape's bounding box.

The svg:x attribute is usable with the following elements: <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2 and <draw:regular-polygon> 10.3.6.

The svg:x attribute has the data type coordinate 18.3.10.

19.573.6 <draw:glue-point>

The svg:x attribute specifies the horizontal position of the glue point. The coordinate is either a percentage value relative to the drawing shape's center in horizontal direction, or, if the draw:align attribute is also specified, an absolute distance value relative to the edge specified by the draw:align attribute.

The svg:x attribute is usable with the following element: <draw:glue-point> 10.3.16.

The values of the svg:x attribute are a value of type distance 18.3.15 or a value of type percent 18.3.23.

19.573.7 <office:annotation>

The svg:x attribute specifies the horizontal position of an annotation. Its meaning is the same as for a <draw:caption> element. See 19.573.5.

The svg:x attribute is usable with the following element: <office:annotation> 14.1.

The svg:x attribute has the data type coordinate 18.3.10.

19.573.8 <presentation:placeholder>

See 19.573.5. Percentage values are relative to the height of the drawing page.

The svg:x attribute is usable with the following element: <presentation:placeholder> 16.42.

The values of the svg:x attribute are a value of type coordinate 18.3.10 or a value of type percent 18.3.23.

19.574 svg:x1

19.574.1 <draw:connector>, <draw:line> and <draw:measure>

See §9.5 of [SVG].

The svg:x1 attribute may be omitted on <draw:connector> elements when the connector is connected to a shape by a draw:start-shape attribute. The start position then is the position of the glue point to which the connector is connected.

The svg:x1 attribute is usable with the following elements: <draw:connector> 10.3.10, <draw:line> 10.3.3 and <draw:measure> 10.3.12.

The svg:x1 attribute has the data type coordinate 18.3.10.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.574.2 <svg:linearGradient>

See §13.3.2 of [SVG].

For a `<svg:linearGradient>` 16.40.2 element the default value for this attribute is `0%`.

The `svg:x1` attribute is usable with the following element: `<svg:linearGradient>` 16.40.2.

The values of the `svg:x1` attribute are a value of type `coordinate` 18.3.10 or a value of type `percent` 18.3.23.

19.575 svg:x2

19.575.1 <draw:connector>, <draw:line> and <draw:measure>

See §9.5 of [SVG].

The `svg:x2` attribute may be omitted on `<draw:connector>` elements when the connector is connected to a shape by a `draw:end-shape` attribute. The end position then is the position of the glue point to which the connector is connected.

The `svg:x2` attribute is usable with the following elements: `<draw:connector>` 10.3.10, `<draw:line>` 10.3.3 and `<draw:measure>` 10.3.12.

The `svg:x2` attribute has the data type `coordinate` 18.3.10.

19.575.2 <svg:linearGradient>

See §13.3.2 of [SVG].

For a `<svg:linearGradient>` 16.40.2 element the default value for this attribute is `100%`.

The `svg:x2` attribute is usable with the following element: `<svg:linearGradient>` 16.40.2.

The values of the `svg:x2` attribute are a value of type `coordinate` 18.3.10 or a value of type `percent` 18.3.23.

19.576 svg:x-height

See §20.8.3 of [SVG].

The `svg:x-height` attribute is usable with the following element: `<style:font-face>` 16.21.

The `svg:x-height` attribute has the data type `integer` 18.2.

19.577 svg:y

19.577.1 <chart:data-label>, <chart:equation>, <chart:footer>, <chart:legend>, <chart:plot-area>, <chart:subtitle>, <chart:title>

The `svg:y` attribute specifies the vertical distance of the upper left corner of the given element from the upper left corner of the `<chart:chart>` element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The svg:y attribute is usable with the following elements: <chart:data-label> 11.14, <chart:equation> 11.18, <chart:footer> 11.2.3, <chart:legend> 11.3, <chart:plot-area> 11.4, <chart:subtitle> 11.2.2 and <chart:title> 11.2.1.

The svg:y attribute has the data type coordinate 18.3.10.

19.577.2 <draw:area-polygon>

The svg:y attribute defines the y-axis coordinate of a polygonal image map area's bounding box.

The svg:y attribute is usable with the following element: <draw:area-polygon> 10.4.13.5.

The svg:y attribute has the data type coordinate 18.3.10.

19.577.3 <draw:area-rectangle>

The svg:y attributes defines the y-axis coordinate of a rectangular image map area.

The svg:y attribute is usable with the following element: <draw:area-rectangle> 10.4.13.3.

The svg:y attribute has the data type coordinate 18.3.10.

19.577.4 <dr3d:scene>

See 19.577.5.

The svg:y attribute is usable with the following element: <dr3d:scene> 10.5.2.

The svg:y attribute has the data type coordinate 18.3.10.

19.577.5 <draw:caption>, <draw:custom-shape>, <draw:circle>, <draw:control>, <draw:ellipse>, <draw:frame>, <draw:g>, <draw:rect>, <draw:page-thumbnail>, <draw:path>, <draw:polygon>, <draw:polyline>, <draw:regular-polygon>

See §5.1.2 of [SVG]. For drawing shapes that have a non rectangular shape, the coordinate refers to the drawing shape's bounding box.

The svg:y attribute is usable with the following elements: <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2 and <draw:regular-polygon> 10.3.6.

The svg:y attribute has the data type coordinate 18.3.10.

19.577.6 <draw:glue-point>

The svg:y attribute specifies the vertical position of the glue point. The coordinate is either a percentage value relative to the drawing shape's center in vertical direction, or, if the draw:align attribute is also specified, an absolute distance value relative to the edge specified by the draw:align attribute.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The svg:y attribute is usable with the following element: <draw:glue-point> 10.3.16.

The values of the svg:y attribute are a value of type distance 18.3.15 or a value of type percent 18.3.23.

19.577.7 <office:annotation>

The svg:y attribute specifies the position where the annotation is displayed. Its meaning is the same as for a <draw:caption> element. See 19.573.5.

The svg:y attribute is usable with the following element: <office:annotation> 14.1.

The svg:y attribute has the data type coordinate 18.3.10.

19.577.8 <presentation:placeholder>

See 19.577.5. Percentage values are relative to the height of the drawing page.

The svg:y attribute is usable with the following element: <presentation:placeholder> 16.42.

The values of the svg:y attribute are a value of type coordinate 18.3.10 or a value of type percent 18.3.23.

19.578 svg:y1

19.578.1 <draw:connector>, <draw:line> and <draw:measure>

See §9.5 of [SVG].

The svg:y1 attribute may be omitted on <draw:connector> elements when the connector is connected to a shape by a draw:start-shape attribute. The start position then is the position of the glue point to which the connector is connected.

The svg:y1 attribute is usable with the following elements: <draw:connector> 10.3.10, <draw:line> 10.3.3 and <draw:measure> 10.3.12.

The svg:y1 attribute has the data type coordinate 18.3.10.

19.578.2 <svg:linearGradient>

See §13.3.2 of [SVG].

For a <svg:linearGradient> 16.40.2 element the default value for this attribute is 0%.

The svg:y1 attribute is usable with the following element: <svg:linearGradient> 16.40.2.

The values of the svg:y1 attribute are a value of type coordinate 18.3.10 or a value of type percent 18.3.23.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.579 svg:y2

19.579.1 <draw:connector>, <draw:line> and <draw:measure>

See §9.5 of [SVG].

The `svg:y2` attribute may be omitted on `<draw:connector>` elements when the connector is connected to a shape by a `draw:end-shape` attribute. The end position then is the position of the glue point to which the connector is connected.

The `svg:y2` attribute is usable with the following elements: `<draw:connector>` 10.3.10, `<draw:line>` 10.3.3 and `<draw:measure>` 10.3.12.

The `svg:y2` attribute has the data type `coordinate` 18.3.10.

19.579.2 <svg:linearGradient>

See §13.3.2 of [SVG].

For a `<svg:linearGradient>` 16.40.2 element the default value for this attribute is `100%`.

The `svg:y2` attribute is usable with the following element: `<svg:linearGradient>` 16.40.2.

The values of the `svg:y2` attribute are a value of type `coordinate` 18.3.10 or a value of type `percent` 18.3.23.

19.580 table:acceptance-state

The `table:acceptance-state` attribute specifies whether a tracked change has been accepted or rejected already, or whether an acceptance or rejection is still pending.

The defined values for the `table:acceptance-state` attribute are:

- `accepted`: a tracked change has been accepted.
- `pending`: a tracked change is pending approval or rejection.
- `rejected`: a tracked change has been rejected.

The default value for this attribute is `pending`.

The `table:acceptance-state` attribute is usable with the following elements: `<table:cell-content-change>` 9.9.17, `<table:deletion>` 9.9.9, `<table:insertion>` 9.9.3 and `<table:movement>` 9.9.13.

The values of the `table:acceptance-state` attribute are `accepted`, `rejected` or `pending`.

19.581 table:algorithm

The `table:algorithm` attribute specifies the algorithm used to compare sort keys. To avoid name conflicts between different consumers, the name of the algorithm should begin with a namespace prefix, followed by a ":" (U+003A, COLON) separator.

The `table:algorithm` attribute is usable with the following element: `<table:sort>` 9.4.19.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:algorithm` attribute has the data type `string` 18.2.

19.582 table:add-empty-lines

The `table:add-empty-lines` attribute specifies whether an empty row is inserted in the data pilot table after the data (including the subtotals) for each member of the field.

The defined values for the `table:add-empty-lines` attribute are:

- `false`: an empty line should not be inserted after the data for a member, including any subtotal of that member.
- `true`: an empty line should not be inserted after the data for a member, including any subtotal of that member.

The `table:add-empty-lines` attribute is usable with the following element: `<table:data-pilot-layout-info>` 9.6.15.

The `table:add-empty-lines` attribute has the data type `boolean` 18.3.3.

19.583 table:allow-empty-cell

The `table:allow-empty-cell` attribute specifies whether a cell can be empty.

The defined values for the `table:allow-empty-cell` attribute are:

- `false`: cell cannot be empty.
- `true`: cell can be empty.

The default value for this attribute is `true`.

The `table:allow-empty-cell` attribute is usable with the following element: `<table:content-validation>` 9.4.5.

The `table:allow-empty-cell` attribute has the data type `boolean` 18.3.3.

19.584 table:application-data

The `table:application-data` attribute specifies extra information about a data pilot table, which can be used by the consumer. This data shall not influence the behavior of the data pilot.

The `table:application-data` attribute is usable with the following element: `<table:data-pilot-table>` 9.6.3.

The `table:application-data` attribute has the data type `string` 18.2.

19.585 table:automatic-find-labels

The `table:automatic-find-labels` attribute specifies whether a consumer should attempt to find labels of rows and columns.

The defined values for the `table:automatic-find-labels` attribute are:

- `false`: consumers should not attempt to find labels of rows and columns.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: consumers should attempt find labels of rows and columns.

Note: The `table:automatic-find-labels` attribute enables the use of the automatic lookup of labels capability defined by OpenFormula. OpenFormula, 5.10.2. (*update*)

The default value for this attribute is `true`.

The `table:automatic-find-labels` attribute is usable with the following element: `<table:calculation-settings>` 9.4.1.

The `table:automatic-find-labels` attribute has the data type `boolean` 18.3.3.

19.586 table:base-cell-address

The `table:base-cell-address` attribute specifies the address of the base cell for relative addresses in formulas that occur within a condition. This attribute is only necessary when the condition contains a formula. The value of this attribute shall be an absolute cell address that contains a table name. The dollar signs “$” (U+0024, DOLLAR SIGN) that indicate an absolute address may be omitted.

The `table:base-cell-address` attribute is usable with the following elements: `<table:content-validation>` 9.4.5, `<table:named-expression>` 9.4.13 and `<table:named-range>` 9.4.12.

The `table:base-cell-address` attribute has the data type `cellAddress` 18.3.4.

19.587 table:bind-styles-to-content

The `table:bind-styles-to-content` attribute specifies whether cells retain their style after a subtotal calculation. This attribute is only evaluated if a `<table:sort-groups>` element is present.

The defined values for the `table:bind-styles-to-content` attribute are:

- `false`: cells need not retain their style after a subtotal calculation.
- `true`: cells should retain their style after a subtotal calculation.

The default value for this attribute is `true`.

The `table:bind-styles-to-content` attribute is usable with the following elements: `<table:sort>` 9.4.19 and `<table:subtotal-rules>` 9.4.21.

The `table:bind-styles-to-content` attribute has the data type `boolean` 18.3.3.

19.588 table:border-color

The `table:border-color` attribute specifies the color of a border that is displayed around a scenario that belongs to a scenario table.

The `table:border-color` attribute is usable with the following element: `<table:scenario>` 9.2.7.

The `table:border-color` attribute has the data type `color` 18.3.9.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.589 table:buttons

The `table:buttons` attribute specifies the cells in a data pilot table that should be displayed as buttons to trigger interactive operations on the table like changing the order of columns. Its value is a list of white space separated cell-addresses. The value of this attribute shall be an absolute cell address that contains a table name. The dollar signs "$" (U+0024, DOLLAR SIGN) that indicate an absolute address may be omitted.

The `table:buttons` attribute is usable with the following element: `<table:data-pilot-table>` 9.6.3.

The `table:buttons` attribute has the data type `cellRangeAddressList` 18.3.6.

19.590 table:case-sensitive

The `table:case-sensitive` attribute specifies whether to distinguish between upper and lower case when comparing, sorting or filtering content.

That attribute is only evaluated if the operations take place on strings.

The defined values for the `table:case-sensitive` attribute are:

- `false`: upper and lower case are not distinguished when comparing, sorting or filtering content.
- `true`: upper and lower case are distinguished when comparing, sorting or filtering content.

For a `<table:calculation-settings>` 9.4.1 element the default value for this attribute is `true`.

For `<table:filter-condition>` 9.5.5, `<table:sort>` 9.4.19 and `<table:subtotal-rules>` 9.4.21 elements the default value for this attribute is `false`.

The `table:case-sensitive` attribute is usable with the following elements: `<table:calculation-settings>` 9.4.1, `<table:filter-condition>` 9.5.5, `<table:sort>` 9.4.19 and `<table:subtotal-rules>` 9.4.21.

The `table:case-sensitive` attribute has the data type `boolean` 18.3.3.

19.591 table:cell-address

The `table:cell-address` attribute specifies the original address of a cell used in a calculation.

The `table:cell-address` attribute is usable with the following element: `<table:change-track-table-cell>` 9.9.16.

The `table:cell-address` attribute has the data type `cellAddress` 18.3.4.

19.592 table:cell-range

The `table:cell-range` attribute specifies a list of ranges of cells.

The `table:cell-range` attribute is usable with the following elements: `<chart:footer>` 11.2.3, `<chart:subtitle>` 11.2.2 and `<chart:title>` 11.2.1.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The table:cell-range attribute has the data type cellRangeAddressList 18.3.6.

19.593 table:cell-range-address

19.593.1 General

The table:cell-range-address attribute specifies specifies a range of cells or a list of ranges of cells.

19.593.2 <chart:categories>

The table:cell-range-address attribute specifies the region from which the category labels are taken. If this attribute or the <chart:categories> element is omitted the chart:data-source-has-labels attribute of the <chart:plot-area> element should be evaluated.

The table:cell-range-address attribute is usable with the following element: <chart:categories> 11.9.

The table:cell-range-address attribute has the data type cellRangeAddressList 18.3.6.

19.593.3 <chart:domain> - bubble

The table:cell-range-address attribute specifies the x and y-coordinate values for bubble charts when the chart:class attribute of its parent <chart:series> element has the value chart:bubble.

The table:cell-range-address attribute is usable with the following element: <chart:domain> 11.12.

The table:cell-range-address attribute has the data type cellRangeAddressList 18.3.6.

19.593.4 <chart:domain>- scatter

The table:cell-range-address attribute specifies the x-coordinate values for scatter charts when the chart:class attribute of its parent <chart:series> element has the value chart:scatter.

The table:cell-range-address attribute is usable with the following element: <chart:domain> 11.12.

The table:cell-range-address attribute has the data type cellRangeAddressList 18.3.6.

19.593.5 <chart:domain> - surface

The table:cell-range-address attribute of the first <chart:domain> element specifies the y-coordinate values and the table:cell-range-address attribute of the second <chart:domain> element specifies the x-coordinate values for surface charts when the chart:class attribute of its parent <chart:series> element has the value chart:surface

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

and the chart:values-cell-range-address attribute of this <chart:series> element specifies a range with more than one row and more than one column.

The table:cell-range-address attribute is usable with the following element: <chart:domain> 11.12.

The table:cell-range-address attribute has the data type cellRangeAddressList 18.3.6.

19.593.6 <chart:plot-area> (deprecated)

The table:cell-range-address attribute specifies the ranges of data for a chart.

The table:cell-range-address attribute at the <chart:plot-area> element has no effect in case the data is assigned to the <chart:series> elements directly by chart:values-cell-range-address attributes.

The use of the table:cell-range-address attribute is deprecated in favor of the chart:values-cell-range-address attributes of <chart:series> elements.

The table:cell-range-address attribute is usable with the following element: <chart:plot-area> 11.4.

The table:cell-range-address attribute has the data type cellRangeAddressList 18.3.6.

19.593.7 <table:highlighted-range>

The table:cell-range-address attribute specifies the address of a range that is highlighted.

The table:cell-range-address attribute is usable with the following element: <table:highlighted-range> 9.3.4.

The table:cell-range-address attribute has the data type cellRangeAddress 18.3.5.

19.593.8 <table:named-range>

The table:cell-range-address attribute specifies the address of a named range. The address can be either absolute or relative. If the cell range address is relative, the parent <table:named-range> element shall have a table:base-cell-address attribute with a value. A relative cell address defines an offset which shall be interpreted relative to the cell where the named range is used. The offset is the same as the offsets between the table cell addressed by the relative cell range address and the table cell specified by the table:base-cell-address attribute.

The table:cell-range-address attribute is usable with the following element: <table:named-range> 9.4.12.

The table:cell-range-address attribute has the data type cellRangeAddress 18.3.5.

19.593.9 <table:source-cell-range>

The table:cell-range-address attribute specifies the cell range containing the source data. The value of this attribute shall be an absolute cell address that contains a table name. The dollar signs “$” (U+0024, DOLLAR SIGN) that indicate an absolute address may be omitted.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:cell-range-address` attribute is usable with the following element: `<table:source-cell-range>` 9.6.5.

The `table:cell-range-address` attribute has the data type `cellRangeAddress` 18.3.5.

19.594 table:column

The `table:column` attribute specifies the column number of a cell.

The `table:column` attribute is usable with the following elements: `<table:cell-address>` 9.9.18, `<table:source-range-address>` 9.9.14 and `<table:target-range-address>` 9.9.15.

The `table:column` attribute has the data type `integer` 18.2.

19.595 table:comment

The `table:comment` attribute specifies a comment about a scenario.

The `table:comment` attribute is usable with the following element: `<table:scenario>` 9.2.7.

The `table:comment` attribute has the data type `string` 18.2.

19.596 table:condition

The `table:condition` attribute specifies a condition that applies to the value of a table cell that references a `<table:content-validation>` element having the table:condition attribute. When evaluation of the condition results in "false", any action taken is determine by the other attributes and child elements of the `<table:content-validation>` element.

Note: Possible actions include presentation of a message, triggering an event, and performance of a script, with or without invalidating the value. The `table:allow-empty-cell` attribute value influences whether the `table:condition` is applicable.

The value of this attribute should be a namespace prefix, followed by a ":" (U+003A, COLON), followed by Boolean expression. If the namespace prefix is missing it defaults to the "urn:oasis:names:tc:opendocument:xmlns:of:1.2" namespace. The XML namespace that applies to the `table:condition` attribute specifies the syntax and semantics of the *`expression`* occurrences in the table:condition syntax.

Note: The value of the `<table:content-validation>` `table:base-cell-address` can influence how references are resolved in an *expression* anywhere within the defined conditions.

An OpenDocument Consumer when hosting a formula evaluator make available the host-dependent properties defined by table 12 in 19.644.

The defined conditions are:

- `cell-content-text-length()` *`op value`*, where *`op`* is one of the relational operators ""<",">", "<=", ">=", "=" or "!=": true if the length of the cell's text compared to the value specified in the condition by *`value`* using the relational operator *`op`* evaluates to true.
- `cell-content-text-length-is-between(value1, value2)`: true if the length of the cell's text is between value1 and value2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `cell-content-text-length-is-not-between(value1, value2)`: true if the length of the cell's text is not between *value1* and *value2*.
- `cell-content-is-in-list(list)`, where *list* is one or more string entries, separated by ";" (U+003B, SEMICOLON), or an *expression*: true if the cell's content is in *list*.
- `cell-content-is-decimal-number() and condition`, where *condition* is one of the value conditions below: true if the cell has a numeric value and *condition* is true.
- `cell-content-is-whole-number() and condition`, where *condition* is one of the value conditions below: true if the cell's cell has a whole value and *condition* is true.
- `cell-content-is-date() and condition`, where *condition* is one of the value conditions below: true if the cell has a date value and *condition* is true.
- `cell-content-is-time() and condition`, where *condition* is one of the value conditions below: true if the cell has a time value and *condition* is true.
- `is-true-formula(expression)`: true if evaluation of the *expression* yields a value that converts to logical type value true in the semantics for the *expression*; false otherwise.

The defined value conditions are:

- `cell-content() op value`, where *op* is one of the relational operators "<", ">", "<=", ">=", "=" or "!=": true if the cell's value compared to the value specified in the condition by *value* using the relational operator *op* evaluates to true.
- `cell-content-is-between(value1, value2)`: true if the cell's value is between *value1* and *value2*.
- `cell-content-is-not-between(value1, value2)`: true if the cell's value is not between *value1* and *value2*.
- `is-true-formula(expression)`: true if evaluation of the *expression* yields a value that converts to logical type value true in the semantics for the *expression*; false otherwise.

Within the conditions:

- *value*, *value1* and *value2* are a *numberValue*, a *string* or an *expression*.
- *numberValue* is a whole or decimal number in the lexical form of the [xmlschema-2] decimal datatype.
- *string* expresses a value of the [xmlschema-2] string datatype by surrounding the sequence of string characters in quotation marks (U+0022, QUOTATION MARK). A quotation mark within the string itself is expressed with two consecutive quotation marks.
- *expression* is a lexical form that is neither numberValue nor string and that is a well-formed expression determined by the namespace applicable to the table:condition value.

The `table:condition` attribute is usable with the following element: `<table:content-validation>` 9.4.5.

The `table:condition` attribute has the data type `string` 18.2.

19.597 table:condition-source

The `table:condition-source` attribute specifies whether the condition is contained in a filter or encoded in a cell range.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the `table:condition-source` attribute are:

- `cell-range`: condition encoded into the cell range specified by a `table:condition-source-range-address` attribute.
- `self`: condition specified by `<table:filter>` element's child elements.

The default value for this attribute is `self`.

The `table:condition-source` attribute is usable with the following element: `<table:filter>` 9.5.2.

The values of the `table:condition-source` attribute are `self` or `cell-range`.

19.598 table:condition-source-range-address

The `table:condition-source-range-address` attribute specifies a cell range that contains encoded conditions. The first row of the cell range shall contain the labels of the columns whose content should be filtered. The following rows contain conditions that have to evaluate to true for the cells contained in the columns. The conditions in each row are connected by an “and” operation, while the rows are connected by an “or” operation. This means that a row is of the source table is displayed if there is at least one row in the condition range where all conditions evaluate to true if they are applied to the columns specified in the first row of the condition range.

The `table:condition-source-range-address` attribute is usable with the following element: `<table:filter>` 9.5.2.

The `table:condition-source-range-address` attribute has the data type `cellRangeAddress` 18.3.5.

19.599 table:contains-error

The `table:contains-error` attribute specifies whether a cell range contained an error at the point of evaluation.

The defined values for the `table:contains-error` attribute are:

- `false`: cell range contains no error at point of evaluation.
- `true`: cell range contains an error at point of evaluation.

The default value for this attribute is `false`.

The `table:contains-error` attribute is usable with the following element: `<table:highlighted-range>` 9.3.4.

The `table:contains-error` attribute has the data type `boolean` 18.3.3.

19.600 table:contains-header

The `table:contains-header` attribute specifies whether the content of the database range's first row or column defines labels which may be used to reference a whole row or column.

The defined values for the `table:contains-header` attribute are:

- `false`: the first row or column of the database range does not define labels.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: the first row or column of the database range defines labels.

The default value for this attribute is `true`.

The `table:contains-header` attribute is usable with the following element: `<table:database-range>` 9.4.15.

The `table:contains-header` attribute has the data type `boolean` 18.3.3.

19.601 table:content-validation-name

The `table:content-validation-name` attribute specifies the name of a validity check.

The value of this attribute is a name found in the `table:name` attribute of a `<table:content-validation>` element. 9.4.5 If this attribute is not present, a cell may have arbitrary content.

The `table:content-validation-name` attribute is usable with the following elements: `<table:covered-table-cell>` 9.1.5 and `<table:table-cell>` 9.1.4.

The `table:content-validation-name` attribute has the data type `string` 18.2.

19.602 table:copy-back

The `table:copy-back` attribute specifies whether data is copied back into a scenario table if another scenario is activated.

The defined values for the `table:copy-back` attribute are:

- `false`: data is not copied back into a scenario table if another scenario is activated.
- `true`: data copied back into a scenario table if another scenario is activated.

The default value for this attribute is `true`.

The `table:copy-back` attribute is usable with the following element: `<table:scenario>` 9.2.7.

The `table:copy-back` attribute has the data type `boolean` 18.3.3.

19.603 table:copy-formulas

The `table:copy-formulas` attribute specifies whether formulas are copied from a scenario table to a destination table.

The defined values for the `table:copy-formulas` attribute are:

- `false`: only values resulting from formulas are copied.
- `true`: formulas are copied.

The default value for this attribute is `true`.

The `table:copy-formulas` attribute is usable with the following element: `<table:scenario>` 9.2.7.

The `table:copy-formulas` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.604 table:copy-styles

The `table:copy-styles` attribute specifies whether styles are copied from a scenario table to a destination table together with the data.

The defined values for the `table:copy-styles` attribute are:

- `false`: styles are not copied with data.
- `true`: styles are copied with data.

The default value for this attribute is `true`.

The `table:copy-styles` attribute is usable with the following element: `<table:scenario>` 9.2.7.

The `table:copy-styles` attribute has the data type `boolean` 18.3.3.

19.605 table:count

The `table:count` attribute specifies the count of inserted rows, columns or tables.

The default value for this attribute is `1`.

The `table:count` attribute is usable with the following element: `<table:insertion>` 9.9.3.

The `table:count` attribute has the data type `positiveInteger` 18.2.

19.606 table:country

The `table:country` attribute specifies the country information for the natural language in which comparisons will occur.

The `table:country` attribute is usable with the following element: `<table:sort>` 9.4.19.

The `table:country` attribute has the data type `countryCode` 18.3.11.

19.607 table:data-field

The `table:data-field` attribute specifies the data field whose values are taken into account.

The `table:data-field` attribute is usable with the following elements: `<table:data-pilot-display-info>` 9.6.13 and `<table:data-pilot-sort-info>` 9.6.14.

The `table:data-field` attribute has the data type `string` 18.2.

19.608 table:data-cell-range-address

The `table:data-cell-range-address` attribute specifies the cell range address of data.

The `table:data-cell-range-address` attribute is usable with the following element: `<table:label-range>` 9.4.9.

The `table:data-cell-range-address` attribute has the data type `cellRangeAddress` 18.3.5.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.609 table:database-name

A `table:database-name` attribute specifies the name of an SQL database for the importation of data.

The `table:database-name` attribute is usable with the following elements: `<table:database-source-query>` 9.4.18, `<table:database-source-sql>` 9.4.16 and `<table:database-source-table>` 9.4.17.

The `table:database-name` attribute has the data type `string` 18.2.

19.610 table:database-table-name

A `table:database-table-name` attribute specifies a database table for the importation of data.

The `table:database-table-name` attribute is usable with the following element: `<table:database-source-table>` 9.4.17.

The `table:database-table-name` attribute has the data type `string` 18.2.

19.611 table:data-type

19.611.1 General

The `table:data-type` attribute specifies a data type for tables.

19.611.2 <table:filter-condition>

The `table:data-type` attribute specifies whether a comparison shall take place as text or as numeric values.

The defined values for the `table:data-type` attribute are:

- `number`: comparison as numeric values.
- `text`: comparison as text values.

For a `<table:filter-condition>` 9.5.5 element the default value for this attribute is `text`.

The `table:data-type` attribute is usable with the following element: `<table:filter-condition>` 9.5.5.

The values of the `table:data-type` attribute are `text` or `number`.

19.611.3 <table:sort-by>

The `table:data-type` attribute specifies the data type of a field to be sorted.

The defined values for the `table:data-type` attribute are:

- `automatic`: consumer determines the type of data in a field.
- `number`: numeric data type.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `text`: text data type.
- a value of type `string` (name of a user defined sort order, implementation-dependent)

For a `<table:sort-by>` 9.4.20 element the default value for this attribute is `automatic`.

The `table:data-type` attribute is usable with the following element: `<table:sort-by>` 9.4.20.

The values of the `table:data-type` attribute are `text`, `number`, `automatic` or a value of type `string` 18.2.

19.611.4 <table:sort-groups>

The `table:data-type` attribute specifies the data type of a field to be sorted.

If the attribute value is `automatic`, the consumer shall determine what type of data is in the field. User defined sort orders are implementation specific.

The defined values for the `table:data-type` attribute are:

- `automatic`: consumer determines the type of data in a field.
- `number`: numeric data type.
- `text`: text data type.
- a value of type `string` (name of a user defined sort order, implementation-dependent)

For a `<table:sort-groups>` 9.4.22 element the default value for this attribute is `automatic`.

The `table:data-type` attribute is usable with the following element: `<table:sort-groups>` 9.4.22.

The values of the `table:data-type` attribute are `text`, `number`, `automatic` or a value of type `string` 18.2.

19.612 table:date-end

The `table:date-end` attribute specifies the end value for a grouping of date values.

All values that are higher than the end value are contained in a single group, while values that are equal to or lower than the end value are grouped as specified by the `table:grouped-by` and `table:step` attributes.

The defined values for the `table:date-end` attribute are:

- `auto`: the highest value of the field is taken as the end value.
- a value of type `dateOrDateTime`: `18.3.14`

The `table:date-end` attribute is usable with the following element: `<table:data-pilot-groups>` 9.6.17.

The values of the `table:date-end` attribute are a value of type `dateOrDateTime` 18.3.14 or `auto`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.613 table:date-start

The `table:date-start` attribute specifies the start value for a grouping of date values.

The defined values for the `table:date-start` attribute are:

- `auto`: the lowest value of the field is used as the start value.
- a value of type `dateOrDateTime`: `18.3.14`

The `table:date-start` attribute is usable with the following element: `<table:data-pilot-groups>` 9.6.17.

The values of the `table:date-start` attribute are a value of type `dateOrDateTime` 18.3.14 or `auto`.

19.614 table:date-value

The `table:date-value` attribute specifies the null date. The null date is the date that results in the value “0” if a date value is converted into a numeric value.

The default value for this attribute is `1899-12-30`.

The `table:date-value` attribute is usable with the following element: `<table:null-date>` 9.4.2.

The `table:date-value` attribute has the data type `date` 18.2.

19.615 table:default-cell-style-name

The `table:default-cell-style-name` attribute specifies a default cell style. Cells defined by a `<table:table-cell>` element that do not have a `table:style-name` attribute value use the specified default cell style.

If an individual cell has a default style specified by a `table:default-cell-style-name` attribute on a `<table:table-column>` element and by a style:default-cell-style-name on a `<table:table-row>` element, the default style specified by the `<table:table-row>` element shall be applied to the cell and the default style specified by the <table:table-column element shall be ignored.

The `table:default-cell-style-name` attribute is usable with the following elements: `<table:table-column>` 9.1.6 and `<table:table-row>` 9.1.3.

The `table:default-cell-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.616 table:direction

The `table:direction` attribute specifies the direction of a relation between a cell and a highlighted range.

The defined values for the `table:direction` attribute are:

- `from-another-table`: relationship begins at another table.
- `from-same-table`: relationship begins at the same table.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `to-another-table`: relationship ends at another table.

The `table:direction` attribute is usable with the following element: `<table:highlighted-range>` 9.3.4.

The values of the `table:direction` attribute are `from-another-table`, `to-another-table` or `from-same-table`.

19.617 table:display

The `table:display` attribute specifies whether a table is displayed.

The defined values for the `table:display` attribute are:

- `false`: table is not displayed.
- `true`: table is displayed.

For `<table:table-column-group>` 9.1.10 and `<table:table-row-group>` 9.1.9 elements the default value for this attribute is `true`.

For `<table:error-message>` 9.4.7 and `<table:help-message>` 9.4.6 elements the default value for this attribute is `false`.

The `table:display` attribute is usable with the following elements: `<table:data-pilot-member>` 9.6.12, `<table:error-message>` 9.4.7, `<table:help-message>` 9.4.6, `<table:table-column-group>` 9.1.10 and `<table:table-row-group>` 9.1.9.

The `table:display` attribute has the data type `boolean` 18.3.3.

19.618 table:display-border

The `table:display-border` attribute specifies whether to display a border around a scenario that belongs to a scenario table.

The defined values for the `table:display-border` attribute are:

- `false`: border is not displayed.
- `true`: border is displayed.

The default value for this attribute is `true`.

The `table:display-border` attribute is usable with the following element: `<table:scenario>` 9.2.7.

The `table:display-border` attribute has the data type `boolean` 18.3.3.

19.619 table:display-duplicates

The `table:display-duplicates` attribute specifies whether to display duplicate matches in a result.

The defined values for the `table:display-duplicates` attribute are:

- `false`: duplicate matches not displayed in results.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: duplicate matches displayed in results.

The default value for this attribute is `true`.

The `table:display-duplicates` attribute is usable with the following element: `<table:filter>` 9.5.2.

The `table:display-duplicates` attribute has the data type `boolean` 18.3.3.

19.620 table:display-filter-buttons

The `table:display-filter-buttons` attribute specifies whether to display filter buttons. Filter buttons are list box controls displayed in the label cells whose list entries are the values that exist in the labeled row or column. Selecting one of these entries is the equivalent of applying a filter to the database range that selects all row or columns where the cells in the labeled row or column have the selected value.

The defined values for the `table:display-filter-buttons` attribute are:

- `false`: filter buttons are not displayed.
- `true`: filter buttons are displayed.

The default value for this attribute is `false`.

The `table:display-filter-buttons` attribute is usable with the following element: `<table:database-range>` 9.4.15.

The `table:display-filter-buttons` attribute has the data type `boolean` 18.3.3.

19.621 table:display-list

The `table:display-list` attribute specifies whether a list of values that occurs within a condition is displayed in a UI when a user is entering a cell value.

The defined values for the `table:display-list` attribute are:

- `none`: the list values are not displayed.
- `sort-ascending`: the list values are displayed in ascending order.
- `unsorted`: the list values are displayed in the order they occur in the condition.

The default value for this attribute is `unsorted`.

The `table:display-list` attribute is usable with the following element: `<table:content-validation>` 9.4.5.

The values of the `table:display-list` attribute are `none`, `unsorted` or `sort-ascending`.

19.622 table:display-member-mode

The `table:display-member-mode` attribute specifies whether the value count specified by `table:member-count` attribute should be taken from the top or from the bottom of a data field's column. 19.667

The defined values for the `table:display-member-mode` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- from-bottom
- from-top

The table:display-member-mode attribute is usable with the following element: <table:data-pilot-display-info> 9.6.13.

The values of the table:display-member-mode attribute are from-top or from-bottom.

19.623 table:drill-down-on-double-click

The table:drill-down-on-double-click attribute specifies how the data pilot table reacts on a double click in the data pilot table. A double click other than as specified in a data pilot table has no effect.

The defined values for the table:drill-down-on-double-click attribute are:

- false: a double click on a member label or the empty area next to it starts the edit mode of the table cell, like for cells outside of the data pilot table.

  Note: This can be used to rename group fields or members.

- true: a double click on a member label or the empty area next to it shows or hides details for that member.

The default value for this attribute is true.

The table:drill-down-on-double-click attribute is usable with the following element: <table:data-pilot-table> 9.6.3.

The table:drill-down-on-double-click attribute has the data type boolean 18.3.3.

19.624 table:embedded-number-behavior

The table:embedded-number-behavior attribute specifies how string values that contain digits are sorted. If the value is alpha-numeric, string comparison as specified by the other attributes of <table:sort> element is used for sorting.

The defined values for the table:embedded-number-behavior attribute are:

- alpha-numeric: other attributes are used to specify sorting.
- double: a digit of type double, 18.2
- integer: a digit of type integer, 18.2

Note: If the attribute value is integer or float, string-prefixed numbers will be sorted in a "natural", number-aware way, i.e. A1, A2, A3, ... , A19, A20, instead of the normal, alpha-numeric behavior, i.e. A1, A10, A11, A12, ... ,A19, A2, A20, A3, A4, ... , A8, A9.

The following illustrates how two strings shall be compared if the attribute value is integer or float.

Step 1: The two strings are compared by using the alpha-numeric algorithm to test whether they are equal. If they are equal, the comparison will stop immediately returning an equality as result.

Step 2:.The prefix substrings of the two strings are determined by locating the first occurrence of a digit character in the two strings; the substrings from the very first characters through the characters preceding the first digits are the prefix substrings. If a string starts with a digit, the

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

prefix substring of this string is empty. If there is no digit in either one of the compared strings, the natural sort process will end and the alpha-numeric comparison will be performed instead.

Step 3: After the prefix substrings have been determined for both strings, a alpha-numeric comparison is performed on the two prefix substrings. If they differ, the result is returned and the process will end.

Step 4. The numeric substrings are determined by locating the first occurrences of a non-digit character after the first digit characters; the substrings from the first digit characters through the characters preceding the first non-digit character are the numeric substrings. These substrings are converted into double-precision values. The converted values are compared by numeric comparison. If these values differ, then the result will be returned and the process will end.

Step 5. The suffix substrings, which are the strings that start after the last digits of the numeric substring, will be determined. This suffix substrings replace the original strings, and the whole process will start again with step 1.

Decimal separators are treated as follows : If the attribute value is integer, then a decimal separator is not considered as a digit. If the attribute value is float, the treatment of a decimal separator is context-dependent: If a decimal separator occurs adjacent to one or two digit characters, it is considered a digit character as long as it is the only occurrence in that given numeric substring. In other words, a second occurrence of a decimal separator in sequence of digits and decimal separators is treated as a non-digit character. Therefore the character immediately preceding the separator becomes the last character of the numeric substring, while the separator itself becomes the first character of the suffix substring.

This sorting process is illustrated by the following figure:



Figure 1 - Natural sort

The default value for this attribute is `alpha-numeric`.

The `table:embedded-number-behavior` attribute is usable with the following element: `<table:sort>` 9.4.19.

The values of the `table:embedded-number-behavior` attribute are `alpha-numeric`, `integer` or `double`.

19.625 table:enabled

The `table:enabled` attribute specifies whether the `<table:data-pilot-display-info>` element is evaluated or not.

The defined values for the `table:enabled` attribute are:

- `false`: the `<table:data-pilot-display-info>` element is not evaluated.
- `true`: the `<table:data-pilot-display-info>` element is evaluated.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:enabled` attribute is usable with the following element: `<table:data-pilot-display-info>` 9.6.13.

The `table:enabled` attribute has the data type `boolean` 18.3.3.

19.626 table:end

The `table:end` attribute specifies the end value for a grouping of numeric values. All values that are higher than the end value are contained in a single group, while values that are equal to or lower than the end value are grouped as specified by `table:grouped-by` and `table:step` attributes.

The defined values for the `table:end` attribute are:

- `auto`: the highest value of the field is taken as the end value.
- a value of type `double`

The `table:end` attribute is usable with the following element: `<table:data-pilot-groups>` 9.6.17.

The values of the `table:end` attribute are a value of type `double` 18.2 or `auto`.

19.627 table:end-cell-address

The `table:end-cell-address` attribute specifies specify end position of the shape if it is included in a spreadsheet document.

The `table:end-cell-address` attribute is usable with the following elements: `<dr3d:scene>` 10.5.2, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:connector>` 10.3.10, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:g>` 10.3.15, `<draw:line>` 10.3.3, `<draw:measure>` 10.3.12, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2, `<draw:regular-polygon>` 10.3.6 and `<office:annotation>` 14.1.

The `table:end-cell-address` attribute has the data type `cellAddress` 18.3.4.

19.628 table:end-column

The `table:end-column` attribute specifies the end column of a range if the range address is a cell range address. The value of a `table:end-column` attribute is inclusive.

The `table:end-column` attribute is usable with the following elements: `<table:source-range-address>` 9.9.14 and `<table:target-range-address>` 9.9.15.

The `table:end-column` attribute has the data type `integer` 18.2.

19.629 table:end-position

The `table:end-position` attribute specifies the number of the last deleted row or column. The value of a `table:end-position` attribute is exclusive.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:end-position` attribute is usable with the following element: `<table:movement-cut-off>` 9.9.12.

The `table:end-position` attribute has the data type `integer` 18.2.

19.630 table:end-row

The `table:end-row` attribute specifies the end row of a range if the range address is a cell range address. The value of a `table:end-row` attribute is inclusive.

The `table:end-row` attribute is usable with the following elements: `<table:source-range-address>` 9.9.14 and `<table:target-range-address>` 9.9.15.

The `table:end-row` attribute has the data type `integer` 18.2.

19.631 table:end-table

The `table:end-table` attribute specifies the end table of a range if the range address is a cell range address. The value of a `table:end-table` attribute is inclusive.

The `table:end-table` attribute is usable with the following elements: `<table:source-range-address>` 9.9.14 and `<table:target-range-address>` 9.9.15.

The `table:end-table` attribute has the data type `integer` 18.2.

19.632 table:end-x

The `table:end-x` attribute specifies the x-coordinate of the end position of a shape relative to the top left edge of a cell. The size attributes of the shape are ignored.

The `table:end-x` attribute is usable with the following elements: `<dr3d:scene>` 10.5.2, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:connector>` 10.3.10, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:g>` 10.3.15, `<draw:line>` 10.3.3, `<draw:measure>` 10.3.12, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2, `<draw:regular-polygon>` 10.3.6 and `<office:annotation>` 14.1.

The `table:end-x` attribute has the data type `coordinate` 18.3.10.

19.633 table:end-y

The `table:end-y` attribute specifies the y-coordinate of the end position of a shape relative to the top left edge of a cell. The size attributes of the shape are ignored.

The `table:end-y` attribute is usable with the following elements: `<dr3d:scene>` 10.5.2, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:connector>` 10.3.10, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:g>` 10.3.15, `<draw:line>` 10.3.3, `<draw:measure>` 10.3.12, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2, `<draw:regular-polygon>` 10.3.6 and `<office:annotation>` 14.1.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:end-y` attribute has the data type `coordinate` 18.3.10.

19.634 table:execute

The `table:execute` attribute specifies whether a macro should be executed or not.

The defined values for the `table:execute` attribute are:

- `false`: macro is not executed.
- `true`: macro is executed.

The default value for this attribute is `true`.

The `table:execute` attribute is usable with the following element: `<table:error-macro>` 9.4.8.

The `table:execute` attribute has the data type `boolean` 18.3.3.

19.635 table:expression

The `table:expression` attribute specifies an expression. If the expression contains a named range or another named expression, the named range or named expression shall be specified first, before the containing expression. If the expression contains a relative cell range address, a `table:base-cell-address` attribute shall also appear on the `<table:named-expression>` element.

Relative cell range addresses that occur in an expression define an offset which shall be interpreted relative to the cell where a named expression is used. The offset is the same as the offsets between the table cell addressed by the relative cell range address and the table cell specified by the `table:base-cell-address` attribute.

The value of this attribute may have a namespace prefix, followed by a ":" (U+003A, COLON), followed by an expression. If the namespace prefix is missing it defaults to the "urn:oasis:names:tc:opendocument:xmlns:of:1.2" namespace. If a namespace prefix is present, the expression shall start with an '=' equal sign. If no namespace prefix is present, the '=' equal sign may be omitted. The XML namespace name bound to the namespace prefix specifies the syntax and semantics of the formulas and values occurring within the condition.

An OpenDocument Consumer when hosting a formula evaluator make available the host-dependent properties defined by table 12 in 19.644.

The `table:expression` attribute is usable with the following element: `<table:named-expression>` 9.4.13.

The `table:expression` attribute has the data type `string` 18.2.

19.636 table:field-name

The `table:field-name` attribute specifies a category column whose members' values are used in operations defined by a `table:type` attribute that determines the display of values of the data field of which the `<table:data-pilot-field-reference>` element is a part.

The `table:field-name` attribute is usable with the following element: `<table:data-pilot-field-reference>` 9.6.16.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The table:field-name attribute has the data type string 18.2.

19.637 table:field-number

The table:field-number number attribute specifies a row or column number to sort, subtotal or filter. It is the number of a row or column within a database range.

The table:field-number attribute is usable with the following elements: <table:filter-condition> 9.5.5, <table:sort-by> 9.4.20 and <table:subtotal-field> 9.4.24.

The table:field-number attribute has the data type nonNegativeInteger 18.2.

19.638 table:filter-name

The table:filter-name attribute specifies the file type of the document containing the original table. The value of this attribute is implementation-dependent.

The table:filter-name attribute is usable with the following elements: <table:cell-range-source> 9.3.1 and <table:table-source> 9.2.6.

The table:filter-name attribute has the data type string 18.2.

19.639 table:filter-options

The table:filter-options attribute specifies implementation-dependent settings for a file type.

The table:filter-options attribute is usable with the following elements: <table:cell-range-source> 9.3.1 and <table:table-source> 9.2.6.

The table:filter-options attribute has the data type string 18.2.

19.640 table:first-row-end-column (deprecated)

The table:first-row-end-column attribute specifies the whether the cell in the first row, end column gets its style from its row or column.

The use of this attribute is deprecated. The table:use-first-row-styles or table:use-last-column-styles attributes should be used instead.

The defined values for the table:first-row-end-column attribute are:

- column: cell in first row, end column should inherit its style from the column where it appears.
- row: cell in first row, end column should inherit its style from the row where it appears.

The table:first-row-end-column attribute is usable with the following element: <table:table-template> 16.18.

The values of the table:first-row-end-column attribute are row or column.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.641 table:first-row-start-column (deprecated)

The `table:first-row-start-column` attribute specifies the whether the cell in the first row, start column gets its style from its row or column.

The use of this attribute is deprecated. The `table:use-first-row-styles` or `table:use-first-column-styles` attributes should be used instead.

The defined values for the `table:first-row-start-column` attribute are:

- `column`: cell in first row, start column should inherit its style from the column where it appears.
- `row`: cell in first row, start column should inherit its style from the row where it appears.

The `table:first-row-start-column` attribute is usable with the following element: `<table:table-template>` 16.18.

The values of the `table:first-row-start-column` attribute are `row` or `column`.

19.642 table:formula

The `table:formula` attribute specifies a formula for a table cell.

Formulas specify calculations to be performed within table cells. The attribute value should begin with a namespace prefix followed by ":" (U+003A, COLON), followed by the text of the formula. The namespace bound to the prefix determines the syntax and semantics of the formula.

Whenever the initial text of a formula has the appearance of an NCName followed by ":", an OpenDocument producer SHALL provide a valid namespace prefix and separating ":" before the text of the formula in order to eliminate any ambiguity.

If a namespace prefix is not specified, it defaults to the "urn:oasis:names:tc:opendocument:xmlns:of:1.2" namespace.

An OpenDocument Consumer when hosting a formula evaluator has the host-dependent properties specified in Table 12.

Table 12 Host-dependent Properties

Property	***Attribute***	***Default Value***
HOST-CASE-SENSITIVE	`table:case-sensitive`	`true`
HOST-PRECISION-AS-SHOWN	`table:precision-as-shown`	`false`
HOST-SEARCH-CRITERIA-MUST-APPLY-TO-WHOLE-CELL	`table:search-criteria-must-apply-to-whole-cell`	`true`
HOST-AUTOMATIC-FIND-LABELS	`table:automatic-find-labels`	`true`
HOST-USE-REGULAR-EXPRESSIONS	`table:use-regular-expressions`	`true`
HOST-USE-WILDCARDS	`table:use-wildcards`	`false`

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

HOST-NULL-YEAR	table:null-year	1930
HOST-NULL-DATE	table:null-date	1899-12-30
HOST-LOCALE	N/A	Implementation-defined
HOST-ITERATION-STATUS	table:status	disable
HOST-ITERATION-MAXIMUM-DIFFERENCE	table:maximum-difference	0
HOST-ITERATION-STEPS	table:steps	100

Note: Host-dependent properties are applicable to `style:condition` (19.468), `table:condition` (19.596) and, `table:expression` (19.635) attributes.

The `table:formula` attribute is usable with the following elements: `<table:change-track-table-cell>` 9.9.16, `<table:covered-table-cell>` 9.1.5 and `<table:table-cell>` 9.1.4.

The `table:formula` attribute has the data type `string` 18.2.

19.643 table:function

19.643.1 General

The `table:function` attribute specifies functions that are applied to tables.

The `table:function` attribute on all elements has the following defined values:

- `average`: the average of all numeric values.
- `count`: the count of all non-empty values, including text.
- `countnums`: the count of all numeric values.
- `max`: the maximum of all numeric values.
- `min`: the minimum of all numeric values.
- `product`: the product of all numeric values.
- `stdev`: the standard deviation, treating all numeric values as a sample from a population.
- `stdevp`: the standard deviation, treating all numeric values as a whole population.
- `sum`: the sum of all numeric values.
- `var`: the variance, treating all numeric values as a sample from a population.
- `varp`: the variance, treating all numeric values as a whole population.
- a value of type `string`: an implementation-dependent function name.

19.643.2 <table:consolidation>

The `table:function` attribute specifies functions.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:function` attribute is usable with the following element: `<table:consolidation>` 9.7.

The values of the `table:function` attribute are `average`, `count`, `countnums`, `max`, `min`, `product`, `stdev`, `stdevp`, `sum`, `var`, `varp` or a value of type `string` 18.2.

19.643.3 <table:data-pilot-field>

The `table:function` attribute specifies specifies the function which is applied to the cell values of data columns.

For `<table:data-pilot-field>` elements whose `table:orientation` attribute has the value `data`, the defined values for the `table:function` attribute are those defined in 19.643.1.

For `<table:data-pilot-field>` elements whose `table:orientation` attribute has the value `column` or `row`, the only defined value for the `table:function` attribute is:

- `auto`: no function is applied to that category field.

The `table:function` attribute is usable with the following element: `<table:data-pilot-field>` 9.6.7.

The values of the `table:function` attribute are `auto`, `average`, `count`, `countnums`, `max`, `min`, `product`, `stdev`, `stdevp`, `sum`, `var`, `varp` or a value of type `string` 18.2.

19.643.4 <table:data-pilot-subtotal>

The `table:function` attribute specifies the type of subtotals to calculate.

The addition to the values defined in 19.643.1 the following value is defined:

- `auto`: specifies that subtotals shall use the same function(s) that are used to calculate the `<table:data-pilot-field>` elements with `table:orientation`="`data`".

The `table:function` attribute is usable with the following element: `<table:data-pilot-subtotal>` 9.6.10.

The values of the `table:function` attribute are `auto`, `average`, `count`, `countnums`, `max`, `min`, `product`, `stdev`, `stdevp`, `sum`, `var`, `varp` or a value of type `string` 18.2.

19.643.5 <table:subtotal-field>

The `table:function` attribute specifies the type of subtotals to calculate.

The `table:function` attribute is usable with the following element: `<table:subtotal-field>` 9.4.24.

The values of the `table:function` attribute are `average`, `count`, `countnums`, `max`, `min`, `product`, `stdev`, `stdevp`, `sum`, `var`, `varp` or a value of type `string` 18.2.

19.644 table:grand-total

The `table:grand-total` attribute specifies whether a grand total column, row, or both should be displayed in addition to values calculated for each combination of values in the category columns.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the table:grand-total attribute are:

- both: grand totals for rows and columns are displayed in addition to values calculated for other combinations of values.
- column: grand totals for columns are displayed in addition to values calculated for other combinations of values.
- none: grand totals for rows and columns are not displayed in addition to values calculated for other combinations of values.
- row: grand totals for rows are displayed in addition to values calculated for other combinations of values.

The default value for this attribute is both.

The table:grand-total attribute is usable with the following element: <table:data-pilot-table> 9.6.3.

The values of the table:grand-total attribute are none, row, column or both.

19.645 table:group-by-field-number

The table:group-by-field-number attribute specifies a field, that is to be grouped. It is the number of a row or column within a database range.

The table:group-by-field-number attribute is usable with the following element: <table:subtotal-rule> 9.4.23.

The table:group-by-field-number attribute has the data type nonNegativeInteger 18.2.

19.646 table:grouped-by

The table:grouped-by attribute specifies the grouping of the date values. Date values can be grouped by seconds, minutes, hours, days, months, quarters or years.

Note: If date values are for instance grouped by minutes, all dates or times that are within the same minute are within one group.

The defined values for the table:grouped-by attribute are:

- seconds: a value expressed as seconds.
- minutes: a value expressed as minutes.
- hours: a value expressed as hours.
- days: a value expressed as days.
- months: a value expressed as months.
- quarters: a value expressed as quarters (4 equal 3 month segments).
- years: a value expressed as years.

The table:grouped-by attribute is usable with the following element: <table:data-pilot-groups> 9.6.17.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The values of the table:grouped-by attribute are seconds, minutes, hours, days, months, quarters or years.

19.647 table:has-persistent-data

The table:has-persistent-data attribute specifies whether the current data in a database range is saved when the document itself is saved.

The defined values for the table:has-persistent-data attribute are:

- false: data in a database range is not saved when the document itself is saved.
- true: data in a database range is saved when the document itself is saved.

The default value for this attribute is true.

The table:has-persistent-data attribute is usable with the following element: <table:database-range> 9.4.15.

The table:has-persistent-data attribute has the data type boolean 18.3.3.

19.648 table:id

The table:id attribute specifies the id of an insertion or tracked change.

The table:id attribute is usable with the following elements: <table:cell-content-change> 9.9.17, <table:cell-content-deletion> 9.9.7, <table:change-deletion> 9.9.8, <table:deletion> 9.9.9, <table:dependency> 9.9.5, <table:insertion> 9.9.3, <table:insertion-cut-off> 9.9.11, <table:movement> 9.9.13 and <table:previous> 9.9.19.

The table:id attribute has the data type string 18.2.

19.649 table:identify-categories

The table:identify-categories attribute specifies whether rows that do not contain a value in one of the category columns should use the value of the nearest ancestor row that has a value, or should be moved into a group (or category) of its own.

The defined values for the table:identify-categories attribute are:

- false: empty rows form a group or category.
- true: empty rows use the value of the nearest ancestor row that has a value for classification into a group or category.

The default value for this attribute is false.

The table:identify-categories attribute is usable with the following element: <table:data-pilot-table> 9.6.3.

The table:identify-categories attribute has the data type boolean 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.650 table:ignore-empty-rows

The `table:ignore-empty-rows` attribute specifies whether empty rows in a source range should be ignored.

The defined values for the `table:ignore-empty-rows` attribute are:

- `false`: empty rows in a source range are not ignored.
- `true`: empty rows in a source range are ignored.

The default value for this attribute is `false`.

The `table:ignore-empty-rows` attribute is usable with the following element: `<table:data-pilot-table>` 9.6.3.

The `table:ignore-empty-rows` attribute has the data type `boolean` 18.3.3.

19.651 table:index

The `table:index` attribute specifies for the `<table:operation>` element on which it appears, its order in a series of `<table:operation>` elements under a `<table:detective>` element.

The `table:index` attribute is usable with the following element: `<table:operation>` 9.3.3.

The `table:index` attribute has the data type `nonNegativeInteger` 18.2.

19.652 table:is-active

The `table:is-active` attribute specifies whether a scenario that belongs to a scenario table is active.

The defined values for the `table:is-active` attribute are:

- `false`: scenario that belongs to a scenario table is inactive.
- `true`: scenario that belongs to a scenario table is active.

The `table:is-active` attribute is usable with the following element: `<table:scenario>` 9.2.7.

The `table:is-active` attribute has the data type `boolean` 18.3.3.

19.653 table:is-data-layout-field

The `table:is-data-layout-field` attribute specifies whether a field is a data layout field.

The defined values for the `table:is-data-layout-field` attribute are:

- `false`: field is not a data layout field.
- `true`: field is a data layout field.

The default value for this attribute is `false`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:is-data-layout-field` attribute is usable with the following element: `<table:data-pilot-field>` 9.6.7.

The `table:is-data-layout-field` attribute has the data type `string` 18.2.

19.654 table:is-selection

The `table:is-selection` attribute specifies whether the database range includes a complete database, or a selection of records from a database only.

The defined values for the `table:is-selection` attribute are:

- `false`: database range includes a section of records from a database.
- `true`: database range includes a complete database.

The default value for this attribute is `false`.

The `table:is-selection` attribute is usable with the following element: `<table:database-range>` 9.4.15.

The `table:is-selection` attribute has the data type `boolean` 18.3.3.

19.655 table:is-sub-table

The `table:is-sub-table` attribute specifies if a nested table is a subtable.

If a table cell only contains a single table but no paragraphs or other content, the table can be specified as subtable. It occupies the whole cell and no other content can appear in the cell.

The borders of a subtable merge with the borders of the cell where it is specified. A subtable does not have its own style.

A nested table that is not specified to be a subtable appears as a table within a table, that is, it has borders distinct from those of the parent cell and respects the padding of the parent cell.

The defined values for the `table:is-sub-table` attribute are:

- `false`: nested table is not a subtable.
- `true`: nested table is a subtable.

The default value for this attribute is `false`.

The `table:is-sub-table` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:is-sub-table` attribute has the data type `boolean` 18.3.3.

19.656 table:label-cell-range-address

The `table:label-cell-range-address` attribute specifies a cell range address for labels.

The `table:label-cell-range-address` attribute is usable with the following element: `<table:label-range>` 9.4.9.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:label-cell-range-address` attribute has the data type `cellRangeAddress` 18.3.5.

19.657 table:language

The `table:language` attribute specifies the natural language in which a comparison will occur.

The `table:language` attribute is usable with the following element: `<table:sort>` 9.4.19.

The `table:language` attribute has the data type `languageCode` 18.3.17.

19.658 table:last-column-spanned

The `table:last-column-spanned` attribute together with the `table:last-row-spanned` attribute specifies the last known size of a range. If the size of the range has changed since the determination of its size, the value of these attributes will be incorrect.

The `table:last-column-spanned` attribute is usable with the following element: `<table:cell-range-source>` 9.3.1.

The `table:last-column-spanned` attribute has the data type `positiveInteger` 18.2.

19.659 table:last-row-end-column (deprecated)

The `table:last-row-end-column` attribute specifies the whether the cell in the last row, end column gets its style from its row or column.

The use of this attribute is deprecated. The `table:use-last-row-styles` or `table:use-last-column-styles` attributes should be used instead.

The defined values for the `table:last-row-end-column` attribute are:

- `column`: cell in last row, end column should inherit its style from the column where it appears.
- `row`: cell in last row, end column should inherit its style from the column where it appears.

The `table:last-row-end-column` attribute is usable with the following element: `<table:table-template>` 16.18.

The values of the `table:last-row-end-column` attribute are `row` or `column`.

19.660 table:last-row-spanned

The `table:last-row-spanned` attribute together with the `table:last-column-spanned` attribute specifies the last known size of a range. If the size of the range has changed since the determination of its size, the value of these attributes will be incorrect.

The `table:last-row-spanned` attribute is usable with the following element: `<table:cell-range-source>` 9.3.1.

The `table:last-row-spanned` attribute has the data type `positiveInteger` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.661 table:last-row-start-column (deprecated)

The `table:last-row-start-column` attribute specifies the whether the cell in the last row, start column gets its style from its row or column.

The use of this attribute is deprecated. The `table:use-last-row-styles` or `table:use-first-column-styles` attributes should be used instead.

The defined values for the `table:last-row-start-column` attribute are:

- `column`: cell in last row, start column should inherit its style from the column where it appears.
- `row`: cell in last row, start column should inherit its style from the column where it appears.

The `table:last-row-start-column` attribute is usable with the following element: `<table:table-template>` 16.18.

The values of the `table:last-row-start-column` attribute are `row` or `column`.

19.662 table:layout-mode

The `table:layout-mode` attribute specifies how to layout a field.

The defined values for the `table:layout-mode` attribute are:

- `outline-subtotals-bottom`: Like `outline-subtotals-top`, except that subtotals are shown at the bottom (below the member's data, as in tabular layout mode).
- `outline-subtotals-top`: In outline layout mode, the members from the following field start in the row below a member's name. Subtotals are shown at the top (in the same row as the member's name). When the subtotals take up more than one row (manually selected, or because there are multiple data fields), they are always shown below the member's data, regardless of the setting.
- `tabular-layout`: Tabular layout mode is the layout, where each member's name is on the same row as the first member from the following field. Subtotals are always shown below a member's data in this mode.

The `table:layout-mode` attribute is usable with the following element: `<table:data-pilot-layout-info>` 9.6.15.

The values of the `table:layout-mode` attribute are `tabular-layout`, `outline-subtotals-top` or `outline-subtotals-bottom`.

19.663 table:link-to-source-data

The `table:link-to-source-data` attribute specifies whether the data in a consolidation table range should be linked to the source data, so that it is automatically updated if any changes are made to the source data.

The defined values for the `table:link-to-source-data` attribute are:

- `false`: data in consolidated table range not linked to source data.
- `true`: data in consolidated table range is linked to source data.

The default value for this attribute is `false`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:link-to-source-data` attribute is usable with the following element: `<table:consolidation>` 9.7.

The `table:link-to-source-data` attribute has the data type `boolean` 18.3.3.

19.664 table:marked-invalid

The `table:marked-invalid` attribute specifies whether the current cell is marked invalid. This attribute cannot be used together with any other attributes.

The defined values for the `table:marked-invalid` attribute are:

- `false`: current cell not marked invalid.
- `true`: current cell marked invalid.

The `table:marked-invalid` attribute is usable with the following element: `<table:highlighted-range>` 9.3.4.

The `table:marked-invalid` attribute has the data type `boolean` 18.3.3.

19.665 table:matrix-covered

The `table:matrix-covered` attribute specifies if a cell is contained in a matrix.

The defined values for the `table:matrix-covered` attribute are:

- `false`: cell is not included in a matrix.
- `true`: cell is included in a matrix.

The default value for this attribute is `false`.

The `table:matrix-covered` attribute is usable with the following element: `<table:change-track-table-cell>` 9.9.16.

The `table:matrix-covered` attribute has the data type `boolean` 18.3.3.

19.666 table:maximum-difference

The `table:maximum-difference` attribute specifies the maximum difference between two iterative calculation results. The iteration is stopped if the result is less than the value of this attribute.

The default value for this attribute is `0.001`.

The `table:maximum-difference` attribute is usable with the following element: `<table:iteration>` 9.4.3.

The `table:maximum-difference` attribute has the data type `double` 18.2.

19.667 table:member-count

The `table:member-count` attribute specifies the number of values from the top or from the bottom of a data field's column are shown.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:member-count` attribute is usable with the following element: `<table:data-pilot-display-info>` 9.6.13.

The `table:member-count` attribute has the data type `nonNegativeInteger` 18.2.

19.668 table:member-name

The `table:member-name` attribute specifies the value of a data pilot member.

The `table:member-name` attribute is usable with the following element: `<table:data-pilot-field-reference>` 9.6.16.

The `table:member-name` attribute has the data type `string` 18.2.

19.669 table:member-type

The `table:member-type` attribute specifies the member of the referenced category column, whose value within the current data field is taken into account.

The defined values for the `table:member-type` attribute are:

- `named`: the `table:member-name` attribute on the same `<table:data-pilot-field-reference>` element specifies the member whose value within the data field is taken into account.
- `next`: the value of the data field for the next visible member of the referenced category column is taken into account. Empty members are skipped.
- `previous`: the value of the data field for the next visible member of the referenced category column is taken into account. Empty members are skipped.

The `table:member-type` attribute is usable with the following element: `<table:data-pilot-field-reference>` 9.6.16.

The values of the `table:member-type` attribute are `named`, `previous` or `next`.

19.670 table:message-type

The `table:message-type` attribute specifies the display of messages.

The defined values for the `table:message-type` attribute are:

- `information`: message is displayed as information only.
- `stop`: message is displayed as an error and the operation that caused the validation check is stopped.
- `warning`: message is displayed as a warning.

The default value for this attribute is `stop`.

The `table:message-type` attribute is usable with the following element: `<table:error-message>` 9.4.7.

The values of the `table:message-type` attribute are `stop`, `warning` or `information`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.671 table:mode

The `table:mode` attribute specifies what data should be copied from a source table to a destination table.

The defined values for the `table:mode` attribute are:

- `copy-all`: formulas and styles are copied.
- `copy-results-only`: only formula results and non-calculated cell content are copied.

The default value for this attribute is `copy-all`.

The `table:mode` attribute is usable with the following element: `<table:table-source>` 9.2.6.

The values of the `table:mode` attribute are `copy-all` or `copy-results-only`.

19.672 table:multi-deletion-spanned

The `table:multi-deletion-spanned` attribute specifies the total number of deleted rows or columns when multiple columns or rows were deleted simultaneously. Each deleted row or column is represented by a `<table:deletion>` element. The first <table:deletion element in a set representing a simultaneous deletion, shall carry a `table:multi-deletion-spanned` attribute that specifies the total number of deleted rows or columns.

The `table:multi-deletion-spanned` attribute is usable with the following element: `<table:deletion>` 9.9.9.

The `table:multi-deletion-spanned` attribute has the data type `integer` 18.2.

19.673 table:name

19.673.1 General

The `table:name` attribute specifies a name.

19.673.2 <table:cell-range-source>

The `table:name` attribute specifies the name of a source database range or named range.

The `table:name` attribute is usable with the following element: `<table:cell-range-source>` 9.3.1.

The `table:name` attribute has the data type `string` 18.2.

19.673.3 <table:content-validation>

The `table:name` attribute specifies the name of a content validation rule. It is used to reference the validation rule from the cell the rule should applied.

The `table:name` attribute is usable with the following element: `<table:content-validation>` 9.4.5.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:name` attribute has the data type `string` 18.2.

19.673.4 <table:data-pilot-group>

The `table:name` attribute specifies the name of a group.

The `table:name` attribute is usable with the following element: `<table:data-pilot-group>` 9.6.18.

The `table:name` attribute has the data type `string` 18.2.

19.673.5 <table:data-pilot-group-member>

The `table:name` attribute specifies the name of a member.

The `table:name` attribute is usable with the following element: `<table:data-pilot-group-member>` 9.6.19.

The `table:name` attribute has the data type `string` 18.2.

19.673.6 <table:data-pilot-member>

The `table:name` attribute specifies the value for which display information is specified.

The `table:name` attribute is usable with the following element: `<table:data-pilot-member>` 9.6.12.

The `table:name` attribute has the data type `string` 18.2.

19.673.7 <table:data-pilot-table>

The `table:name` attribute specifies the name of a data pilot table.

The `table:name` attribute is usable with the following element: `<table:data-pilot-table>` 9.6.3.

The `table:name` attribute has the data type `string` 18.2.

19.673.8 <table:database-range>

The `table:name` attribute specifies the name of a database range on which to perform operations. Within a single document, only one database range may have no name. This database range is created by the consumer and is used to filter or sort data in a cell ranges without the user creating a database range.

The `table:name` attribute is usable with the following element: `<table:database-range>` 9.4.15.

The `table:name` attribute has the data type `string` 18.2.

19.673.9 <table:named-expression>

The `table:name` attribute specifies the name of an expression.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:name` attribute is usable with the following element: `<table:named-expression>` 9.4.13.

The `table:name` attribute has the data type `string` 18.2.

19.673.10 <table:named-range>

The `table:name` attribute specifies the name of a database range on which to perform operations. Within a single document, only one database range may have no name.

The `table:name` attribute is usable with the following element: `<table:named-range>` 9.4.12.

The `table:name` attribute has the data type `string` 18.2.

19.673.11 <table:operation>

The `table:name` attribute specifies the name of a detective operation.

The defined values for the `table:name` attribute are:

- `remove-dependents`: removes highlighting from cells that use the value of the current cell in their formula.
- `remove-precedents`: removes highlighting from cells whose values are use in the formula of the current cell.
- `trace-dependents`: highlights cells that use the value of the current cell in their formula.
- `trace-errors`: highlights cells that cause an error while calculating the result of the current cell's formula.
- `trace-precedents`: highlights cells whose values are use in the formula of the current cell.

The nature of the highlighting imposed or removed from cells as the result of detective operations is implementation-defined.

The `table:name` attribute is usable with the following element: `<table:operation>` 9.3.3.

The values of the `table:name` attribute are `trace-dependents`, `remove-dependents`, `trace-precedents`, `remove-precedents` or `trace-errors`.

19.673.12 <table:source-service>

The `table:name` attribute specifies the name of a service. The value of this attribute is implementation-dependent.

The `table:name` attribute is usable with the following element: `<table:source-service>` 9.6.6.

The `table:name` attribute has the data type `string` 18.2.

19.673.13 <table:table>

The `table:name` attribute specifies the name of a table.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:name` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:name` attribute has the data type `string` 18.2.

19.673.14 <table:table-template>

The `table:name` attribute specifies the name of a table template.

The `table:name` attribute is usable with the following element: `<table:table-template>` 16.18.

The `table:name` attribute has the data type `string` 18.2.

19.674 table:null-year

The `table:null-year` attribute specifies the start year for year values that contain only two digits. All two digit year values are interpreted as a year that is the same as or follows the start year.

The default value for this attribute is `1930`.

The `table:null-year` attribute is usable with the following element: `<table:calculation-settings>` 9.4.1.

The `table:null-year` attribute has the data type `positiveInteger` 18.2.

19.675 table:number-columns-repeated

19.675.1 General

The `table:number-columns-repeated` attribute specifies the repetition of columns.

19.675.2 <table:covered-table-cell>

The `table:number-columns-repeated` attribute specifies the number of successive columns in which a cell is repeated. It may be used to describe two or more adjoining cells with a single cell element, if they meet the following conditions:

- The cells contain the same content and style.
- The cells are not merged horizontally or vertically.

For a `<table:covered-table-cell>` 9.1.5 element the default value for this attribute is `1`.

The `table:number-columns-repeated` attribute is usable with the following element: `<table:covered-table-cell>` 9.1.5.

The `table:number-columns-repeated` attribute has the data type `positiveInteger` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.675.3 <table:table-cell>

The `table:number-columns-repeated` attribute specifies the number of successive columns in which a cell is repeated. It may be used to describe two or more adjoining cells with a single cell element, if they meet the following conditions:

- The cells contain the same content and style.
- The cells are not merged horizontally or vertically.

For a `<table:table-cell>` 9.1.4 element the default value for this attribute is `1`.

The `table:number-columns-repeated` attribute is usable with the following element: `<table:table-cell>` 9.1.4.

The `table:number-columns-repeated` attribute has the data type `positiveInteger` 18.2.

19.675.4 <table:table-column>

The `table:number-columns-repeated` attribute specifies the number of columns to which a column description applies. If two or more columns are adjoining, and have the same style, this attribute may be used to describe them with a single `<table:table-column>` element.

For a `<table:table-column>` 9.1.6 element the default value for this attribute is `1`.

The `table:number-columns-repeated` attribute is usable with the following element: `<table:table-column>` 9.1.6.

The `table:number-columns-repeated` attribute has the data type `positiveInteger` 18.2.

19.676 table:number-columns-spanned

The `table:number-columns-spanned` attribute specifies the number of columns that a cell spans.

When a cell covers another cell because of a column or row span value greater than one, a `<table:covered-table-cell>` element shall appear in the table to represent the covered cell.

The default value for this attribute is `1`.

The `table:number-columns-spanned` attribute is usable with the following element: `<table:table-cell>` 9.1.4.

The `table:number-columns-spanned` attribute has the data type `positiveInteger` 18.2.

19.677 table:number-rows-repeated

The `table:number-rows-repeated` attribute specifies the number of rows to which a row element applies. If two or more rows are adjoining, and have the same content and style, and do not contain vertically merged cells, they may be described by a single `<table:table-row>` element that has a `table:number-rows-repeated` attribute with a value greater than 1.

The default value for this attribute is `1`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:number-rows-repeated` attribute is usable with the following element: `<table:table-row>` 9.1.3.

The `table:number-rows-repeated` attribute has the data type `positiveInteger` 18.2.

19.678 table:number-rows-spanned

The `table:number-rows-spanned` attribute specifies the number of columns that a cell spans.

The default value for this attribute is `1`.

The `table:number-rows-spanned` attribute is usable with the following element: `<table:table-cell>` 9.1.4.

The `table:number-rows-spanned` attribute has the data type `positiveInteger` 18.2.

19.679 table:number-matrix-columns-spanned

The `table:number-matrix-columns-spanned` attribute specifies the number of rows spanned by a matrix.

The `table:number-matrix-columns-spanned` attribute is usable with the following elements: `<table:change-track-table-cell>` 9.9.16 and `<table:table-cell>` 9.1.4.

The `table:number-matrix-columns-spanned` attribute has the data type `positiveInteger` 18.2.

19.680 table:number-matrix-rows-spanned

The `table:number-matrix-rows-spanned` attribute specifies the number of rows spanned by a matrix.

The `table:number-matrix-rows-spanned` attribute is usable with the following elements: `<table:change-track-table-cell>` 9.9.16 and `<table:table-cell>` 9.1.4.

The `table:number-matrix-rows-spanned` attribute has the data type `positiveInteger` 18.2.

19.681 table:object-name

The `table:object-name` attribute specifies the name of the object in the source which contains the data and is passed to the service implementation. Its value is implementation-dependent and service specific.

The `table:object-name` attribute is usable with the following element: `<table:source-service>` 9.6.6.

The `table:object-name` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.682 table:on-update-keep-size

The `table:on-update-keep-size` attribute specifies the behavior of a database range if the size of the data in the data source changes.

The defined values for the `table:on-update-keep-size` attribute are:

- `false`: range does not retain its size.
- `true`: range retains its size.

The default value for this attribute is `true`.

The `table:on-update-keep-size` attribute is usable with the following element: `<table:database-range>` 9.4.15.

The `table:on-update-keep-size` attribute has the data type `boolean` 18.3.3.

19.683 table:on-update-keep-styles

The `table:on-update-keep-styles` attribute specifies the behavior if the database range is updated. If the attribute value is “true”, the cell styles that are assigned to the cells in the first non-label row of the database range are used for all rows with in the database range. If the attribute value is “false”, all cells in the database range get the default cell style of the document assigned.

The defined values for the `table:on-update-keep-styles` attribute are:

- `false`: all cells in the database range get the default cell style of the document assigned.
- `true`: cell styles that are assigned to the cells in the first non-label row of the database range are used for all rows with in the database range.

The default value for this attribute is `false`.

The `table:on-update-keep-styles` attribute is usable with the following element: `<table:database-range>` 9.4.15.

The `table:on-update-keep-styles` attribute has the data type `boolean` 18.3.3.

19.684 table:operator

The `table:operator` attribute specifies the operator to use in a filter condition. Each cell contained in columns specified by a field number (`table:field-number` attribute) is compared to a value (`table:value` attribute) using the specified operator. The result of this comparison is the result of the filter sub-conditions specified by a `<table:filter-condition>` element.

The defined operators that use regular expressions are:

- `match` (matches)
- `!match` (does not match)

The `table:value` attribute contains the regular expression.

Regular expressions are implementation-dependent expressions that, at a minimum, conform to the requirements of Conformance Clause C1 of [UTR18].

The defined operators that do not use regular expressions are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- = (Equal to)
- != (Not equal to)
- < (Less than)
- > (Greater than)
- <= (Less than or equal to)
- >= (Greater than or equal to)
- `begins` (begins with)
- `contains` (contains)
- `!contains` (does not contain)
- `ends` (ends with)
- `!begins` (does not begin with)
- `!ends` (does not end with)
- `bottom percent` (like `bottom values`, except that the `office:value` attribute specifies the number of cells for which the condition is true as a percentage)
- `bottom values` (true for the *n* cells that have the smallest value, where *n* is the value of the `office:value` attribute)
- `empty` (`true` for empty cells)
- `!empty` (`true` for non-empty cells)
- `top percent` (like `bottom percent`, but for the largest values)
- `top values` (like `bottom values`, but for the largest values)

Depending on the value of the `table:data-type` attribute, all operations take place on string or numeric values.

The `table:operator` attribute is usable with the following element: `<table:filter-condition>` 9.5.5.

The `table:operator` attribute has the data type `string` 18.2.

19.685 table:order

The `table:order` attribute specifies a sort order should be in ascending or descending order.

The defined values for the `table:order` attribute are:

- `ascending`: sorting of values should be in ascending order.
- `descending`: sorting of values should be in descending order.

Note: Sorting is locale and implementation-dependent.

For `<table:sort-by>` 9.4.20 and `<table:sort-groups>` 9.4.22 elements the default value for this attribute is `ascending`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The table:order attribute is usable with the following elements: <table:data-pilot-sort-info> 9.6.14, <table:sort-by> 9.4.20 and <table:sort-groups> 9.4.22.

The values of the table:order attribute are ascending or descending.

19.686 table:orientation

19.686.1 General

The table:orientation attribute specifies the sorting of tables.

19.686.2 <table:data-pilot-field>

The table:orientation attribute specifies the orientation of a source field.

The defined values for the table:orientation attribute are:

- column: field specifies a category column
- data: field specifies a data column
- hidden: field has a corresponding column in a data pilot's source but are not visible in the data pilot table.
- page: specifies that an automatic filter (one that allows to choose one of the values that are contained in the column) should be generated for the corresponding column. In that case, an additional field with row, column or data orientation shall exist for the column. The table:selected-page attribute specifies which value is selected for the filter.
- row: specifies a category column

The table:orientation attribute is usable with the following element: <table:data-pilot-field> 9.6.7.

The values of the table:orientation attribute are row, column, data, hidden or page.

19.686.3 <table:database-range>

The table:orientation attribute specifies whether data fields are organized in row or columns.

The defined values for the table:orientation attribute are:

- column: organization is by columns
- row: organization is by rows

For a <table:database-range> 9.4.15 element the default value for this attribute is row.

The table:orientation attribute is usable with the following element: <table:database-range> 9.4.15.

The values of the table:orientation attribute are column or row.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.686.4 <table:label-range>

The `table:orientation` attribute specifies whether labels label rows or columns.

The defined values for the `table:orientation` attribute are:

- `column`: label range oriented by column
- `row`: label range oriented by row

The `table:orientation` attribute is usable with the following element: `<table:label-range>` 9.4.9.

The values of the `table:orientation` attribute are `column` or `row`.

19.687 table:page-breaks-on-group-change

The `table:page-breaks-on-group-change` attribute specifies whether to insert a page break after the subtotal for each group.

The defined values for the `table:page-breaks-on-group-change` attribute are:

- `false`: page breaks are not inserted after subtotals for a group.
- `true`: page breaks are inserted after subtotals for a group.

The default value for this attribute is `false`.

The `table:page-breaks-on-group-change` attribute is usable with the following element: `<table:subtotal-rules>` 9.4.21.

The `table:page-breaks-on-group-change` attribute has the data type `boolean` 18.3.3.

19.688 table:paragraph-style-name

The `table:paragraph-style-name` attribute specifies the paragraph style which should be applied to the empty paragraphs created in cells for tables created from a template.

The `table:paragraph-style-name` attribute is usable with the following elements: `<table:body>` 16.19.6, `<table:even-columns>` 16.19.9, `<table:even-rows>` 16.19.7, `<table:first-column>` 16.19.4, `<table:first-row>` 16.19.2, `<table:last-column>` 16.19.5, `<table:last-row>` 16.19.3, `<table:odd-columns>` 16.19.10 and `<table:odd-rows>` 16.19.8.

The `table:paragraph-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.689 table:parse-sql-statement

A `table:parse-sql-statement` attribute specifies whether the consumer will parse SQL statements.

The defined values for the `table:parse-sql-statement` attribute are:

- `false`: consumer does not parse SQL statements.
- `true`: consumer parses SQL statements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The default value for this attribute is `false`.

The `table:parse-sql-statement` attribute is usable with the following element: `<table:database-source-sql>` 9.4.16.

The `table:parse-sql-statement` attribute has the data type `boolean` 18.3.3.

19.690 table:password

The `table:password` attribute specifies the password needed to access the source. It is passed to the service implementation. Its value is implementation-dependent and service specific.

The `table:password` attribute is usable with the following element: `<table:source-service>` 9.6.6.

The `table:password` attribute has the data type `string` 18.2.

19.691 table:position

The `table:position` attribute specifies the position where an insertion or deletion was made in a table. Depending on the type of insertion or deletion, the value is the number of a row, a column or a table.

If multiple rows or columns get deleted, the `table:start-position` and `table:end-position` attributes contain the number of the first (inclusive) and last (exclusive) deleted rows or columns.

The `table:position` attribute is usable with the following elements: `<table:deletion>` 9.9.9, `<table:insertion>` 9.9.3, `<table:insertion-cut-off>` 9.9.11 and `<table:movement-cut-off>` 9.9.12.

The `table:position` attribute has the data type `integer` 18.2.

19.692 table:precision-as-shown

The `table:precision-as-shown` attribute specifies whether to perform a calculation using the rounded values displayed in the spreadsheet or using all of the digits in a value.

The defined values for the `table:precision-as-shown` attribute are:

- `false`: calculations are performed using all of the digits in values, but the result is displayed as a rounded number.
- `true`: calculations are performed using the rounded values displayed in the spreadsheet.

The default value for this attribute is `false`.

The `table:precision-as-shown` attribute is usable with the following element: `<table:calculation-settings>` 9.4.1.

The `table:precision-as-shown` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.693 table:print

The `table:print` attribute specifies if a table will be printed. The `table:print` attribute value is overridden by the `table:display` attribute. If the table is not displayed, it will also not be printed.

If a table is printed, the table range printed can be specified by the `table:print-ranges` attribute. If there is no `table:print-ranges` attribute or it has no value specified, the non-empty portion of a table will be printed.

The defined values for the `table:print` attribute are:

- `false`: table can not be printed.
- `true`: table can be printed.

The default value for this attribute is `true`.

The `table:print` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:print` attribute has the data type `boolean` 18.3.3.

19.694 table:print-ranges

The `table:print-ranges` attribute specifies print ranges of a table. Print ranges define the cells that will be printed. It contains a list of cell addresses or cell range addresses.

The `table:print-ranges` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:print-ranges` attribute has the data type `cellRangeAddressList` 18.3.6.

19.695 table:protect

The `table:protect` attribute specifies whether a table cell is protected. Users can not edit the content of a cell that is marked as protected.

This attribute is deprecated in favor of the `table:protected` attribute.

The defined values for the `table:protect` attribute are:

- `false`: cell is not protected.
- `true`: cell is protected.

The default value for this attribute is `false`.

The `table:protect` attribute is usable with the following elements: `<table:covered-table-cell>` 9.1.5 and `<table:table-cell>` 9.1.4.

The `table:protect` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.696 table:protected

19.696.1 General

The `table:protected` attribute specifies protection for tables.

19.696.2 <table:covered-table-cell>

The `table:protected` attribute specifies whether a table cell is protected. Users can not edit the content of a cell that is marked as protected.

The defined values for the `table:protected` attribute are:

- `false`: cell is not protected.
- `true`: cell is protected.

For a `<table:covered-table-cell>` 9.1.5 element the default value for this attribute is `false`.

The `table:protected` attribute is usable with the following element: `<table:covered-table-cell>` 9.1.5.

The `table:protected` attribute has the data type `boolean` 18.3.3.

19.696.3 <table:scenario>

The `table:protected` attribute specifies specifies whether the data that is displayed within the scenario is protected from being edited. The attribute is only evaluated if the table on which the scenario displayed is also protected.

The defined values for the `table:protected` attribute are:

- `false`: data is not protected.
- `true`: data is protected.

The `table:protected` attribute is usable with the following element: `<table:scenario>` 9.2.7.

The `table:protected` attribute has the data type `boolean` 18.3.3.

19.696.4 <table:table>

The `table:protected` attribute specifies whether a table is protected from editing. If the table is protected, the `table:protection-key` attribute can specify an authorization requirement for resetting the protection to enable editing. 19.697 For a protected table, the protection of table cells may be controlled individually by the `style:cell-protect` attribute. 20.246 Table cells are protected only if they have a table cell style assigned whose `style:cell-protect` attribute value is different than `none`.

The defined values for the `table:protected` attribute are:

- `false`: table is not protected.
- `true`: table is protected.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:protected` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:protected` attribute has the data type `boolean` 18.3.3.

For a `<table:table>` 9.1.2 element the default value for this attribute is `false`.

19.696.5 <table:table-cell>

The `table:protected` attribute specifies whether a table cell is protected. Users can not edit the content of a cell that is marked as protected.

The defined values for the `table:protected` attribute are:

- `false`: cell is not protected.
- `true`: cell is protected.

For a `<table:table-cell>` 9.1.4 element the default value for this attribute is `false`.

The `table:protected` attribute is usable with the following element: `<table:table-cell>` 9.1.4.

The `table:protected` attribute has the data type `boolean` 18.3.3.

19.697 table:protection-key

The `table:protection-key` attribute, when present, specifies that an authorization is required for removing the protection of a table, table cell or scenario. The authentication procedure is identified by the `table:protection-key-digest-algorithm` attribute. 19.698 The attribute value is binary data that may be used by the authentication procedure.

The password shall be provided as a sequence of bytes in UTF-8 encoding.

The `table:protection-key` attribute is usable with the following elements: `<office:spreadsheet>` 3.7 and `<table:table>` 9.1.2.

The `table:protection-key` attribute has the data type `string` 18.2.

19.698 table:protection-key-digest-algorithm

The `table:protection-key-digest-algorithm` attribute value is an IRI that identifies an authentication procedure for removing a protection.

If the IRI identifies a message-digest algorithm specified in §5.7 of [xmlenc-core], the value of `table:protection-key` attribute shall be the hash value of the password that is required to authorize removal of the protection. The password shall be provided as a sequence of bytes in UTF-8 encoding.

Any other procedures, their identifying IRIs, and their application of `table:protection-key` values are implementation-defined.

Consumers shall support http://www.w3.org/2000/09/xmldsig#sha1, which is the default, and http://www.w3.org/2000/09/xmldsig#sha256. They may support other algorithms described in §5.7 of [xmlenc-core] or alternative procedures. Producers should use http://www.w3.org/2000/09/xmldsig#sha256.

The default value for this attribute is `http://www.w3.org/2000/09/xmldsig#sha1`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The table:protection-key-digest-algorithm attribute is usable with the following elements: <office:spreadsheet> 3.7 and <table:table> 9.1.2.

The table:protection-key-digest-algorithm attribute has the data type anyIRI 18.3.2.

19.699 table:query-name

A table:query-name attribute specifies a query to perform on a database whose data is being imported.

The table:query-name attribute is usable with the following element: <table:database-source-query> 9.4.18.

The table:query-name attribute has the data type string 18.2.

19.700 table:range-usable-as

The table:range-usable-as attribute specifies whether the name of the range can be used within the specification of a print range, a filter, a repeating row, or a repeat column.

The defined values for the table:range-usable-as attribute are:

- none
- a white space-separated list that consists of any of the values print-range, filter, repeat-row or repeat-column.

The default value for this attribute is none.

The table:range-usable-as attribute is usable with the following element: <table:named-range> 9.4.12.

The values of the table:range-usable-as attribute are none, or white space separated non-empty lists of one of these values: print-range, filter, repeat-row, or repeat-column..

19.701 table:refresh-delay

The table:refresh-delay attribute specifies a time delay between automatic refresh actions.

The table:refresh-delay attribute is usable with the following elements: <table:cell-range-source> 9.3.1, <table:database-range> 9.4.15 and <table:table-source> 9.2.6.

The table:refresh-delay attribute has the data type duration 18.2.

19.702 table:rejecting-change-id

The table:rejecting-change-id attribute specifies the id of a previously tracked change that has been rejected.

The table:rejecting-change-id attribute is usable with the following elements: <table:cell-content-change> 9.9.17, <table:deletion> 9.9.9, <table:insertion> 9.9.3 and <table:movement> 9.9.13.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:rejecting-change-id` attribute has the data type `string` 18.2.

19.703 table:rfc-language-tag

The `table:rfc-language-tag` attribute specifies a language identifier according to the rules of [RFC5646], or its successors.

It shall only be used if its value can not be expressed as a valid combination of the `table:language`, `table:script` and `table:country` attributes.

Producers may add support for consumers that don't support the `table:rfc-language-tag` attribute by specifying `table:language`, `table:script` and `table:country` attributes with values that are implementation-dependent.

The `table:rfc-language-tag` attribute augments the `table:language`, `table:script` and `table:country` attributes. It shall only be used if its value could not be expressed as a valid combination of those. The value shall be a language identifier according to the rules of [RFC5646], or its successors. If a fall-back is provided for consumers that do not support the `table:rfc-language-tag` attribute, producers should add `table:language`, `table:script` and `table:country` attributes whose values are as close as possible to the value of the `table:rfc-language-tag` attribute. Producers shall not use values for these attributes that contradict the value of the `table:rfc-language-tag` attribute.

The `table:rfc-language-tag` attribute is usable with the following element: `<table:sort>` 9.4.19.

The `table:rfc-language-tag` attribute has the data type `language` 18.3.16.

19.704 table:row

The `table:row` attribute specifies the row number of a cell.

The `table:row` attribute is usable with the following elements: `<table:cell-address>` 9.9.18, `<table:source-range-address>` 9.9.14 and `<table:target-range-address>` 9.9.15.

The `table:row` attribute has the data type `integer` 18.2.

19.705 table:scenario-ranges

The `table:scenario-ranges` attribute specifies the table range that is displayed as a scenario. The value of this attribute is a white space separated list of cell range addresses.

The `table:scenario-ranges` attribute is usable with the following element: `<table:scenario>` 9.2.7.

The `table:scenario-ranges` attribute has the data type `cellRangeAddressList` 18.3.6.

19.706 table:script

The `table:script` attribute specifies the script information for the natural language in which comparisons will occur. The attribute should be used only if necessary according to the rules of §2.2.3 of [RFC5646], or its successors.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:script` attribute is usable with the following element: `<table:sort>` 9.4.19.

The `table:script` attribute has the data type `scriptCode` 18.3.29.

19.707 table:search-criteria-must-apply-to-whole-cell

The `table:search-criteria-must-apply-to-whole-cell` attribute specifies whether a search pattern matches the entire content of a cell.

Note: The `table:search-criteria-must-apply-to-whole-cell` is used with the `<table:filter-condition>` element when the `table:data-type` attribute has the value `text` and the `table:operator` attribute has a value of: `match`, `!match`, `=`, or `!=`.

The defined values for the `table:search-criteria-must-apply-to-whole-cell` are:

- `false`: search pattern can match a substring at any position within a cell.
- `true`: search pattern must match entire content of a cell.

The default value for this attribute is `true`.

The `table:search-criteria-must-apply-to-whole-cell` attribute is usable with the following element: `<table:calculation-settings>` 9.4.1.

The `table:search-criteria-must-apply-to-whole-cell` attribute has the data type `boolean` 18.3.3.

19.708 table:selected-page

The `table:selected-page` attribute specifies which value is selected for an automatic filter.

The `table:selected-page` attribute is usable with the following element: `<table:data-pilot-field>` 9.6.7.

The `table:selected-page` attribute has the data type `string` 18.2.

19.709 table:show-details

The `table:show-details` attribute specifies whether additional fields are displayed for a member. This attribute changes the behavior of a data pilot only if there are multiple fields with the orientation row or column.

The defined values for the `table:show-details` attribute are:

- `false`: field with a row or column orientation that is not the last field with this orientation, no members are displayed for following fields with the same orientation. Data displayed for these fields is summarized using a function specified by the data pilot's function attribute.
- `true`: field with a row or column orientation that is not the last field with this orientation, members are displayed for following fields with the same orientation.

The `table:show-details` attribute is usable with the following element: `<table:data-pilot-member>` 9.6.12.

The `table:show-details` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.710 table:show-empty

The `table:show-empty` attribute specifies whether fields that do not have any members should be displayed. If this attribute is not present, it is implementation-defined whether fields without members are displayed.

The defined values for the `table:show-details` attribute are:

- `false`: fields without members are not displayed.
- `true`: fields without members are displayed.

The `table:show-empty` attribute is usable with the following element: `<table:data-pilot-level>` 9.6.8.

The `table:show-empty` attribute has the data type `boolean` 18.3.3.

19.711 table:show-filter-button

The `table:show-filter-button` attribute specifies whether a filter button is shown in the UI for a data pilot table. A filter button displays a user interface for a filter if pushed.

The defined values for the `table:show-filter-button` attribute are:

- `false`: filter button is not shown in UI.
- `true`: filter button is shown in UI.

The default value for this attribute is `true`.

The `table:show-filter-button` attribute is usable with the following element: `<table:data-pilot-table>` 9.6.3.

The `table:show-filter-button` attribute has the data type `boolean` 18.3.3.

19.712 table:sort-mode

The `table:sort-mode` attribute specifies how to sort the members of a single data pilot field.

The defined values for the `table:sort-mode` attribute are:

- `data`: fields are sorted by values in the data field specified by a `table:data-field` attribute.
- `manual`: fields are sorted by a user
- `name`: fields are sorted by name of the field
- `none`: fields are not sorted.

The `table:sort-mode` attribute is usable with the following element: `<table:data-pilot-sort-info>` 9.6.14.

The values of the `table:sort-mode` attribute are `data`, `none`, `manual` or `name`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.713 table:source-cell-range-addresses

The `table:source-cell-range-addresses` attribute specifies source cell ranges.

The `table:source-cell-range-addresses` attribute is usable with the following element: `<table:consolidation>` 9.7.

The `table:source-cell-range-addresses` attribute has the data type `cellRangeAddressList` 18.3.6.

19.714 table:source-field-name

The `table:source-field-name` attribute specifies the name or label of a column that connects to a field.

There can be multiple `<table:data-pilot-field>` elements with the same value for this attribute.

The `table:source-field-name` attribute is usable with the following elements: `<table:data-pilot-field>` 9.6.7 and `<table:data-pilot-groups>` 9.6.17.

The `table:source-field-name` attribute has the data type `string` 18.2.

19.715 table:source-name

The `table:source-name` attribute specifies a source name that is passed to the service implementation. Its value is implementation-dependent and service specific.

The `table:source-name` attribute is usable with the following element: `<table:source-service>` 9.6.6.

The `table:source-name` attribute has the data type `string` 18.2.

19.716 table:sql-statement

An `table:sql-statement` attribute specifies the SQL statement to use when importing data from an SQL database.

The `table:sql-statement` attribute is usable with the following element: `<table:database-source-sql>` 9.4.16.

The `table:sql-statement` attribute has the data type `string` 18.2.

19.717 table:start

The `table:start` attribute specifies the start value for a grouping of numeric values. All values that are lower than the start value are contained in a single group, while values that are equal to or higher than the start value are grouped as specified by the `table:grouped-by` and `table:step` attributes.

The defined values for the `table:start` attribute are:

- `auto`: the lowest value of the field is used as the start value.
- a value of type `double`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:start` attribute is usable with the following element: `<table:data-pilot-groups>` 9.6.17.

The values of the `table:start` attribute are a value of type `double` 18.2 or `auto`.

19.718 table:start-column

The `table:start-column` attribute specifies the start-column for a cell range address. The value of a `table:start-column` attribute is inclusive.

The `table:start-column` attribute is usable with the following elements: `<table:source-range-address>` 9.9.14 and `<table:target-range-address>` 9.9.15.

The `table:start-column` attribute has the data type `integer` 18.2.

19.719 table:start-position

The `table:start-position` attribute specifies the number of the first deleted row or column if multiple rows or columns are deleted. The value of a `table:start-position` attribute is inclusive.

The `table:start-position` attribute is usable with the following element: `<table:movement-cut-off>` 9.9.12.

The `table:start-position` attribute has the data type `integer` 18.2.

19.720 table:start-row

The `table:start-row` attribute specifies the start-row for a cell range address. The value of a `table:start-row` attribute is inclusive.

The `table:start-row` attribute is usable with the following elements: `<table:source-range-address>` 9.9.14 and `<table:target-range-address>` 9.9.15.

The `table:start-row` attribute has the data type `integer` 18.2.

19.721 table:start-table

The `table:start-table` attribute specifies the start-table for a cell range address. The value of a `table:start-table` attribute is inclusive.

The `table:start-table` attribute is usable with the following elements: `<table:source-range-address>` 9.9.14 and `<table:target-range-address>` 9.9.15.

The `table:start-table` attribute has the data type `integer` 18.2.

19.722 table:status

The `table:status` attribute specifies whether iterative calculations are enabled.

The defined values for the `table:status` attribute are:

- `enable`: iterative calculations will occur.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `disable`: iterative calculations will not occur.

The default value for this attribute is `disable`.

The `table:status` attribute is usable with the following element: `<table:iteration>` 9.4.3.

The values of the `table:status` attribute are `enable` or `disable`.

19.723 table:step

The `table:step` attribute specifies the grouping of numeric values, by specifying the distance between the groups.

The `table:step` attribute is usable with the following element: `<table:data-pilot-groups>` 9.6.17.

The `table:step` attribute has the data type `double` 18.2.

19.724 table:steps

The `table:steps` attributes specifies the maximum number of iterative calculations.

The default value for this attribute is `100`.

The `table:steps` attribute is usable with the following element: `<table:iteration>` 9.4.3.

The `table:steps` attribute has the data type `positiveInteger` 18.2.

19.725 table:structure-protected

The `table:structure-protected` attribute specifies whether a table is protected from the insertion, deletion, moving or renaming of tables in the document. If the table structure is protected and the `table:protection-key` attribute is present, an authorization is required for resetting the protection to enable editing.

The defined values for the `table:show-details` attribute are:

- `false`: table is not protected.
- `true`: table is protected.

The default value for this attribute is `false`.

The `table:structure-protected` attribute is usable with the following element: `<office:spreadsheet>` 3.7.

The `table:structure-protected` attribute has the data type `boolean` 18.3.3.

19.726 table:style-name

19.726.1 General

The `table:style-name` attribute specifies styles that are assigned to elements. The style can be either an automatic or common style.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.726.2 <table:background>

The `table:style-name` attribute specifies a `<style:style>` element for the table. The style specified by the `<style:style>` element is of the table family.

The `table:style-name` attribute is usable with the following element: `<table:background>` 16.20.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.3 <table:body>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-cell`.

The `table:style-name` attribute is usable with the following element: `<table:body>` 16.19.6.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.4 <table:covered-table-cell>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-cell`.

If a cell does not have a cell style assigned, then the `table:default-cell-style-name` attribute of the table row specifies the cell style. If that does not exist, the `table:default-cell-style-name` attribute of the table column specifies the cell style. If that does not exist, the default style with family `table-cell` specifies the style for the cell.

The `table:style-name` attribute is usable with the following element: `<table:covered-table-cell>` 9.1.5.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.5 <table:even-columns>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-cell`.

The `table:style-name` attribute is usable with the following element: `<table:even-columns>` 16.19.9.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.6 <table:even-rows>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-cell`.

The `table:style-name` attribute is usable with the following element: `<table:even-rows>` 16.19.7.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.7 <table:first-column>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-cell`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:style-name` attribute is usable with the following element: `<table:first-column>` 16.19.4.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.8 <table:first-row>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-cell`.

The `table:style-name` attribute is usable with the following element: `<table:first-row>` 16.19.2.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.9 <table:last-column>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-cell`.

The `table:style-name` attribute is usable with the following element: `<table:last-column>` 16.19.5.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.10 <table:last-row>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-cell`.

The `table:style-name` attribute is usable with the following element: `<table:last-row>` 16.19.3.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.11 <table:odd-columns>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-cell`.

The `table:style-name` attribute is usable with the following element: `<table:odd-columns>` 16.19.10.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.12 <table:odd-rows>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-cell`.

The `table:style-name` attribute is usable with the following element: `<table:odd-rows>` 16.19.8.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.13 <table:table-cell>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-cell`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If a cell does not have a cell style assigned, then the `table:default-cell-style-name` attribute of the table row specifies the cell style. If that does not exist, the `table:default-cell-style-name` attribute of the table column specifies the cell style. If that does not exist, the default style with family table-cell specifies the style for the cell.

The `table:style-name` attribute is usable with the following element: `<table:table-cell>` 9.1.4.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.14 <table:table-column>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-column`.

The `table:style-name` attribute is usable with the following element: `<table:table-column>` 9.1.6.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.15 <table:table-row>

The `table:style-name` attribute specifies a `<style:style>` element of type `table-row`.

The `table:style-name` attribute is usable with the following element: `<table:table-row>` 9.1.3.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.726.16 <table:table>

The `table:style-name` attribute specifies a `<style:style>` element of type `table`.

The `table:style-name` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.727 table:table

The `table:table` attribute specifies a table number for insertions, deletions and for table cells.

The `table:table` attribute is usable with the following elements: `<table:cell-address>` 9.9.18, `<table:deletion>` 9.9.9, `<table:insertion>` 9.9.3, `<table:source-range-address>` 9.9.14 and `<table:target-range-address>` 9.9.15.

The `table:table` attribute has the data type `integer` 18.2.

19.728 table:table-background

The `table:table-background` attribute specifies whether a shape is in the table background if the drawing shape is included in a spreadsheet document.

The defined values for the `table:show-details` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `false`: shape is included in foreground of a table.
- `true`: shape is included in background of a table.

The `table:table-background` attribute is usable with the following elements: `<dr3d:scene>` 10.5.2, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:connector>` 10.3.10, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:g>` 10.3.15, `<draw:line>` 10.3.3, `<draw:measure>` 10.3.12, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2, `<draw:regular-polygon>` 10.3.6 and `<office:annotation>` 14.1.

The `table:table-background` attribute has the data type `boolean` 18.3.3.

19.729 table:table-name

The `table:table-name` attribute specifies the name of the table in the source document to which the current table is linked. If the attribute is omitted, the current table is linked to the first table in the source document.

The `table:table-name` attribute is usable with the following element: `<table:table-source>` 9.2.6.

The `table:table-name` attribute has the data type `string` 18.2.

19.730 table:target-cell-address

The `table:target-cell-address` attribute specifies a target cell address.

The `table:target-cell-address` attribute is usable with the following element: `<table:consolidation>` 9.7.

The `table:target-cell-address` attribute has the data type `cellAddress` 18.3.4.

19.731 table:target-range-address

19.731.1 General

The `table:target-range-address` attribute specifies a cell range address. The value of this attribute shall be an absolute cell address that contains a table name. The dollar signs “$” (U+0024, DOLLAR SIGN) that indicate an absolute address may be omitted.

19.731.2 <table:data-pilot-table>

The `table:target-range-address` attribute specifies the cell range where a data pilot table will be displayed.

The `table:target-range-address` attribute is usable with the following element: `<table:data-pilot-table>` 9.6.3.

The `table:target-range-address` attribute has the data type `cellRangeAddress` 18.3.5.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.731.3 <table:database-range>

The `table:target-range-address` attribute specifies the cell range address of a database range.

The `table:target-range-address` attribute is usable with the following element: `<table:database-range>` 9.4.15.

The `table:target-range-address` attribute has the data type `cellRangeAddress` 18.3.5.

19.731.4 <table:filter>

The `table:target-range-address` attribute specifies the cell range for the result of a filter operation, but all table rows remain visible. If the attribute is not present, the rows that do not match the filter conditions are not displayed.

The `table:target-range-address` attribute is usable with the following element: `<table:filter>` 9.5.2.

The `table:target-range-address` attribute has the data type `cellRangeAddress` 18.3.5.

19.731.5 <table:sort>

The `table:target-range-address` attribute specifies the cell range for the result of a sort operation. If the attribute is not present, the cell range for the result is identical to the cell range of the database range.

The `table:target-range-address` attribute is usable with the following element: `<table:sort>` 9.4.19.

The `table:target-range-address` attribute has the data type `cellRangeAddress` 18.3.5.

19.732 table:template-name

The `table:template-name` attribute specifies a table template by name.

The `table:template-name` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:template-name` attribute has the data type `string` 18.2.

19.733 table:title

The `table:title` attribute that specifies a title of a help or error message.

The `table:title` attribute is usable with the following elements: `<table:error-message>` 9.4.7 and `<table:help-message>` 9.4.6.

The `table:title` attribute has the data type `string` 18.2.

19.734 table:track-changes

The `table:track-changes` attribute specifies whether change tracking is enabled.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the table:track-changes attribute are:

- false: changes are not tracked.
- true: changes are tracked.

The default value for this attribute is false.

The table:track-changes attribute is usable with the following element: <table:tracked-changes> 9.9.2.

The table:track-changes attribute has the data type boolean 18.3.3.

19.735 table:type

19.735.1 General

The table:type attribute specifies a type for a table.

19.735.2 <table:data-pilot-field-reference>

The table:type attribute specifies the processing of a referenced category column for display.

The defined values for the table:type attribute are:

- column-percentage: Same as row-percentage, but the total for the result's column is used.
- index: The row and column totals and the grand total are calculated as described for row-percentage, and then are used to calculate the following expression: (original result * grand total) / (row total * column total). Division by zero results in an error.
- member-difference: From each result, the value calculated for the category column member specified by the table:member-type and table:member-name attributes is subtracted.
- member-percentage: Each result is divided by the value calculated for the category column member specified by the table:member-type and table:member-name attributes. Division by zero results in an error. Empty results are shown as “0”. If the table:member-type attribute has the value previous, “1” is displayed as first value. If the table:member-type attribute has the value next, “1” is displayed as last value.
- member-percentage-difference: From each result, the value calculated for the category column member specified by the table:member-type and table:member-name attributes is subtracted, and the result is divided by this value again. Division by zero results in an error. Otherwise, the rules for member-difference apply.
- none: This value means that the results in the data fields are displayed unmodified.
- row-percentage: Each result is divided by the total result for its row in the data pilot table. If there are multiple data fields, the total for the result's data field is used. If there are subtotals with manually selected summary functions, the total is calculated with the data field's summary function. Division by zero results in an error.
- running-total: Each result is added to the sum of the results for preceding members in the referenced category column, in the reference field's sort order, and the total sum is shown.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `total-percentage`: Same as `row-percentage`, but the grand total for the result's data field is used.

The `table:type` attribute is usable with the following element: `<table:data-pilot-field-reference>` 9.6.16.

The values of the `table:type` attribute are `none`, `member-difference`, `member-percentage`, `member-percentage-difference`, `running-total`, `row-percentage`, `column-percentage`, `total-percentage` or `index`.

19.735.3 <table:deletion>

The `table:type` attribute specifies the type of a deletion.

The defined values for the `table:type` attribute are:

- `column`: column deleted.
- `row`: row deleted.
- `table`: table deleted.

The `table:type` attribute is usable with the following element: `<table:deletion>` 9.9.9.

The values of the `table:type` attribute are `row`, `column` or `table`.

19.735.4 <table:insertion>

The `table:type` attribute specifies the type of an insertion.

The defined values for the `table:type` attribute are:

- `column`: column inserted.
- `row`: row inserted.
- `table`: table inserted.

The `table:type` attribute is usable with the following element: `<table:insertion>` 9.9.3.

The values of the `table:type` attribute are `row`, `column` or `table`.

19.736 table:use-banding-columns-styles

The `table:use-banding-columns-styles` attribute specifies if the styles referenced by the `<table:even-columns>` and `<table:odd-columns>` elements of a table template referenced by the `table:template-name` attribute are used for cells that are contained in even and odd columns.

The defined values for the `table:use-banding-columns-styles` attribute are:

- `false`: cells are not styled based on even or odd column location.
- `true`: cells are styled based on even or odd column location.

The default value for this attribute is `false`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:use-banding-columns-styles` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:use-banding-columns-styles` attribute has the data type `boolean` 18.3.3.

19.737 table:use-banding-rows-styles

The `table:use-banding-rows-styles` attribute specifies if the styles referenced by the `<table:even-rows>` and `<table:odd-rows>` elements of a table template referenced by the table:template-name attribute are used for cells that are contained in even and odd rows.

The defined values for the `table:use-banding-rows-styles` attribute are:

- `false`: cells not styled based on even or odd row location.
- `true`: cells styled based on even or odd row location.

The default value for this attribute is `false`.

The `table:use-banding-rows-styles` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:use-banding-rows-styles` attribute has the data type `boolean` 18.3.3.

19.738 table:use-first-column-styles

The `table:use-first-column-styles` attribute specifies if the styles referenced by the `<table:first-column>` element of the table template referenced by the `table:template-name` attribute are used for cells that are contained in the table's first column.

The defined values for the `table:use-first-column-styles` attribute are:

- `false`: cells not styled based on first column location.
- `true`: cells styled based on first column location.

The default value for this attribute is `false`.

The `table:use-first-column-styles` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:use-first-column-styles` attribute has the data type `boolean` 18.3.3.

19.739 table:use-first-row-styles

The `table:use-first-row-styles` attribute specifies if the styles referenced by the `<table:first-row>` element of the table template referenced by the `table:template-name` attribute are used for cells that are contained in the table's first row.

The defined values for the `table:use-first-row-styles` attribute are:

- `false`: cells not styled based on first row location.
- `true`: cells styled based on first row location.

The default value for this attribute is `false`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:use-first-row-styles` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:use-first-row-styles` attribute has the data type `boolean` 18.3.3.

19.740 table:use-last-column-styles

The `table:use-last-column-styles` attribute specifies if the styles referenced by the `<table:last-column>` element of the table template referenced by the `table:template-name` attribute are used for cells that are contained in the table's last column.

The defined values for the `table:use-last-column-styles` attribute are:

- `false`: cells not styled based on last column location.
- `true`: cells styled based on last column location.

The default value for this attribute is `false`.

The `table:use-last-column-styles` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:use-last-column-styles` attribute has the data type `boolean` 18.3.3.

19.741 table:use-last-row-styles

The `table:use-last-row-styles` attribute specifies if the styles referenced by the `<table:last-row>` element of the table template referenced by the `table:template-name` attribute are used for cells that are contained in the table's last row.

The defined values for the `table:use-last-row-styles` attribute are:

- `false`: cells not styled based on last row location.
- `true`: cells styled based on last row location.

The default value for this attribute is `false`.

The `table:use-last-row-styles` attribute is usable with the following element: `<table:table>` 9.1.2.

The `table:use-last-row-styles` attribute has the data type `boolean` 18.3.3.

19.742 table:use-labels

The `table:use-labels` attribute specifies whether labels should be used by the consolidation for rows, columns or both. If labels are used for rows or columns, mathematical functions are applied to cells with equally labeled rows or columns rather than to cells with the same relative cell address.

The defined values for the `table:type` attribute are:

- `both`: column and row labels used for consolidation.
- `column`: column labels used for consolidation.
- `none`: labels not used for consolidation.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `row`: row labels used for consolidation.

The default value for this attribute is `none`.

The `table:use-labels` attribute is usable with the following element: `<table:consolidation>` 9.7.

The values of the `table:use-labels` attribute are `none`, `row`, `column` or `both`.

19.743 table:use-regular-expressions

The `table:use-regular-expressions` attribute specifies whether regular expressions are enabled for character string comparisons and when searching.

Regular expressions are implementation-dependent expressions that, at a minimum, conform to the requirements of Conformance Clause C1 of [UTR18].

The defined values for the `table:use-regular-expressions` attribute are:

- `false`: regular expressions not enabled for string comparisons and searches.
- `true`: regular expressions enabled for string comparisons and searches.

The default value for this attribute is `true`.

The `table:use-regular-expressions` attribute is usable with the following element: `<table:calculation-settings>` 9.4.1.

The `table:use-regular-expressions` attribute has the data type `boolean` 18.3.3.

19.744 table:use-wildcards

The `table:use-wildcards` attribute specifies whether wildcards are enabled for character string comparisons and when searching.

If enabled, in a query or search string of a function, the “?” (U+003F, QUESTION MARK), “`*`" (U+002A, ASTERISK), and “`~`" (U+007E, TILDE) are defined as:

- "`?`" (U+003F, QUESTION MARK): matches any single character;
- "`*`" (U+002A, ASTERISK): matches any sequence of characters, including an empty string;
- "`~`" (U+007E, TILDE): escapes the special meaning of a QUESTION MARK, ASTERISK or TILDE character that follows immediately after the TILDE character.

The `table:use-regular-expressions` attribute and the `table:use-wildcards` attribute are mutually exclusive. The attribute values cannot be `true` for both attributes.

The defined values for the `table:use-wildcards` attribute are:

- `false`: wildcards are not enabled for character string comparisons and searching.
- `true`: wildcards are enabled for character string comparisons and searching.

The default value for this attribute is `false`.

The `table:use-wildcards` attribute is usable with the following element: `<table:calculation-settings>` 9.4.1.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `table:use-wildcards` attribute has the data type `boolean` 18.3.3.

19.745 table:used-hierarchy

The `table:used-hierarchy` attribute specifies a unique number assigned by an external component to select the hierarchy that should be applied to a source field.

If the data pilot source is provided by an external component or service, the data contained within category columns may be grouped by its value and it may be further divided into sub-groups or hierarchies. If an external component supports hierarchies, it shall assign unique numbers to those hierarchies.

The default value -1 means that no hierarchy should be applied to a source field.

The default value for this attribute is `-1`.

The `table:used-hierarchy` attribute is usable with the following element: `<table:data-pilot-field>` 9.6.7.

The `table:used-hierarchy` attribute has the data type `integer` 18.2.

19.746 table:user-name

The `table:user-name` attribute specifies the user name needed to access a source. It is passed to a service implementation. Its value is implementation-dependent and service specific.

The `table:user-name` attribute is usable with the following element: `<table:source-service>` 9.6.6.

The `table:user-name` attribute has the data type `string` 18.2.

19.747 table:value

19.747.1 <table:filter-condition>

The `table:value` attribute specifies a value for the filter condition.

The `table:value` attribute is usable with the following element: `<table:filter-condition>` 9.5.5.

The values of the `table:value` attribute are a value of type `string` 18.2 or a value of type `double` 18.2.

19.747.2 <table:filter-set-item>

The `table:value` attribute specifies a single value within a set of filter values.

The `table:value` attribute is usable with the following element: `<table:filter-set-item>` 9.5.6.

The `table:value` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.748 table:value-type

The `table:value-type` attribute specifies the value type of a null date.

The default value for this attribute is `date`.

The `table:value-type` attribute is usable with the following element: `<table:null-date>` 9.4.2.

The only value of the `table:value-type` attribute is `date`.

19.749 table:visibility

The `table:visibility` attribute specifies whether a row or column is visible.,

The defined values for the `table:visibility` attribute are:

- `collapse`: a row or column is not visible.
- `filter`: a row or column is not visible as the result of applying a filter.
- `visible`: a row or column is visible.

The default value for this attribute is `visible`.

The `table:visibility` attribute is usable with the following elements: `<table:table-column>` 9.1.6 and `<table:table-row>` 9.1.3.

The values of the `table:visibility` attribute are `visible`, `collapse` or `filter`.

19.750 text:active

The `text:active` attribute specifies the setting of the page variable.

The value of an active page variable is increased on each page.

An inactive page variable is not incremented between pages.

The defined values for the `text:active` attribute are:

- `false`: page variable is turned off.
- `true`: page variable is turned on.

The default value for this attribute is false.

The `text:active` attribute is usable with the following element: `<text:page-variable-set>` 7.7.1.2.

The `text:active` attribute has the data type `boolean` 18.3.3.

19.751 text:address

The `text:address` attribute specifies the address for a bibliography index entry.

The `text:address` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The text:address attribute has the data type string 18.2.

19.752 text:alphabetical-separators

The text:alphabetical-separators attribute specifies whether entries beginning with the same letter are grouped and separated from the entries beginning with the next letter.

The defined values for the text:alphabetical-separators attribute are:

- false: entries beginning with the same letter are not grouped together and separated from entries beginning with the next letter.
- true: entries beginning with the same letter are grouped together and separated from entries beginning with the next letter.

The default value for this attribute is false.

The text:alphabetical-separators attribute is usable with the following element: <text:alphabetical-index-source> 8.8.2.

The text:alphabetical-separators attribute has the data type boolean 18.3.3.

19.753 text:anchor-page-number

The text:anchor-page-number attribute specifies the physical page number of an anchor if the drawing object is bound to a page within a text document.

The text:anchor-page-number attribute is usable with the following elements: <dr3d:scene> 10.5.2, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6 and <office:annotation> 14.1.

The text:anchor-page-number attribute has the data type positiveInteger 18.2.

19.754 text:anchor-type

The text:anchor-type attribute specifies how a frame is bound to a text document. The anchor position is the point at which a frame is bound to a text document. The defined values for the text:anchor-type attribute are shown in Table 15.

Table 15 - Text anchor positions

If the value of the text:anchor-type attribute is ...	***The anchor position is...***	***The drawing shape element appears ...***	***Notes***
as-char	There is no anchor position. The drawing shape behaves like a character.	At the position where the character appears in the document.	

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If the value of the `text:anchor-type` attribute is ...	*The anchor position is...*	*The drawing shape element appears ...*	*Notes*
`char`	The character after the drawing shape element.	Just before the character.	
`frame`	The parent text box that the current drawing shape element is contained in.	In the element representing the text box to which the drawing object is bound. If an image is bound to a text box, the image element is located in the text box element.	
`page`	The page that has the same physical page number as the value of the `text:anchor-page-number` attribute that is attached to the drawing shape element. If no `text:anchor-page-number` attribute is given, the anchor position is the page at which the character behind the drawing object element appears.	Either ● At the start of the document body, outside any paragraph or frame, provided a `text:anchor-page-number` attribute is given. Or ● Inside any paragraph element that is not contained in a header, footer, footnote, or text box, if a `text:anchor-page-number` attribute is not given.	The physical page number is the number assigned to the page if all pages in the document are counted starting with page 1.
`paragraph`	The paragraph that the current drawing shape element is contained in.	At the start of the paragraph element.	

The `text:anchor-type` attribute is usable with the following elements: `<dr3d:scene>` 10.5.2, `<draw:caption>` 10.3.11, `<draw:circle>` 10.3.8, `<draw:connector>` 10.3.10, `<draw:control>` 10.3.13, `<draw:custom-shape>` 10.6.1, `<draw:ellipse>` 10.3.9, `<draw:frame>` 10.4.2, `<draw:g>` 10.3.15, `<draw:line>` 10.3.3, `<draw:measure>` 10.3.12, `<draw:page-thumbnail>` 10.3.14, `<draw:path>` 10.3.7, `<draw:polygon>` 10.3.5, `<draw:polyline>` 10.3.4, `<draw:rect>` 10.3.2, `<draw:regular-polygon>` 10.3.6 and `<office:annotation>` 14.1.

The values of the `text:anchor-type` attribute are `page`, `frame`, `paragraph`, `char` or `as-char`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.755 text:annote

The `text:annote` attribute specifies the annotation for a bibliography index entry.

The `text:annote` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:annote` attribute has the data type `string` 18.2.

19.756 text:author

The `text:author` attribute specifies the author or authors for a bibliography index entry.

The `text:author` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:author` attribute has the data type `string` 18.2.

19.757 text:bibliography-data-field

The `text:bibliography-data-field` attribute specifies which part of a bibliography data field will be displayed.

The defined values for the `text:bibliography-data-field` attribute are:

- `address`: 19.751.
- `annote`: 19.755.
- `author`: 19.756.
- `bibliography-type`: 19.758.
- `booktitle`: 19.759.
- `chapter`: 19.767.
- `custom1`: 19.786.
- `custom2`: 19.787.
- `custom3`: 19.788.
- `custom4`: 19.789.
- `custom5`: 19.790.
- `edition`: 19.800.
- `editor`: 19.801.
- `howpublished`: 19.807.
- `identifier`: 19.810.
- `institution`: 19.814.
- `isbn`: 19.817.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `issn`: 19.818.
- `journal`: 19.819.
- `month`: 19.834.
- `note`: 19.836.
- `number`: 19.838.
- `organizations`: 19.843.
- `pages`: 19.846.
- `publisher`: 19.852.
- `report-type`: 19.856.
- `school`: 19.860.
- `series`: 19.862.
- `title`: 19.882.
- `url`: 19.884.
- `volume`: 19.902.
- `year`: 19.903.

The `text:bibliography-data-field` attribute is usable with the following element: `<text:index-entry-bibliography>` 8.13.5.

The values of the `text:bibliography-data-field` attribute are `address`, `annote`, `author`, `bibliography-type`, `booktitle`, `chapter`, `custom1`, `custom2`, `custom3`, `custom4`, `custom5`, `edition`, `editor`, `howpublished`, `identifier`, `institution`, `isbn`, `issn`, `journal`, `month`, `note`, `number`, `organizations`, `pages`, `publisher`, `report-type`, `school`, `series`, `title`, `url`, `volume` or `year`.

19.758 text:bibliography-type

The `text:bibliography-type` attribute specifies to which type of bibliographical entry a template applies.

The defined values for the `text:bibliography-type` attribute are:

- `article`: an article in a journal or magazine.
- `book`: a book with a named publisher.
- `booklet`: a work that is printed and bound, but without a named publisher or sponsoring institution.
- `conference`: an article in conference proceedings.
- `custom1`: the first of five user defined fields for a bibliographic entry.
- `custom2`: the second of five user defined fields for a bibliographic entry.
- `custom3`: the third of five user defined fields for a bibliographic entry.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `custom4`: the fourth of five user defined fields for a bibliographic entry.
- `custom5`: the fifth of five user defined fields for a bibliographic entry.
- `email`: email address.
- `inbook`: a part of a book that can be identified.
- `incollection`: a part of a book that has its own title.
- `inproceedings`: a paper in conference proceedings.
- `journal`: a journal name.
- `manual`: technical documentation.
- `mastersthesis`: a masters thesis.
- `misc`: a type classification when more specific values are not appropriate.
- `phdthesis`: a PhD thesis.
- `proceedings`: the proceedings of a conference.
- `techreport`: a report published by a school or other institution.
- `unpublished`: a document with an author and title but not formally published.
- `www`: the IRI for a document.

Note: The definitions for article, book, booklet, inbook, incollection, in proceedings, journal, manual, mastersthesis, misc, phdthesis, proceedings, techreport, and unpublished are based on [BibTeXing].

The `text:bibliography-type` attribute is usable with the following elements: `<text:bibliography-entry-template>` 8.9.3 and `<text:bibliography-mark>` 8.1.11.

The values of the `text:bibliography-type` attribute are `article`, `book`, `booklet`, `conference`, `custom1`, `custom2`, `custom3`, `custom4`, `custom5`, `email`, `inbook`, `incollection`, `inproceedings`, `journal`, `manual`, `mastersthesis`, `misc`, `phdthesis`, `proceedings`, `techreport`, `unpublished` or `www`.

19.759 text:booktitle

The `text:booktitle` attribute specifies the book title for a bibliography index entry.

The `text:booktitle` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:booktitle` attribute has the data type `string` 18.2.

19.760 text:bullet-char

The `text:bullet-char` attribute specifies the [UNICODE] character to use as the bullet in a bullet level style.

The defined values for the `text:bullet-char` attribute are shown in Table 16:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Table 16 - Typical bullet characters

UNICODE Character Code	*Typical Shape*	*UNICODE Character Name*
U+2022	•	BULLET
U+25CF	●	BLACK CIRCLE
U+2714	✔	HEAVY CHECK MARK
U+2717	✗	BALLOT X
U+2794	➔	HEAVY WIDE-HEADED RIGHTWARDS ARROW
U+27A2	➢	THREE-D TOP-LIGHTED RIGHTWARDS ARROWHEAD

Note: These characters need not be available in all fonts.

The `text:bullet-char` attribute is usable with the following element: `<text:list-level-style-bullet>` 16.31.

The `text:bullet-char` attribute has the data type `character` 18.3.7.

19.761 text:bullet-relative-size

The `text:bullet-relative-size` attribute specifies a percentage value for the bullet size relative to the font size of the paragraphs in the bullet list.

The `text:bullet-relative-size` attribute is usable with the following element: `<text:list-level-style-bullet>` 16.31.

The `text:bullet-relative-size` attribute has the data type `percent` 18.3.23.

19.762 text:capitalize-entries

The `text:capitalize-entries` attribute specifies whether the entries in an index are capitalized.

The defined values for the `text:capitalize-entries` attribute are:

- `false`: the case of entries in an index should not change.
- `true`: the entries in an index should be capitalized.

The `text:capitalize-entries` attribute controls capitalization of index entries during the generation of indexes. Index entries may be entered in either upper or lower case, without regard to the `text:capitalize-entries` attribute.

The default value for this attribute is `false`.

The `text:capitalize-entries` attribute is usable with the following element: `<text:alphabetical-index-source>` 8.8.2.

The `text:capitalize-entries` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.763 text:c

The `text:c` attribute specifies the number of " " (U+0020, SPACE) characters that a `<text:s>` element represents. A missing `text:c` attribute is interpreted as a single " " (U+0020, SPACE) character.

The `text:c` attribute is usable with the following element: `<text:s>` 6.1.3.

The `text:c` attribute has the data type `nonNegativeInteger` 18.2.

19.764 text:caption-sequence-format

The `text:caption-sequence-format` attribute specifies the format of entries for an index of illustrations obtained from image captions.

The defined values for the `text:caption-sequence-format` attribute are:

- `caption`: text of the caption in which the referenced sequence field is included (without sequence number and value).
- `category-and-value`: displays the name and value of the referenced sequence field.
- `text`: displays the value of the referenced sequence field.

The `text:caption-sequence-format` attribute is usable with the following elements: `<text:illustration-index-source>` 8.4.2 and `<text:table-index-source>` 8.5.2.

The values of the `text:caption-sequence-format` attribute are `text`, `category-and-value` or `caption`.

19.765 text:caption-sequence-name

The `text:caption-sequence-name` attribute specifies the sequence by which captions are identified.

If the `text:use-caption` attribute is set to `true`, this attribute shall be present.

Note: Illustration captions are regular paragraphs. For index generation, a paragraph is considered to be a caption if it contains the sequence variable with the name specified by the `text:caption-sequence-name` attribute.

The `text:caption-sequence-name` attribute is usable with the following elements: `<text:illustration-index-source>` 8.4.2 and `<text:table-index-source>` 8.5.2.

The `text:caption-sequence-name` attribute has the data type `string` 18.2.

19.766 text:change-id

The `text:change-id` attribute specifies the id that links `<text:change-start>`, `<text:change-end>`, and `<text:change>` elements to the `<text:changed-region>` element that contains change information.

The `text:change-id` attribute is usable with the following elements: `<text:change>` 5.5.7.4, `<text:change-end>` 5.5.7.3 and `<text:change-start>` 5.5.7.2.

The `text:change-id` attribute has the data type `IDREF` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.767 text:chapter

The `text:chapter` attribute specifies the chapter reference for a bibliography index entry.

The `text:chapter` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:chapter` attribute has the data type `string` 18.2.

19.768 text:citation-body-style-name

The `text:citation-body-style-name` attribute specifies the text style to use for a note citation in the text flow.

The `text:citation-body-style-name` attribute is usable with the following element: `<text:notes-configuration>` 16.29.3.

The `text:citation-body-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.769 text:citation-style-name

The `text:citation-style-name` attribute specifies the text style to use for a note citation within the footnote.

The `text:citation-style-name` attribute is usable with the following element: `<text:notes-configuration>` 16.29.3.

The `text:citation-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.770 text:class-names

19.770.1 General

A `text:class-names` attribute specifies a white space separated list of style names. The referenced styles are applied in the order they are contained in the list.

If both `text:style-name` and `text:class-names` are present, the style referenced by the `text:style-name` attribute is applied before the styles referenced by `text:class-names` attribute. If a conditional style is specified together with a `text:class-names` attribute, but without a `text:style-name` attribute, the text:style-name attribute is assumed to have the value of the first style name in the list defined by the text:class-name attribute.

19.770.2 <text:h>

A `text:class-names` attribute specifies a white space separated list of `paragraph` style names.

The `text:class-names` attribute is usable with the following element: `<text:h>` 5.1.2.

The `text:class-names` attribute has the data type `styleNameRefs` 18.3.33.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.770.3 <text:p>

A `text:class-names` attribute specifies a white space separated list of `paragraph` style names.

The `text:class-names` attribute is usable with the following element: `<text:p>` 5.1.3.

The `text:class-names` attribute has the data type `styleNameRefs` 18.3.33.

19.770.4 <text:span>

A `text:class-names` attribute specifies a white space separated list of text style names.

The `text:class-names` attribute is usable with the following element: `<text:span>` 6.1.7.

The `text:class-names` attribute has the data type `styleNameRefs` 18.3.33.

19.771 text:column-name

The `text:column-name` attribute specifies the name of the column from which data is displayed. The value of this attribute shall be a column name contained in the current selection as specified by the data source.

The `text:column-name` attribute is usable with the following element: `<text:database-display>` 7.6.3.

The `text:column-name` attribute has the data type `string` 18.2.

19.772 text:combine-entries

The `text:combine-entries` attribute specifies whether multiple entries for a single word should be combined into a single entry.

The defined values for the `text:combine-entries` attribute are:

- `false`: multiple entries for a single word should not be combined into a single entry.
- `true`: multiple entries for a single word should be combined into a single entry.

The default value for this attribute is `true`.

The `text:combine-entries` attribute is usable with the following element: `<text:alphabetical-index-source>` 8.8.2.

The `text:combine-entries` attribute has the data type `boolean` 18.3.3.

19.773 text:combine-entries-with-dash

The `text:combine-entries-with-dash` attributes specifies that multiple entries for a single word that should be displayed as a single entry, as per a `text:combine-entries` attribute, should be displayed as a range of numbers separated by a dash.

The defined values for the `text:combine-entries-with-dash` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `false`: multiple entries for a single word should not be displayed as a range of numbers separated by a dash.
- `true`: multiple entries for a single word should be displayed as a range of numbers separated by a dash.

The default value for this attribute is `false`.

The `text:combine-entries-with-dash` attribute is usable with the following element: `<text:alphabetical-index-source>` 8.8.2.

The `text:combine-entries-with-dash` attribute has the data type `boolean` 18.3.3.

19.774 text:combine-entries-with-pp

The `text:combine-entries-with-pp` attributes specifies that multiple entries for a single word that should be displayed as a single entry, as per a `text:combine-entries` attribute, should be displayed as the start page number, followed by a "`ff`", or the appropriate label for the chosen language.

- `false`: multiple entries for a single word are should not be displayed as the start page number, followed by a "`ff`", or the appropriate label for the chosen language.
- `true`: multiple entries for a single word are should be displayed as the start page number, followed by a "`ff`", or the appropriate label for the chosen language.

The default value for this attribute is `true`.

The `text:combine-entries-with-pp` attribute is usable with the following element: `<text:alphabetical-index-source>` 8.8.2.

The `text:combine-entries-with-pp` attribute has the data type `boolean` 18.3.3.

19.775 text:comma-separated

The `text:comma-separated` attribute specifies how to treat multiple index entries. Instead of listing each index entry on a separate line, multiple entries can be listed on a single line separated by a comma “,” (U+002C, COMMA). If the value of this attribute is `true`, multiple entries are listed on a single line separated by a comma. By default, the value of this attribute is `false` and each index entry is displayed on a separate line.

The defined values for the `text:comma-separated` attribute are:

- `false`: each index entry for a word is displayed on a separate line.
- `true`: each index entry for a word is listed on a single line separated by a comma “,” (U+002C, COMMA).

The default value for this attribute is `false`.

The `text:comma-separated` attribute is usable with the following element: `<text:alphabetical-index-source>` 8.8.2.

The `text:comma-separated` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.776 text:cond-style-name

The `text:cond-style-name` attribute specifies a conditional-style, that is, a style that contains conditions and maps to other styles. The styles referenced shall be a paragraph style. 16.3

If a conditional style is applied to a paragraph, the `text:style-name` attribute should contain the name of the style that was the result of the conditional style evaluation, while the conditional style name itself is the value of the `text:cond-style-name` attribute. The referenced style can be a common style or an automatic style.

The `text:cond-style-name` attribute is usable with the following elements: `<text:h>` 5.1.2 and `<text:p>` 5.1.3.

The `text:cond-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.777 text:condition

19.777.1 General

The `text:condition` attribute specifies a condition. Conditions do not have a predefined syntax, but the attribute value should begin with a namespace prefix, followed by a ":" (U+003A, COLON) separator, followed by the text of a formula. The namespace bound to the prefix determines the syntax and semantics of the formula.

19.777.2 <text:conditional-text>

The `text:condition` attribute specifies the condition that determines which of the two text strings of an `<text:conditional-text>` text field is displayed.

The `text:condition` attribute is usable with the following element: `<text:conditional-text>` 7.7.3.

The `text:condition` attribute has the data type `string` 18.2.

19.777.3 <text:database-next>

The `text:condition` attribute specifies a condition expression. The expression is evaluated and if the result interpreted as a Boolean value is true, the next row is used as the new current row.

If the `<text:database-next>` element has no text:condition attribute, the next available row is selected.

The `text:condition` attribute is usable with the following element: `<text:database-next>` 7.6.4.

The `text:condition` attribute has the data type `string` 18.2.

19.777.4 <text:database-row-select>

The `text:condition` attribute specifies a condition for selecting a row. If the attribute is present, a new row will be selected only if the condition evaluates to a value interpreted as true.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If a <text:database-row-select> element has no text:condition attribute, the next row is selected.

The text:condition attribute is usable with the following element: <text:database-row-select> 7.6.5.

The text:condition attribute has the data type string 18.2.

19.777.5 <text:hidden-paragraph>

The text:condition attribute specifies a Boolean expression. If the expression evaluates to true, the paragraph is hidden. If the expression evaluates to false, the paragraph is displayed.

The text:condition attribute is usable with the following element: <text:hidden-paragraph> 7.7.11.

The text:condition attribute has the data type string 18.2.

19.777.6 <text:hidden-text>

The text:condition attribute specifies a Boolean expression. If the expression evaluates to true, the text is hidden. If the expression evaluates to false, the text is displayed.

The text:condition attribute is usable with the following element: <text:hidden-text> 7.7.4.

The text:condition attribute has the data type string 18.2.

19.777.7 <text:section>

The text:condition attribute specifies the condition under which a section is hidden. The condition is encoded as a string. If the value of text:display is condition, the text:condition attribute shall be present.

The text:condition attribute is usable with the following element: <text:section> 5.4.

The text:condition attribute has the data type string 18.2.

19.778 text:connection-name

The text:connection-name attribute specifies the name of the DDE connection to which a field refers.

The text:connection-name attribute is usable with the following element: <text:dde-connection> 7.7.12.

The text:connection-name attribute has the data type string 18.2.

19.779 text:consecutive-numbering

The text:consecutive-numbering attribute specifies whether the style uses consecutive numbering for all list levels or whether each list level restarts the numbering.

The defined values for the text:consecutive-numbering attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `false`: each list level restarts numbering.
- `true`: consecutive numbering is used for all list levels.

The default value for this attribute is `false`.

The `text:consecutive-numbering` attribute is usable with the following element: `<text:list-style>` 16.30.

The `text:consecutive-numbering` attribute has the data type `boolean` 18.3.3.

19.780 text:continue-list

The `text:continue-list` attribute specifies the `xml:id` value of a list that is to be continued.

The `text:continue-list` attribute is usable with the following element: `<text:list>` 5.3.1.

The `text:continue-list` attribute has the data type `IDREF` 18.2.

19.781 text:continue-numbering

The `text:continue-numbering` attribute specifies, if the numbering of the preceding list is continued or not. This attribute is ignored, if attribute `text:continue-list` 19.780 is present.

The defined values for the `text:continue-numbering` attribute are:

- `true`: if `text:continue-list` attribute is not present and the numbering style of the preceding list is the same as the current list, the number of the first list item in the current list is the number of the last item in the preceding list incremented by one.
- `false`: if the `text:continue-list` attribute is not present, the numbering of the preceding list is not continued.

The use of the `text:continue-numbering` attribute with the `<text:numbered-paragraph>` element has been deprecated.

The `text:continue-numbering` attribute is usable with the following elements: `<text:list>` 5.3.1 and `<text:numbered-paragraph>` 5.3.6.

The `text:continue-numbering` attribute has the data type `boolean` 18.3.3.

19.782 text:copy-outline-levels

The `text:copy-outline-levels` attribute specifies whether index entries are indented according to the outline level of their source.

The defined values for the `text:copy-outline-levels` attribute are:

- `false`: no indentation is added.
- `true`: index entries are indented according to the outline level of their source.

The default value for this attribute is `false`.

The `text:copy-outline-levels` attribute is usable with the following element: `<text:user-index-source>` 8.7.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:copy-outline-levels` attribute has the data type `boolean` 18.3.3.

19.783 text:count-empty-lines

The `text:count-empty-lines` attribute specifies whether empty lines are included in the line count.

The defined values for the `text:count-empty-lines` attribute are:

- `false`: empty lines are not included in a line count.
- `true`: empty lines are included in a line count.

The default value for this attribute is `true`.

The `text:count-empty-lines` attribute is usable with the following element: `<text:linenumbering-configuration>` 16.29.1.

The `text:count-empty-lines` attribute has the data type `boolean` 18.3.3.

19.784 text:count-in-text-boxes

The `text:count-in-text-boxes` attribute specifies whether text in text boxes is included in the line count. If the value of this attribute is `true`, text within text boxes is included in the line count.

The defined values for the `text:count-in-text-boxes` attribute are:

- `false`: text within text boxes is not included in a line count.
- `true`: text within text boxes is included in a line count.

The default value for this attribute is `false`.

The `text:count-in-text-boxes` attribute is usable with the following element: `<text:linenumbering-configuration>` 16.29.1.

The `text:count-in-text-boxes` attribute has the data type `boolean` 18.3.3.

19.785 text:current-value

The `text:current-value` attribute specifies the evaluation result of a condition given by the expression in a `text:condition` attribute. 620 The value of this attribute is updated whenever the expression is evaluated.

The `text:current-value` attribute is usable with the following element: `<text:conditional-text>` 7.7.3.

The `text:current-value` attribute has the data type `boolean` 18.3.3.

19.786 text:custom1

The `text:custom1` attribute specifies the first of up to five user defined fields for a bibliography index entry.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:custom1` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:custom1` attribute has the data type `string` 18.2.

19.787 text:custom2

The `text:custom2` attribute specifies the second of up to five user defined fields for a bibliography index entry.

The `text:custom2` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:custom2` attribute has the data type `string` 18.2.

19.788 text:custom3

The `text:custom3` attribute specifies the third of up to five user defined fields for a bibliography index entry.

The `text:custom3` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:custom3` attribute has the data type `string` 18.2.

19.789 text:custom4

The `text:custom4` attribute specifies the fourth of up to five user defined fields for a bibliography index entry.

The `text:custom4` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:custom4` attribute has the data type `string` 18.2.

19.790 text:custom5

The `text:custom5` attribute specifies the fifth of up to five user defined fields for a bibliography index entry.

The `text:custom5` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:custom5` attribute has the data type `string` 18.2.

19.791 text:database-name

The `text:database-name` attribute specifies a source database by its name.

The `text:database-name` attribute is usable with the following elements: `<text:database-display>` 7.6.3, `<text:database-name>` 7.6.7, `<text:database-next>` 7.6.4, `<text:database-row-number>` 7.6.6 and `<text:database-row-select>` 7.6.5.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:database-name` attribute has the data type `string` 18.2.

19.792 text:date-adjust

The `text:date-adjust` attribute specifies an adjustment to the value of a date field. If the time period is negative, it is subtracted from the value of the date field.

The `text:date-adjust` attribute is usable with the following element: `<text:date>` 7.3.2.

The `text:date-adjust` attribute has the data type `duration` 18.2.

19.793 text:date-value

The `text:date-value` attribute specifies a date value. If no value is specified, whether the field is marked as fixed or not, the current date is assumed.

Note: This attribute can also be used to specify a future date.

The `text:date-value` attribute is usable with the following elements: `<text:creation-date>` 7.5.3, `<text:date>` 7.3.2, `<text:modification-date>` 7.5.16 and `<text:print-date>` 7.5.8.

The `text:date-value` attribute has the data type `dateOrDateTime` 18.3.14.

19.794 text:default-style-name

The `text:default-style-name` attribute specifies a default footnote paragraph style for new footnotes that are inserted into a document. It is not evaluated for footnotes that already exist.

The `text:default-style-name` attribute is usable with the following element: `<text:notes-configuration>` 16.29.3.

The `text:default-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.795 text:description

The `text:description` attribute specifies a message that is displayed when users are prompted for input.

The `text:description` attribute is usable with the following elements: `<text:placeholder>` 7.7.2, `<text:text-input>` 7.4.15, `<text:user-field-input>` 7.4.10 and `<text:variable-input>` 7.4.6.

The `text:description` attribute has the data type `string` 18.2.

19.796 text:display

19.796.1 General

The `text:display` attribute specifies options for the display of text.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.796.2 <text:chapter>

The `text:display` attribute specifies the information that a chapter field should display.

The defined values for the `text:display` attribute are:

- `name`: name of a chapter.
- `number`: number of a chapter.
- `number-and-name`: name and number of a chapter.
- `plain-number`: number of a chapter without text defined by `style:num-prefix` 19.502 and `style:num-suffix` 19.503, both of which are attributes on the `<text:outline-level-style>` element that defines the format for a chapter number.16.35.
- `plain-number-and-name`: name of a chapter with the number of the same chapter without text defined by `style:num-prefix` 19.502 and `style:num-suffix` 19.503, both of which are attributes on the `<text:outline-level-style>` element that defines the format for a chapter number.16.35.

The `text:display` attribute is usable with the following element: `<text:chapter>` 7.3.8.

The values of the `text:display` attribute are `name`, `number`, `number-and-name`, `plain-number-and-name` or `plain-number`.

19.796.3 <text:expression>

The `text:display` attribute specifies the display of a field.

The defined values for the `text:display` attribute are:

- `formula`: displays the formula instead of the value of a field.
- `none`: hides the content of a field.
- `value`: displays the value of a field.

The `text:display` attribute is usable with the following element: `<text:expression>` 7.4.14.

The values of the `text:display` attribute are `value` or `formula`.

19.796.4 <text:file-name>

The `text:display` attribute specifies how much of the file name to display.

The defined values for the `text:display` attribute are:

- `full`: full file name, extension and file path.
- `path`: file path only.
- `name`: file name without extension.
- `name-and-extension`: file name and extension.

The filename may be an IRI, either because an IRI has been used to retrieve the file, or the consumer internally uses IRIs and therefore converts system specific paths into an IRI. If this is

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

the case, and if the path, the name or the extension cannot be evaluated from the IRI, then the IRI should be displayed unmodified.

The `text:display` attribute is usable with the following element: `<text:file-name>` 7.3.9.

The values of the `text:display` attribute are `full`, `path`, `name` or `name-and-extension`.

19.796.5 <text:index-entry-chapter>

The `text:display` attribute specifies the information that a chapter field should display.

The defined values for the `text:display` attribute are:

- `name`: name of a chapter.
- `number`: number of a chapter.
- `number-and-name`: name and number of a chapter.
- `plain-number`: number of a chapter without text defined by `style:num-prefix` 19.502 and `style:num-suffix` 19.503, both of which are attributes on the `<text:outline-level-style>` element that defines the format for a chapter number.16.35.
- `plain-number-and-name`: name of a chapter with the number of the same chapter without text defined by `style:num-prefix` 19.502 and `style:num-suffix` 19.503, both of which are attributes on the `<text:outline-level-style>` element that defines the format for a chapter number.16.35.

For a `<text:index-entry-chapter>` 8.13.1 element the default value for this attribute is `number`.

The `text:display` attribute is usable with the following element: `<text:index-entry-chapter>` 8.13.1.

The values of the `text:display` attribute are `name`, `number`, `number-and-name`, `plain-number` or `plain-number-and-name`.

19.796.6 <text:section>

The `text:display` attribute specifies whether the section is hidden.

The defined values for the `text:display` attribute are:

- `condition`: the section is hidden under the condition specified in the `text:condition` attribute.
- `none`: the section is hidden unconditionally.
- `true`: the section is displayed. This is the default setting.

The `text:display` attribute is usable with the following element: `<text:section>` 5.4.

The values of the `text:display` attribute are `true`, `none` or `condition`.

19.796.7 <text:table-formula>

The `text:display` attribute specifies the type of the value that appears in this element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the `text:display` attribute are:

- `formula`: the formula used to calculate the value of the field.
- `value`: the value of the field.

The `text:display` attribute is usable with the following element: `<text:table-formula>` 7.7.14.

The values of the `text:display` attribute are `value` or `formula`.

19.796.8 <text:template-name>

The `text:display` attribute specifies the information about a document template to display.

The defined values for the `text:display` attribute are:

- `area`: The category of the template. Assignments of categories to templates is implementation-dependent.
- `full`: full file name, extension and file path.
- `name`: file name only.
- `name-and-extension`: file name and extension.
- `path`: file path only.
- `title`: The title.

The `text:display` attribute is usable with the following element: `<text:template-name>` 7.3.10.

The values of the `text:display` attribute are `full`, `path`, `name`, `name-and-extension`, `area` or `title`.

19.796.9 <text:user-field-get>

The `text:display` attribute specifies the display of a user field.

The defined values for the `text:display` attribute are:

- `formula`: displays the formula instead of the value of a field.
- `none`: hides the content of a field.
- `value`: displays the value of a field.

The `text:display` attribute is usable with the following element: `<text:user-field-get>` 7.4.9.

The values of the `text:display` attribute are `value`, `formula` or `none`.

19.796.10 <text:variable-get>

The `text:display` attribute specifies the display of a variable get field.

The defined values for the `text:display` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `formula`: displays the formula instead of the value of a field.
- `value`: displays the value of a field.

The `text:display` attribute is usable with the following element: `<text:variable-get>` 7.4.5.

The values of the `text:display` attribute are `value` or `formula`.

19.796.11 <text:variable-input>

The `text:display` attribute specifies the display of a variable input field.

The defined values for the `text:display` attribute are:

- `none`: hides the content of a field.
- `value`: displays the value of a field.

The `text:display` attribute is usable with the following element: `<text:variable-input>` 7.4.6.

The values of the `text:display` attribute are `value` or `none`.

19.796.12 <text:variable-set>

The `text:display` attribute specifies the display of a variable set field.

The defined values for the `text:display` attribute are:

- `none`: hides the content of a field.
- `value`: displays the value of a field.

The `text:display` attribute is usable with the following element: `<text:variable-set>` 7.4.4.

The values of the `text:display` attribute are `value` or `none`.

19.797 text:display-levels

The `text:display-levels` attribute specifies the number of levels whose numbers are displayed at the current level.

The default value for this attribute is `1`.

The `text:display-levels` attribute is usable with the following elements: `<text:list-level-style-number>` 16.32 and `<text:outline-level-style>` 16.35.

The `text:display-levels` attribute has the data type `positiveInteger` 18.2.

19.798 text:display-outline-level

The `text:display-outline-level` attribute specifies the numbering of a sequence by chapter. This attribute specifies an outline level that determines which chapters to reference for the chapter-specific numbering. All chapters that are at or below the specified outline level reset

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

the value of the sequence to zero, the default value. The chapter number of the last chapter at or below the specified outline level is prefixed to the sequence number. Choosing an outline level of zero results in a continuous numbering of all sequence elements for that sequence variable.

The `text:display-outline-level` attribute is usable with the following element: `<text:sequence-decl>` 7.4.12.

The `text:display-outline-level` attribute has the data type `nonNegativeInteger` 18.2.

19.799 text:duration

The `text:duration` attribute contains the value of a `<text:editing-duration>` field element if its value is fixed.

The `text:duration` attribute is usable with the following element: `<text:editing-duration>` 7.5.14.

The `text:duration` attribute has the data type `duration` 18.2.

19.800 text:edition

The `text:edition` attribute specifies the edition for a bibliography index entry.

The `text:edition` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:edition` attribute has the data type `string` 18.2.

19.801 text:editor

The `text:editor` attribute specifies the editor for a bibliography index entry.

The `text:editor` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:editor` attribute has the data type `string` 18.2.

19.802 text:filter-name

The `text:filter-name` attribute specifies the filter type to be used to import the link target. The value of this attribute is implementation-dependent.

The `text:filter-name` attribute is usable with the following element: `<text:section-source>` 5.4.2.

The `text:filter-name` attribute has the data type `string` 18.2.

19.803 text:fixed

The `text:fixed` attribute specifies whether the value of a field element is fixed.

The defined values for the `text:fixed` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `false`: value of the field element where this attribute appears may be changed.
- `true`: value of the field element where this attribute appears is preserved.

The `text:fixed` attribute is usable with the following elements: `<text:author-initials>` 7.3.7.2, `<text:author-name>` 7.3.7.1, `<text:creation-date>` 7.5.3, `<text:creation-time>` 7.5.4, `<text:creator>` 7.5.17, `<text:date>` 7.3.2, `<text:description>` 7.5.5, `<text:editing-cycles>` 7.5.13, `<text:editing-duration>` 7.5.14, `<text:file-name>` 7.3.9, `<text:initial-creator>` 7.5.2, `<text:keywords>` 7.5.12, `<text:modification-date>` 7.5.16, `<text:modification-time>` 7.5.15, `<text:page-number>` 7.3.4, `<text:print-date>` 7.5.8, `<text:printed-by>` 7.5.9, `<text:print-time>` 7.5.7, `<text:sender-city>` 7.3.6.13, `<text:sender-company>` 7.3.6.10, `<text:sender-country>` 7.3.6.15, `<text:sender-email>` 7.3.6.7, `<text:sender-fax>` 7.3.6.9, `<text:sender-firstname>` 7.3.6.2, `<text:sender-initials>` 7.3.6.4, `<text:sender-lastname>` 7.3.6.3, `<text:sender-phone-private>` 7.3.6.8, `<text:sender-phone-work>` 7.3.6.11, `<text:sender-position>` 7.3.6.6, `<text:sender-postal-code>` 7.3.6.14, `<text:sender-state-or-province>` 7.3.6.16, `<text:sender-street>` 7.3.6.12, `<text:sender-title>` 7.3.6.5, `<text:subject>` 7.5.11, `<text:time>` 7.3.3, `<text:title>` 7.5.10 and `<text:user-defined>` 7.5.6.

The `text:fixed` attribute has the data type `boolean` 18.3.3.

19.804 text:footnotes-position

The `text:footnotes-position` attribute specifies a position for a footnote.

The defined values for the `text:footnotes-position` attribute are:

- `document`: end of the document.
- `page`: bottom of the page where the footnote citation is located.
- `section`: end of the section.
- `text`: at the page where the footnote citation is located, immediately below the page's text.

The `text:footnotes-position` attribute is usable with the following element: `<text:notes-configuration>` 16.29.3.

The values of the `text:footnotes-position` attribute are `text`, `page`, `section` or `document`.

19.805 text:formula

The `text:formula` attribute specifies the formula or expression used to compute the value of a field.

The attribute value should begin with a namespace prefix followed by ":" (U+003A, COLON) followed by the text of the formula. The namespace bound to the prefix determines the syntax and semantics of the formula.

The `text:formula` attribute is usable with the following elements: `<text:expression>` 7.4.14, `<text:sequence>` 7.4.13, `<text:table-formula>` 7.7.14, `<text:user-field-decl>` 7.4.8 and `<text:variable-set>` 7.4.4.

The `text:formula` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.806 text:global (deprecated)

The `text:global` attribute specifies whether the user interface of a consumer should consider the documents to which linked text sections are linked as individually editable parts of the document.

The defined values for the `text:global` attribute are:

- `false`: the user interface need not make a distinction between linked text sections and non-linked text sections.
- `true`: the user interface considers the content of linked text sections as parts of the document which may be edited by editing the documents to which the linked text sections are linked.

The `text:global` attribute is deprecated in favor of the application/vnd.oasis.opendocument.text-master MIME type. Using this MIME type for a document has the same effect as the value `true` for a `text:global` attribute.

The default value for this attribute is `false`.

The `text:global` attribute is usable with the following element: `<office:text>` 3.4.

The `text:global` attribute has the data type `boolean` 18.3.3.

19.807 text:howpublished

The `text:howpublished` attribute specifies the publication type for a bibliography index entry.

The `text:howpublished` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:howpublished` attribute has the data type `string` 18.2.

19.808 text:increment

The `text:increment` attribute causes line numbers to be numbered as multiples of a specified increment.

The `text:increment` attribute is usable with the following elements: `<text:linenumbering-configuration>` 16.29.1 and `<text:linenumbering-separator>` 16.29.2.

The `text:increment` attribute has the data type `nonNegativeInteger` 18.2.

19.809 text:id

19.809.1 General

The `text:id` attribute specifies an identifier or a name for an element.

19.809.2 <draw:text-box>

The `text:id` attribute specifies an identifier for an element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

OpenDocument consumers shall ignore a `text:id` attribute if it occurs on a `<draw:text-box>` element with an `xml:id` attribute value.

When consuming OpenDocument v1.0 and v1.1 documents, OpenDocument consumers should process `text:id` attributes as they were `xml:id` attributes.

OpenDocument producers may write `text:id` attributes for `<draw:text-box>` elements in addition to an `xml:id` attribute.

The value of a `text:id` attribute shall equal the value of an `xml:id` attribute on the same `<draw:text-box>` element.

The `text:id` attribute is deprecated in favor of `xml:id`. 19.914

The `text:id` attribute is usable with the following element: `<draw:text-box>` 10.4.3.

The `text:id` attribute has the data type `NCName` 18.2.

19.809.3 <text:alphabetical-index-mark-end>

The `text:id` attribute specifies a name by which start- and end mark elements are connected to each other.

The `text:id` attribute is usable with the following element: `<text:alphabetical-index-mark-end>` 8.1.9.

The `text:id` attribute has the data type `string` 18.2.

19.809.4 <text:alphabetical-index-mark-start>

The `text:id` attribute specifies a name by which start- and end mark elements are connected to each other.

The `text:id` attribute is usable with the following element: `<text:alphabetical-index-mark-start>` 8.1.8.

The `text:id` attribute has the data type `string` 18.2.

19.809.5 <text:changed-region>

The `text:id` attribute specifies the ID value for the element in the absence of an `xml:id` attribute. If there is an `xml:id` attribute on the element, any `text:id` attribute shall have the same NCName value as the `xml:id` attribute.

The ID value is used in text:change-id IDREF values to refer to a particular `<text:changed-region>` element.

The `text:id` attribute is deprecated.

Note: The `text:id` attribute may be present in `<text:changed-region>` elements produced in conformance with previous versions of the OpenDocument Format. Preservation of the attribute along with the preferred use of `xml:id` might be useful in situations where backwards compatibility is being maintained.

The `text:id` attribute is usable with the following element: `<text:changed-region>` 5.5.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:id` attribute has the data type `NCName` 18.2.

19.809.6 <text:h>

The `text:id` attribute specifies an identifier for an element.

OpenDocument consumers shall ignore a `text:id` attribute if it occurs on a `<text:h>` element with an `xml:id` attribute value. If there is no `xml:id` attribute value, then a `text:id` attribute should be processed as it were an `xml:id` attribute.

OpenDocument producers may write `text:id` attributes for `<text:h>` elements in addition to an `xml:id` attribute.

A `<text:h>` element shall not have an `text:id` attribute if it has no `xml:id` attribute value. The value of a `text:id` attribute shall equal the value of an `xml:id` attribute on the same `<text:h>` element.

The `text:id` attribute is deprecated in favor of `xml:id`. 19.914

The `text:id` attribute is usable with the following element: `<text:h>` 5.1.2.

The `text:id` attribute has the data type `NCName` 18.2.

19.809.7 <text:note>

The `text:id` attribute specifies specifies a name by which notes can be referenced from `<text:note-ref>` elements. See 7.7.7.

The `text:id` attribute is usable with the following element: `<text:note>` 6.3.2.

The `text:id` attribute has the data type `string` 18.2.

19.809.8 <text:p>

The `text:id` attribute specifies an identifier for an element.

OpenDocument consumers shall ignore a `text:id` attribute if it occurs on a `<text:p>` element with an `xml:id` attribute value. If there is no `xml:id` attribute value, then a `text:id` attribute should be processed as it were an `xml:id` attribute.

OpenDocument producers may write `text:id` attributes for `<text:p>` elements in addition to an `xml:id` attribute.

A `<text:p>` element shall not have an `text:id` attribute if it has no `xml:id` attribute value. The value of a `text:id` attribute shall equal the value of an `xml:id` attribute on the same `<text:p>` element.

The `text:id` attribute is deprecated in favor of `xml:id`. 19.914

The `text:id` attribute is usable with the following element: `<text:p>` 5.1.3.

The `text:id` attribute has the data type `NCName` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.809.9 <text:toc-mark-end>

The `text:id` attribute specifies a name by which start- and end mark elements are connected to each other.

The `text:id` attribute is usable with the following element: `<text:toc-mark-end>` 8.1.3.

The `text:id` attribute has the data type `string` 18.2.

19.809.10 <text:toc-mark-start>

The `text:id` attribute specifies a name by which start- and end mark elements are connected to each other. The name specified by the `text:id` attribute shall be unique except for a matching `<text:toc-mark-end>` element.

The `text:id` attribute is usable with the following element: `<text:toc-mark-start>` 8.1.2.

The `text:id` attribute has the data type `string` 18.2.

19.809.11 <text:user-index-mark-end>

The `text:id` attribute specifies a string by which start- and end mark elements are connected to each other. The string shall be unique except for matching its corresponding `<text:user-index-mark-start>` element.

The `text:id` attribute is usable with the following element: `<text:user-index-mark-end>` 8.1.6.

The `text:id` attribute has the data type `string` 18.2.

19.809.12 <text:user-index-mark-start>

The `text:id` attribute specifies a string by which start- and end mark elements are connected to each other. The string shall be unique except for matching its corresponding `<text:user-index-mark-end>` element.

The `text:id` attribute is usable with the following element: `<text:user-index-mark-start>` 8.1.5.

The `text:id` attribute has the data type `string` 18.2.

19.810 text:identifier

The `text:identifier` attribute specifies an identifier for a bibliography index entry.

The `text:identifier` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:identifier` attribute has the data type `string` 18.2.

19.811 text:index-name

The `text:index-name` attribute specifies the name of a user defined index.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Note: In order to support multiple user-defined indexes with different contents, user index marks have a `text:index-name` attribute. The same attribute can be used with a `<text:user-index-source>` element to specify which index marks apply to the current index.

The `text:index-name` attribute is usable with the following elements: `<text:user-index-mark>` 8.1.7, `<text:user-index-mark-start>` 8.1.5 and `<text:user-index-source>` 8.7.2.

The `text:index-name` attribute has the data type `string` 18.2.

19.812 text:index-scope

The `text:index-scope` attribute specifies whether an index is constructed for an entire document or for a chapter.

The defined values for the `text:index-scope` attribute are:

- `chapter`: the index is constructed for the chapter that contains the index. A chapter consists of all those paragraphs and headings which have the same immediately preceding heading with outline level `1`.
- `document`: the index is constructed for the entire document.

The default value for this attribute is `document`.

For `<text:alphabetical-index-source>` 8.8.2, `<text:illustration-index-source>` 8.4.2, `<text:object-index-source>` 8.6.2, `<text:table-index-source>` 8.5.2 and `<text:user-index-source>` 8.7.2 elements the default value for this attribute is `document`.

The `text:index-scope` attribute is usable with the following elements: `<text:alphabetical-index-source>` 8.8.2, `<text:illustration-index-source>` 8.4.2, `<text:object-index-source>` 8.6.2, `<text:table-index-source>` 8.5.2, `<text:table-of-content-source>` 8.3.2 and `<text:user-index-source>` 8.7.2.

The values of the `text:index-scope` attribute are `document` or `chapter`.

19.813 text:ignore-case

The `text:ignore-case` attribute specifies whether the capitalization of words is ignored. If the value is `true`, the capitalization is ignored and entries that are identical except for character case are listed as the same entries. If the value is `false`, the capitalization of words is not ignored.

The defined values for the `text:ignore-case` attribute are:

- `false`: index entries that are identical except for character case should be listed as the same entries.
- `true`: index entries that are identical but differ in character case should not be listed as separate entries.

The default value for this attribute is `false`.

The `text:ignore-case` attribute is usable with the following element: `<text:alphabetical-index-source>` 8.8.2.

The `text:ignore-case` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.814 text:institution

The `text:institution` attribute specifies an institution for a bibliography index entry.

The `text:institution` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:institution` attribute has the data type `string` 18.2.

19.815 text:is-hidden

The `text:is-hidden` attribute specifies whether a field or or paragraph is currently visible.

Note: The value of this attribute is overwritten with a new value as soon as the consumer evaluates the expression.

The defined values for the `text:is-hidden` attribute are:

- `false`: condition for display has evaluated to false, field or paragraph is visible.
- `true`: condition for display has evaluated to true, field or paragraph is not visible.

The `text:is-hidden` attribute is usable with the following elements: `<text:hidden-paragraph>` 7.7.11 and `<text:hidden-text>` 7.7.4.

The `text:is-hidden` attribute has the data type `boolean` 18.3.3.

19.816 text:is-list-header

The `text:is-list-header` attribute specifies the appearance of a specific heading without numbering.

The defined values for the `text:is-list-header` attribute are:

- `false`: heading will be numbered.
- `true`: heading will be not numbered, even if the header has a list-style..

The default value for this attribute is `false`.

The `text:is-list-header` attribute is usable with the following element: `<text:h>` 5.1.2.

The `text:is-list-header` attribute has the data type `boolean` 18.3.3.

19.817 text:isbn

The `text:isbn` attribute specifies an ISBN for a bibliography index entry.

The `text:isbn` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:isbn` attribute has the data type `string` 18.2.

19.818 text:issn

The `text:issn` attribute specifies an ISSN for a bibliography index entry.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:issn` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:issn` attribute has the data type `string` 18.2.

19.819 text:journal

The `text:journal` attribute specifies a journal for a bibliography index entry.

The `text:journal` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:journal` attribute has the data type `string` 18.2.

19.820 text:key

The `text:key` attribute specifies a type for the index entries that should be used for sorting. See 8.1.11.

The defined values for the `text:key` attribute are:

- `address`: 19.751.
- `annote`: 19.755.
- `author`: 19.756.
- `bibliography-type`: 19.758.
- `booktitle`: 19.759.
- `chapter`: 19.767.
- `custom1`: 19.786.
- `custom2`: 19.787.
- `custom3`: 19.788.
- `custom4`: 19.789.
- `custom5`: 19.790.
- `edition`: 19.800.
- `editor`: 19.801.
- `howpublished`: 19.807.
- `identifier`: 19.810.
- `institution`: 19.814.
- `isbn`: 19.817.
- `issn`: 19.818.
- `journal`: 19.819.
- `month`: 19.834.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- note: 19.836.
- number: 19.838.
- organizations: 19.843.
- pages: 19.846.
- publisher: 19.852.
- report-type: 19.856.
- school: 19.860.
- series: 19.862.
- title: 19.882.
- url: 19.884.
- volume: 19.902.
- year: 19.903.

The text:key attribute is usable with the following element: <text:sort-key> 16.29.7.

The values of the text:key attribute are address, annote, author, bibliography-type, booktitle, chapter, custom1, custom2, custom3, custom4, custom5, edition, editor, howpublished, identifier, institution, isbn, issn, journal, month, note, number, organizations, pages, publisher, report-type, school, series, title, url, volume or year.

19.821 text:key1

The text:key1 attribute specifies an additional key for an alphabetical index mark. If only one key is used, it shall be contained in a text:key1 attribute.

The text:key1 attribute is usable with the following elements: <text:alphabetical-index-mark> 8.1.10 and <text:alphabetical-index-mark-start> 8.1.8.

The text:key1 attribute has the data type string 18.2.

19.822 text:key2

The text:key2 attribute specifies an additional key for an alphabetical index mark.

The text:key2 attribute is usable with the following elements: <text:alphabetical-index-mark> 8.1.10 and <text:alphabetical-index-mark-start> 8.1.8.

The text:key2 attribute has the data type string 18.2.

19.823 text:key1-phonetic

The text:key1-phonetic attribute specifies a phonetic key for <text:toc-mark-start> and <text:alphabetical-index-mark-start> elements. Phonetic keys should be used for sorting.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The text:key1-phonetic attribute is usable with the following elements: <text:alphabetical-index-mark> 8.1.10 and <text:alphabetical-index-mark-start> 8.1.8.

The text:key1-phonetic attribute has the data type string 18.2.

19.824 text:key2-phonetic

The text:key2-phonetic attribute specifies an additional phonetic key for <text:toc-mark-start> and <text:alphabetical-index-mark-start> elements.

The text:key2-phonetic attribute is usable with the following elements: <text:alphabetical-index-mark> 8.1.10 and <text:alphabetical-index-mark-start> 8.1.8.

The text:key2-phonetic attribute has the data type string 18.2.

19.825 text:kind

The text:kind attribute specifies which part of a measure is displayed.

The defined values for the text:kind attribute are:

- gap: Adds space to text if the measure text's writing direction is perpendicular to the measure line.
- unit: The measure's unit is displayed.
- value: The measure's value is displayed.

Note: The purpose of the gap value is add space between the measure line and the text if the text is displayed perpendicular to the measure line.

The text:kind attribute is usable with the following element: <text:measure> 7.7.13.

The values of the text:kind attribute are value, unit or gap.

19.826 text:label

The text:label attribute specifies a label for user inserted notes in a document. If this attribute is omitted, the element content is used.

The text:label attribute is usable with the following element: <text:note-citation> 6.3.3.

The text:label attribute has the data type string 18.2.

19.827 text:label-followed-by

The text:label-followed-by attribute specifies a character that is inserted behind a list label.

The defined values for the text:label-followed-by attribute are:

- listtab: a tab character is inserted after a list label before the text starts.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `nothing`: text starts directly after a list label.
- `space`: a " " (U+0020, SPACE) character is inserted after a list label before the text starts.

The `text:label-followed-by` attribute is usable with the following element: `<style:list-level-label-alignment>` 17.20.

The values of the `text:label-followed-by` attribute are `listtab`, `space` or `nothing`.

19.828 text:level

The `text:level` attribute specifies the level of an outline or number list style.

For a `<text:numbered-paragraph>` 5.3.6 element the default value for this attribute is `1`.

The `text:level` attribute is usable with the following elements: `<text:list-level-style-bullet>` 16.31, `<text:list-level-style-image>` 16.33, `<text:list-level-style-number>` 16.32, `<text:numbered-paragraph>` 5.3.6 and `<text:outline-level-style>` 16.35.

The `text:level` attribute has the data type `positiveInteger` 18.2.

19.829 text:list-id

The `text:list-id` attribute specifies an id that is used to group numbered paragraphs form a list. All numbered paragraphs with the same `text:list-id` value belong to one list. This list defines the counter domain for the numbered paragraphs. In this context, a list is defined as a number of list items, spanning multiple levels. As with lists in `<text:list>` representation the list style of the first numbered paragraph at every list level is used for the start value.

The `text:list-id` attribute did not exist in OpenDocument v1.0 and v1.1. For such text documents which do not contain the `text:list-id` attribute the following rules are applied to form a list from a group of numbered paragraphs:

- A series of numbered paragraphs each using the same list style belong to the same list.
- A numbered paragraph that does not have a `text:list-id` gets the `text:list-id` of the last numbered paragraph on the same list level using the same list style. If the previous numbered-paragraph has a different list style, then a new list is started.

The `text:list-id` attribute is usable with the following element: `<text:numbered-paragraph>` 5.3.6.

The `text:list-id` attribute has the data type `NCName` 18.2.

19.830 text:list-tab-stop-position

The `text:list-tab-stop-position` attribute specifies an additional tab stop which is inserted into the list of tab stops that are defined for a list item. By default the tab stop's position is behind list label. The text of the first line of list item starts at this tab stop. In left-to-right layout environments this tab stop is interpreted as a left tab. While in right-to-left layout environments it is interpreted as a right tab.

The `text:list-tab-stop-position` attribute is ignored unless the `text:label-followed-by` attribute has the value `listtab`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

There are two cases in which this additional tab stop does not specify the start the of the text of the first line of the list item:

- The position of the additional tab stop is before the end of the list label.
- Between the end of the list label and the position of the additional tab stop exists already a tab stop.

In these cases, the tab character that is inserted behind the list label advances to the next tab stop, or a default tab stop if none exists. However, other tab stops contained in the list item's text may advance to the additional list tab stop. The additional tab stop is further applied to the full text of tab stop, that is, not only the first line.

The `text:list-tab-stop-position` attribute is usable with the following element: `<style:list-level-label-alignment>` 17.20.

The `text:list-tab-stop-position` attribute has the data type `length` 18.3.18.

19.831 text:main-entry

The `text:main-entry` attribute specifies which of multiple index marks for the same entry is the main entry.

The defined values for the `text:main-entry` attribute are:

- `false`: no index mark is specified as the main entry from multiple index marks for the same entry.
- `true`: one index mark out of multiple index marks for the same entry is specified as the main entry.

The default value for this attribute is `false`.

The `text:main-entry` attribute is usable with the following elements: `<text:alphabetical-index-mark>` 8.1.10 and `<text:alphabetical-index-mark-start>` 8.1.8.

The `text:main-entry` attribute has the data type `boolean` 18.3.3.

19.832 text:main-entry-style-name

The `text:main-entry-style-name` attribute specifies the character style to use for main entries. Sub entries are formatted using the default character style determined by the paragraph style of the entries.

The `text:main-entry-style-name` attribute is usable with the following element: `<text:alphabetical-index-source>` 8.8.2.

The `text:main-entry-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.833 text:master-page-name

The `text:master-page-name` attribute specifies the name of a master page.

For `<text:page>` elements 5.2.2, the attribute specifies the name of the master page which is used to format the page.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

For <text:notes-configuration> elements 16.29.3, the attributes specifies the master page which is used to format the pages on which the notes are displayed.

The text:master-page-name attribute is usable with the following elements: <text:notes-configuration> 16.29.3 and <text:page> 5.2.2.

The text:master-page-name attribute has the data type styleNameRef 18.3.32.

19.834 text:month

The text:month attribute specifies a month for a bibliography index entry.

The text:month attribute is usable with the following element: <text:bibliography-mark> 8.1.11.

The text:month attribute has the data type string 18.2.

19.835 text:name

19.835.1 General

The text:name attribute specifies a name.

19.835.2 <text:alphabetical-index>

The text:name attribute specifies a unique name for an alphabetical index.

The text:name attribute is usable with the following element: <text:alphabetical-index> 8.8.

The text:name attribute has the data type string 18.2.

19.835.3 <text:bibliography>

The text:name attribute specifies a unique name for a bibliography.

The text:name attribute is usable with the following element: <text:bibliography> 8.9.

The text:name attribute has the data type string 18.2.

19.835.4 <text:bookmark>

The text:name attribute specifies a name for a bookmark.

The text:name attribute is usable with the following element: <text:bookmark> 6.2.1.2.

The text:name attribute has the data type string 18.2.

19.835.5 <text:bookmark-end>

The text:name attribute specifies a name that shall match the text:name attribute on only one <text:bookmark-start> element in a document.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:name` attribute is usable with the following element: `<text:bookmark-end>` 6.2.1.4.

The `text:name` attribute has the data type `string` 18.2.

19.835.6 <text:bookmark-start>

The `text:name` attribute specifies a name that shall match the `text:name` attribute on only one `<text:bookmark-end>` element in a document.

The `text:name` attribute is usable with the following element: `<text:bookmark-start>` 6.2.1.3.

The `text:name` attribute has the data type `string` 18.2.

19.835.7 <text:execute-macro>

The `text:name` attribute specifies a macro to invoke when a field is activated.

The `text:name` attribute is usable with the following element: `<text:execute-macro>` 7.7.10.

The `text:name` attribute has the data type `string` 18.2.

19.835.8 <text:illustration-index>

The `text:name` attribute specifies a unique name for an illustration index.

The `text:name` attribute is usable with the following element: `<text:illustration-index>` 8.4.

The `text:name` attribute has the data type `string` 18.2.

19.835.9 <text:index-title>

The `text:name` attribute specifies a unique name for an index title.

The `text:name` attribute is usable with the following element: `<text:index-title>` 8.2.3.

The `text:name` attribute has the data type `string` 18.2.

19.835.10 <text:object-index>

The `text:name` attribute specifies a unique name for an object index.

The `text:name` attribute is usable with the following element: `<text:object-index>` 8.6.

The `text:name` attribute has the data type `string` 18.2.

19.835.11 <text:reference-mark>

The `text:name` attribute specifies a unique name for reference elements.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:name` attribute is usable with the following element: `<text:reference-mark>` 6.2.2.2.

The `text:name` attribute has the data type `string` 18.2.

19.835.12 <text:reference-mark-end>

The `text:name` attribute specifies a unique name for reference elements.

The `text:name` attribute is usable with the following element: `<text:reference-mark-end>` 6.2.2.4.

The `text:name` attribute has the data type `string` 18.2.

19.835.13 <text:reference-mark-start>

The `text:name` attribute specifies a unique name for reference elements.

The `text:name` attribute is usable with the following element: `<text:reference-mark-start>` 6.2.2.3.

The `text:name` attribute has the data type `string` 18.2.

19.835.14 <text:section>

The `text:name` attribute specifies a unique name for a section.

The `text:name` attribute is usable with the following element: `<text:section>` 5.4.

The `text:name` attribute has the data type `string` 18.2.

19.835.15 <text:sequence>

The `text:name` attribute specifies name of variable to display. It shall match the name of a sequence variable already declared by a preceding `<text:sequence-decl>`.element

The `text:name` attribute is usable with the following element: `<text:sequence>` 7.4.13.

The `text:name` attribute has the data type `variableName` 18.3.39.

19.835.16 <text:sequence-decl>

The `text:name` attribute specifies unique name of a variable to be declared.

The `text:name` attribute is usable with the following element: `<text:sequence-decl>` 7.4.12.

The `text:name` attribute has the data type `variableName` 18.3.39.

19.835.17 <text:table-of-content>

The `text:name` attribute specifies a unique name for a `<text:table-of-content>` element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:name` attribute is usable with the following element: `<text:table-of-content>` 8.3.

The `text:name` attribute has the data type `string` 18.2.

19.835.18 <text:table-index>

The `text:name` attribute specifies a unique name for a table index.

The `text:name` attribute is usable with the following element: `<text:table-index>` 8.5.

The `text:name` attribute has the data type `string` 18.2.

19.835.19 <text:user-defined>

The `text:name` attribute specifies a name that corresponds to the value of a `meta:name` attribute on a `<meta:user-defined>` element.

The `text:name` attribute is usable with the following element: `<text:user-defined>` 7.5.6.

The `text:name` attribute has the data type `string` 18.2.

19.835.20 <text:user-field-decl>

The `text:name` attribute specifies a unique name for a user defined field declaration.

The `text:name` attribute is usable with the following element: `<text:user-field-decl>` 7.4.8.

The `text:name` attribute has the data type `variableName` 18.3.39.

19.835.21 <text:user-field-get>

The `text:name` attribute specifies name of a user defined field that shall be declared already by a preceding `<text:user-field-decl>` element.

The `text:name` attribute is usable with the following element: `<text:user-field-get>` 7.4.9.

The `text:name` attribute has the data type `variableName` 18.3.39.

19.835.22 <text:user-field-input>

The `text:name` attribute specifies a name of a user defined field that shall be declared already by a preceding `<text:user-field-decl>` element.

The `text:name` attribute is usable with the following element: `<text:user-field-input>` 7.4.10.

The `text:name` attribute has the data type `variableName` 18.3.39.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.835.23 <text:user-index>

The `text:name` attribute specifies a unique name for a user specified index.

The `text:name` attribute is usable with the following element: `<text:user-index>` 8.7.

The `text:name` attribute has the data type `string` 18.2.

19.835.24 <text:variable-set>

The `text:name` attribute specifies a variable name that shall match a variable name already declared by a preceding `<text:variable-decl>` element.

The `text:name` attribute is usable with the following element: `<text:variable-set>` 7.4.4.

The `text:name` attribute has the data type `variableName` 18.3.39.

19.835.25 <text:variable-decl>

The `text:name` attribute specifies unique name for a variable declaration.

The `text:name` attribute is usable with the following element: `<text:variable-decl>` 7.4.3.

The `text:name` attribute has the data type `variableName` 18.3.39.

19.835.26 <text:variable-get>

The `text:name` attribute specifies a variable name that shall match a preceding `<text:variable-decl>` element.

The `text:name` attribute is usable with the following element: `<text:variable-get>` 7.4.5.

The `text:name` attribute has the data type `variableName` 18.3.39.

19.835.27 <text:variable-input>

The `text:name` attribute specifies a variable name that shall match the name of variable already declared by a preceding `<text:variable-decl>` element.

The `text:name` attribute is usable with the following element: `<text:variable-input>` 7.4.6.

The `text:name` attribute has the data type `variableName` 18.3.39.

19.836 text:note

The `text:note` attribute specifies a note for a bibliography index entry.

The `text:note` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:note` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.837 text:note-class

The `text:note-class` attribute specifies the class of a note.

The defined values for the `text:note-class` attribute are:

- `endnote`: note appears at the end of a chapter or document.
- `footnote`: note appears at the footer of a page.

The `text:note-class` attribute is usable with the following elements: `<text:note>` 6.3.2, `<text:note-ref>` 7.7.7 and `<text:notes-configuration>` 16.29.3.

The values of the `text:note-class` attribute are `footnote` or `endnote`.

19.838 text:number

The `text:number` attribute specifies a number for a bibliography index entry.

The `text:number` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:number` attribute has the data type `string` 18.2.

19.839 text:number-lines

The `text:number-lines` attribute specifies whether lines are numbered.

The defined values for the `text:number-lines` attribute are:

- `false`: lines are not numbered.
- `true`: lines are numbered.

For a `<text:linenumbering-configuration>` 16.29.1 element the default value for this attribute is `true`.

The `text:number-lines` attribute is usable with the following element: `<text:linenumbering-configuration>` 16.29.1.

The `text:number-lines` attribute has the data type `boolean` 18.3.3.

19.840 text:number-position

The `text:number-position` attribute specifies margin where line numbers appear.

The defined values for the `text:number-position` attribute are:

- `inner`: page numbers appear on the inner side of a page.
- `left`: page numbers appear on the left side of a page.
- `outer`: page numbers appear on the outer side of a page.
- `right`: page numbers appear on the right side of a page

The default value for this attribute is `left`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:number-position` attribute is usable with the following element: `<text:linenumbering-configuration>` 16.29.1.

The values of the `text:number-position` attribute are `left`, `right`, `inner` or `outer`.

19.841 text:numbered-entries

The `text:numbered-entries` attribute specifies whether a number is displayed for bibliography entries instead of their short name.

The defined values for the `text:numbered-entries` attribute are:

- `false`: short names for bibliographic entries displayed.
- `true`: number displayed for bibliographic entries.

The default value for this attribute is `false`.

The `text:numbered-entries` attribute is usable with the following element: `<text:bibliography-configuration>` 16.29.6.

The `text:numbered-entries` attribute has the data type `boolean` 18.3.3.

19.842 text:offset

The `text:offset` attribute specifies the distance between a line number and the margin.

The `text:offset` attribute is usable with the following element: `<text:linenumbering-configuration>` 16.29.1.

The `text:offset` attribute has the data type `nonNegativeLength` 18.3.20.

19.843 text:organizations

The `text:organizations` attribute specifies one or more organizations for a bibliography index entry.

The `text:organizations` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:organizations` attribute has the data type `string` 18.2.

19.844 text:outline-level

19.844.1 General

The `text:outline-level` attribute specifies an outline level.

19.844.2 <text:alphabetical-index-entry-template>

The `text:outline-level` attribute specifies the level to which a template applies.

The defined values for the `text:outline-level` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `1`: index mark with only text but no keys assigned is assigned to level one.
- `2`: index mark with text and one key, key is assigned to level one and index mark value is assigned to level two.
- `3`: index mark with two keys, first key is assigned to level one, second key is assigned to level two, and the index mark value is assigned to level three.
- `separator`: the template defines an alphabetical separator.

The `text:outline-level` attribute is usable with the following element: `<text:alphabetical-index-entry-template>` 8.8.4.

The values of the `text:outline-level` attribute are `1`, `2`, `3` or `separator`.

19.844.3 <text:chapter>

The `text:outline-level` attribute specifies an outline level to use. The `<text:chapter>` element displays a chapter number or title up to the specified outline level.

The `text:outline-level` attribute is usable with the following element: `<text:chapter>` 7.3.8.

The `text:outline-level` attribute has the data type `nonNegativeInteger` 18.2.

19.844.4 <text:h>

The `text:outline-level` attribute specifies the level of a heading, starting with 1. Headings without a level attribute are assumed to be at level 1.

The `text:outline-level` attribute is usable with the following element: `<text:h>` 5.1.2.

The `text:outline-level` attribute has the data type `positiveInteger` 18.2.

19.844.5 <text:index-entry-chapter>

The `text:outline-level` attribute specifies an outline level for an index entry.

The `text:outline-level` attribute is usable with the following element: `<text:index-entry-chapter>` 8.13.1.

The `text:outline-level` attribute has the data type `positiveInteger` 18.2.

19.844.6 <text:index-source-styles>

The `text:outline-level` attribute specifies an outline level for an index entry.

The `text:outline-level` attribute is usable with the following element: `<text:index-source-styles>` 8.10.

The `text:outline-level` attribute has the data type `positiveInteger` 18.2.

19.844.7 <text:user-index-mark>

The `text:outline-level` attribute specifies an outline level for an index entry.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:outline-level` attribute is usable with the following element: `<text:user-index-mark>` 8.1.7.

The `text:outline-level` attribute has the data type `positiveInteger` 18.2.

19.844.8 <text:table-of-content-entry-template>

The `text:outline-level` attribute specifies to which outline level an entry configuration applies. Outline levels shall be unique for the template elements in one index source.

The `text:outline-level` attribute is usable with the following element: `<text:table-of-content-entry-template>` 8.3.3.

The `text:outline-level` attribute has the data type `positiveInteger` 18.2.

19.844.9 <text:table-of-content-source>

The `text:outline-level` attribute specifies which outline levels are used when generating a table of contents. The value of this attribute shall be an integer greater than zero. If this attribute is omitted, all outline levels are used by default.

The `text:outline-level` attribute is usable with the following element: `<text:table-of-content-source>` 8.3.2.

The `text:outline-level` attribute has the data type `positiveInteger` 18.2.

19.844.10 <text:toc-mark>

The `text:outline-level` attribute specifies an outline level for a table of contents index entry.

The `text:outline-level` attribute is usable with the following element: `<text:toc-mark>` 8.1.4.

The `text:outline-level` attribute has the data type `positiveInteger` 18.2.

19.844.11 <text:toc-mark-start>

The `text:outline-level` attribute specifies an outline level for a table of contents index entry.

The `text:outline-level` attribute is usable with the following element: `<text:toc-mark-start>` 8.1.2.

The `text:outline-level` attribute has the data type `positiveInteger` 18.2.

19.844.12 <text:user-index-entry-template>

The `text:outline-level` attribute specifies the template applied to entries at a specified outline level in a user-defined index. All `<text:user-index-entry-template>` elements that are contained in the same parent element shall specify different outline levels.

The `text:outline-level` attribute is usable with the following element: `<text:user-index-entry-template>` 8.7.3.

The `text:outline-level` attribute has the data type `positiveInteger` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.844.13 <text:user-index-mark-start>

The `text:outline-level` attribute specifies an outline level for a user index entry.

The `text:outline-level` attribute is usable with the following element: `<text:user-index-mark-start>` 8.1.5.

The `text:outline-level` attribute has the data type `positiveInteger` 18.2.

19.845 text:page-adjust

19.845.1 General

The `text:page-adjust` attribute specifies an adjustment to page numbering.

19.845.2 <text:page-number>

The `text:page-adjust` attribute specifies an adjustment of the value of a page number field, in order to display of page numbers of following or preceding pages. The specified value is added to the current page number. If a page with the resulting page number does not exist, no number is displayed.

The `text:page-adjust` attribute is usable with the following element: `<text:page-number>` 7.3.4.

The `text:page-adjust` attribute has the data type `integer` 18.2.

19.845.3 <text:page-variable-set>

The `text:page-adjust` attribute specifies a page adjustment. The value of an active page variable is the current page number plus any page adjustment value immediately prior to the occurrence of this variable in document order.

The `text:page-adjust` attribute is usable with the following element: `<text:page-variable-set>` 7.7.1.2.

The `text:page-adjust` attribute has the data type `integer` 18.2.

19.846 text:pages

The `text:pages` attribute specifies the page number or page numbers for a bibliography index entry.

The `text:pages` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:pages` attribute has the data type `string` 18.2.

19.847 text:placeholder-type

The `text:placeholder-type` attribute specifies the content type of a placeholder.

The defined values for the `text:placeholder-type` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `image`: placeholder can be replaced by an image.
- `object`: placeholder can be replaced by an object.
- `table`: placeholder can be replaced by a table.
- `text`: placeholder can be replaced by text.
- `text-box`: placeholder can be replaced by a text-box.

The `text:placeholder-type` attribute is usable with the following element: `<text:placeholder>` 7.7.2.

The values of the `text:placeholder-type` attribute are `text`, `table`, `text-box`, `image` or `object`.

19.848 text:prefix

The `text:prefix` attribute specifies a string that is displayed before a bibliography entry's short name or number if it occurs outside the bibliography.

The `text:prefix` attribute is usable with the following element: `<text:bibliography-configuration>` 16.29.6.

The `text:prefix` attribute has the data type `string` 18.2.

19.849 text:protected

The `text:protected` attribute specifies whether a section is protected. A section can be protected, which means that a user can not edit the section. The protection is enforced by the user interface only.

Note: If the section is protected and the `text:protection-key` attribute is present, an authorization is required for resetting the protection to enable editing. 19.850

The defined values for the `text:protected` attribute are:

- `false`: section is not protected from editing.
- `true`: section is protected from editing.

The `text:protected` attribute is usable with the following elements: `<text:alphabetical-index>` 8.8, `<text:bibliography>` 8.9, `<text:illustration-index>` 8.4, `<text:index-title>` 8.2.3, `<text:object-index>` 8.6, `<text:section>` 5.4, `<text:table-index>` 8.5, `<text:table-of-content>` 8.3 and `<text:user-index>` 8.7.

The `text:protected` attribute has the data type `boolean` 18.3.3.

19.850 text:protection-key

The `text:protection-key` attribute, when present, specifies that an authorization is required for removing the protection of a section. The authentication procedure is identified by the `text:protection-key-digest-algorithm` attribute 19.851 The attribute value is binary data that may be used by the authentication procedure.

The password shall be provided as a sequence of bytes in UTF-8 encoding.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:protection-key` attribute is usable with the following elements: `<text:alphabetical-index>` 8.8, `<text:bibliography>` 8.9, `<text:illustration-index>` 8.4, `<text:index-title>` 8.2.3, `<text:object-index>` 8.6, `<text:section>` 5.4, `<text:table-index>` 8.5, `<text:table-of-content>` 8.3 and `<text:user-index>` 8.7.

The `text:protection-key` attribute has the data type `string` 18.2.

19.851 text:protection-key-digest-algorithm

The `text:protection-key-digest-algorithm` attribute value is an IRI that identifies an authentication procedure for removing a protection.

If the IRI identifies a message-digest algorithm specified in §5.7 of [xmlenc-core], the value of `text:protection-key` attribute shall be the hash value of the password that is required to authorize removal of the protection. The password shall be provided as a sequence of bytes in UTF-8 encoding.

Any other procedures, their identifying IRIs, and their application of `text:protection-key` values are implementation-defined.

Consumers shall support http://www.w3.org/2000/09/xmldsig#sha1, which is the default, and http://www.w3.org/2000/09/xmldsig#sha256. They may support other algorithms described in §5.7 of [xmlenc-core] or alternative procedures. Producers should use http://www.w3.org/2000/09/xmldsig#sha256.

The default value for this attribute is `http://www.w3.org/2000/09/xmldsig#sha1`.

The `text:protection-key-digest-algorithm` attribute is usable with the following elements: `<text:alphabetical-index>` 8.8, `<text:bibliography>` 8.9, `<text:illustration-index>` 8.4, `<text:index-title>` 8.2.3, `<text:object-index>` 8.6, `<text:section>` 5.4, `<text:table-index>` 8.5, `<text:table-of-content>` 8.3 and `<text:user-index>` 8.7.

The `text:protection-key-digest-algorithm` attribute has the data type `anyIRI` 18.3.2.

19.852 text:publisher

The `text:publisher` attribute specifies a publisher for a bibliography index entry.

The `text:publisher` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:publisher` attribute has the data type `string` 18.2.

19.853 text:ref-name

19.853.1 General

The `text:ref-name` attribute specifies a name that is used as a reference.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.853.2 <text:bookmark-ref>

The `text:ref-name` attribute identifies a `<text:bookmark>` or `<text:bookmark-start>` element by the value of that element's `text:name` attribute.

The `text:ref-name` attribute is usable with the following element: `<text:bookmark-ref>` 7.7.6.

The `text:ref-name` attribute has the data type `string` 18.2.

19.853.3 <text:note-ref>

The `text:ref-name` attribute identifies a `<text:note>` element by the value of that element's `text:id` attribute.

The `text:ref-name` attribute is usable with the following element: `<text:note-ref>` 7.7.7.

The `text:ref-name` attribute has the data type `string` 18.2.

19.853.4 <text:reference-ref>

The `text:ref-name` attribute identifies a `<text:reference-mark>` or `<text:reference-mark-start>` element by the value of that element's `text:name` attribute.

The `text:ref-name` attribute identifies the element referenced by this reference field element.

The `text:ref-name` attribute is usable with the following element: `<text:reference-ref>` 7.7.5.

The `text:ref-name` attribute has the data type `string` 18.2.

19.853.5 <text:sequence>

The `text:ref-name` attribute specifies the name for a sequence field that is the subject of a reference field. No two sequence fields can have the same reference name.

If a sequence field is not the target of a reference, this attribute can be omitted.

The `text:ref-name` attribute is usable with the following element: `<text:sequence>` 7.4.13.

The `text:ref-name` attribute has the data type `string` 18.2.

19.853.6 <text:sequence-ref>

The `text:ref-name` attribute identifies a `<text:sequence>` element by the value of that element's `text:ref-name` attribute.

The `text:ref-name` attribute is usable with the following element: `<text:sequence-ref>` 7.7.8.

The `text:ref-name` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.854 text:reference-format

The `text:reference-format` attribute specifies what information about a reference is displayed. If the reference format is not specified, the page format is used as the default.

The defined values for the `text:reference-format` attribute supported by all reference fields are:

- `chapter`: displays the number of the chapter in which the referenced item appears.
- `direction`: displays whether the referenced item is above or below the reference field.
- `page`: displays the number of the page on which the referenced item appears.
- `text`: displays the text of the referenced item.

Additional defined values for the `text:reference-format` attribute supported by references to sequence fields are:

- `caption`: displays the caption in which the sequence is used.
- `category-and-value`: displays the name and value of the sequence.
- `value`: displays the value of the sequence.

References to bookmarks and other references support additional values, which display the *list label* of the referenced item. If the referenced item is contained in a list or a numbered paragraph, the list label is the formatted number of the paragraph which contains the referenced item. If the referenced item is not contained in a list or numbered paragraph, the list label is empty, and the referenced field therefore displays nothing. If the referenced bookmark or reference contains more than one paragraph, the list label of the paragraph at which the bookmark or reference starts is taken.

Additional defined values for the `text:reference-format` attribute supported by all references to bookmark's or other reference fields are:

- `number`: displays the list label of the referenced item. To unambiguously identify the referenced item at the document position of the reference field, the list label content for as many superior list levels are added in front as are required to make the reference unambiguous. The required superior levels of the referenced item are the ones, which differ from the superior levels of the document position of the reference field.

  The list label of the referenced item may already contain numbers of superior levels. If this is the case, and if *n* is the level of the most superior level contained in the list label, then no list label content of superior levels smaller or equal than *n* are added.

- `number-all-superior`: displays the list label of the referenced item and adds the contents of all list labels of superior levels in front of it.

  The list label of the referenced item may already contain numbers of superior levels. If this is the case, and if *n* is the level of the most superior level contained in the list label, then no list label content of superior levels smaller or equal than *n* are added.

- `number-no-superior`: displays the contents of the list label of the referenced item.

The `text:reference-format` attribute is usable with the following elements: `<text:bookmark-ref>` 7.7.6, `<text:note-ref>` 7.7.7, `<text:reference-ref>` 7.7.5 and `<text:sequence-ref>` 7.7.8.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

For <text:reference-ref> 7.7.5 elements, the values of the text:reference-format attribute are page, chapter, direction, text, number-no-superior, number-all-superior or number.

For <text:bookmark-ref> 7.7.6 elements, the values of the text:reference-format attribute are page, chapter, direction, text, number-no-superior, number-all-superior or number.

For <text:note-ref> 7.7.7 elements, the values of the text:reference-format attribute are page, chapter, direction or text.

For <text:sequence-ref> 7.7.8 elements, the values of the text:reference-format attribute are page, chapter, direction, text, category-and-value, caption or value.

19.855 text:relative-tab-stop-position

The text:relative-tab-stop-position attribute specifies whether the position of tab stops is relative to the left margin or to the left indent as determined by the paragraph style. It is used in the specification for the generation of index entries and table of content entries.

The defined values for the text:relative-tab-stop-position attribute are:

- false: paragraph style determines position of tab stops relative to the left margin.
- true: paragraph style determines the position of tab stops relative to the left ident.

The default value for this attribute is true.

The text:relative-tab-stop-position attribute is usable with the following elements: <text:alphabetical-index-source> 8.8.2, <text:illustration-index-source> 8.4.2, <text:object-index-source> 8.6.2, <text:table-index-source> 8.5.2, <text:table-of-content-source> 8.3.2 and <text:user-index-source> 8.7.2.

The text:relative-tab-stop-position attribute has the data type boolean 18.3.3.

19.856 text:report-type

The text:report-type attribute specifies a report type for a bibliography index entry.

The text:report-type attribute is usable with the following element: <text:bibliography-mark> 8.1.11.

The text:report-type attribute has the data type string 18.2.

19.857 text:restart-numbering

The text:restart-numbering attribute specifies whether to restart the numbering of headings.

The defined values for the text:restart-numbering attribute are:

- false: numbering of headings does not restart.
- true: numbering of headings does restart.

The default value for this attribute is false.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:restart-numbering` attribute is usable with the following element: `<text:h>` 5.1.2.

The `text:restart-numbering` attribute has the data type `boolean` 18.3.3.

19.858 text:restart-on-page

The `text:restart-on-page` attribute specifies whether the line count is reset to 1 at the start of every page.

If the value of this attribute is `true`, the line count is reset to 1 at the beginning of every page, resulting in page-specific numbering of lines. The default value of this attribute is `false`, resulting in document-specific numbering of lines.

The defined values for the `text:restart-on-page` attribute are:

- `false`: line count is not reset, resulting in document-specific numbering of lines.
- `true`: line count is reset to 1 at the beginning of every page, resulting in page-specific line numbering.

The default value for this attribute is `false`.

The `text:restart-on-page` attribute is usable with the following element: `<text:linenumbering-configuration>` 16.29.1.

The `text:restart-on-page` attribute has the data type `boolean` 18.3.3.

19.859 text:row-number

The `text:row-number` attribute specifies a row number to select when a condition is `true`.

The `text:row-number` attribute is usable with the following element: `<text:database-row-select>` 7.6.5.

The `text:row-number` attribute has the data type `nonNegativeInteger` 18.2.

19.860 text:school

The `text:school` attribute specifies a school for a bibliography index entry.

The `text:school` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:school` attribute has the data type `string` 18.2.

19.861 text:section-name

The `text:section-name` attribute specifies a section to which a section is linked by its name. The referenced section occurs either in the document referenced by the `xlink:href` attribute on the same `<text:section-source>` element, or in the same document if the `xlink:href` attribute is not present.

If the `text:section-name` attribute is not present, the section is linked to the entire document referenced by the `xlink:href` attribute, unless the `xlink:href` attribute contains a fragment

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

identifier. If neither the xlink:href attribute nor the text:section-name attribute is present, the <text:section-source> element shall be ignored.

The text:section-name attribute is usable with the following element: <text:section-source> 5.4.2.

The text:section-name attribute has the data type string 18.2.

19.862 text:series

The text:series attribute specifies the series for a bibliography index entry.

The text:series attribute is usable with the following element: <text:bibliography-mark> 8.1.11.

The text:series attribute has the data type string 18.2.

19.863 text:select-page

19.863.1 General

The text:select-page attribute specifies conditional display of text.

19.863.2 <text:page-continuation>

The text:select-page attribute specifies whether to check for a previous or next page and if that page exists, continuation text is printed.

The defined values for the text:select-page attribute are:

- next: check for next page and if it exists, prints continuation text.
- previous: check for previous page and if it exists, print continuation text.

The text:select-page attribute is usable with the following element: <text:page-continuation> 7.3.5.

The values of the text:select-page attribute are previous or next.

19.863.3 <text:page-number>

The text:select-page attribute specifies whether to display or not the number of a previous or following page rather than the number of the current page.

The defined values for the text:select-page attribute are:

- current: number of the current page.
- next: number of the page immediately following the current page.
- previous: number of the page immediately preceding the current page.

Note: To display the current page number on all pages except the first or last page, use a combination of the text:select-page and text:page-adjust attributes.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:select-page` attribute is usable with the following element: `<text:page-number>` 7.3.4.

The values of the `text:select-page` attribute are `previous`, `current` or `next`.

19.864 text:separation-character

The `text:separation-character` attribute specifies the character used to separate values representing levels in an outline.

If the value of the `text:display-outline-level` attribute is a non-zero value, a separation character may be specified. The default separation character is " . " (U+002E, FULL STOP). If the value of `text:display-outline-level` is zero, this attribute shall be omitted.

The `text:separation-character` attribute is usable with the following element: `<text:sequence-decl>` 7.4.12.

The `text:separation-character` attribute has the data type `character` 18.3.7.

19.865 text:sort-algorithm

The `text:sort-algorithm` specifies a locale specific sorting algorithm by name.

The `text:sort-algorithm` attribute is usable with the following elements: `<text:alphabetical-index-source>` 8.8.2 and `<text:bibliography-configuration>` 16.29.6.

The `text:sort-algorithm` attribute has the data type `string` 18.2.

19.866 text:sort-ascending

The `text:sort-ascending` attribute specifies whether locale specific sorting takes place in ascending or descending order.

The defined values for the `text:sort-ascending` attribute are:

- `false`: sorting takes place in descending order.
- `true`: sorting takes place in ascending order.

The default value for this attribute is `true`.

The `text:sort-ascending` attribute is usable with the following element: `<text:sort-key>` 16.29.7.

The `text:sort-ascending` attribute has the data type `boolean` 18.3.3.

19.867 text:sort-by-position

The `text:sort-by-position` attribute specifies whether bibliography entries are displayed in the order of their positions in the document, or by selected fields.

The defined values for the `text:sort-by-position` attribute are:

- `false`: bibliographic entries are displayed in the order of their positions in a document.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: bibliographic entries are displayed as sorted by selected fields. The collation order for entries sorted by fields is determined by by the attributes `fo:language`, `fo:country`, `fo:script`, `style:rfc-language-tag` and `text:sort-algorithm`.

The default value for this attribute is `true`.

The `text:sort-by-position` attribute is usable with the following element: `<text:bibliography-configuration>` 16.29.6.
The `text:sort-by-position` attribute has the data type `boolean` 18.3.3.

19.868 text:start-value

19.868.1 General

The `text:start-value` attribute specifies the start value for numbering.

19.868.2 <text:h>

The `text:start-value` attribute specifies a value that restarts numbering at the current heading.

The `text:start-value` attribute is usable with the following element: `<text:h>` 5.1.2.
The `text:start-value` attribute has the data type `nonNegativeInteger` 18.2.

19.868.3 <text:list-item>

The `text:start-value` attribute specifies a value that restarts numbering of a list at the current item. This attribute can only be applied to items in a list with a numbering list style.

The `text:start-value` attribute is usable with the following element: `<text:list-item>` 5.3.4.
The `text:start-value` attribute has the data type `nonNegativeInteger` 18.2.

19.868.4 <text:list-level-style-number>

The `text:start-value` attribute specifies a value that restarts numbering at the current list level.

For a `<text:list-level-style-number>` 16.32 element the default value for this attribute is `1`.

The `text:start-value` attribute is usable with the following element: `<text:list-level-style-number>` 16.32.
The `text:start-value` attribute has the data type `positiveInteger` 18.2.

19.868.5 <text:notes-configuration>

The `text:start-value` attribute specifies the value at which note numbering starts.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

For a <text:notes-configuration> 16.29.3 element the default value for this attribute is 1.

The text:start-value attribute is usable with the following element: <text:notes-configuration> 16.29.3.

The text:start-value attribute has the data type nonNegativeInteger 18.2.

19.868.6 <text:numbered-paragraph>

The text:start-value attribute specifies a value that restarts numbering of a numbered paragraph at the current item.

The text:start-value attribute is usable with the following element: <text:numbered-paragraph> 5.3.6.

The text:start-value attribute has the data type nonNegativeInteger 18.2.

19.868.7 <text:outline-level-style>

The text:start-value attribute specifies the first number of a heading item at the current level.

For a <text:outline-level-style> 16.35 element the default value for this attribute is 1.

The text:start-value attribute is usable with the following element: <text:outline-level-style> 16.35.

The text:start-value attribute has the data type positiveInteger 18.2.

19.869 text:start-numbering-at

The text:start-numbering-at attribute specifies if footnote numbers start with a new number at the beginning of the document or at the beginning of each chapter or page.

The defined values for the text:start-numbering-at attribute are:

- chapter: footnote numbers start with a new number at the beginning of a chapter.
- document: footnote numbers start with a new number at the beginning of a document.
- page: footnote numbers start with a new number at the beginning of a page.

The text:start-numbering-at attribute is usable with the following element: <text:notes-configuration> 16.29.3.

The values of the text:start-numbering-at attribute are document, chapter or page.

19.870 text:string-value-phonetic

The text:string-value-phonetic attribute specifies a phonetic description of a word.

The text:string-value-phonetic attribute is usable with the following elements: <text:alphabetical-index-mark> 8.1.10 and <text:alphabetical-index-mark-start> 8.1.8.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:string-value-phonetic` attribute has the data type `string` 18.2.

19.871 text:string-value

19.871.1 General

The `text:string-value` attribute specifies text for display.

19.871.2 <text:alphabetical-index-mark>

The `text:string-value` attribute specifies text to be displayed in an alphabetical index.

The `text:string-value` attribute is usable with the following element: `<text:alphabetical-index-mark>` 8.1.10.

The `text:string-value` attribute has the data type `string` 18.2.

19.871.3 <text:hidden-text>

The `text:string-value` attribute specifies the text to display if a `text:condition` attribute has the value of `false`. If this attribute is omitted, the element content is used.

The `text:string-value` attribute is usable with the following element: `<text:hidden-text>` 7.7.4.

The `text:string-value` attribute has the data type `string` 18.2.

19.871.4 <text:page-continuation>

The `text:string-value` attribute specifies continuation text to display. If this attribute is omitted, the element content is used.

The `text:string-value` attribute is usable with the following element: `<text:page-continuation>` 7.3.5.

The `text:string-value` attribute has the data type `string` 18.2.

19.871.5 <text:toc-mark>

The `text:string-value` attribute specifies text to be displayed in a table of contents.

The `text:string-value` attribute is usable with the following element: `<text:toc-mark>` 8.1.4.

The `text:string-value` attribute has the data type `string` 18.2.

19.871.6 <text:user-index-mark>

The `text:string-value` attribute specifies text to be displayed in an index.

The `text:string-value` attribute is usable with the following element: `<text:user-index-mark>` 8.1.7.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:string-value` attribute has the data type `string` 18.2.

19.872 text:string-value-if-false

The `text:string-value-if-false` attribute specifies text string to display if a condition is `false`.

The `text:string-value-if-false` attribute is usable with the following element: `<text:conditional-text>` 7.7.3.

The `text:string-value-if-false` attribute has the data type `string` 18.2.

19.873 text:string-value-if-true

The `text:string-value-if-true` attribute specifies a text string to display if a condition is `true`.

The `text:string-value-if-true` attribute is usable with the following element: `<text:conditional-text>` 7.7.3.

The `text:string-value-if-true` attribute has the data type `string` 18.2.

19.874 text:style-name

19.874.1 General

The `text:style-name` attribute specifies a style by name, with the additional requirement that it belong to a family of styles.

19.874.2 <text:a>

The `text:style-name` attribute specifies a text style for an unvisited hyperlink.

The `text:style-name` attribute is usable with the following element: `<text:a>` 6.1.8.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.3 <text:alphabetical-index>

The `text:style-name` attribute specifies a section family style.

The `text:style-name` attribute is usable with the following element: `<text:alphabetical-index>` 8.8.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.4 <text:alphabetical-index-entry-template>

The `text:style-name` attribute specifies a paragraph family style.

The `text:style-name` attribute is usable with the following element: `<text:alphabetical-index-entry-template>` 8.8.4.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.5 <text:bibliography>

The `text:style-name` attribute specifies a section family style.

The `text:style-name` attribute is usable with the following element: `<text:bibliography>` 8.9.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.6 <text:bibliography-entry-template>

The `text:style-name` attribute specifies a paragraph family style.

The `text:style-name` attribute is usable with the following element: `<text:bibliography-entry-template>` 8.9.3.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.7 <text:h>

The `text:style-name` attribute specifies a style that shall have the family paragraph. If a conditional style is applied, this attribute has the name of the style that was the result of the conditional style evaluation.

If both `text:style-name` and `text:class-names` are present, the style referenced by the `text:style-name` attribute is treated as the first style in the list in `text:class-names`. Consumers should support the `text:class-names` attribute and also should preserve it while editing.

The `text:style-name` attribute is usable with the following element: `<text:h>` 5.1.2.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.8 <text:illustration-index>

The `text:style-name` attribute specifies a section family style.

The `text:style-name` attribute is usable with the following element: `<text:illustration-index>` 8.4.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.9 <text:illustration-index-entry-template>

The `text:style-name` attribute specifies a paragraph family style.

The `text:style-name` attribute is usable with the following element: `<text:illustration-index-entry-template>` 8.4.3.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.874.10 <text:index-entry-bibliography>

The `text:style-name` attribute specifies character family styles.

The `text:style-name` attribute is usable with the following element: `<text:index-entry-bibliography>` 8.13.5.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.11 <text:index-entry-chapter>

The `text:style-name` attribute specifies character family styles.

The `text:style-name` attribute is usable with the following element: `<text:index-entry-chapter>` 8.13.1.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.12 <text:index-entry-link-end>

The `text:style-name` attribute specifies character family styles.

The `text:style-name` attribute is usable with the following element: `<text:index-entry-link-end>` 8.13.8.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.13 <text:index-entry-link-start>

The `text:style-name` attribute specifies character family styles.

The `text:style-name` attribute is usable with the following element: `<text:index-entry-link-start>` 8.13.7.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.14 <text:index-entry-page-number>

The `text:style-name` attribute specifies character family styles.

The `text:style-name` attribute is usable with the following element: `<text:index-entry-page-number>` 8.13.3.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.15 <text:index-entry-span>

The `text:style-name` attribute specifies character family styles.

The `text:style-name` attribute is usable with the following element: `<text:index-entry-span>` 8.13.4.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.874.16 <text:index-entry-tab-stop>

The `text:style-name` attribute specifies character family styles.

The `text:style-name` attribute is usable with the following element: `<text:index-entry-tab-stop>` 8.13.6.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.17 <text:index-entry-text>

The `text:style-name` attribute specifies character family styles.

The `text:style-name` attribute is usable with the following element: `<text:index-entry-text>` 8.13.2.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.18 <text:index-source-style>

The `text:style-name` attribute specifies a paragraph family style.

The `text:style-name` attribute is usable with the following element: `<text:index-source-style>` 8.11.

The `text:style-name` attribute has the data type `styleName` 18.3.31.

19.874.19 <text:index-title>

The `text:style-name` attribute specifies section family styles.

The `text:style-name` attribute is usable with the following element: `<text:index-title>` 8.2.3.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.20 <text:index-title-template>

The `text:style-name` attribute specifies character family styles.

The `text:style-name` attribute is usable with the following element: `<text:index-title-template>` 8.12.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.21 <text:linenumbering-configuration>

The `text:style-name` attribute specifies a `text` style.

The `text:style-name` attribute is usable with the following element: `<text:linenumbering-configuration>` 16.29.1.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.874.22 <text:list>

The `text:style-name` attribute specifies the name of a list style that is applied to a list.

If this attribute is not included and therefore no list style is specified, one of the following actions is taken:

- If a list is contained within another list, the list style defaults to the style of the surrounding list.
- If there is no list style specified for the surrounding list, but the list's list items contain paragraphs that have paragraph styles attached specifying a list style, that list style is used.
- An implementation-dependent default list style is used.

To determine which formatting properties are applied to a list, the list level and list style name are taken into account.

The `text:style-name` attribute is usable with the following element: `<text:list>` 5.3.1.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.23 <text:list-level-style-number>

The `text:style-name` attribute specifies a `text` style.

The `text:style-name` attribute is usable with the following element: `<text:list-level-style-number>` 16.32.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.24 <text:list-level-style-bullet>

The `text:style-name` attribute specifies character family styles.

The `text:style-name` attribute is usable with the following element: `<text:list-level-style-bullet>` 16.31.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.25 <text:numbered-paragraph>

The `text:style-name` attribute specifies the name of a list style that is applied to a list.

If this attribute is not included and therefore no list style is specified, one of the following actions is taken:

- If the list is contained within another list, the list style defaults to the style of the surrounding list.
- If there is no list style specified for the surrounding list, but the list contains paragraphs that have paragraph styles attached specifying a list style, this list style is used for any of these paragraphs.
- An implementation-dependent default list style is applied to any other paragraphs.

To determine which formatting properties are applied to a list, the list level and list style name are taken into account.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:style-name` attribute is usable with the following element: `<text:numbered-paragraph>` 5.3.6.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.26 <text:object-index>

The `text:style-name` attribute specifies section family styles.

The `text:style-name` attribute is usable with the following element: `<text:object-index>` 8.6.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.27 <text:object-index-entry-template>

The `text:style-name` attribute specifies a paragraph family style.

The `text:style-name` attribute is usable with the following element: `<text:object-index-entry-template>` 8.6.3.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.28 <text:outline-level-style>

The `text:style-name` attribute specifies character family styles.

The `text:style-name` attribute is usable with the following element: `<text:outline-level-style>` 16.35.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.29 <text:p>

The `text:style-name` attribute specifies a style that shall have the family paragraph. If a conditional style is applied, this attribute has the name of the style that was the result of the conditional style evaluation.

If both `text:style-name` and `text:class-names` are present, the style referenced by the `text:style-name` attribute is treated as the first style in the list in `text:class-names`. Consumers should support the `text:class-names` attribute and also should preserve it while editing.

The `text:style-name` attribute is usable with the following element: `<text:p>` 5.1.3.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.30 <text:ruby>

The `text:style-name` attribute specifies a style for ruby which shall be a style with family of ruby.

The `text:style-name` attribute is usable with the following element: `<text:ruby>` 6.4.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.31 <text:ruby-text>

The `text:style-name` attribute specifies a style for ruby which shall be a style with family of text.

The `text:style-name` attribute is usable with the following element: `<text:ruby-text>` 6.4.3.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.32 <text:section>

The `text:style-name` attribute specifies a section family style for a section.

The `text:style-name` attribute is usable with the following element: `<text:section>` 5.4.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.33 <text:span>

The `text:style-name` attribute specifies style for span which shall be a style with family of `text`.

If both `text:style-name` and `text:class-names` are present, the style referenced by the `text:style-name` attribute is treated as the first style in the list in `text:class-names`. Consumers should support the `text:class-names` attribute and also should preserve it while editing.

The `text:style-name` attribute is usable with the following element: `<text:span>` 6.1.7.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.34 <text:table-index-entry-template>

The `text:style-name` attribute specifies a paragraph family style.

The `text:style-name` attribute is usable with the following element: `<text:table-index-entry-template>` 8.5.3.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.35 <text:table-of-content>

The `text:style-name` attribute specifies a section family style.

The `text:style-name` attribute is usable with the following element: `<text:table-of-content>` 8.3.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.874.36 <text:table-of-content-entry-template>

The `text:style-name` attribute specifies a paragraph family style.

The `text:style-name` attribute is usable with the following element: `<text:table-of-content-entry-template>` 8.3.3.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.37 <text:table-index>

The `text:style-name` attribute specifies section family styles.

The `text:style-name` attribute is usable with the following element: `<text:table-index>` 8.5.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.38 <text:user-index>

The `text:style-name` attribute specifies a section family style.

The `text:style-name` attribute is usable with the following element: `<text:user-index>` 8.7.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.874.39 <text:user-index-entry-template>

The `text:style-name` attribute specifies a paragraph family style.

The `text:style-name` attribute is usable with the following element: `<text:user-index-entry-template>` 8.7.3.

The `text:style-name` attribute has the data type `styleNameRef` 18.3.32.

19.875 text:style-override

The `text:style-override` attribute specifies an override to the list style to be applied to a list item.

The `text:style-override` attribute is usable with the following element: `<text:list-item>` 5.3.4.

The `text:style-override` attribute has the data type `styleNameRef` 18.3.32.

19.876 text:suffix

The `text:suffix` attribute specifies a string that is displayed after a bibliography entry's short name or number if it occurs outside the bibliography.

The `text:suffix` attribute is usable with the following element: `<text:bibliography-configuration>` 16.29.6.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The text:suffix attribute has the data type string 18.2.

19.877 text:tab-ref

The text:tab-ref attribute contains the number of the tab-stop to which a tab character refers. The position 0 marks the start margin of a paragraph.

Note: The text:tab-ref attribute is only a hint to help non-layout oriented consumers to determine the tab/tab-stop association. Layout oriented consumers should determine the tab positions based on the style information.

The text:tab-ref attribute is usable with the following element: <text:tab> 6.1.4.

The text:tab-ref attribute has the data type nonNegativeInteger 18.2.

19.878 text:table-name

The text:table-name attribute specifies a table within a source database.

The text:table-name attribute is usable with the following elements: <text:database-display> 7.6.3, <text:database-name> 7.6.7, <text:database-next> 7.6.4, <text:database-row-number> 7.6.6 and <text:database-row-select> 7.6.5.

The text:table-name attribute has the data type string 18.2.

19.879 text:table-type

The text:table-type attribute specifies the type of reference made by to a database.

The defined values for the text:table-type attribute are:

- table : the value of the text:table-name attribute is the name of a database table.
- query : the value of the text:table-name attribute is the name of a database query.
- command : the value of the text:table-name attribute is an SQL statement.

The text:table-type attribute is usable with the following elements: <text:database-display> 7.6.3, <text:database-name> 7.6.7, <text:database-next> 7.6.4, <text:database-row-number> 7.6.6 and <text:database-row-select> 7.6.5.

The values of the text:table-type attribute are table, query or command.

19.880 text:time-adjust

The text:time-adjust attribute specifies an adjustment of the value of a time by a specific time period. Positive values adjust the time to a time in the future, while negative values adjust the time to a time in the past. Duration values are truncated to full minutes.

Note: Truncation of time values is defined by number:truncate-on-overflow. 19.365

The text:time-adjust attribute is usable with the following element: <text:time> 7.3.3.

The text:time-adjust attribute has the data type duration 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.881 text:time-value

The `text:time-value` attribute specifies the time at which a document was last edited.

If no value is specified, whether the field is marked as fixed or not, the current time is assumed.

The `text:time-value` attribute is usable with the following elements: `<text:creation-time>` 7.5.4, `<text:modification-time>` 7.5.15, `<text:print-time>` 7.5.7 and `<text:time>` 7.3.3.

The `text:time-value` attribute has the data type `timeOrDateTime` 18.3.36.

19.882 text:title

The `text:title` attribute specifies a title for a bibliography index entry.

The `text:title` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:title` attribute has the data type `string` 18.2.

19.883 text:track-changes

The `text:track-changes` attribute specifies whether changes to the document should be tracked and recorded.

The defined values for the `text:sort-ascending` attribute are:

- `false`: changes are not tracked.
- `true`: changes are tracked.

The default value for this attribute is `true`.

The `text:track-changes` attribute is usable with the following element: `<text:tracked-changes>` 5.5.1.

The `text:track-changes` attribute has the data type `boolean` 18.3.3.

19.884 text:url

The `text:url` attribute specifies an IRI for a bibliography index entry.

The `text:url` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:url` attribute has the data type `string` 18.2.

19.885 text:use-caption

The `text:use-caption` attribute specifies whether captions or names of illustrations or tables are used for an index.

The defined values of the `text:use-caption` attribute are:

- `false`: illustration or table names are used for an index.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: illustration or table captions are used for an index.

The default value for this attribute is `true`.

The `text:use-caption` attribute is usable with the following elements: `<text:illustration-index-source>` 8.4.2 and `<text:table-index-source>` 8.5.2.

The `text:use-caption` attribute has the data type `boolean` 18.3.3.

19.886 text:use-chart-objects

The `text:use-chart-objects` attribute specifies whether to include embedded chart objects in an index of objects.

The defined values for the `text:use-chart-objects` attribute are:

- `false`: object is not included in index of objects.
- `true`: object is included in index of objects.

The default value for this attribute is `false`.

The `text:use-chart-objects` attribute is usable with the following element: `<text:object-index-source>` 8.6.2.

The `text:use-chart-objects` attribute has the data type `boolean` 18.3.3.

19.887 text:use-draw-objects

The `text:use-draw-objects` attributes specifies whether embedded draw objects (defined by `<draw:object>` 10.4.6.2 elements) will be included in an index of objects.

The defined values for the `text:use-draw-objects` attribute are:

- `false`: draw objects not included in an index of objects.
- `true`: draw objects included in an index of objects.

The default value for this attribute is `false`.

The `text:use-draw-objects` attribute is usable with the following element: `<text:object-index-source>` 8.6.2.

The `text:use-draw-objects` attribute has the data type `boolean` 18.3.3.

19.888 text:use-floating-frames

The `text:use-floating-frames` attribute specifies whether text boxes will be included n user-defined indexes.

The defined values for the `text:use-floating-frames` attribute are:

- `false`: text boxes not included in user-defined indexes.
- `true`: text boxes included in user-defined indexes.

The default value for this attribute is `false`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:use-floating-frames` attribute is usable with the following element: `<text:user-index-source>` 8.7.2.

The `text:use-floating-frames` attribute has the data type `boolean` 18.3.3.

19.889 text:use-graphics

The `text:use-graphics` attribute specifies whether graphics are include in user-defined indexes.

The defined values for the `text:use-graphics` attribute are:

- `false`: graphics are not included in user-defined indexes.
- `true`: graphics are included in user-defined indexes.

The default value for this attribute is `false`.

The `text:use-graphics` attribute is usable with the following element: `<text:user-index-source>` 8.7.2.

The `text:use-graphics` attribute has the data type `boolean` 18.3.3.

19.890 text:use-index-marks

The `text:use-index-marks` attribute specifies whether table of contents index marks are used to generate index entries. The `text:outline-level` attribute specifies up to which level index marks are being included.19.844

The defined values for the `text:use-index-marks` attribute are:

- `false`: table of contents does not include entries generated from table of contents index marks.
- `true`: table of contents does include entries generated from table of contents index marks.

For a `<text:user-index-source>` 8.7.2 element the default value for this attribute is `false`.

The `text:use-index-marks` attribute is usable with the following elements: `<text:table-of-content-source>` 8.3.2 and `<text:user-index-source>` 8.7.2.

The `text:use-index-marks` attribute has the data type `boolean` 18.3.3.

19.891 text:use-index-source-styles

The `text:use-index-source-styles` attribute specifies whether index entries are generated for paragraphs formatted using the paragraph styles listed in the `<text:index-source-styles>` element.

The `text:outline-level` attribute specifies up to which level index source styles are being included. 19.844

The defined values for the `text:use-index-source-styles` attribute are:

- `false`: index entries are not generated for paragraphs formatted using the paragraph styles listed in a `<text:index-source-styles>` element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: index entries are generated for paragraphs formatted using the paragraph styles listed in a `<text:index-source-styles>` element.

For a `<text:user-index-source>` 8.7.2 element the default value for this attribute is `false`.

The `text:use-index-source-styles` attribute is usable with the following elements: `<text:table-of-content-source>` 8.3.2 and `<text:user-index-source>` 8.7.2.

The `text:use-index-source-styles` attribute has the data type `boolean` 18.3.3.

19.892 text:use-keys-as-entries

The `text:use-keys-as-entries` attribute specifies the use of the up to two keys for an index mark as entries in the index.

The defined values for the `text:use-keys-as-entries` attribute are:

- `false`: additional keys are used as sub entries.
- `true`: additional keys are used as additional entries.

The default value for this attribute is `false`.

The `text:use-keys-as-entries` attribute is usable with the following element: `<text:alphabetical-index-source>` 8.8.2.

The `text:use-keys-as-entries` attribute has the data type `boolean` 18.3.3.

19.893 text:use-math-objects

The `text:use-math-objects` attribute specifies whether embedded math objects are included in an index of objects.

The defined values for the `text:use-math-objects` attribute are:

- `false`: math objects are not included in an index of objects.
- `true`: math objects are included in an index of objects.

The default value for this attribute is `false`.

The `text:use-math-objects` attribute is usable with the following element: `<text:object-index-source>` 8.6.2.

The `text:use-math-objects` attribute has the data type `boolean` 18.3.3.

19.894 text:use-objects

The `text:use-objects` attributes specifies whether an object is included in a user defined index.

The defined values for the `text:use-objects` attribute are:

- `false`: objects are not included in a user define index.
- `true`: objects are included in a user defined index.

The default value for this attribute is `false`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:use-objects` attribute is usable with the following element: `<text:user-index-source>` 8.7.2.

The `text:use-objects` attribute has the data type `boolean` 18.3.3.

19.895 text:use-other-objects

The `text:use-other-objects` attribute specifies whether other embedded objects are included in an index of objects. Other objects are those not covered by `text:use-chart-objects`, `text:use-draw-objects`, `text:use-math-objects`, and `text:use-spreadsheet-objects` attributes.

The defined values for the `text:use-other-objects` attribute are:

- `false`: other objects are not included in an index of objects.
- `true`: other objects are included in an index of objects.

The default value for this attribute is `false`.

The `text:use-other-objects` attribute is usable with the following element: `<text:object-index-source>` 8.6.2.

The `text:use-other-objects` attribute has the data type `boolean` 18.3.3.

19.896 text:use-outline-level

The `text:use-outline-level` attribute specifies whether headings are used to generate index entries. The `text:outline-level` attribute specifies up to which level headings are being included. 19.844

The defined values for the `text:use-outline-level` attribute are:

- `false`: table of contents does not include entries generated from headings.
- `true`: table of contents does include entries generated from headings.

The default value for this attribute is `true`.

The `text:use-outline-level` attribute is usable with the following element: `<text:table-of-content-source>` 8.3.2.

The `text:use-outline-level` attribute has the data type `boolean` 18.3.3.

19.897 text:use-soft-page-breaks

The `text:use-soft-page-breaks` attribute specifies whether a document contains soft page breaks.

A soft page break is a page break that has been included in a document by a page oriented consumer at a position where the document itself does not include a page break as defined by `fo:break-after` 20.178 or `fo:break-before` 20.178.

Soft page breaks are specified by the `<text:soft-page-break>` element.

OpenDocument producers need not produce`<text:soft-page-break>` elements. They may include them if they have computed a paginated layout. Consumers may handle the element

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

while computing the layout, but it shall not depend on its existence. Soft page breaks are only defined for text documents.

Producers that store soft page breaks shall indicate this by setting the `text:use-soft-page-breaks` attribute to `true`. Producers that do not store soft page breaks shall indicate that by omitting this attribute, or by setting it to false.

A producer that does not support pagination and soft page-breaks and that modifies an OpenDocument file, which includes soft page-breaks, shall set the `text:use-soft-page-breaks` attribute to `false` (or remove it). It should also remove the `<text:soft-page-break>` elements from the document.

Producers that compute a paginated layout of a document should provide a facility for the export of soft page breaks for the purposes of consistent page breaks and for conversion to talking book formats ([DAISY]).

For `<text:soft-page-break>` elements that appear within table rows, the maximum number of `<text:soft-page-break>` elements that appear within the single table cells determines the number of page breaks that appear within the table row. The `<text:soft-page-break>` elements contained in each cell determine the positions where these page breaks appear within the cell content.

When `<text:soft-page-break>` elements appear within text boxes and other content displayed outside the text flow, they do not start a new page, but only indicate where the text-box's content breaks between two pages.

The defined values for the `text:use-soft-page-breaks` attribute are:

- `false`: soft page breaks not supported.
- `true`: soft page breaks supported.

The default value for this attribute is `false`.

The `text:use-soft-page-breaks` attribute is usable with the following element: `<office:text>` 3.4.

The `text:use-soft-page-breaks` attribute has the data type `boolean` 18.3.3.

19.898 text:use-spreadsheet-objects

The `text:use-spreadsheet-objects` attribute specifies whether embedded spreadsheet objects will appear in an object index.

The defined values for the `text:use-spreadsheet-objects` attribute are:

- `false`: spreadsheet objects do not appear in an object index.
- `true`: spreadsheet objects do appear in an object index.

The default value for this attribute is `false`.

The `text:use-spreadsheet-objects` attribute is usable with the following element: `<text:object-index-source>` 8.6.2.

The `text:use-spreadsheet-objects` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.899 text:use-tables

The `text:use-tables` attribute specifies whether tables will appear in a user defined index.

The defined values for the `text:use-tables` attribute are:

- `false`: tables will not appear in a user defined index.
- `true`: tables will appear in a user defined index.

The default value for this attribute is `false`.

The `text:use-tables` attribute is usable with the following element: `<text:user-index-source>` 8.7.2.

The `text:use-tables` attribute has the data type `boolean` 18.3.3.

19.900 text:value

The `text:value` attribute specifies the current row number for a `<text:database-row-number>` element. The number changes when new data is added to the current document.

The `text:value` attribute is usable with the following element: `<text:database-row-number>` 7.6.6.

The `text:value` attribute has the data type `nonNegativeInteger` 18.2.

19.901 text:visited-style-name

The `text:visited-style-name` attribute specifies a style for a hyperlink that has been visited.

The `text:visited-style-name` attribute is usable with the following element: `<text:a>` 6.1.8.

The `text:visited-style-name` attribute has the data type `styleNameRef` 18.3.32.

19.902 text:volume

The `text:volume` attribute specifies a volume for a bibliography index entry.

The `text:volume` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:volume` attribute has the data type `string` 18.2.

19.903 text:year

The `text:year` attribute specifies a year for a bibliography index entry.

The `text:year` attribute is usable with the following element: `<text:bibliography-mark>` 8.1.11.

The `text:year` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.904 xforms:bind

The `xforms:bind` attribute specifies the binding of a OpenDocument control to an XForm form.

With OpenDocument form buttons, the bind attribute refers to an `<xforms:submission>` element with the given ID. Pushing the button causes the appropriate XForms submission action to be performed.

Note: OpenDocument form button controls are: `<form:button>` 13.5.15, and, `<form:image>` 13.5.16.

With OpenDocument form non-button controls, the `xforms:bind` attribute refers to an `<xforms:bind>` element with the given ID. Any such bound control reads and writes its data as determined by the appropriate bind element.

Note: OpenDocument form non-button controls are: `<form:checkbox>` 13.5.17, `<form:column>` 13.5.23, `<form:combobox>` 13.5.11, `<form:date>` 13.5.8, `<form:file>` 13.5.5, `<form:fixed-text>` 13.5.10, `<form:formatted-text>` 13.5.6, `<form:frame>` 13.5.19, `<form:generic-control>` 13.5.25, `<form:grid>` 13.5.22, `<form:hidden>` 13.5.21, `<form:image-frame>` 13.5.20, `<form:item>` 13.5.12, `<form:listbox>` 13.5.13, `<form:number>` 13.5.7, `<form:option>` 13.5.14, `<form:password>` 13.5.4,`<form:radio>` 13.5.18, `<form:text>` 13.5.2, `<form:textarea>` 13.5.3, `<form:time>` 13.5.9, and `<form:value-range>` 13.5.24.

The `xforms:bind` attribute is usable with the following elements: `<form:button>` 13.5.15, `<form:checkbox>` 13.5.17, `<form:combobox>` 13.5.11, `<form:date>` 13.5.8, `<form:file>` 13.5.5, `<form:fixed-text>` 13.5.10, `<form:formatted-text>` 13.5.6, `<form:frame>` 13.5.19, `<form:generic-control>` 13.5.25, `<form:grid>` 13.5.22, `<form:hidden>` 13.5.21, `<form:image>` 13.5.16, `<form:image-frame>` 13.5.20, `<form:listbox>` 13.5.13, `<form:number>` 13.5.7, `<form:password>` 13.5.4, `<form:radio>` 13.5.18, `<form:text>` 13.5.2, `<form:textarea>` 13.5.3, `<form:time>` 13.5.9 and `<form:value-range>` 13.5.24.

The `xforms:bind` attribute has the data type `string` 18.2.

19.905 xhtml:about

The `xhtml:about` attribute specifies the subject of an RDF statement for in content metadata. Predicates for RDF statements are specified by the `xhtml:property` attribute. 19.908

The RDF statement's object is specified by the `xhtml:content` attribute, if present, or it is

- the literal content between a pair of `<text:bookmark-start>` and `<text:bookmark-end>` elements that are paired by the values of their `text:name` attributes. 6.2.1.3, 6.2.1.4
- for elements other than `<text:bookmark-start>`/`<text:bookmark-end>`, the literal content of the element containing an `xhtml:about` attribute.

The `xhtml:datatype` attribute provides the data type of the RDF object. 19.907

The `xhtml:about` attribute is usable with the following elements: `<table:covered-table-cell>` 9.1.5, `<table:table-cell>` 9.1.4, `<text:bookmark-start>` 6.2.1.3, `<text:h>` 5.1.2, `<text:meta>` 6.1.9 and `<text:p>` 5.1.3.

The `xhtml:about` attribute has the data type `URIorSafeCURIE` 18.3.37.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.906 xhtml:content

The `xhtml:content` attribute specifies an object of an RDF statement for in content metadata. 19.905.

The `xhtml:content` attribute is usable with the following elements: `<table:covered-table-cell>` 9.1.5, `<table:table-cell>` 9.1.4, `<text:bookmark-start>` 6.2.1.3, `<text:h>` 5.1.2, `<text:meta>` 6.1.9 and `<text:p>` 5.1.3.

The `xhtml:content` attribute has the data type `string` 18.2.

19.907 xhtml:datatype

The `xhtml:datatype` attribute specifies the RDF data type (see §5 of [RDF-CONCEPTS]) of the object of an RDF statement.

The `xhtml:datatype` attribute is usable with the following elements: `<table:covered-table-cell>` 9.1.5, `<table:table-cell>` 9.1.4, `<text:bookmark-start>` 6.2.1.3, `<text:h>` 5.1.2, `<text:meta>` 6.1.9 and `<text:p>` 5.1.3.

The `xhtml:datatype` attribute has the data type `CURIE` 18.3.12.

19.908 xhtml:property

The `xhtml:property` attribute specifies a list of one or more CURIEs. Each CURIE is the predicate of an RDF statement for in content metadata. 19.905.

The `xhtml:property` attribute is usable with the following elements: `<table:covered-table-cell>` 9.1.5, `<table:table-cell>` 9.1.4, `<text:bookmark-start>` 6.2.1.3, `<text:h>` 5.1.2, `<text:meta>` 6.1.9 and `<text:p>` 5.1.3.

The `xhtml:property` attribute has the data type `CURIEs` 18.3.13.

19.909 xlink:actuate

See §5.6.2 of [XLink].

The `xlink:actuate` attribute has the value `onRequest` for the following elements: `<db:component>` 12.25.5, `<db:connection-resource>` 12.7, `<draw:a>` 10.4.12, `<form:form>` 13.3, `<meta:template>` 4.3.2.12, `<presentation:event-listener>` 10.9.2, `<presentation:sound>` 10.8.2, `<script:event-listener>` 14.4.2, `<svg:definition-src>` 16.25, `<svg:font-face-uri>` 16.24, `<table:cell-range-source>` 9.3.1, `<table:table-source>` 9.2.6 and `<text:a>` 6.1.8.

The `xlink:actuate` attribute has the value `onLoad` for the following elements: `<draw:applet>` 10.4.7, `<draw:fill-image>` 16.40.6, `<draw:floating-frame>` 10.4.10, `<draw:image>` 10.4.4, `<draw:object>` 10.4.6.2, `<draw:object-ole>` 10.4.6.3, `<draw:plugin>` 10.4.8, `<meta:auto-reload>` 4.3.2.13, `<style:background-image>` 17.3 and `<text:list-level-style-image>` 16.33.

For `<db:connection-resource>` 12.7, `<draw:a>` 10.4.12, `<form:form>` 13.3, `<meta:template>` 4.3.2.12, `<presentation:event-listener>` 10.9.2, `<presentation:sound>` 10.8.2, `<script:event-listener>` 14.4.2, `<svg:definition-src>` 16.25, `<svg:font-face-uri>` 16.24, `<table:cell-range-source>` 9.3.1,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<table:table-source> 9.2.6 and <text:a> 6.1.8 elements the default value for this attribute is onRequest.

For <draw:applet> 10.4.7, <draw:fill-image> 16.40.6, <draw:floating-frame> 10.4.10, <draw:image> 10.4.4, <draw:object> 10.4.6.2, <draw:object-ole> 10.4.6.3, <draw:plugin> 10.4.8, <meta:auto-reload> 4.3.2.13, <style:background-image> 17.3 and <text:list-level-style-image> 16.33 elements the default value for this attribute is onLoad.

The xlink:actuate attribute is usable with the following elements: <db:component> 12.25.5, <db:connection-resource> 12.7, <draw:a> 10.4.12, <draw:applet> 10.4.7, <draw:fill-image> 16.40.6, <draw:floating-frame> 10.4.10, <draw:image> 10.4.4, <draw:object> 10.4.6.2, <draw:object-ole> 10.4.6.3, <draw:plugin> 10.4.8, <form:form> 13.3, <meta:auto-reload> 4.3.2.13, <meta:template> 4.3.2.12, <presentation:event-listener> 10.9.2, <presentation:sound> 10.8.2, <script:event-listener> 14.4.2, <style:background-image> 17.3, <svg:definition-src> 16.25, <svg:font-face-uri> 16.24, <table:cell-range-source> 9.3.1, <table:table-source> 9.2.6, <text:a> 6.1.8 and <text:list-level-style-image> 16.33.

19.910 xlink:href

19.910.1 General

The xlink:href attribute specifies a remote resource. Its data type is anyURI. See §5.4 of [XLink].

19.910.2 <anim:audio>

The xlink:href attribute specifies an audio stream.

The xlink:href attribute is usable with the following element: <anim:audio> 15.5.

The xlink:href attribute has the data type anyIRI 18.3.2.

19.910.3 <chart:chart>

The xlink:href attribute at the <chart:chart> element specifies the document which provides the data for a chart. The following values are supported:

- "."(U+002E, FULL STOP): The data is provided by the chart document itself. It is taken from the <table:table> element inside the <chart:chart> element.
- ".."(U+002E, FULL STOP followed by U+002E, FULL STOP): The data is provided by the document into which the chart is embedded. This is only supported if the chart is embedded into another document.
- A relative IRI: The data is provided by an embedded object referenced by the IRI. This embedded object shall be within the same package as the chart itself.

All cell range addresses that are specified within a chart are relative to the document referenced by the xlink:href attribute.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If the xlink:href attribute is omitted, its value is assumed to be ". ." (U+002E, FULL STOP followed by U+002E, FULL STOP).

The xlink:href attribute is usable with the following element: <chart:chart> 11.1.

The xlink:href attribute has the data type anyIRI 18.3.2.

19.910.4 <chart:symbol-image>

The xlink:href attribute specifies a file containing an image.

The xlink:href attribute is usable with the following element: <chart:symbol-image> 17.23.

The xlink:href attribute has the data type anyIRI 18.3.2.

19.910.5 <db:component>

The xlink:href attribute specifies a form or report document.

The xlink:href attribute is usable with the following element: <db:component> 12.25.5.

The xlink:href attribute has the data type anyIRI 18.3.2.

19.910.6 <db:connection-resource>

The xlink:href attribute specifies either a database, or database connection data encoded as an IRI.

The xlink:href attribute is usable with the following element: <db:connection-resource> 12.7.

The xlink:href attribute has the data type anyIRI 18.3.2.

19.910.7 <db:file-based-database>

The xlink:href attribute specifies the location of a file that defines a database. If a database consists of multiple files of different types which all are required for it to be operational, xlink:href points to one of those files which defines the database as a whole.

The xlink:href attribute is usable with the following element: <db:file-based-database> 12.5.

The xlink:href attribute has the data type anyIRI 18.3.2.

19.910.8 <draw:a>

The xlink:href attribute specifies a target location for the hyperlink.

The xlink:href attribute is usable with the following element: <draw:a> 10.4.12.

The xlink:href attribute has the data type anyIRI 18.3.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.910.9 <draw:applet>

The `xlink:href` attribute specifies the base IRI for an applet. If the `xlink:href` attribute is not specified, then the base IRI of an applet is the same as the file entry base IRI (see 2.6 of OpenDocument part 3) of the file containing the `<draw:applet>` element.

The `xlink:href` attribute is usable with the following element: `<draw:applet>` 10.4.7.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.10 <draw:area-circle>

The `xlink:href` attribute specifies a target location for the hyperlink.

The `xlink:href` attribute is usable with the following element: `<draw:area-circle>` 10.4.13.4.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.11 <draw:area-polygon>

The `xlink:href` attribute specifies a target location for the hyperlink.

The `xlink:href` attribute is usable with the following element: `<draw:area-polygon>` 10.4.13.5.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.12 <draw:area-rectangle>

The `xlink:href` attribute specifies a target location for the hyperlink.

The `xlink:href` attribute is usable with the following element: `<draw:area-rectangle>` 10.4.13.3.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.13 <draw:fill-image>

The `xlink:href` attribute specifies a file containing an image.

The `xlink:href` attribute is usable with the following element: `<draw:fill-image>` 16.40.6.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.14 <draw:floating-frame>

The `xlink:href` attribute specifies the source of a floating frame.

The `xlink:href` attribute is usable with the following element: `<draw:floating-frame>` 10.4.10.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

19.910.15 <draw:image>

The `xlink:href` attribute specifies a file containing an image.

The `xlink:href` attribute is usable with the following element: `<draw:image>` 10.4.4.
The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.16 <draw:object>

The `xlink:href` attribute specifies the location of an embedded object.

The `xlink:href` attribute is usable with the following element: `<draw:object>` 10.4.6.2.
The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.17 <draw:object-ole>

The `xlink:href` attribute specifies the location of an embedded object.

The `xlink:href` attribute is usable with the following element: `<draw:object-ole>` 10.4.6.3.
The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.18 <draw:plugin>

The `xlink:href` attribute specifies the source of a plugin.

The `xlink:href` attribute is usable with the following element: `<draw:plugin>` 10.4.8.
The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.19 <form:button>

The `xlink:href` attribute specifies a resource that is loaded if a button is operated.

The `xlink:href` attribute is usable with the following element: `<form:button>` 13.5.15.
The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.20 <form:connection-resource>

The `xlink:href` attribute specifies either a database, or database connection encoded as an IRI.

The `xlink:href` attribute is usable with the following element: `<form:connection-resource>` 7.6.2.
The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.21 <form:image>

The `xlink:href` attribute specifies a resource that is loaded if a button is operated.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `xlink:href` attribute is usable with the following element: `<form:image>` 13.5.16.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.22 <form:form>

The `xlink:href` attribute specifies the processing agent for a form.

The `xlink:href` attribute is usable with the following element: `<form:form>` 13.3.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.23 <meta:auto-reload>

The `xlink:href` attribute specifies the IRI of a replacement document.

The `xlink:href` attribute is usable with the following element: `<meta:auto-reload>` 4.3.2.13.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.24 <meta:template>

The `xlink:href` attribute specifies the location of a document template.

The `xlink:href` attribute is usable with the following element: `<meta:template>` 4.3.2.12.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.25 <presentation:event-listener>

The `xlink:href` attribute specifies depending on the action selected by the `presentation:action` attribute either a document bookmark or an application.

The `xlink:href` attribute is usable with the following element: `<presentation:event-listener>` 10.9.2.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.26 <presentation:sound>

The `xlink:href` attribute specifies a sound that is played when an effect is executed.

The `xlink:href` attribute is usable with the following element: `<presentation:sound>` 10.8.2.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.27 <script:event-listener>

The `xlink:href` attribute specifies macro code that should be called for an event. The IRI may have any protocol. The interpretation of the IRI is script language dependent.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `xlink:href` attribute is usable with the following element: `<script:event-listener>` 14.4.2.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.28 <style:background-image>

The `xlink:href` attribute specifies an image.

The `xlink:href` attribute is usable with the following element: `<style:background-image>` 17.3.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.29 <svg:definition-src>

See § 20.8.3 of [SVG].

The `xlink:href` attribute is usable with the following element: `<svg:definition-src>` 16.25.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.30 <svg:font-face-uri>

See § 20.8.3 of [SVG].

The `xlink:href` attribute is usable with the following element: `<svg:font-face-uri>` 16.24.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.31 <table:cell-range-source>

The `xlink:href` attribute specifies an IRI for a document containing a source table.

The `xlink:href` attribute is usable with the following element: `<table:cell-range-source>` 9.3.1.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.32 <table:table-source>

The `xlink:href` attribute specifies an IRI of a document containing a source table.

The `xlink:href` attribute is usable with the following element: `<table:table-source>` 9.2.6.

The `xlink:href` attribute has the data type `anyIRI` 18.3.2.

19.910.33 <text:a>

The `xlink:href` attribute specifies the target location of a hyperlink.

The `xlink:href` attribute is usable with the following element: `<text:a>` 6.1.8.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The xlink:href attribute has the data type anyIRI 18.3.2.

19.910.34 <text:alphabetical-index-auto-mark-file>

The xlink:href attribute specifies the location of an alphabetical index mark file that contains a list of terms.

The xlink:href attribute is usable with the following element: <text:alphabetical-index-auto-mark-file> 8.8.3.

The xlink:href attribute has the data type anyIRI 18.3.2.

19.910.35 <text:list-level-style-image>

The xlink:href attribute specifies an image.

The xlink:href attribute is usable with the following element: <text:list-level-style-image> 16.33.

The xlink:href attribute has the data type anyIRI 18.3.2.

19.910.36 <text:script>

The xlink:href attribute specifies the location script source code.

The xlink:href attribute is usable with the following element: <text:script> 7.7.9.

The xlink:href attribute has the data type anyIRI 18.3.2.

19.910.37 <text:section-source>

The xlink:href attribute specifies the document or document fragment to which a section is linked. If the IRI contains a fragment identifier, and if the referenced document is an OpenDocument document, the fragment identifier should be interpreted as the name of a section to which a section is linked. A fragment identifier should be ignored if a text:section-name attribute is present.

The xlink:href attribute is usable with the following element: <text:section-source> 5.4.2.

The xlink:href attribute has the data type anyIRI 18.3.2.

19.911 xlink:show

See §5.6.1 of [XLink].

For a <meta:auto-reload> 4.3.2.13 element the value for this attribute is replace.

For <draw:applet> 10.4.7, <draw:fill-image> 16.40.6, <draw:floating-frame> 10.4.10, <draw:image> 10.4.4, <draw:object> 10.4.6.2, <draw:object-ole> 10.4.6.3, <draw:plugin> 10.4.8, <presentation:event-listener> 10.9.2, <style:background-image> 17.3, <text:list-level-style-image> 16.33 and <text:section-source> 5.4.2 elements the value for this attribute is embed.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

For <draw:a> 10.4.12, <draw:area-circle> 10.4.13.4, <draw:area-polygon> 10.4.13.5, <draw:area-rectangle> 10.4.13.3, <meta:hyperlink-behaviour> 4.3.2.14, <presentation:sound> 10.8.2 and <text:a> 6.1.8 elements the supported values for this attribute are new or replace.

For a <meta:auto-reload> 4.3.2.13 element the default value for this attribute is replace.

For <draw:applet> 10.4.7, <draw:fill-image> 16.40.6, <draw:floating-frame> 10.4.10, <draw:image> 10.4.4, <draw:object> 10.4.6.2, <draw:object-ole> 10.4.6.3, <draw:plugin> 10.4.8, <presentation:event-listener> 10.9.2, <style:background-image> 17.3, <text:list-level-style-image> 16.33 and <text:section-source> 5.4.2 elements the default value for this attribute is embed.

For <db:connection-resource> 12.7 the default value for this attribute is none.

The xlink:show attribute is usable with the following elements: <db:component> 12.25.5, <db:connection-resource> 12.7, <draw:a> 10.4.12, <draw:applet> 10.4.7, <draw:area-circle> 10.4.13.4, <draw:area-polygon> 10.4.13.5, <draw:area-rectangle> 10.4.13.3, <draw:fill-image> 16.40.6, <draw:floating-frame> 10.4.10, <draw:image> 10.4.4, <draw:object> 10.4.6.2, <draw:object-ole> 10.4.6.3, <draw:plugin> 10.4.8, <meta:auto-reload> 4.3.2.13, <meta:hyperlink-behaviour> 4.3.2.14, <presentation:event-listener> 10.9.2, <presentation:sound> 10.8.2, <style:background-image> 17.3, <text:a> 6.1.8, <text:list-level-style-image> 16.33 and <text:section-source> 5.4.2.

19.912 xlink:title

The xlink:title attribute specifies a title to be associated with a document template.

The xlink:title attribute is usable with the following element: <meta:template> 4.3.2.12.

The xlink:title attribute has the data type string 18.2.

19.913 xlink:type

See §3.2 of [XLink]. This attribute always has the value simple in OpenDocument document instances.

For <db:connection-resource> 12.7, <db:file-based-database> 12.5, <draw:a> 10.4.12, <draw:applet> 10.4.7, <draw:area-circle> 10.4.13.4, <draw:area-polygon> 10.4.13.5, <draw:area-rectangle> 10.4.13.3, <draw:fill-image> 16.40.6, <draw:floating-frame> 10.4.10, <draw:image> 10.4.4, <draw:object> 10.4.6.2, <draw:object-ole> 10.4.6.3, <draw:plugin> 10.4.8, <form:form> 13.3, <meta:auto-reload> 4.3.2.13, <meta:template> 4.3.2.12, <presentation:event-listener> 10.9.2, <presentation:sound> 10.8.2, <script:event-listener> 14.4.2, <style:background-image> 17.3, <svg:definition-src> 16.25, <svg:font-face-uri> 16.24, <table:cell-range-source> 9.3.1, <table:table-source> 9.2.6, <text:a> 6.1.8, <text:alphabetical-index-auto-mark-file> 8.8.3, <text:list-level-style-image> 16.33, <text:script> 7.7.9 and <text:section-source> 5.4.2 elements the default value for this attribute is simple.

The xlink:type attribute is usable with the following elements: <chart:chart> 11.1, <db:component> 12.25.5, <db:connection-resource> 12.7, <db:file-based-database> 12.5, <draw:a> 10.4.12, <draw:applet> 10.4.7, <draw:area-circle>

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

10.4.13.4, <draw:area-polygon> 10.4.13.5, <draw:area-rectangle> 10.4.13.3, <draw:fill-image> 16.40.6, <draw:floating-frame> 10.4.10, <draw:image> 10.4.4, <draw:object> 10.4.6.2, <draw:object-ole> 10.4.6.3, <draw:plugin> 10.4.8, <form:form> 13.3, <meta:auto-reload> 4.3.2.13, <meta:template> 4.3.2.12, <presentation:event-listener> 10.9.2, <presentation:sound> 10.8.2, <script:event-listener> 14.4.2, <style:background-image> 17.3, <svg:definition-src> 16.25, <svg:font-face-uri> 16.24, <table:cell-range-source> 9.3.1, <table:table-source> 9.2.6, <text:a> 6.1.8, <text:alphabetical-index-auto-mark-file> 8.8.3, <text:list-level-style-image> 16.33, <text:script> 7.7.9 and <text:section-source> 5.4.2.

19.914 xml:id

The `xml:id` attribute is standardized by the W3C [XML-ID] and gives an element a unique identification in its XML file.

The `xml:id` attribute is usable with the following elements: <anim:audio> 15.5, <anim:command> 15.6.1, <anim:iterate> 15.4.4, <anim:par> 15.4.2, <anim:seq> 15.4.3, <chart:chart> 11.1, <chart:data-point> 11.13, <chart:plot-area> 11.4, <chart:series> 11.11, <dr3d:cube> 10.5.4, <dr3d:extrude> 10.5.6, <dr3d:rotate> 10.5.7, <dr3d:scene> 10.5.2, <dr3d:sphere> 10.5.5, <draw:a> 10.4.12, <draw:applet> 10.4.7, <draw:caption> 10.3.11, <draw:circle> 10.3.8, <draw:connector> 10.3.10, <draw:control> 10.3.13, <draw:custom-shape> 10.6.1, <draw:ellipse> 10.3.9, <draw:floating-frame> 10.4.10, <draw:frame> 10.4.2, <draw:g> 10.3.15, <draw:image> 10.4.4, <draw:line> 10.3.3, <draw:measure> 10.3.12, <draw:object> 10.4.6.2, <draw:object-ole> 10.4.6.3, <draw:page> 10.2.4, <draw:page-thumbnail> 10.3.14, <draw:path> 10.3.7, <draw:plugin> 10.4.8, <draw:polygon> 10.3.5, <draw:polyline> 10.3.4, <draw:rect> 10.3.2, <draw:regular-polygon> 10.3.6, <draw:text-box> 10.4.3, <form:button> 13.5.15, <form:checkbox> 13.5.17, <form:combobox> 13.5.11, <form:date> 13.5.8, <form:file> 13.5.5, <form:fixed-text> 13.5.10, <form:formatted-text> 13.5.6, <form:frame> 13.5.19, <form:generic-control> 13.5.25, <form:grid> 13.5.22, <form:hidden> 13.5.21, <form:image> 13.5.16, <form:image-frame> 13.5.20, <form:listbox> 13.5.13, <form:number> 13.5.7, <form:password> 13.5.4, <form:radio> 13.5.18, <form:text> 13.5.2, <form:textarea> 13.5.3, <form:time> 13.5.9, <form:value-range> 13.5.24, <office:annotation> 14.1, <presentation:sound> 10.8.2, <table:covered-table-cell> 9.1.5, <table:table> 9.1.2, <table:table-cell> 9.1.4, <table:table-column> 9.1.6, <table:table-row> 9.1.3, <text:alphabetical-index> 8.8, <text:bibliography> 8.9, <text:bookmark> 6.2.1.2, <text:bookmark-start> 6.2.1.3, <text:changed-region> 5.5.2, <text:h> 5.1.2, <text:illustration-index> 8.4, <text:index-title> 8.2.3, <text:list> 5.3.1, <text:list-header> 5.3.3, <text:list-item> 5.3.4, <text:meta> 6.1.9, <text:meta-field> 7.5.19, <text:numbered-paragraph> 5.3.6, <text:object-index> 8.6, <text:p> 5.1.3, <text:section> 5.4, <text:table-index> 8.5, <text:table-of-content> 8.3 and <text:user-index> 8.7.

The `xml:id` attribute has the data type `ID` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20 Formatting Attributes

20.1 General

In an OpenDocument Format document, <style:*-properties> elements contain the definitions of formatting that is associated with document structure elements. Formatting definitions are expressed as attributes on the <style:*-properties> elements or as child elements of these elements. This chapter defines formatting properties that are represented by attributes. Formatting properties that are represented by elements are defined in chapter 17.

20.2 chart:angle-offset

The chart:angle-offset attribute specifies a counter clockwise rotation of a polar coordinate in a circle, ring or polar chart. The attribute value is an angle. See 18.3.1. The default value is 90deg.

This attribute is evaluated for chart styles that are applied to a <chart:plot-area> element.

The chart:angle-offset attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:angle-offset attribute has the data type angle 18.3.1.

20.3 chart:auto-position

The chart:auto-position attribute specifies if an object should be positioned automatically.

The default value is true if svg:x and svg:y attributes are not specified. It is false if the svg:x and svg:y attributes are specified.

The chart:auto-position attribute is evaluated for chart styles applied to elements that may have svg:x and svg:y attributes.

The defined values for the chart:auto-position attribute are:

- false: svg:x and svg:y attribute values are used to position an object.
- true: svg:x and svg:y attribute values are ignored and the consumer chooses a position.

The chart:auto-position attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:auto-position attribute has the data type boolean 18.3.3.

20.4 chart:auto-size

The chart:auto-size attribute specifies if the size of an object should be chosen automatically.

The default value is true if svg:width and svg:height attributes are not specified. It is false if the svg:width and svg:height attributes are specified.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The chart:auto-size attribute is evaluated for chart styles applied to elements that have svg:width and svg:height attributes.

The defined values for the chart:auto-size attribute are:

- false: svg:width and svg:height attribute values are used to size an object.
- true: svg:width and svg:height attribute values are ignored and the consumer chooses a size.

The chart:auto-size attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:auto-size attribute has the data type boolean 18.3.3.

20.5 chart:axis-label-position

The chart:axis-label-position attribute specifies the position of the axis labels.

The defined values for the chart:axis-label-position attribute are:

- near-axis: The labels are placed adjacent to the axis line. On which side of the line the labels are placed depends on the chart:axis-position attribute. If the chart:axis-position attribute has the value start or end, the labels are placed outside the coordinate system. Otherwise the labels are placed adjacent to the axis on the side that belongs to the lower values on the crossing axis.
- near-axis-other-side: The labels are placed adjacent to the axis on the opposite side as for near-axis.
- outside-end: The labels are placed outside the coordinate region on that side where the crossing axis has its maximum value.
- outside-start: The labels are placed outside the coordinate region on that side where the crossing axis has its minimum value.

If the chart:axis-label-position attribute is missing but a chart:axis-position attribute is given, the value of the chart:axis-label-position attribute is assumed to be near-axis.

This attribute is evaluated for a chart style that is applied to a <chart:axis> element.

The chart:axis-label-position attribute is usable with the following element: <style:chart-properties> 17.22.

The values of the chart:axis-label-position attribute are near-axis, near-axis-other-side, outside-start or outside-end.

20.6 chart:axis-position

The chart:axis-position attribute specifies the position of the axis line on the scale of the crossing axis.

If the attribute is set for a y-axis, the position indicates a value on the scale of the first x-axis.

If the attribute is set for a x-axis, the position indicates a value on the scale of the first y-axis.

This attribute is evaluated for a chart style that is applied to a <chart:axis> element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the chart:axis-position attribute are:

- end: The axis line is placed at the end of the crossing axis.
- start: The axis line is placed at the start of the crossing axis.
- a value of type double: The axis line is placed at the given value on the crossing axis. If the crossing axis is an axis displaying categories rather than values, a value of 1 indicates that the axis should be placed at the first category, a value of 2 indicates that the axis should be placed at the second category and so forth.

The chart:axis-position attribute is usable with the following element: <style:chart-properties> 17.22.

The values of the chart:axis-position attribute are start, end or a value of type double 18.2.

20.7 chart:connect-bars

The chart:connect-bars attribute specifies if bars in a bar chart that belong to the same series are connected by lines.

This attribute is evaluated for chart styles that are applied to a <chart:plot-area> element.

The defined values for the chart:connect-bars attribute are:

- false: bars belonging to the same series are not connected by lines.
- true: bars belonging to the same series are connected by lines.

The chart:connect-bars attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:connect-bars attribute has the data type boolean 18.3.3.

20.8 chart:data-label-number

The chart:data-label-number attribute specifies whether the value and/or the percentage of a data point should be displayed within a data label. By default, neither the value nor a percentage is displayed.

The defined values for the chart:data-label-number attribute are:

- none: neither the value nor the percentage should be displayed.
- percentage: only the percentage value should be displayed.
- value: only the value should be displayed within the data label.
- value-and-percentage: both the value and the percentage should be displayed.

This attribute is evaluated for chart styles that are applied to a <chart:data-label>, <chart:data-point>, <chart:series> or <chart:plot-area> elements.

The style:data-style-name attribute can be used together with this attribute to indicate which number format should be used to display the value.

The style:percentage-data-style-name attribute can be used together with this attribute to indicate which number format should be used to display the percentage value.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The chart:data-label-number attribute is usable with the following element: <style:chart-properties> 17.22.

The values of the chart:data-label-number attribute are none, value, percentage or value-and-percentage.

20.9 chart:data-label-symbol

The chart:data-label-symbol attribute specifies whether to display a legend symbol within the data label of a data point.

This attribute is evaluated for chart styles that are applied to a <chart:data-label>, <chart:data-point>, <chart:series> or <chart:plot-area> elements.

The defined values for the chart:data-label-symbol attribute are:

- false: a legend symbol is not displayed within the data label of a data point.
- true: a legend symbol is displayed within the data label of a data point.

The chart:data-label-symbol attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:data-label-symbol attribute has the data type boolean 18.3.3.

20.10 chart:data-label-text

The chart:data-label-text attribute specifies whether to display the category within the data label of a data point.

This attribute is evaluated for chart styles that are applied to <chart:data-label>, <chart:data-point>, a <chart:series> or a <chart:plot-area> elements.

The defined values for the chart:data-label-text attribute are:

- false: a category is not displayed within the data label of a data point.
- true: a category is displayed within the data label of a data point.

The chart:data-label-text attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:data-label-text attribute has the data type boolean 18.3.3.

20.11 chart:deep

The chart:deep attribute specifies whether data series are displayed behind each other along the z-axis or not. The chart:deep attribute is ignored unless a chart:three-dimensional attribute is present and has the value true. 20.58

This attribute is evaluated for a chart style that is applied to a <chart:plot-area> element.

The defined values for the chart:deep attribute are:

- false: data series are not displayed behind each other along the z-axis.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: data series are displayed behind each other along the z-axis. The z-axis displays the name of the series.

The `chart:deep` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:deep` attribute has the data type `boolean` 18.3.3.

20.12 chart:display-label

The `chart:display-label` attribute specifies whether labels are displayed on an axis or not.

This attribute is evaluated for a chart style that is applied to a `<chart:axis>` element.

Note: The labels controlled by `chart:display-label` attribute appear on an axis as opposed to being labels for the axis.

The defined values for the `chart:display-label` attribute are:

- `false`: labels are not displayed on an axis.
- `true`: labels are displayed on an axis.

The `chart:display-label` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:display-label` attribute has the data type `boolean` 18.3.3.

20.13 chart:error-category

The `chart:error-category` attribute is used to determine which function is used to calculate error indicators at data points. By default, no error indicators are shown.

The defined values for the `chart:error-category` attribute are:

- `cell-range`: Use values from cell ranges for positive and negative error indicators. The `chart:error-lower-range` and `chart:error-upper-range` attributes determine the cell ranges which contain the values to be used for negative and positive error indicators.
- `constant`: Use fixed absolute values for both directions: positive and negative The absolute value for a positive direction is given with `chart:error-upper-limit` attribute. The absolute value for a negative direction is given with `chart:error-lower-limit` attribute.
- `error-margin`: Use a fixed percentage of the largest value – this is called error-margin. The percentage value is given within `chart:error-margin` attribute.
- `none`: No error indicators are shown.
- `percentage`: Use a fixed percentage of each value The percentage value is given within `chart:error-percentage` attribute.
- `standard-deviation`: Standard deviation of the values of a series assuming an equal distribution.
- `standard-error`: Standard error (standard deviation of the mean) of the values of a series.
- `variance`: Variance of the values of a series assuming an equal distribution.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

This attribute is evaluated for chart styles that are applied to `<chart:error-indicator>`, `<chart:series>` or `<chart:plot-area>` elements.

The `chart:error-category` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The values of the `chart:error-category` attribute are `none`, `variance`, `standard-deviation`, `percentage`, `error-margin`, `constant`, `standard-error` or `cell-range`.

20.14 chart:error-lower-indicator

The `chart:error-lower-indicator` attribute specifies whether negative error indicators are displayed (the error value is subtracted from the data point value).

This attribute should be used together with the `chart:error-category` attribute.

The defined values for the `chart:error-lower-indicator` attribute are:

- `false`: negative error indicators are not displayed.
- `true`: negative error indicators are displayed.

The `chart:error-lower-indicator` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:error-lower-indicator` attribute has the data type `boolean` 18.3.3.

20.15 chart:error-lower-limit

The `chart:error-lower-limit` attribute specifies the absolute value in the negative direction that is used to display error indicators, if a `chart:error-category` attribute has the value `constant`. 20.13

The `chart:error-lower-limit` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:error-lower-limit` attribute has the data type `double` 18.2.

20.16 chart:error-lower-range

The `chart:error-lower-range` attribute specifies the cell range used for negative error indicators when a `chart:error-category` attribute has a value of `cell-range`. 20.13

The `chart:error-lower-range` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:error-lower-range` attribute has the data type `cellRangeAddressList` 18.3.6.

20.17 chart:error-margin

The `chart:error-margin` attribute specifies the percentage of the largest value in a series used in the display of error indicators for each data point of a series.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

This attribute should be used together with the `chart:error-category` attribute if it has the value `error-margin`.

The `chart:error-margin` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:error-margin` attribute has the data type `double` 18.2.

20.18 chart:error-percentage

The `chart:error-percentage` attribute specifies the percentage that is used in the display of error indicators for each data point of a series.

This attribute should be used together with a `chart:error-category` attribute if the `chart:error-category` attribute has the value `percentage`.

The `chart:error-percentage` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:error-percentage` attribute has the data type `double` 18.2.

20.19 chart:error-upper-indicator

The `chart:error-upper-indicator` attribute specifies whether positive error indicators should be displayed (the error value is added to the data point value).

This attribute should be used together with a `chart:error-category` attribute.

The defined values for the `chart:error-upper-indicator` attribute are:

- `false`: positive error indicators are not displayed.
- `true`: positive error indicators are displayed.

The `chart:error-upper-indicator` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:error-upper-indicator` attribute has the data type `boolean` 18.3.3.

20.20 chart:error-upper-limit

The `chart:error-upper-limit` attribute specifies the absolute value in the positive direction that is used to display error indicators, if the `chart:error-category` attribute has the value `constant`. 20.13

This attribute should be used together with `chart:error-category` attribute.

The `chart:error-upper-limit` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:error-upper-limit` attribute has the data type `double` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.21 chart:error-upper-range

The `chart:error-upper-range` attribute specifies the cell range used for positive error indicators when the `chart:error-category` attribute has the value `cell-range` 20.13.

The `chart:error-upper-range` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:error-upper-range` attribute has the data type `cellRangeAddressList` 18.3.6.

20.22 chart:gap-width

The `chart:gap-width` attribute specifies a gap between neighboring groups of bars in a bar chart (that is the distance between the last bar in one category and the first bar in the following category). It is specified as an integer percentage relative to the width of a single bar.

This attribute is evaluated for chart styles that are applied to a `<chart:axis>` element with `chart:dimension` attribute set to y.

Note: Bars attached to different axis can be arranged differently as long as they are grouped per axis (`chart:group-bars-per-axis` attribute has the value `true`).

The `chart:gap-width` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:gap-width` attribute has the data type `integer` 18.2.

20.23 chart:group-bars-per-axis

The `chart:group-bars-per-axis` attribute specifies whether bars in a bar chart are displayed side by side or behind each other when they are attached to different y-axes.

This attribute is evaluated for chart styles that are applied to a `<chart:plot-area>` element.

The defined values for the `chart:group-bars-per-axis` attribute are:

- `false`: all bars on the same x-axis are handled as one group and are displayed side by side.
- `true`: only bars attached to the same x- and y-axis are handled as one group.

The `chart:group-bars-per-axis` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:group-bars-per-axis` attribute has the data type `boolean` 18.3.3.

20.24 chart:hole-size

The `chart:hole-size` attribute specifies the diameter of the inner hole of a ring chart as percentage of the outer diameter of the outermost ring.

This attribute is evaluated for chart styles that are applied to a `<chart:plot-area>` element.

The `chart:hole-size` attribute is usable with the following element: `<style:chart-properties>` 17.22.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `chart:hole-size` attribute has the data type `percent` 18.3.23.

20.25 chart:include-hidden-cells

The `chart:include-hidden-cells` attribute specifies whether data points in hidden cells are plotted in a chart. The default is to plot data points in hidden cells.

This attribute can be used within styles that are applied to a `<chart:plot-area>` element.

The defined values for the `chart:include-hidden-cells` attribute are:

- `false`: data points in hidden cells are not plotted in a chart.
- `true`: data points in hidden cells are plotted in a chart.

The `chart:include-hidden-cells` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:include-hidden-cells` attribute has the data type `boolean` 18.3.3.

20.26 chart:interpolation

The `chart:interpolation` attribute specifies interpolations for line and scatter charts.

The defined values for the `chart:interpolation` attribute are:

- `b-spline` – B-Splines. 20.51 If the `chart:spline-resolution` attribute has value 1 this is identical to the `chart:interpolation` attribute value `none`. If the `chart:spline-resolution` attribute has value $k>1$ and the `chart:spline-order` attribute has value *p* then given a sequence of data points, a B-spline interpolation with polynomials of degree *p* is constructed as described here. First we omit any consecutive repeated data points obtaining $(x_0,y_0),\ldots,(x_n,y_n)$ where for all $i=1,\ldots,n$, $(x_{i-1},y_{i-1})\neq(x_i,y_i)$.

  We then construct a parameter list $t_0,\ldots,t_n$ using the centripetal method with a power of 0.5: $t_k=\frac{\sum_{i=1}^{k}\sqrt[4]{(x_i-x_{i-1})^2+(y_i-y_{i-1})^2}}{\sum_{i=1}^{n}\sqrt[4]{(x_i-x_{i-1})^2+(y_i-y_{i-1})^2}}$ for $k=1,\ldots,n$ and $t_0=0$.

  Next we generate a knot vector $u_0,\ldots,u_m$ with $m=n+p+1$:

$$\begin{aligned} u_0=u_1=\cdots=u_p &= 0 \\ u_{j+p} &= \frac{1}{p}\sum_{i=j}^{j+p-1} t_i \quad \text{for} \quad j=1,2,\ldots,n-p \\ u_{m-p}=u_{m-p+1}=\cdots=u_m &= 1 \end{aligned}$$

  Now let $N_{i,p}(u)$ be the B-spline basis function defined recursively by

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

$$N_{i,0}(u) = \begin{Bmatrix} 1 & \text{if } u_i \le u < u_{i+1} \\ 0 & \text{otherwise} \end{Bmatrix}$$

$$N_{i,s}(u) = \frac{u-u_i}{u_{i+s}-u_i} \cdot N_{i,s-1}(u) + \frac{u_{i+s+1}-u}{u_{i+s+1}-u_{i+1}} \cdot N_{i+1,s-1}(u) \quad \text{for } s>0$$

Let $C = \begin{bmatrix} c_0 & d_0 \\ c_1 & d_1 \\ \vdots & \vdots \\ c_n & d_n \end{bmatrix}$ be the solution of the matrix equation $X = N \cdot C$ with

$N = \begin{bmatrix} N_{0,p}(t_0) & N_{1,p}(t_0) & \cdots & N_{n,p}(t_0) \\ N_{0,p}(t_1) & N_{1,p}(t_1) & \cdots & N_{n,p}(t_1) \\ \vdots & \vdots & \ddots & \vdots \\ N_{0,p}(t_n) & N_{1,p}(t_n) & \cdots & N_{n,p}(t_n) \end{bmatrix}$ and $X = \begin{bmatrix} x_0 & y_0 \\ x_1 & y_1 \\ \vdots & \vdots \\ x_n & y_n \end{bmatrix}$.

$(c_0, d_0), (c_1, d_1), \ldots, (c_n, d_n)$ are the control points of the desired B-spline of degree *p* passing through the data points $(x_0, y_0), \ldots, (x_n, y_n)$.

For $0<u<1$ let $P_{i,r}(u)$ be recursively defined by

$$P_{i,0}(u) = (c_i, d_i)$$

$$P_{i,r}(u) = (1-a_{i,r}) \cdot P_{i-1,r-1} + a_{i,r} \cdot P_{i,r-1} \quad \text{with} \quad a_{i,r} = \frac{u-u_i}{u_{i+p-r+1}-u_i} \quad \text{for} \quad r>0$$

If $0<u<1$ and $u_s<u<u_{s+1}$, then $P_{s,p}(u)$ is the point on this B-spline corresponding to the parameter *u*. If $0<u<1$ and $u=u_s$, then $P_{s-1,p-1}(u)$ is the point on this B-spline corresponding to the parameter *u*.

Note: $P_{s,p}(u)$ and $P_{s-1,p-1}(u)$ are best calculated using de Boor's algorithm for a B-spline of degree *p* with control points $(c_0, d_0), (c_1, d_1), \ldots, (c_n, d_n)$ and knots $u_0, \ldots, u_m$.

The approximation of this B-spline is then plotted by using $P_{s,p}(u)$ and $P_{s-1,p-1}(u)$ to calculate the coordinates of the points on the spline corresponding to the parameters:

$$\begin{array}{llll} 0=t_0, & t_0+1\cdot\frac{t_1-t_0}{k}, & t_0+2\cdot\frac{t_1-t_0}{k}, & \ldots, \quad t_0+k\cdot\frac{t_1-t_0}{k}=t_1, \\ & t_1+1\cdot\frac{t_2-t_1}{k}, & t_1+2\cdot\frac{t_2-t_1}{k}, & \ldots, \quad t_1+k\cdot\frac{t_2-t_1}{k}=t_2, \\ & & & \ldots \\ & t_{n-1}+1\cdot\frac{t_n-t_{n-1}}{k}, & t_{n-1}+2\cdot\frac{t_n-t_{n-1}}{k}, & \ldots, \quad t_{n-1}+k\cdot\frac{t_n-t_{n-1}}{k}=t_n=1 \end{array}$$

and connecting these points with straight line segments.

- `cubic-spline` – Cubic Splines. If the `chart:spline-resolution` attribute has value 1 this is identical to the `chart:interpolation` attribute value `none`. If the `chart:spline-`

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

`resolution` attribute has value $k>1$ then given a sequence of data points, $(x_0,y_0),\ldots,(x_n,y_n)$ a cubic spline interpolation is constructed as described here:

Find the unique cubic polynomials $f_1,f_2,\ldots,f_n$ $g_1,g_2,\ldots,g_n$ and such that:

for all $i=1,\ldots,n$, $f_i(i)=x_i$ and $f_i(i-1)=x_{i-1}$,

for all $i=1,\ldots,(n-1)$, $f'_i(i)=f'_{i+1}(i)$ with f' denoting the first derivative of *f,*

for all $i=1,\ldots,(n-1)$, $f''_i(i)=f''_{i+1}(i)$ with f'' denoting the second derivative of *f,*

for all $i=1,\ldots,n$, $g_i(i)=y_i$ and $g_i(i-1)=y_{i-1}$,

for all $i=1,\ldots,(n-1)$, $g'_i(i)=g'_{i+1}(i)$ with g' denoting the first derivative of *g,*

for all $i=1,\ldots,(n-1)$, $g''_i(i)=g''_{i+1}(i)$ with g'' denoting the second derivative of *g,*

and

- $f''_1(0)=0$, $f''_n(n)=0$, $g''_1(0)=0$ and $g''_n(n)=0$ if $(x_0,y_0)\neq(x_n,y_n)$ (ie. the curve will not be closed) or
- $f''_1(0)=\frac{3}{2}\cdot(x_1+x_{n-1}-2x_0)=f''_n(n)$ and $g''_1(0)=\frac{3}{2}\cdot(y_1+y_{n-1}-2y_0)=g''_n(n)$ if $(x_0,y_0)=(x_n,y_n)$ (I,e. the curve will be closed).

With these cubic polynomials we define the splines (piecewise polynomial functions) $F(t)=f_i(t)\,\text{for}\,(i-1)\le t\le i$ and $G(t)=g_i(t)\,\text{for}\,(i-1)\le t\le i$. (In view of the first and fourth conditions above this yields well defined functions *F* and *G*.) The interpolation line is then obtained by connecting consecutive points in

$$(F(0),G(0)),\left(F\left(\frac{1}{k}\right),G\left(\frac{1}{k}\right)\right),\left(F\left(\frac{2}{k}\right),G\left(\frac{2}{k}\right)\right),\ldots,\left(F\left(\frac{n\cdot k-1}{k}\right),G\left(\frac{n\cdot k-1}{k}\right)\right),\left(F\left(\frac{n\cdot k}{k}\right),G\left(\frac{n\cdot k}{k}\right)\right)$$

using straight line segments.

- `none` - Straight lines. Consecutive data points are connected by straight line segments.

This attribute is evaluated for chart styles that are applied to a `<chart:plot-area>` or `<chart:series>` element.

The `chart:interpolation` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The values of the `chart:interpolation` attribute are `none`, `cubic-spline` or `b-spline`.

20.27 chart:interval-major

The `chart:interval-major` attribute specifies major intervals on an axis 11.8.

This attribute is evaluated for a chart style that is applied to a `<chart:axis>` element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The chart:interval-major attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:interval-major attribute has the data type double 18.2.

20.28 chart:interval-minor-divisor

The chart:interval-minor-divisor attribute specifies a divisor for the chart:interval-major value, the division of which determines the minor interval.

This attribute is evaluated for a chart style that is applied to a <chart:axis> element.

The chart:interval-minor-divisor attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:interval-minor-divisor attribute has the data type positiveInteger 18.2.

20.29 chart:japanese-candle-stick

The chart:japanese-candle-stick attribute specifies the display of opening and closing values in a stock chart.

The defined values for the chart:japanese-candle-stick attribute are:

- false – opening and closing values are displayed as left and right tick-lines
- true – opening and closing values are displayed as colored bars, where the color of the bar depends on whether the opening value is larger than the closing value

This attribute is evaluated for chart styles that are applied to a <chart:plot-area> element.

The chart:japanese-candle-stick attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:japanese-candle-stick attribute has the data type boolean 18.3.3.

20.30 chart:label-arrangement

The chart:label-arrangement attribute specifies the arrangement of labels on an axis.

The defined values for the chart:label-arrangement attribute are:

- side-by-side: Labels are not staggered, they are aligned on one line.
- stagger-even: Even labels are aligned on the same line as used for side by side arrangement. Counting starts with one, so the first label is odd.
- stagger-odd: All odd labels are aligned on the line used for side by side arrangement. Counting starts with one, so the first label is odd.

This attribute is evaluated for a chart style that is applied to a <chart:axis> element.

The chart:label-arrangement attribute is usable with the following element: <style:chart-properties> 17.22.

The values of the chart:label-arrangement attribute are side-by-side, stagger-even or stagger-odd.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.31 chart:label-position

The `chart:label-position` attribute specifies where data labels are placed.

The defined values for the `chart:label-position` attribute are:

- `avoid-overlap`: an algorithm should be used that tries to place the labels without overlapping each other.
- `bottom`: the data label is placed below the data point.
- `bottom-left`: the data label is placed to the bottom left of the data point.
- `bottom-right`: the data label is placed to the bottom right of the data point.
- `center`: the data label is centered on the data point.
- `inside`: the data label is placed inside the data point (for pie charts the label is placed inside the piece on the bisecting line aligned to the outer radius, for bar charts the label is inside the bar aligned to that end that is given by the data points value, for polar charts the label is placed on that side of the data point that points to the polar charts center).
- `left`: the data label is placed left of the data point.
- `near-origin`: the data label is placed inside the data point on that side that is near to the origin - where the origin is the beginning of the bar in a bar chart or the base line in an area chart (for bar charts the label is placed inside the bar like with value inside, but aligned to the opposite end of the bar).
- `outside`: the data label is placed outside the data point (for pie charts the label is placed outside the circle aligned to the outer radius, for bar charts the label is outside the bar aligned to that end that is given by the data points value, for polar charts the label is placed on that side of the data point that points away from the polar charts center).
- `right`: the data label is placed right of the data point.
- `top`: the data label is placed on top of the data point.
- `top-left`: the data label is placed to the top left of the data point.
- `top-right`: the data label is placed to the top right of the data point.

This attribute is evaluated for chart styles that are applied to `<chart:data-label>`, `<chart:data-point>`, `<chart:series>` or `<chart:plot-area>` elements.

The `chart:label-position` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The values of the `chart:label-position` attribute are `avoid-overlap`, `center`, `top`, `top-right`, `right`, `bottom-right`, `bottom`, `bottom-left`, `left`, `top-left`, `inside`, `outside` or `near-origin`.

20.32 chart:label-position-negative

If the `chart:label-position-negative` attribute is set in addition to a `chart:label-position` attribute (20.31), it is used for all labels that belong to data points with negative values. Otherwise the position set in a `chart:label-position` attribute is used for positive and negative values. If a `chart:label-position-negative` attribute is used without an `chart:label-position` attribute it is ignored.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the chart:label-position-negative attribute are:

- avoid-overlap: an algorithm should be used that tries to place the labels without overlapping each other.
- bottom: the data label is placed below the data point.
- bottom-left: the data label is placed to the bottom left of the data point.
- bottom-right: the data label is placed to the bottom right of the data point.
- center: the data label is centered on the data point.
- inside: the data label is placed inside the data point (for pie charts the label is placed inside the piece on the bisecting line aligned to the outer radius, for bar charts the label is inside the bar aligned to that end that is given by the data points value, for polar charts the label is placed on that side of the data point that points to the polar charts center).
- left: the data label is placed left of the data point.
- near-origin: the data label is placed inside the data point on that side that is near to the origin - where the origin is the beginning of the bar in a bar chart or the base line in an area chart (for bar charts the label is placed inside the bar like with value inside, but aligned to the opposite end of the bar).
- outside: the data label is placed outside the data point (for pie charts the label is placed outside the circle aligned to the outer radius, for bar charts the label is outside the bar aligned to that end that is given by the data points value, for polar charts the label is placed on that side of the data point that points away from the polar charts center).
- right: the data label is placed right of the data point.
- top: the data label is placed on top of the data point.
- top-left: the data label is placed to the top left of the data point.
- top-right: the data label is placed to the top right of the data point.

The chart:label-position-negative attribute is usable with the following element: <style:chart-properties> 17.22.

The values of the chart:label-position-negative attribute are avoid-overlap, center, top, top-right, right, bottom-right, bottom, bottom-left, left, top-left, inside, outside or near-origin.

20.33 chart:lines (deprecated)

The chart:lines attribute specifies whether connecting lines between data points are shown.

Note: The display of lines can be specified by the draw:stroke attribute.

The defined values for the chart:lines attribute are:

- false: connecting lines between data points are not shown.
- true: connecting lines between data points are shown.

The chart:lines attribute is usable with the following element: <style:chart-properties> 17.22.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The chart:lines attribute has the data type boolean 18.3.3.

20.34 chart:link-data-style-to-source

The chart:link-data-style-to-source attribute can only be used in chart documents that are part of a document that provides the data for the chart.

This attribute is evaluated for a chart style that is applied to a <chart:axis> element.

The defined values for the chart:link-data-style-to-source attribute are:

- false: number format used for rendering axis labels is defined by the style:data-style-name attribute. 19.469
- true: number format used for rendering the axis labels is inherited from the document providing the data.

The chart:link-data-style-to-source attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:link-data-style-to-source attribute has the data type boolean 18.3.3.

20.35 chart:logarithmic

The chart:logarithmic attribute specifies whether logarithmic scaling will be used on an axis. By default, proportional scaling is used.

This attribute is evaluated for a chart style that is applied to a <chart:axis> element.

The defined values for the chart:logarithmic attribute are:

- false: proportional scaling is used.
- true: logarithmic scaling is used.

The chart:logarithmic attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:logarithmic attribute has the data type boolean 18.3.3.

20.36 chart:maximum

The chart:maximum attribute specifies the maximum value of an axis.

This attribute is evaluated for a chart style that is applied to a <chart:axis> element.

The chart:maximum attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:maximum attribute has the data type double 18.2.

20.37 chart:mean-value

The chart:mean-value attribute specifies whether to display a line that represents the statistical mean value of all data points of a series.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

This attribute is evaluated for chart styles that are applied to a <chart:plot-area> element or a <chart:series> element.

The defined values for the chart:mean-value attribute are:

- false: line representing the statistical mean of all the data points in a series is not displayed.
- true: line representing the statistical mean of all the data points in a series is displayed.

The chart:mean-value attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:mean-value attribute has the data type boolean 18.3.3.

20.38 chart:minimum

The chart:minimum attribute specifies the minimum value of an axis.

This attribute is evaluated for a chart style that is applied to a <chart:axis> element.

The chart:minimum attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:minimum attribute has the data type double 18.2.

20.39 chart:origin

The chart:origin attribute defines the origin of the graphical representation of a data series attached to an axis.

Note: For example, the beginning of the bars in a bar chart or the base line in an area chart can be set by the chart:origin attribute in the style of the y-axis to which the data series is attached.

If the first x-axis has a chart:axis-position attribute, that position is taken to indicate the origin of the data points attached to the first y-axis. It overrides the chart:origin attribute of the first y-axis.

This attribute is evaluated for a chart style that is applied to a <chart:axis> element.

The chart:origin attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:origin attribute has the data type double 18.2.

20.40 chart:overlap

The chart:overlap attribute specifies how much bars within the same category in a bar chart overlap. The attribute value is an integer that is interpreted as a percentage relative to the width of a single bar. Negative values specify gaps between bars.

This attribute is evaluated for chart styles that are applied to a <chart:axis> element when a chart:dimension attribute set to y.

Note: This allows bars to be attached to different axis arranged differently as long as they are grouped per axis (chart:group-bars-per-axis attribute is true).

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `chart:overlap` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:overlap` attribute has the data type `integer` 18.2.

20.41 chart:pie-offset

The `chart:pie-offset` attribute specifies the distance of a segment from the center of the circle in case of circle charts. The offset is given as an integer which is interpreted as a percentage of the radius of the circle.

In case of ring charts the `chart:pie-offset` attribute specifies an additional distance of a segment from the center of the circle. The distance is given as percentage of the thickness of the ring.

This attribute is evaluated for chart styles that are applied to a `<chart:data-point>` or `<chart:series>` element.

The `chart:pie-offset` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:pie-offset` attribute has the data type `nonNegativeInteger` 18.2.

20.42 chart:percentage

The `chart:percentage` attribute specifies a percentage accumulation of values per category.

This attribute is evaluated for chart styles that are applied to a `<chart:plot-area>` element.

The defined values for the `chart:percentage` attribute are:

- `false`: the attribute has no effect
- `true`: values should be accumulated by category. The sum of the values per category is treated as 100 percent and the y-axis displays according percentages.

y-axis

The `chart:percentage` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:percentage` attribute has the data type `boolean` 18.3.3.

20.43 chart:regression-type

The `chart:regression-type` attribute specifies the regression function for a series. A regression function can be used to approximate the data points in a series.

The defined values for the `chart:regression-type` attribute are:

- `exponential` – Exponential regression – approximate the values of the series using the model: $y = A \cdot e^{B \cdot x}$.
- `linear` – Linear regression – approximate the values of the series using the model: $y = A \cdot x + B$.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `logarithmic` – Logarithmic regression – approximate the values of the series using the model: $y = A \cdot ln(x) + B$.
- `none` – no regression curve will be displayed (default value)
- `power` – Regression with a power function – approximate the values of the series using the model: $y = A \cdot x^B$.

This attribute is evaluated for chart styles that are applied to `<chart:regression-curve>`, `<chart:series>` or `<chart:plot-area>` elements.

The `chart:regression-type` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The values of the `chart:regression-type` attribute are `none`, `linear`, `logarithmic`, `exponential` or `power`.

20.44 chart:reverse-direction

The `chart:reverse-direction` attribute specifies whether the direction of an axis follows the Cartesian coordinate system or the reverse. False is the default.

In a Cartesian coordinate system the x-axis points from left to right and the y-axis points from bottom to top. 3D Cartesian coordinate systems are left handed and polar coordinate systems are counter clockwise. If x and y axes are swapped as in horizontal bar charts (when attribute `chart:vertical` value is `true`), the unswapped coordinate system follows the Cartesian coordinate system and is left handed.

This attribute is evaluated for chart styles that are applied to a `<chart:axis>` element.

The defined values for the `chart:reverse-direction` attribute are:

- `false`: direction of axis follows the Cartesian coordinate system.
- `true`: direction of axis follows the reverse of the Cartesian coordinate system.

The `chart:reverse-direction` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:reverse-direction` attribute has the data type `boolean` 18.3.3.

20.45 chart:right-angled-axes

The `chart:right-angled-axes` attribute specifies a modification of the projection of a 3D chart. In a Cartesian coordinate system the projections of x and y-axis are horizontal and vertical.

This attribute is evaluated for chart styles that are applied to a `<chart:plot-area>` element. The chart:right-angled-axes attribute is ignored unless a `chart:three-dimensional` attribute is present and has the value `true`.

The defined values for the `chart:right-angled-axes` attribute are:

- `false`: the attribute has no effect.
- `true`: a 3D chart is sheared instead of rotated. For Cartesian coordinate systems the x and y-axis do form a right angle in the 2D-projection.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The chart:right-angled-axes attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:right-angled-axes attribute has the data type boolean 18.3.3.

20.46 chart:scale-text

The chart:scale-text attribute specifies that the text contained in an object should be scaled whenever the size of the chart changes. This attribute can appear at all chart objects that contain text.

The defined values for the chart:scale-text attribute are:

- false: text contained in an object should not be scaled when the size of its containing chart changes.
- true: text contained in an object should be scaled when the size of its containing chart changes.

The chart:scale-text attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:scale-text attribute has the data type boolean 18.3.3.

20.47 chart:series-source (deprecated)

The chart:series-source attribute specifies whether a tabular data for a chart contains all the data series in columns or rows .

The tabular data can be given by the table:cell-range-address attribute at the <chart:plot-area> element or by the <table:table> element inside the <chart:chart> element.

When data is assigned more specifically to a chart element, with a values-cell-range-address attribute on a <chart:series> element, the more specific data assignment has priority.

The chart:series-source attribute is evaluated for a chart style that is applied to a <chart:plot-area> element.

The defined values for the chart:series-source attribute are:

- columns: tabular data for a chart contains all the data series in a columns.
- rows: tabular data for a chart contains all the data series in a rows.

The chart:series-source attribute is usable with the following element: <style:chart-properties> 17.22.

The values of the chart:series-source attribute are columns or rows.

20.48 chart:sort-by-x-values

The chart:sort-by-x-values attribute specifies whether the data points of a data series should be displayed in ascending order of the x values, or in the order they are contained in the underlying data. It is evaluated for styles that are assigned to the <chart:plot-area> element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The chart:sort-by-x-values attribute is used for chart types with data series that contain x-values (for example scatter charts, 19.15).

The defined values for the chart:sort-by-x-values attribute are:

- false: data points of a data series should be displayed in the order they are contained in the underlying data.
- true: data points of a data series should be displayed in ascending order of the x values.

The chart:sort-by-x-values attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:sort-by-x-values attribute has the data type boolean 18.3.3.

20.49 chart:solid-type

The chart:solid-type attribute specifies the rendering of bars in three-dimensional bar charts.

The defined values for the chart:solid-type attribute are:

- cone – bars have the shape of cones
- cuboid – bars have the shape of cuboids
- cylinder – bars have the shape of cylinders
- pyramid – bars have the shape of pyramids

This attribute is evaluated for chart styles that are applied to <chart:data-point>, <chart:series> or <chart:plot-area> elements.

The chart:solid-type attribute is usable with the following element: <style:chart-properties> 17.22.

The values of the chart:solid-type attribute are cuboid, cylinder, cone or pyramid.

20.50 chart:spline-order

The chart:spline-order attribute specifies the degree of the polynomials used as part of the spline.

This attribute should be used together with chart:interpolation attribute when it has the value b-spline.

The chart:spline-order attribute is usable with the following element: <style:chart-properties> 17.22.

The chart:spline-order attribute has the data type positiveInteger 18.2.

20.51 chart:spline-resolution

The chart:spline-resolution attribute specifies the number of straight line segments used between any two data points.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

This attribute should be used together with `chart:interpolation` attribute when it has a value other than `none`.

The `chart:spline-resolution` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:spline-resolution` attribute has the data type `positiveInteger` 18.2.

20.52 chart:stacked

The `chart:stacked` attribute specifies the accumulation of the series values per category. Each value is in addition to the other values in the same category.

This attribute is evaluated for chart styles that are applied to a `<chart:plot-area>` element.

The defined values for the `chart:stacked` attribute are:

- `false`: series values should not be accumulated by category.
- `true`: series values should be accumulated by category. Bars in bar charts are stacked on top of each other.

The `chart:stacked` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:stacked` attribute has the data type `boolean` 18.3.3.

20.53 chart:symbol-height

The `chart:symbol-height` attribute specifies the height of a symbol to be used for a data point in a chart.

This attribute should be used together with `chart:symbol-type` attribute when the `chart:symbol-type` attribute has a value other than `none`.

The `chart:symbol-height` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:symbol-height` attribute has the data type `nonNegativeLength` 18.3.20.

20.54 chart:symbol-name

The `chart:symbol-name` attribute specifies a symbol to be used for a data point in a chart.

The glyphs associated with the values of the `chart:symbol-name` attribute are implementation-defined.

This attribute should be used only together with `chart:symbol-type` attribute and only when the `chart:symbol-type` attribute has the value `named-symbol`.

The `chart:symbol-name` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The values of the `chart:symbol-name` attribute are `square`, `diamond`, `arrow-down`, `arrow-up`, `arrow-right`, `arrow-left`, `bow-tie`, `hourglass`, `circle`, `star`, `x`, `plus`, `asterisk`, `horizontal-bar` or `vertical-bar`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.55 chart:symbol-type

The `chart:symbol-type` attribute specifies if a symbol is used for a data point in a chart, and if so, which type of symbol is to be used.

The defined values for the `chart:symbol-type` attribute are:

- `automatic`: the consumer chooses from the list of available named symbols (see `chart:symbol-name` attribute 20.54), choose a different symbol per series in round-robin fashion,in this order: `square`, `diamond`, `arrow-down`, `arrow-up`, `arrow-right`, `arrow-left`, `bow-tie`, `hourglass`, `circle`, `star`, `x`, `plus`, `asterisk`, `horizontal-bar`, `vertical-bar`.
- `named-symbol`: a symbol specified within `chart:symbol-name` attribute should be used.
- `none`: no symbol should be used.
- `image`: an image defined by a `<chart:symbol-image>` element is used as symbol.

This attribute is evaluated for chart styles that are applied to `<chart:data-point>`, `<chart:series>` or `<chart:plot-area>` elements.

The `chart:symbol-type` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The values of the `chart:symbol-type` attribute are `none`, `automatic`, `named-symbol` or `image`.

20.56 chart:symbol-width

The `chart:symbol-width` attribute specifies the width of a symbol to be used for a data point in a chart.

This attribute should be used together with `chart:symbol-type` attribute when the `chart:symbol-type` attribute has a value other than `none`.

The `chart:symbol-width` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:symbol-width` attribute has the data type `nonNegativeLength` 18.3.20.

20.57 chart:text-overlap

The `chart:text-overlap` attribute specifies whether axis labels may overlap each other.

This attribute is evaluated for a chart style that is applied to a `<chart:axis>` element.

The defined values for the `chart:text-overlap` attribute are:

- `false`: axis labels shall not overlap each other.
- `true`: axis labels may overlap each other.

The `chart:text-overlap` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:text-overlap` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.58 chart:three-dimensional

The `chart:three-dimensional` attribute specifies whether a chart is displayed as a 3D scene.

This attribute is evaluated for chart styles that are applied to a `<chart:plot-area>` element.

The defined values for the `chart:three-dimensional` attribute are:

- `false`: chart should not be displayed as a 3D scene.
- `true`: chart should be displayed as a 3D scene.

The `chart:three-dimensional` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:three-dimensional` attribute has the data type `boolean` 18.3.3.

20.59 chart:tick-marks-major-inner

The `chart:tick-marks-major-inner` attribute specifies the existence of major inner tick marks on an axis. They are drawn with respect to the major interval that may be specified by the `chart:interval-major` attribute, and are drawn towards the inside of the plot area. That is, they are drawn to the right for an axis displayed on the left hand side of the plot area, and to the left for an axis displayed on the right hand side of the plot area.

If a `chart:tick-marks-major-inner` attribute and a `chart:tick-marks-major-outer` attribute are both set to `true`, one tick mark is drawn that crosses the axis.

This attribute is evaluated for a chart style that is applied to a `<chart:axis>` element.

The defined values for the `chart:tick-marks-major-inner` attribute are:

- `false`: major inner tick marks should not appear on an axis.
- `true`: major inner tick marks should appear on an axis.

The `chart:tick-marks-major-inner` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:tick-marks-major-inner` attribute has the data type `boolean` 18.3.3.

20.60 chart:tick-marks-major-outer

The `chart:tick-marks-major-outer` attribute specifies the existence of major outer tick marks on an axis. They are drawn with respect to the major interval that may be specified by the `chart:interval-major` attribute, and are drawn towards the outside of the plot area. That is, they are drawn to the left for an axis displayed on the left hand side of the plot area, and to the right for an axis displayed on the right hand side of the plot area.

If a `chart:tick-marks-major-inner` attribute and a `chart:tick-marks-major-outer` attribute are both set to `true`, one tick mark is drawn that crosses the axis.

This attribute is evaluated for a chart style that is applied to a `<chart:axis>` element.

The defined values for the `chart:tick-marks-major-outer` attribute are:

- `false`: major outer tick marks should not appear on an axis.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: major outer tick marks should appear on an axis.

The `chart:tick-marks-major-outer` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:tick-marks-major-outer` attribute has the data type `boolean` 18.3.3.

20.61 chart:tick-marks-minor-inner

The `chart:tick-marks-minor-inner` attribute specifies the existence of minor inner tick marks on an axis. They are drawn with respect to the minor interval divisor that may be specified by the `chart:interval-minor-divisor` attribute, and are drawn towards the inside of the plot area. That is, they are drawn to the right for an axis displayed on the left hand side of the plot area, and to the left for an axis displayed on the right hand side of the plot area.

If a `chart:tick-marks-minor-inner` attribute and a `chart:tick-marks-minor-outer` attribute are both set to `true`, one tick mark is drawn that crosses the axis.

This attribute is evaluated for a chart style that is applied to a `<chart:axis>` element.

The defined values for the `chart:tick-marks-minor-inner` attribute are:

- `false`: minor inner tick marks should not appear on an axis.
- `true`: minor inner tick marks should appear on an axis.

The `chart:tick-marks-minor-inner` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:tick-marks-minor-inner` attribute has the data type `boolean` 18.3.3.

20.62 chart:tick-marks-minor-outer

The `chart:tick-marks-minor-outer` attribute specifies the existence of minor outer tick marks on an axis. They are drawn with respect to the minor interval divisor that may be specified by the `chart:interval-minor-divisor` attribute, and are drawn towards the outside of the plot area. That is, they are drawn to the left for an axis displayed on the left hand side of the plot area, and to the right for an axis displayed on the right hand side of the plot area.

If a `chart:tick-marks-minor-inner` attribute and a `chart:tick-marks-minor-outer` attribute are set to `true`, one tick mark is drawn that crosses the axis.

This attribute is evaluated for a chart style that is applied to a `<chart:axis>` element.

The defined values for the `chart:tick-marks-minor-outer` attribute are:

- `false`: minor outer tick marks should not appear on an axis.
- `true`: minor outer tick marks should appear on an axis.

The `chart:tick-marks-minor-outer` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:tick-marks-minor-outer` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.63 chart:tick-mark-position

The `chart:tick-mark-position` attribute specifies the position of the interval marks.

The defined values for the `chart:tick-mark-position` attribute are:

- `at-labels`: interval marks are placed adjacent to axis labels.
- `at-axis`: interval marks are placed at the axis line.
- `at-labels-and-axis`: interval marks are placed at axis labels and at the axis line.

This attribute makes a difference only if the labels are not placed at the axis line, that is, if the `chart:axis-label-position` attribute has the value `outside-end` or `outside-start`. 20.5

If the `chart:tick-mark-position` attribute is missing but a `chart:axis-position` attribute is given, `chart:tick-mark-position` is assumed to be `at-labels-and-axis`.

This attribute is evaluated for a chart style that is applied to a `<chart:axis>` element.

The `chart:tick-mark-position` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The values of the `chart:tick-mark-position` attribute are `at-labels`, `at-axis` or `at-labels-and-axis`.

20.64 chart:treat-empty-cells

The `chart:treat-empty-cells` attribute specifies how missing and invalid values are plotted in a chart.

The defined values for the `chart:treat-empty-cells` attribute are:

- `ignore`: nothing is plotted for a point with missing values and the plot continues.
- `leave-gap`: nothing is plotted for a point with missing values and a continuous plot stops and restarts at the next valid point.
- `use-zero`: missing values are replaced with zero.

The default behavior is `ignore` for scatter charts (`chart:class` is `chart:scatter`). For all other chart types the default behavior is `leave-gap`.

This attribute is evaluated for `chart` styles that are applied to a `<chart:plot-area>` element.

The `chart:treat-empty-cells` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The values of the `chart:treat-empty-cells` attribute are `use-zero`, `leave-gap` or `ignore`.

20.65 chart:vertical

The `chart:vertical` attribute specifies whether the x-axis in a Cartesian coordinate system is oriented horizontally or vertically.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Note: This attribute is used to distinguish bar (`chart:vertical="true"`) and column (`chart:vertical="false"`) charts.

This attribute is evaluated for chart styles that are applied to a `<chart:plot-area>` element.

The defined values for the `chart:vertical` attribute are:

- `false`: horizontal x-axis, vertical y-axis.
- `true`: vertical x-axis, horizontal y-axis.

The `chart:vertical` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:vertical` attribute has the data type `boolean` 18.3.3.

20.66 chart:visible

The `chart:visible` attribute specifies if an object in a chart is visible or not. By default, objects are visible.

This attribute is evaluated for chart styles that are applied to a `<chart:axis>` element or a `<chart:series>` element.

The defined values for the `chart:visible` attribute are:

- `false`: object is not visible in chart.
- `true`: object is visible in chart.

The `chart:visible` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `chart:visible` attribute has the data type `boolean` 18.3.3.

20.67 dr3d:ambient-color

See: 19.92

The `dr3d:ambient-color` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `dr3d:ambient-color` attribute has the data type `color` 18.3.9.

20.68 dr3d:back-scale

The `dr3d:back-scale` attribute specifies the proportion of the background geometry for 3D rotation and extrude objects.

The `dr3d:back-scale` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `dr3d:back-scale` attribute has the data type `percent` 18.3.23.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.69 dr3d:backface-culling

The `dr3d:backface-culling` attribute specifies whether backface culling is enabled.

The defined values for the `dr3d:backface-culling` attribute are:

- `disabled`: backface culling is not enabled.
- `enabled`: backface culling is enabled.

The `dr3d:backface-culling` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `dr3d:backface-culling` attribute are `enabled` or `disabled`.

20.70 dr3d:close-back

The `dr3d:close-back` attribute specifies if a back face is generated. The attribute can be used with 3D extrude and 3D rotation objects. It is only evaluated for geometries that are closed.

The defined values for the `dr3d:close-back` attribute are:

- `false`: a back face should not be generated.
- `true`: a back face should be generated.

The `dr3d:close-back` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `dr3d:close-back` attribute has the data type `boolean` 18.3.3.

20.71 dr3d:close-front

The `dr3d:close-front` attribute specifies if a front face is generated. The attribute can be used with 3D extrude and 3D rotation objects. It is only evaluated for geometries that are closed.

The defined values for the `dr3d:close-front` attribute are:

- `false`: a front face should not be generated.
- `true`: a front face should be generated.

The `dr3d:close-front` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `dr3d:close-front` attribute has the data type `boolean` 18.3.3.

20.72 dr3d:depth

The `dr3d:depth` attribute specifies an extrusion depth for extruded objects.

The `dr3d:depth` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `dr3d:depth` attribute has the data type `length` 18.3.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.73 dr3d:diffuse-color

The `dr3d:diffuse-color` attribute, along with `dr3d:ambient-color`, `dr3d:emissive-color`, and `dr3d:specular-color` specifies the four colors that define the color of a material.

The `dr3d:diffuse-color` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `dr3d:diffuse-color` attribute has the data type `color` 18.3.9.

20.74 dr3d:edge-rounding

The `dr3d:edge-rounding` attribute specifies the size of an area at the edges of a geometry that is used for rounding edges, if the geometry of a 3D object is generated during run-time.

The `dr3d:edge-rounding` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `dr3d:edge-rounding` attribute has the data type `percent` 18.3.23.

20.75 dr3d:edge-rounding-mode

The `dr3d:edge-rounding-mode` attribute specifies how to generate rounded edges.

Creating rounded edges in a 3D environment requires an inner and outer representation of the outline on which rounded edges will appear.

The defined values for the `dr3d:edge-rounding-mode` attribute are:

- `attractive`: the edge begins at the inner plane by moving points in the direction of combined perpendicular vectors of both neighboring vectors.
- `correct`: the inner face is linearly scaled smaller relative to its center and the original polygon is used for the outer face.

The `dr3d:edge-rounding-mode` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `dr3d:edge-rounding-mode` attribute are `correct` or `attractive`.

20.76 dr3d:emissive-color

The `dr3d:emissive-color` attribute, along with `dr3d:ambient-color`, `dr3d:diffuse-color`, and `dr3d:specular-color` specifies the four colors that define the color of a material.

The `dr3d:emissive-color` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `dr3d:emissive-color` attribute has the data type `color` 18.3.9.

20.77 dr3d:end-angle

The `dr3d:end-angle` attribute specifies the rotation angle for 3D rotation objects. The attribute value is an angle.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

A value of 360 degrees defines that the 3D rotation object is closed and completely rotated. This is also the default. Values smaller than 360 degrees define opened 3D rotation objects (segments). Values larger than 360 degrees define 3D rotation objects with more than one rotation.

Note: The visible effect of values larger than 360 degrees only differs from that of 360 degrees when the `dr3d:back-scale` attribute has a value different than `100%` .

The `dr3d:end-angle` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `dr3d:end-angle` attribute has the data type `angle` 18.3.1.

20.78 dr3d:horizontal-segments

The `dr3d:horizontal-segments` attribute specifies the number of horizontal segments that are used to generate a geometry, if the geometry of a 3D object is generated during run-time.

Note: Typical consumers support values between 2 and 256.

The `dr3d:horizontal-segments` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `dr3d:horizontal-segments` attribute has the data type `nonNegativeInteger` 18.2.

20.79 dr3d:lighting-mode

The `dr3d:lighting-mode` attribute specifies whether lighting is used for a three-dimensional object.

The defined values for the `dr3d:lighting-mode` attribute are:

- `double-sided`: the front and back sides of all planes are displayed if they are visible from the viewer's perspective.
- `standard`: Depending on the value of the `dr3d:normals-direction` attribute, only the front or only the back side sides of the plane are displayed. The opposite sides are not displayed, whether they are visible from the viewer's perspective or not.

Note: The `dr3d:lighting-mode` attribute is also defined for non-3D object uses. 19.99

The `dr3d:lighting-mode` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `dr3d:lighting-mode` attribute are `standard` or `double-sided`.

20.80 dr3d:normals-direction

The `dr3d:normals-direction` attribute specifies which sides of a 3D object's planes are displayed if the `dr3d:lighting-mode` attribute has the value 'standard'.

The defined values for the `dr3d:normals-direction` attribute are:

- `inverse`: only the back sides of planes are displayed.
- `normal`: only the front sides of planes are displayed.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The front side of the plane is the one the normal points away from.

The dr3d:normals-direction attribute has no effect if the dr3d:lighting-mode attribute has the value double-sided.

The dr3d:normals-direction attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the dr3d:normals-direction attribute are normal or inverse.

20.81 dr3d:normals-kind

The dr3d:normals-kind attribute specifies the normal settings for generated lighting.

The defined values for the dr3d:normals-kind attribute are:

- flat: one normal per flat part.
- object: apply object-specific normals.
- sphere: normals behave as the object is a sphere.

The dr3d:normals-kind attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the dr3d:normals-kind attribute are object, flat or sphere.

20.82 dr3d:shadow

The dr3d:shadow attribute enables or disables a three-dimensional shadow for a three-dimensional object.

The defined values for the dr3d:shadow attribute are:

- hidden: three-dimensional shadow should not be shown for a three-dimensional object.
- visible: three-dimensional shadow should be shown for a three-dimensional object.

The dr3d:shadow attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the dr3d:shadow attribute are visible or hidden.

20.83 dr3d:shininess

The dr3d:shininess attribute specifies the shine of a material.

The dr3d:shininess attribute is usable with the following element: <style:graphic-properties> 17.21.

The dr3d:shininess attribute has the data type percent 18.3.23.

20.84 dr3d:specular-color

The dr3d:specular-color attribute, along with dr3d:ambient-color, dr3d:diffuse-color, and dr3d:emissive-color specifies the four colors that define the color of a material.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The dr3d:specular-color attribute is usable with the following element: <style:graphic-properties> 17.21.

The dr3d:specular-color attribute has the data type color 18.3.9.

20.85 dr3d:texture-filter

The dr3d:texture-filter attribute specifies whether texture filtering is enabled.

The defined values for the dr3d:texture-filter attribute are:

- disabled: texture filtering should not be enabled.
- enabled: texture filtering should be enabled.

The dr3d:texture-filter attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the dr3d:texture-filter attribute are enabled or disabled.

20.86 dr3d:texture-kind

The dr3d:texture-kind attribute specifies if texture changes the luminance, intensity, or color of a shape.

The defined values for the dr3d:texture-kind attribute are:

- color: color of a shape.
- intensity: intensity of a shape.
- luminance: luminance of a shape.

The dr3d:texture-kind attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the dr3d:texture-kind attribute are luminance, intensity or color.

20.87 dr3d:texture-mode

The dr3d:texture-mode attribute specifies how the texture is modulated.

The defined values for the dr3d:texture-mode attribute are:

- blend: blends the texture blend color with the object color.
- modulate: modulates the object color with the texture color.
- replace: replaces the object color with the texture color.

The dr3d:texture-mode attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the dr3d:texture-mode attribute are replace, modulate or blend.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.88 dr3d:texture-generation-mode-x

The `dr3d:texture-generation-mode-x` attribute, along with the `dr3d:texture-generation-mode-y` attribute, specifies how textual coordinates are generated.

The defined values for the `dr3d:texture-generation-mode-x` attribute are:

- `object`: This value specifies that the standard object projection method is used.
- `parallel`: This value specifies a flat parallel projection in the specified degree of freedom (X or Y).
- `sphere`: This value forces projection to wrapping in X and/or Y direction.

The `dr3d:texture-generation-mode-x` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `dr3d:texture-generation-mode-x` attribute are `object`, `parallel` or `sphere`.

20.89 dr3d:texture-generation-mode-y

The `dr3d:texture-generation-mode-y` attribute, along with the `dr3d:texture-generation-mode-x` attribute, specifies how textual coordinates are generated.

The defined values for the `dr3d:texture-generation-mode-y` attribute are:

- `object`: This value specifies that the standard object projection method is used.
- `parallel`: This value specifies a flat parallel projection in the specified degree of freedom (X or Y).
- `sphere`: This value forces projection to wrapping in X and/or Y direction.

The `dr3d:texture-generation-mode-y` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `dr3d:texture-generation-mode-y` attribute are `object`, `parallel` or `sphere`.

20.90 dr3d:vertical-segments

The `dr3d:vertical-segments` attribute specifies the number of vertical segments that are used to generate the geometry, if the geometry of a 3D object is generated during run-time.

Note: Typical consumers support values between 2 and 256.

The `dr3d:vertical-segments` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `dr3d:vertical-segments` attribute has the data type `nonNegativeInteger` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.91 draw:auto-grow-height

The `draw:auto-grow-height` attributes specifies whether to automatically increase the height of the drawing object if text is added to the drawing object. This attribute is evaluated only for text boxes.

If both `draw:auto-grow-width` and `draw:auto-grow-height` are present, a consumer should first grow the size of the drawing object in the dimension of the major text flow (width for horizontal writing, and height for vertical writing). Only after that size component is filled, a consumer should adjust the other dimension to fit the text content.

The defined values for the `draw:auto-grow-height` attribute are:

- `false`: height of a drawing object should not automatically increase if text is added to the drawing object.
- `true`: height of a drawing object should automatically increase if text is added to the drawing object.

The `draw:auto-grow-height` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:auto-grow-height` attribute has the data type `boolean` 18.3.3.

20.92 draw:auto-grow-width

The `draw:auto-grow-width` attribute specifies whether to automatically increase the width of the drawing object if text is added to the drawing object. This attribute is evaluated only for text boxes.

The defined values for the `draw:auto-grow-width` attribute are:

- `false`: width of a drawing object should not automatically increase if text is added to the drawing object.
- `true`: width of a drawing object should automatically increase if text is added to the drawing object.

The `draw:auto-grow-width` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:auto-grow-width` attribute has the data type `boolean` 18.3.3.

20.93 draw:background-size

The `draw:background-size` attribute specifies whether the background of a page is rendered on a full page or only inside the borders of a page.

The defined values for the `draw:background-size` attribute are:

- `border`: background should be rendered only inside borders of a page.
- `full`: background should be rendered on a full page.

The `draw:background-size` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The values of the `draw:background-size` attribute are `full` or `border`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.94 draw:blue

The `draw:blue` attribute specifies together with the attributes `draw:green` and `draw:red` a non destructive filter for a linear transformation of the white balance of a pixel image.

If any of these three attributes is specified, an offset is applied to each pixel of an image while is it rendered. The offsets for each color channel is given as a percentage in the range of -100% to +100%.

These offsets is scaled to the range -2^bits to 2^bits, where bits is the number of bits reserved for each color channel within the image. If the resulting value is less than 0 it is set to 0 and if it is greater than the maximum possible value it is set to the maximum.

Note: For example, if the `draw:blue` attribute has the value 50% and and the blue color channel has 8 bits, then 128 is added to the blue color value of each pixel inside the image before it is rendered. If `draw:blue` has the value -50% then 128 is subtracted.

The `draw:blue` attribute specifies the offset for the blue color channel.

The `draw:blue` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:blue` attribute has the data type `signedZeroToHundredPercent` 18.3.30.

20.95 draw:caption-angle

The `draw:caption-angle` attribute specifies the leaving angle of the line of a caption. It is evaluated only if `draw:caption-angle-type` has the value `fixed`. The attribute value is an angle. See 18.3.1.

The `draw:caption-angle` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:caption-angle` attribute has the data type `angle` 18.3.1.

20.96 draw:caption-angle-type

The `draw:caption-angle-type` attribute specifies if the leaving angle of the line of a caption is fixed or free..

The defined values for the `draw:caption-angle-type` attribute are:

- `fixed`: escape angle of line from caption has been specified by a `draw:caption-angle` attribute.
- `free`: consumer can choose the best possible escape angle of the line from a caption.

The `draw:caption-angle-type` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `draw:caption-angle-type` attribute are `fixed` or `free`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.97 draw:caption-escape

The `draw:caption-escape` attribute specifies the point where a caption's connector is connected to the caption's text area, measured from the top left corner of the text area. The value can be an absolute length or a percentage.

The `draw:caption-escape` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `draw:caption-escape` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

20.98 draw:caption-escape-direction

The `draw:caption-escape-direction` attribute specifies the leaving direction for the line of a caption. If this is set to `auto` the consumer can choose the best direction.

The defined values for the `draw:caption-escape-direction` attribute are:

- `auto`: consumer should choose best leaving direction for a line of a caption.
- `horizontal`: the leaving line of a caption should be drawn horizontally.
- `vertical`: the leaving line of a caption should be drawn vertically.

The `draw:caption-escape-direction` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `draw:caption-escape-direction` attribute are `horizontal`, `vertical` or `auto`.

20.99 draw:caption-fit-line-length

The `draw:caption-fit-line-length` attribute enables the consumer to determine the best possible length for a caption line.

The defined values for the `draw:caption-fit-line-length` attribute are:

- `false`: length for caption line is fixed.
- `true`: consumer should determine the best possible length for a caption line.

The `draw:caption-fit-line-length` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:caption-fit-line-length` attribute has the data type `boolean` 18.3.3.

20.100 draw:caption-gap

The `draw:caption-gap` attribute specifies the distance between the text area of the caption and the start of the line.

The `draw:caption-gap` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:caption-gap` attribute has the data type `distance` 18.3.15.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.101 draw:caption-line-length

The `draw:caption-line-length` attribute specifies the length of the first line of a caption. The attribute is only evaluated if `draw:caption-fit-line-length` has the value `false`.

The `draw:caption-line-length` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:caption-line-length` attribute has the data type `length` 18.3.18.

20.102 draw:caption-type

The `draw:caption-type` attribute specifies the geometry of the line of a caption.

The defined values for the `draw:caption-type` attribute are:

- `angled-connector-line`: a line in leaving direction is drawn, followed by a line to the caption point.
- `angled-line`: a line is drawn to the caption point.
- `straight-line`: a line perpendicular to the leaving direction is drawn to the caption point.

The `draw:caption-type` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `draw:caption-type` attribute are `straight-line`, `angled-line` or `angled-connector-line`.

20.103 draw:color-inversion

The `draw:color-inversion` attribute specifies whether the colors in the graphic shape should be inverted.

Note: Given a color "#rrggbb", where rr, gg and bb are 8-bit hexadecimal digits, the inverted color is "#RRGGBB" where RR is the 8 bit hexadecimal number obtained as the difference of hexadecimal FF and rr, GG is the 8-bit hexadecimal number obtained as the difference of hexadecimal FF (=256) and gg, and BB is the 8 bit hexadecimal number obtained as the difference of hexadecimal FF (=256) and bb.

The defined values for the `draw:color-inversion` attribute are:

- `false`: colors in a graphic shape should not be inverted.
- `true`: colors in a graphic shape should be inverted.

The `draw:color-inversion` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:color-inversion` attribute has the data type `boolean` 18.3.3.

20.104 draw:color-mode

The `draw:color-mode` attribute sets the output of colors from a source bitmap or raster graphic.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the draw:color-mode attribute are:

- greyscale: image is displayed using intensity only.
- mono: image is displayed in black and white.
- standard: image is displayed without modification by the draw:color-mode attribute.
- watermark: colors are modified to make the resulting image transparent.

The draw:color-mode attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the draw:color-mode attribute are greyscale, mono, watermark or standard.

20.105 draw:contrast

The draw:contrast attribute specifies a signed percentage value that sets the output contrast of a bitmap or raster graphic.

The draw:contrast attribute is usable with the following element: <style:graphic-properties> 17.21.

The draw:contrast attribute has the data type percent 18.3.23.

20.106 draw:decimal-places

The draw:decimal-places attribute specifies the number of decimal places that are used for the measure text.

The draw:decimal-places attribute is usable with the following element: <style:graphic-properties> 17.21.

The draw:decimal-places attribute has the data type nonNegativeInteger 18.2.

20.107 draw:draw-aspect

The draw:draw-aspect attribute specifies the display embedded objects.

The defined values for the draw:draw-aspect attribute are:

- content: Specifies an object is displayed as an embedded object inside a frame.
- icon: Specifies an icon to display.
- print-view: Specifies an object is displayed as in a print preview.
- thumbnail: Specifies a thumbnail of an object is displayed.

The draw:draw-aspect attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the draw:draw-aspect attribute are content, thumbnail, icon or print-view.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.108 draw:end-guide

The `draw:end-guide` attribute specifies a length that is added to the length of the end extension line. The extension line is extended by this length towards the end reference point.

The `draw:end-guide` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:end-guide` attribute has the data type `length` 18.3.18.

20.109 draw:end-line-spacing-horizontal

The `draw:end-line-spacing-horizontal` attribute increments the length of the leaving line from the end shape. For line connectors, it specifies the absolute length of the leaving line from the end shape. For other connector types, it is ignored.

The `draw:end-line-spacing-horizontal` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:end-line-spacing-horizontal` attribute has the data type `distance` 18.3.15.

20.110 draw:end-line-spacing-vertical

The `draw:end-line-spacing-vertical` attribute increments the length of the leaving line from the end shape. For line connectors, it specifies the absolute length of the leaving line from the end shape. For other connector types, it is ignored.

The `draw:end-line-spacing-vertical` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:end-line-spacing-vertical` attribute has the data type `distance` 18.3.15.

20.111 draw:fill

The `draw:fill` attribute specifies the fill style for a graphic object. Graphic objects that are not closed will not be filled.

Note: A path without a closepath at the end is open and will not be filled.

The defined values for the `draw:fill` attribute are:

- `bitmap`: the drawing object is filled with the bitmap specified by the `draw:fill-image-name` attribute.
- `gradient`: the drawing object is filled with the gradient specified by the `draw:fill-gradient-name` attribute.
- `hatch`: the drawing object is filled with the hatch specified by the `draw:fill-hatch-name` attribute.
- `none`: the drawing object is not filled.
- `solid`: the drawing object is filled with color specified by the `draw:fill-color` attribute.

The `draw:fill` attribute is usable with the following elements: `<style:drawing-page-properties>` 17.25 and `<style:graphic-properties>` 17.21.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The values of the draw:fill attribute are none, solid, bitmap, gradient or hatch.

20.112 draw:fill-color

The draw:fill-color attribute specifies the color of the fill for a graphic object. It is used only if the draw:fill attribute has one of the values solid or hatch.

The draw:fill-color attribute is usable with the following elements: <style:drawing-page-properties> 17.25 and <style:graphic-properties> 17.21.

The draw:fill-color attribute has the data type color 18.3.9.

20.113 draw:fill-gradient-name

The draw:fill-gradient-name attribute specifies a gradient style that is used for filling graphic objects. It is used only if the draw:fill attribute has the value gradient.

The draw:fill-gradient-name attribute is usable with the following elements: <style:drawing-page-properties> 17.25 and <style:graphic-properties> 17.21.

The draw:fill-gradient-name attribute has the data type styleNameRef 18.3.32.

20.114 draw:fill-hatch-name

The draw:fill-hatch-name attribute specifies a hatch style that is used for filling. It is used only if the draw:fill attribute has the value hatch.

The draw:fill-hatch-name attribute is usable with the following elements: <style:drawing-page-properties> 17.25 and <style:graphic-properties> 17.21.

The draw:fill-hatch-name attribute has the data type styleNameRef 18.3.32.

20.115 draw:fill-hatch-solid

The draw:fill-hatch-solid attribute specifies whether the background of a hatch filling is solid or transparent.

The defined values for the draw:fill-hatch-solid attribute are:

- false: background of a hatch filling should be transparent.
- true: background of a hatch filling Is filled with color specified by the draw:fill-color attribute.

The draw:fill-hatch-solid attribute is usable with the following elements: <style:drawing-page-properties> 17.25 and <style:graphic-properties> 17.21.

The draw:fill-hatch-solid attribute has the data type boolean 18.3.3.

20.116 draw:fill-image-height

The draw:fill-image-height attribute overrides the logical height of a source image that is used for filling. If the value of the style:repeat attribute is stretch, this attribute is ignored.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `draw:fill-image-height` attribute is usable with the following elements: `<style:drawing-page-properties>` 17.25 and `<style:graphic-properties>` 17.21.

The values of the `draw:fill-image-height` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

20.117 draw:fill-image-name

The `draw:fill-image-name` attribute specifies a fill image that is used for filling. It is used only if the `draw:fill` attribute has the value `bitmap`.

The `draw:fill-image-name` attribute is usable with the following elements: `<style:drawing-page-properties>` 17.25 and `<style:graphic-properties>` 17.21.

The `draw:fill-image-name` attribute has the data type `styleNameRef` 18.3.32.

20.118 draw:fill-image-ref-point

The `draw:fill-image-ref-point` attribute specifies an alignment of an image in the filling area.

If an alignment (`draw:fill-image-ref-point`) and a movement (`draw:fill-image-ref-point-x`, `draw:fill-image-ref-point-y`) is specified at the same time, the image first is aligned and then moved.

This attribute is only interpreted if the value of the current `style:repeat` attribute is `repeat`.

The defined values for the `draw:fill-image-ref-point` attribute are:

- `bottom`: image aligned with the bottom of the filling area.
- `bottom-left`: image aligned with the bottom-left of the filling area.
- `bottom-right`: image aligned with the bottom-right of the filling area.
- `center`: image aligned with the center of the filling area.
- `left`: image aligned with the left of the filling area.
- `right`: image aligned with the right of the filling area.
- `top`: image aligned with the top of the filling area.
- `top-left`: image aligned with the top-left of the filling area.
- `top-right`: image aligned with the top-right of the filling area.

The `draw:fill-image-ref-point` attribute is usable with the following elements: `<style:drawing-page-properties>` 17.25 and `<style:graphic-properties>` 17.21.

The values of the `draw:fill-image-ref-point` attribute are `top-left`, `top`, `top-right`, `left`, `center`, `right`, `bottom-left`, `bottom` or `bottom-right`.

20.119 draw:fill-image-ref-point-x

The `draw:fill-image-ref-point-x` attribute specifies the horizontal movement of an image as a percentage value, where the percentage value is relative to the image width.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If an alignment (draw:fill-image-ref-point) and a movement (draw:fill-image-ref-point-x, draw:fill-image-ref-point-y) is specified at the same time, the image first is aligned and then moved.

This attribute is only interpreted if the value of the current style:repeat attribute is repeat.

The draw:fill-image-ref-point-x attribute is usable with the following elements: <style:drawing-page-properties> 17.25 and <style:graphic-properties> 17.21.

The draw:fill-image-ref-point-x attribute has the data type percent 18.3.23.

20.120 draw:fill-image-ref-point-y

The draw:fill-image-ref-point-x attribute specifies the horizontal movement of an image as a percentage value, where the percentage value is relative to the image width.

If an alignment (draw:fill-image-ref-point) and a movement (draw:fill-image-ref-point-x, draw:fill-image-ref-point-y) is specified at the same time, the image first is aligned and then moved.

This attribute is only interpreted if the value of the current style:repeat attribute is repeat.

The draw:fill-image-ref-point-y attribute is usable with the following elements: <style:drawing-page-properties> 17.25 and <style:graphic-properties> 17.21.

The draw:fill-image-ref-point-y attribute has the data type percent 18.3.23.

20.121 draw:fill-image-width

The draw:fill-image-width attribute overrides the logical width of a source image that is used for filling. If the value of the style:repeat attribute is stretch, this attribute is ignored.

The draw:fill-image-width attribute is usable with the following elements: <style:drawing-page-properties> 17.25 and <style:graphic-properties> 17.21.

The values of the draw:fill-image-width attribute are a value of type length 18.3.18 or a value of type percent 18.3.23.

20.122 draw:fit-to-contour

The draw:fit-to-contour attribute specifies whether to stretch the text content of a drawing object to fill the contour of an object.

The defined values for the draw:fit-to-contour attribute are:

- false: text content should not be stretched to fill the contour of an object.
- true: text content should be stretched to fill the contour of an object.

The draw:fit-to-contour attribute is usable with the following element: <style:graphic-properties> 17.21.

The draw:fit-to-contour attribute has the data type boolean 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.123 draw:fit-to-size

The `draw:fit-to-size` attribute specifies whether to stretch the text content of a drawing object to fill an entire object.

The defined values for the `draw:fit-to-size` attribute are:

- `false`: text content should not be stretched to fill an entire object.
- `true`: text content should be stretched to fill an entire object.

The `draw:fit-to-size` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:fit-to-size` attribute has the data type `boolean` 18.3.3.

20.124 draw:frame-display-border

The `draw:frame-display-border` attribute specifies whether a border is displayed on a floating frame. This attribute can be used with automatic styles only.

The defined values for the `draw:frame-display-border` attribute are:

- `false`: a border should not be displayed on a floating frame.
- `true`: a border should be displayed on a floating frame.

The `draw:frame-display-border` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:frame-display-border` attribute has the data type `boolean` 18.3.3.

20.125 draw:frame-margin-horizontal

The `draw:frame-margin-horizontal` attribute specifies the horizontal margin between the border and the content of the floating frame. If this attribute is not specified, the default margin is used. This attribute can be used with automatic styles only. The value of this attribute shall be a length in pixels.

The `draw:frame-margin-horizontal` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:frame-margin-horizontal` attribute has the data type `nonNegativePixelLength` 18.3.21.

20.126 draw:frame-display-scrollbar

The `draw:frame-display-scrollbar` attribute specifies whether vertical and horizontal scrollbars are displayed. This attribute can be assigned to automatic styles only.

The defined values for the `draw:frame-display-scrollbar` attribute are:

- `false`: vertical and horizontal scrollbars should not be displayed.
- `true`: vertical and horizontal scrollbars should be displayed.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `draw:frame-display-scrollbar` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:frame-display-scrollbar` attribute has the data type `boolean` 18.3.3.

20.127 draw:frame-margin-vertical

The `draw:frame-margin-vertical` attribute specifies the vertical margin between the border and the content of the floating frame. If this attribute is not specified, the default margin is used. This attribute can be used with automatic styles only. The value of this attribute shall be a length in pixels.

The `draw:frame-margin-vertical` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:frame-margin-vertical` attribute has the data type `nonNegativePixelLength` 18.3.21.

20.128 draw:gamma

The `draw:gamma` attribute specifies a value that sets the output gamma of a bitmap or raster graphic.

The `draw:gamma` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:gamma` attribute has the data type `percent` 18.3.23.

20.129 draw:green

The `draw:green` attribute specifies together with the attributes `draw:blue` and `draw:red` a non destructive filter for a linear transformation of the white balance of a pixel image. See 20.94.

The `draw:green` attribute specifies the offset for the green color channel.

The `draw:green` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:green` attribute has the data type `signedZeroToHundredPercent` 18.3.30.

20.130 draw:gradient-step-count

The `draw:gradient-step-count` attribute specifies the gradient step count of a color interpolation to be a fixed value. By default, the step count is automatically calculated based on the size and resolution of the filled area.

A gradient step count of color interpretation shall be 3 or greater.

A gradient step count of color interpretation may be above 256.

The `draw:gradient-step-count` attribute is usable with the following elements: `<style:drawing-page-properties>` 17.25 and `<style:graphic-properties>` 17.21.

The `draw:gradient-step-count` attribute has the data type `nonNegativeInteger` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.131 draw:guide-distance

The `draw:guide-distance` attribute specifies the distance between the reference points and the start point of extension lines.

Note: This distance may be further modified for the start and end extensions lines individually with the `draw:start-guide` and `draw:end-guide` attributes.

The `draw:guide-distance` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:guide-distance` attribute has the data type `distance` 18.3.15.

20.132 draw:guide-overhang

The `draw:guide-overhang` attribute specifies the length of extension lines after their intersection with a dimension line.

The `draw:guide-overhang` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:guide-overhang` attribute has the data type `length` 18.3.18.

20.133 draw:image-opacity

The `draw:image-opacity` attribute specifies the opacity of an image.

The `draw:image-opacity` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:image-opacity` attribute has the data type `zeroToHundredPercent` 18.3.41.

20.134 draw:line-distance

The `draw:line-distance` attribute specifies the distance between a reference line (as defined by the reference points) and a dimension line.

The `draw:line-distance` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:line-distance` attribute has the data type `distance` 18.3.15.

20.135 draw:luminance

The `draw:luminance` attribute specifies a signed percentage value that sets the output luminance of a bitmap or raster graphic.

The `draw:luminance` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:luminance` attribute has the data type `zeroToHundredPercent` 18.3.41.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.136 draw:marker-end

The `draw:marker-end` attribute specifies a stroke end marker, which is a path that can be connected to the end of a stroke.

The `draw:marker-end` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:marker-end` attribute has the data type `styleNameRef` 18.3.32.

20.137 draw:marker-end-center

The `draw:marker-end-center` attribute specifies whether an end marker is centered at the end of a stroke.

The defined values for the `draw:marker-end-center` attribute are:

- `false`: an end marker should not be centered at the end of a stroke.
- `true`: an end marker should be centered at the end of a stroke.

The `draw:marker-end-center` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:marker-end-center` attribute has the data type `boolean` 18.3.3.

20.138 draw:marker-end-width

The `draw:marker-end-width` attribute specifies the width of the marker at the end of a stroke.

The `draw:marker-end-width` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:marker-end-width` attribute has the data type `length` 18.3.18.

20.139 draw:marker-start

The `draw:marker-start` attribute specifies a stroke start marker, which is a path that can be connected to the start of a stroke.

The `draw:marker-start` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:marker-start` attribute has the data type `styleNameRef` 18.3.32.

20.140 draw:marker-start-center

The `draw:marker-start-center` attribute specifies whether a start marker is centered at the start of a stroke.

The defined values for the `draw:marker-start-center` attribute are:

- `false`: a start marker should not be centered at the start of a stroke.
- `true`: a start marker should be centered at the start of a stroke.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:marker-start-center attribute is usable with the following element: <style:graphic-properties> 17.21.

The draw:marker-start-center attribute has the data type boolean 18.3.3.

20.141 draw:marker-start-width

The draw:marker-start-width attribute specifies the width of the marker at the start of a stroke.

The draw:marker-start-width attribute is usable with the following element: <style:graphic-properties> 17.21.

The draw:marker-start-width attribute has the data type length 18.3.18.

20.142 draw:measure-align

The draw:measure-align attribute specifies the horizontal alignment of a measure text relative to its measure line.

The defined values for the draw:measure-align attribute are:

- automatic: horizontal alignment of a measure text relative to its measure line is chosen by the consumer.
- inside: horizontal alignment of a measure text should be inside relative to its measure line.
- left-outside: horizontal alignment of a measure text should be left-outside relative to its measure line.
- right-outside: horizontal alignment of a measure text should be right-outside relative to its measure line.

The draw:measure-align attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the draw:measure-align attribute are automatic, left-outside, inside or right-outside.

20.143 draw:measure-vertical-align

The draw:measure-vertical-align attribute specifies the vertical alignment of a measure text relative to its measure line. If the value of this attribute is automatic, the consumer chooses the best position.

The defined values for the draw:measure-vertical-align attribute are:

- above: vertical alignment of a measure text should be above relative to its measure line.
- automatic: vertical alignment of a measure text relative to its measure line is chosen by the consumer.
- below: vertical alignment of a measure text should be below relative to its measure line.
- center: vertical alignment of a measure text should be centered relative to its measure line.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `draw:measure-vertical-align` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `draw:measure-vertical-align` attribute are `automatic`, `above`, `below` or `center`.

20.144 draw:ole-draw-aspect

The `draw:ole-draw-aspect` attribute specifies the display of embedded objects. See [OLE].

The use of this attribute is deprecated. The `draw:draw-aspect` attribute should be used instead.

The `draw:ole-draw-aspect` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:ole-draw-aspect` attribute has the data type `nonNegativeInteger` 18.2.

20.145 draw:opacity

The `draw:opacity` attribute specifies the opacity for an image or graphic object. The value is a percentage, where 0% is fully transparent and 100% is fully opaque.

The defined value range for the `draw:opacity` attribute is 0% to 100%, inclusive.

Use of the `draw:opacity` attribute disables any transparency effect and set the opacity for the fill area of a graphic object.

The `draw:opacity` attribute is usable with the following elements: `<style:drawing-page-properties>` 17.25 and `<style:graphic-properties>` 17.21.

The `draw:opacity` attribute has the data type `zeroToHundredPercent` 18.3.41.

20.146 draw:opacity-name

The `draw:opacity-name` attribute specifies an opacity gradient that defines the opacity for the fill area of a graphic object. When applying an opacity gradient, the opacity is interpolated as defined in the referenced opacity gradient style. Opacity is applied after other fill styles have been applied to an image or graphic object.

The value of this attribute overrides the `draw:opacity` attribute.

The `draw:opacity-name` attribute is usable with the following elements: `<style:drawing-page-properties>` 17.25 and `<style:graphic-properties>` 17.21.

The `draw:opacity-name` attribute has the data type `styleNameRef` 18.3.32.

20.147 draw:parallel

The `draw:parallel` attribute specifies whether a measure text is displayed parallel to its measure line or perpendicular to it.

The defined values for the `draw:parallel` attribute are:

- `false`: measure text is displayed perpendicular to its measure line.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: measure text is displayed parallel to its measure line.

The `draw:parallel` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:parallel` attribute has the data type `boolean` 18.3.3.

20.148 draw:placing

The `draw:placing` attribute specifies whether the measure line is rendered below or above the edge defined by the two reference points.

The defined values for the `draw:placing` attribute are:

- `above`: measure line is rendered above the edge defined by two reference points.
- `below`: measure line is rendered below the edge defined by two reference points.

The `draw:placing` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `draw:placing` attribute are `below` or `above`.

20.149 draw:red

The `draw:red` attribute specifies together with the attributes `draw:blue` and `draw:green` a non destructive filter for a linear transformation of the white balance of a pixel image. See 20.94.

The `draw:red` attribute specifies the offset for the red color channel.

The `draw:red` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:red` attribute has the data type `signedZeroToHundredPercent` 18.3.30.

20.150 draw:secondary-fill-color

The `draw:secondary-fill-color` attribute specifies a secondary fill color. It may be used as fill color for the extrusion.

The `draw:secondary-fill-color` attribute is usable with the following elements: `<style:drawing-page-properties>` 17.25 and `<style:graphic-properties>` 17.21.

The `draw:secondary-fill-color` attribute has the data type `color` 18.3.9.

20.151 draw:shadow

The `draw:shadow` attribute enables or disables the visibility of a shadow.

The defined values for the `draw:shadow` attribute are:

- `hidden`: a shadow should not be visible.
- `visible`: a shadow should be visible.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `draw:shadow` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `draw:shadow` attribute are `visible` or `hidden`.

20.152 draw:shadow-color

The `draw:shadow-color` attribute specifies the color in which a shadow is rendered.

The `draw:shadow-color` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:shadow-color` attribute has the data type `color` 18.3.9.

20.153 draw:shadow-offset-x

The `draw:shadow-offset-x` attribute along with the `draw:shadow-offset-y` attribute are used to render a shadow.

A copy of the shape is rendered in the single shadow color (specified by `draw:shadow-color`) behind the shape. The offset attributes specify the offset between the top left edge of the shape and the top left edge of the border.

The `draw:shadow-offset-x` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:shadow-offset-x` attribute has the data type `length` 18.3.18.

20.154 draw:shadow-offset-y

The `draw:shadow-offset-y` attribute along with the `draw:shadow-offset-x` attribute are used to render a shadow.

The `draw:shadow-offset-y` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:shadow-offset-y` attribute has the data type `length` 18.3.18.

20.155 draw:shadow-opacity

The `draw:shadow-opacity` attribute specifies the opacity in which the shadow is rendered. The value of this attribute is a percentage value.

The `draw:shadow-opacity` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:shadow-opacity` attribute has the data type `zeroToHundredPercent` 18.3.41.

20.156 draw:show-unit

The `draw:show-unit` attribute specifies the visibility of a unit in the textual presentation of a measure shape.

The defined values for the `draw:show-unit` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `false`: units should not be visible in the textual presentation of a measure shape.
- `true`: units should be visible in the textual presentation of a measure shape.

The `draw:show-unit` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:show-unit` attribute has the data type `boolean` 18.3.3.

20.157 draw:start-guide

The `draw:start-guide` attribute specifies a length that is added to the length of a start extension line. The extension line is extended by this length towards the start reference point.

The `draw:start-guide` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:start-guide` attribute has the data type `length` 18.3.18.

20.158 draw:start-line-spacing-horizontal

The `draw:start-line-spacing-horizontal` attribute increments the length of the leaving line from the start shape for standard connectors. For lines connectors, these attributes specify the absolute length of the leaving line from the start shape. For other connector types, they are ignored.

The `draw:start-line-spacing-horizontal` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:start-line-spacing-horizontal` attribute has the data type `distance` 18.3.15.

20.159 draw:start-line-spacing-vertical

The `draw:start-line-spacing-vertical` attribute increments the length of the leaving line from the start shape for standard connectors. For lines connectors, these attributes specify the absolute length of the leaving line from the start shape. For other connector types, they are ignored.

The `draw:start-line-spacing-vertical` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:start-line-spacing-vertical` attribute has the data type `distance` 18.3.15.

20.160 draw:stroke

The `draw:stroke` attribute specifies the style of the stroke on the current object.

The defined values for the `draw:stroke` attribute are:

- `dash`: stroke referenced by a `draw:stroke-dash` attribute of a style on the object is drawn.
- `none`: no stroke is drawn.
- `solid`: solid stroke is drawn.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The draw:stroke attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the draw:stroke attribute are none, dash or solid.

20.161 draw:stroke-dash

The draw:stroke-dash attribute specifies the dash style that is used for a stroke.

The draw:stroke-dash attribute is usable with the following element: <style:graphic-properties> 17.21.

The draw:stroke-dash attribute has the data type styleNameRef 18.3.32.

20.162 draw:stroke-dash-names

The draw:stroke-dash-names attribute specifies a list of dash styles that are used for the stroke in addition to the dash specified by the draw:stroke-dash attribute.

For each dash style referenced by the attribute a stroke using that dash style is drawn on top of the already drawn strokes.

The draw:stroke-dash-names attribute is usable with the following element: <style:graphic-properties> 17.21.

The draw:stroke-dash-names attribute has the data type styleNameRefs 18.3.33.

20.163 draw:stroke-linejoin

The draw:stroke-linejoin attribute specifies the shape at the corners of paths or other vector shapes when they are stroked.

The defined values for the draw:stroke-linejoin attribute are:

- bevel: See §11.4 of [SVG].
- middle: mean value between joins is used (deprecated)
- miter: See §11.4 of [SVG].
- none: no shape specified.
- round: See §11.4 of [SVG].

The draw:stroke-linejoin attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the draw:stroke-linejoin attribute are miter, round, bevel, middle or none.

20.164 svg:stroke-linecap

The svg:stroke-linecap attribute specifies the shape of the end of open subpaths when they are stroked.

The defined values for the svg:stroke-linecap attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `butt`: See §11.4 of [SVG].
- `round`: See §11.4 of [SVG].
- `square`: See §11.4 of [SVG].

The `svg:stroke-linecap` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `svg:stroke-linecap` attribute are `butt`, `square` or `round`.

20.165 draw:symbol-color

The `draw:symbol-color` attribute defines the color to be used to draw symbols contained on the drawing object.

The `draw:symbol-color` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:symbol-color` attribute has the data type `color` 18.3.9.

20.166 draw:textarea-horizontal-align

The `draw:textarea-horizontal-align` attribute specifies the horizontal alignment of the text area inside a shape.

The defined values for the `draw:textarea-horizontal-align` attribute are:

- `center`: text area is centered horizontally inside a shape.
- `justify`: text area is justified horizontally inside a shape.
- `left`: text area is left aligned horizontally inside a shape.
- `right`: text area is right aligned horizontally inside a shape.

The `draw:textarea-horizontal-align` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `draw:textarea-horizontal-align` attribute are `left`, `center`, `right` or `justify`.

20.167 draw:textarea-vertical-align

The `draw:textarea-vertical-align` attribute specifies the vertical alignment of the text area inside a shape.

The defined values for the `draw:textarea-vertical-align` attribute are:

- `bottom`: vertical alignment of text area inside a shape should start at the bottom of the shape.
- `justify`: vertical alignment of text area inside a shape should be justified.
- `middle`: vertical alignment of text area inside a shape should start at the middle of the shape.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `top`: vertical alignment of text area inside a shape should start at the top of the shape.

The `draw:textarea-vertical-align` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `draw:textarea-vertical-align` attribute are `top`, `middle`, `bottom` or `justify`.

20.168 draw:tile-repeat-offset

The `draw:tile-repeat-offset` attribute specifies for tiling the translation of each tile in relation to the previous tile. This attribute is only interpreted if the value of the current `style:repeat` attribute is `repeat`. The value of this attribute is a percentage value representing the tiles repeat offset relative to the tiles height or width, followed by either the word `horizontal` or `vertical`.

The defined values for the `draw:tile-repeat-offset` attribute are:

- `horizontal`: images are tiled horizontally with regard to the previous tile.
- `vertical`: images are tiled vertically with regard to the previous tile.

The `draw:tile-repeat-offset` attribute is usable with the following elements: `<style:drawing-page-properties>` 17.25 and `<style:graphic-properties>` 17.21.

The `draw:tile-repeat-offset` attribute has two white space separated values. The first value is of type `zeroToHundredPercent` 18.3.41. The second value is one of: `horizontal` or `vertical`.

20.169 draw:visible-area-height

The visible area of an object may be specified by the `draw:visible-area-height` attribute along with the `draw:visible-area-left`, `draw:visible-area-top`, `draw:visible-area-width` attributes. It is implementation-defined whether these attributes are used to specify the visible area, or whether the producer of the object stores the visible area within the object itself.

When the entire object is visible, the values of the `draw:visible-area-left` and `draw:visible-area-top` attributes are `0` and the `draw:visible-area-width` and `draw:visible-area-height` attributes specify the size of the object. These attributes can be assigned to automatic styles only.

The `draw:visible-area-height` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `draw:visible-area-height` attribute has the data type `positiveLength` 18.3.26.

20.170 draw:visible-area-left

The visible area of an object may be specified by the `draw:visible-area-left` attribute along with the `draw:visible-area-height`, `draw:visible-area-top`, `draw:visible-area-width` attributes. It is implementation-defined whether these attributes are used to specify the visible area, or whether the producer of the object stores the visible area within the object itself.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

When the entire object is visible, the values of the draw:visible-area-left and draw:visible-area-top attributes are 0 and the draw:visible-area-width and draw:visible-area-height attributes specify the size of the object. These attributes can be assigned to automatic styles only.

The draw:visible-area-left attribute is usable with the following element: <style:graphic-properties> 17.21.

The draw:visible-area-left attribute has the data type nonNegativeLength 18.3.20.

20.171 draw:visible-area-top

The visible area of an object may be specified by the draw:visible-area-top attribute along with the draw:visible-area-left, draw:visible-area-height, draw:visible-area-width attributes. It is implementation-defined whether these attributes are used to specify the visible area, or whether the producer of the object stores the visible area within the object itself.

When the entire object is visible, the values of the draw:visible-area-left and draw:visible-area-top attributes are 0 and the draw:visible-area-width and draw:visible-area-height attributes specify the size of the object. These attributes can be assigned to automatic styles only.

The draw:visible-area-top attribute is usable with the following element: <style:graphic-properties> 17.21.

The draw:visible-area-top attribute has the data type nonNegativeLength 18.3.20.

20.172 draw:visible-area-width

The visible area of an object may be specified by the draw:visible-area-width attribute along with the draw:visible-area-left, draw:visible-area-top, draw:visible-area-height attributes. It is implementation-defined whether these attributes are used to specify the visible area, or whether the producer of the object stores the visible area within the object itself.

When the entire object is visible, the values of the draw:visible-area-left and draw:visible-area-top attributes are 0 and the draw:visible-area-width and draw:visible-area-height attributes specify the size of the object. These attributes can be assigned to automatic styles only.

The draw:visible-area-width attribute is usable with the following element: <style:graphic-properties> 17.21.

The draw:visible-area-width attribute has the data type positiveLength 18.3.26.

20.173 draw:unit

The draw:unit attribute specifies the unit of measurement used in the textual presentation of a measure shape.

The defined values for the draw:unit attribute are:

- automatic: unit of measurement chosen by consumer.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `mm`: millimeter.
- `cm`: centimeter.
- `m`: meter
- `km`: kilometer.
- `pt`: point.
- `pc`: pica.
- `inch`: inch.
- `ft`: foot.
- `mi`: mile.

The `draw:unit` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `draw:unit` attribute are `automatic`, `mm`, `cm`, `m`, `km`, `pt`, `pc`, `inch`, `ft` or `mi`.

20.174 draw:wrap-influence-on-position

The `draw:wrap-influence-on-position` attribute specifies placement options for two or more frames or graphic objects with `style:wrap` properties that influence the placement of the other object. (20.390) It is intended as a hint to the layout algorithm to help determine the placement of frames in cases where several correct placements are possible.

The situation in which this attribute makes a difference is when the anchor, position and wrapping mode of a frame influence each other. For example, consider a paragraph of text with two images positioned above the anchor. Without wrapping, the images overlie the text and can simply be placed at the given offset from the anchor.



Figure 2 - Image positions without wrapping

If wrap-around is enabled, the text hidden behind the images now should flow around the images, making the first paragraph use more space than previously. This moves the anchor position further down. If the placement is only done once and concurrently for all objects, this is the final result. This corresponds to the object `once-concurrently`.



Figure 3 - Image positions for “once-concurrently”

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If one image is processed at a time, the position shown Figure 5 results. This corresponds to the option `once-successive`.



Figure 4 - Image positions for "once-successive"

If the images are placed iteratively, until a position is found which corresponds to the given offset from the anchor, a placement that fully satisfies all the given layout formatting properties can be achieved. This corresponds to the option `iterative`.



Figure 5 - Image positions for iterative

The defined values for the `draw:wrap-influence-on-position` attribute are:

- `iterative`: images are placed iteratively until all specified layout formatting properties are satisfied.
- `once-concurrent`: images are aligned with one another.
- `once-successive`: subsequent image is placed after the preceding image.

The `draw:wrap-influence-on-position` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `draw:wrap-influence-on-position` attribute are `iterative`, `once-concurrent` or `once-successive`.

20.175 fo:background-color

The `fo:background-color` attribute specifies a background color for characters, paragraphs, text sections, frames, page bodies, headers, footers, tables, table rows and tables. This can be transparent or a color. If the value is set to transparent, it switches off any background image that is specified by a `<style:background-image>`. 17.3

If a value for a `draw:fill` attribute is provided in a style, any background image that is specified by a `<style:background-image>` element and any background color that is specified with the `fo:background-color` attribute are switched off.

The `fo:background-color` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6, `<style:section-properties>` 17.11, `<style:table-cell-properties>` 17.18,

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

<style:table-properties> 17.15, <style:table-row-properties> 17.17 and <style:text-properties> 16.27.28.

The values of the fo:background-color attribute are transparent or a value of type color 18.3.9.

20.176 fo Border Properties

20.176.1 General

The fo:border, fo:border-top, fo:border-bottom, fo:border-left and fo:border-right attributes specify border properties for these elements:

- <style:graphic-properties>
- <style:header-footer-properties>
- <style:page-layout-properties>
- <style:paragraph-properties>
- <style:table-cell-properties>

20.176.2 fo:border

See §7.29.3 of [XSL].

The fo:border attribute is usable with the following elements: <style:graphic-properties> 17.21, <style:header-footer-properties> 17.5, <style:page-layout-properties> 17.2, <style:paragraph-properties> 17.6 and <style:table-cell-properties> 17.18.

The fo:border attribute has the data type string 18.2.

20.176.3 fo:border-bottom

See §7.29.4 of [XSL].

The fo:border-bottom attribute is usable with the following elements: <style:graphic-properties> 17.21, <style:header-footer-properties> 17.5, <style:page-layout-properties> 17.2, <style:paragraph-properties> 17.6 and <style:table-cell-properties> 17.18.

The fo:border-bottom attribute has the data type string 18.2.

20.176.4 fo:border-left

See §7.29.6 of [XSL].

The fo:border-left attribute is usable with the following elements: <style:graphic-properties> 17.21, <style:header-footer-properties> 17.5, <style:page-layout-properties> 17.2, <style:paragraph-properties> 17.6 and <style:table-cell-properties> 17.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `fo:border-left` attribute has the data type `string` 18.2.

20.176.5 fo:border-right

See §7.29.7 of [XSL].

The `fo:border-right` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-cell-properties>` 17.18.

The `fo:border-right` attribute has the data type `string` 18.2.

20.176.6 fo:border-top

See §7.29.10 of [XSL].

The `fo:border-top` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-cell-properties>` 17.18.

The `fo:border-top` attribute has the data type `string` 18.2.

20.177 fo:break-after

See §7.19.1 of [XSL]. The values `odd-page` and `even-page` are not supported.

This attribute shall not be used at the same time as `fo:break-before`.

In the OpenDocument XSL compatible namespace, the `fo:break-after` attribute does not support `even-page`, `inherit` and `odd-page` values.

The `fo:break-after` attribute is usable with the following elements: `<style:paragraph-properties>` 17.6, `<style:table-column-properties>` 17.16, `<style:table-properties>` 17.15 and `<style:table-row-properties>` 17.17.

The values of the `fo:break-after` attribute are `auto`, `column` or `page`.

20.178 fo:break-before

See §7.19.2 of [XSL]. The values `odd-page` and `even-page` are not supported.

This attribute shall not be used at the same time as `fo:break-after`.

In the OpenDocument XSL compatible namespace, the `fo:break-before` attribute does not support `even-page`, `inherit` and `odd-page` values.

The `fo:break-before` attribute is usable with the following elements: `<style:paragraph-properties>` 17.6, `<style:table-column-properties>` 17.16, `<style:table-properties>` 17.15 and `<style:table-row-properties>` 17.17.

The values of the `fo:break-before` attribute are `auto`, `column` or `page`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.179 fo:clip

See §7.20.1 of [XSL].

In the OpenDocument XSL compatible namespace, the `fo:clip` attribute does not support `em` and `px` values.

The defined value for the `fo:clip` attribute is a value of type `clipShape` 18.3.8.

The `fo:clip` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `fo:clip` attribute are `auto` or a value of type `clipShape` 18.3.8.

20.180 fo:color

See §7.17.1 of [XSL].

In the OpenDocument XSL compatible namespace, the `fo:color` attribute does not support the `inherit` value.

The `fo:color` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `fo:color` attribute has the data type `color` 18.3.9.

20.181 fo:country

See §7.9.1 of [XSL].

The attribute is evaluated for any [UNICODE] characters whose script type is `latin`. 20.348

It may be ignored if is not specified together with a `fo:language` attribute.

In the OpenDocument XSL compatible namespace, the `fo:country` attribute does not support `none` or `inherit` values.

The `fo:country` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `fo:country` attribute has the data type `countryCode` 18.3.11.

20.182 fo:font-family

See §7.8.2 of [XSL].

The `fo:font-family` attribute is evaluated for any [UNICODE] character whose script type is `latin`. 20.348

Instead of this attribute, the `style:font-name` attribute should be used to specify the properties of a font.

The `fo:font-family` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `fo:font-family` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.183 fo:font-size

See §7.8.4 of [XSL].

This attribute is evaluated for any [UNICODE] character whose script type is `latin`. 20.348

The value of this attribute is either an absolute length or a percentage as described in §7.8.4 of [XSL]. In contrast to XSL, percentage values can be used within common styles only and are based on the font height of the parent style rather than to the font height of the attributes neighborhood. Absolute font heights and relative font heights are not supported.

Note: The `style:font-size-asian` attribute (20.276) is evaluated for [UNICODE] characters whose type is `asian`. 20.348 The `style:font-size-complex` attribute (20.277) is evaluated for [UNICODE] characters whose type is `complex`. 20.348

In the OpenDocument XSL compatible namespace, the `fo:font-size` attribute does not support `absolute-size`, `inherit` and `relative-size` values.

The `fo:font-size` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `fo:font-size` attribute are a value of type `positiveLength` 18.3.26 or a value of type `percent` 18.3.23.

20.184 fo:font-style

See §7.8.7 of [XSL].

This attribute is evaluated for any [UNICODE] character whose script type is `latin`. 20.348

In the OpenDocument XSL compatible namespace, the `fo:font-style` attribute does not support `backslant` and `inherit` values.

The `fo:font-style` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `fo:font-style` attribute are `normal`, `italic` or `oblique`.

20.185 fo:font-variant

See §7.8.8 of [XSL].

In the OpenDocument XSL compatible namespace, the `fo:font-variant` attribute does not support the `inherit` value.

The `fo:font-variant` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `fo:font-variant` attribute are `normal` or `small-caps`.

20.186 fo:font-weight

See §7.8.9 of [XSL].

This attribute is evaluated for any [UNICODE] character whose script type is `latin`. 20.348

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

In the OpenDocument XSL compatible namespace, the `fo:font-weight` attribute does not support `bolder`, `inherit` and `lighter` values.

The `fo:font-weight` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `fo:font-weight` attribute are `normal`, `bold`, `100`, `200`, `300`, `400`, `500`, `600`, `700`, `800` or `900`.

20.187 fo:height

See §7.14.4 of [XSL].

The `fo:height` attribute is used with `fo:width` to set the size of a bullet image.

In the OpenDocument XSL compatible namespace, the `fo:height` attribute does not support `auto`, `inherit` and `percentage` values.

The `fo:height` attribute is usable with the following element: `<style:list-level-properties>` 17.19.

The `fo:height` attribute has the data type `positiveLength` 18.3.26.

20.188 fo:hyphenate

See §7.9.4 of [XSL].

In the OpenDocument XSL compatible namespace, the `fo:hyphenate` attribute does not support the `inherit` value.

The `fo:hyphenate` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `fo:hyphenate` attribute has the data type `boolean` 18.3.3.

20.189 fo:hyphenation-keep

See §7.15.1 of [XSL].

The `fo:hyphenation-keep` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The values of the `fo:hyphenation-keep` attribute are `auto` or `page`.

20.190 fo:hyphenation-ladder-count

See §7.15.2 of [XSL].

The defined values for the `fo:hyphenation-ladder-count` attribute are:

- `no-limit`:
- a value of type `positiveInteger`

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `fo:hyphenation-ladder-count` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The values of the `fo:hyphenation-ladder-count` attribute are `no-limit` or a value of type `positiveInteger` 18.2.

20.191 fo:hyphenation-push-char-count

See §7.9.6 of [XSL].

The `fo:hyphenation-push-char-count` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `fo:hyphenation-push-char-count` attribute has the data type `positiveInteger` 18.2.

20.192 fo:hyphenation-remain-char-count

See §7.9.7 of [XSL].

The `fo:hyphenation-remain-char-count` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `fo:hyphenation-remain-char-count` attribute has the data type `positiveInteger` 18.2.

20.193 fo:keep-together

See §7.19.3 of [XSL].

In the OpenDocument XSL compatible namespace, the `fo:keep-together` attribute does not support the `integer` value.

The `fo:keep-together` attribute is usable with the following elements: `<style:paragraph-properties>` 17.6 and `<style:table-row-properties>` 17.17.

The values of the `fo:keep-together` attribute are `auto` or `always`.

20.194 fo:keep-with-next

See §7.9.4 of [XSL].

In the OpenDocument XSL compatible namespace, the `fo:keep-with-next` attribute does not support the `integer` value.

The `fo:keep-with-next` attribute is usable with the following elements: `<style:paragraph-properties>` 17.6 and `<style:table-properties>` 17.15.

The values of the `fo:keep-with-next` attribute are `auto` or `always`.

20.195 fo:language

See §7.9.2 of [XSL]. Compared to the XSL language attribute, the value range of this attribute is extended to additional parts of ISO 639. See 18.3.17.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

This attribute is evaluated for any [UNICODE] character whose script type is `latin`. 20.348

This attribute may be ignored if it is not specified together with a `fo:country` attribute.

In the OpenDocument XSL compatible namespace, the `fo:language` attribute does not support the `inherit` and `none` values.

The `fo:language` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `fo:language` attribute has the data type `languageCode` 18.3.17.

20.196 fo:letter-spacing

See §7.16.2 of [XSL].

In the OpenDocument XSL compatible namespace, the `fo:letter-spacing` attribute does not support the `inherit` and `space` values.

The defined value for the `fo:letter-spacing` attribute is a value of type length 18.3.18.

The `fo:letter-spacing` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `fo:letter-spacing` attribute are a value of type `length` 18.3.18 or `normal`.

20.197 fo:line-height

See §7.15.4 of [XSL].

The value `normal` activates the default line height calculation. The value of this attribute can be a length, a percentage, `normal`.

In the OpenDocument XSL compatible namespace, the `fo:line-height` attribute does not support the `inherit`, `number`, and `space` values.

The defined values for the `fo:line-height` attribute are:

- a value of type `nonNegativeLength` 18.3.20
- `normal`: disables the effects of `style:line-height-at-least` and `style:line-spacing`.
- a value of type `percent` 18.3.23

The `fo:line-height` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The values of the `fo:line-height` attribute are `normal`, a value of type `nonNegativeLength` 18.3.20 or a value of type `percent` 18.3.23.

20.198 fo:margin

See §7.29.14 of [XSL].

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

In the OpenDocument XSL compatible namespace, the fo:margin attribute does not support auto and inherit values.

The fo:margin attribute is usable with the following elements: <style:graphic-properties> 17.21, <style:header-footer-properties> 17.5, <style:page-layout-properties> 17.2, <style:paragraph-properties> 17.6 and <style:table-properties> 17.15.

The values of the fo:margin attribute are a value of type nonNegativeLength 18.3.20 or a value of type percent 18.3.23.

20.199 fo:margin-bottom

See §7.10.2 of [XSL].

If this attribute is contained in a <style:paragraph-properties> element, its value may be a percentage that refers to the corresponding margin of a parent style.

In the OpenDocument XSL compatible namespace, the fo:margin-bottom attribute does not support the auto and inherit values.

The fo:margin-bottom attribute is usable with the following elements: <style:graphic-properties> 17.21, <style:header-footer-properties> 17.5, <style:page-layout-properties> 17.2, <style:paragraph-properties> 17.6 and <style:table-properties> 17.15.

The values of the fo:margin-bottom attribute are a value of type nonNegativeLength 18.3.20 or a value of type percent 18.3.23.

20.200 fo:margin-left

See §7.10.3 of [XSL].

If this attribute is contained in a <style:paragraph-properties> element, its value may be a percentage that refers to the corresponding margin of a parent style.

Tables that align to the left or to the center ignore right margins, and tables that align to the right or to the center ignore left margins.

The fo:margin-left attribute is usable with the following elements: <style:graphic-properties> 17.21, <style:header-footer-properties> 17.5, <style:page-layout-properties> 17.2, <style:paragraph-properties> 17.6, <style:section-properties> 17.11 and <style:table-properties> 17.15.

The values of the fo:margin-left attribute are a value of type length 18.3.18 or a value of type percent 18.3.23.

20.201 fo:margin-right

See §7.10.4 of [XSL].

If this attribute is contained in a <style:paragraph-properties> element, its value may be a percentage that refers to the corresponding margin of a parent style.

Tables that align to the left or to the center ignore right margins, and tables that align to the right or to the center ignore left margins.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `fo:margin-right` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6, `<style:section-properties>` 17.11 and `<style:table-properties>` 17.15.

The values of the `fo:margin-right` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

20.202 fo:margin-top

See §7.10.1 of [XSL].

If this attribute is contained in a `<style:paragraph-properties>` element, its value may be a percentage that refers to the corresponding margin of a parent style.

In the OpenDocument XSL compatible namespace, the `fo:margin-top` attribute does not support the `inherit` value.

The `fo:margin-top` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-properties>` 17.15.

The values of the `fo:margin-top` attribute are a value of type `nonNegativeLength` 18.3.20 or a value of type `percent` 18.3.23.

20.203 fo:max-height

The `fo:max-height` attribute specifies a default maximum height for new frames that are created using a graphics style. See 19.238.

The `fo:max-height` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `fo:max-height` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

20.204 fo:max-width

The `fo:max-width` attribute specifies a default maximum width for new frames that are created using a graphics style. See 19.239.

The `fo:max-width` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `fo:max-width` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.205 fo:min-height

20.205.1 <style:graphic-properties>

The `fo:min-height` attribute specifies a default minimum height for new frames that are created using a graphics style. See 19.240.

The `fo:min-height` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `fo:min-height` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

20.205.2 <style:header-footer-properties>

The `fo:min-height` attribute specifies a minimum height for a header or footer.

The `fo:min-height` attribute is usable with the following element: `<style:header-footer-properties>` 17.5.

The `fo:min-height` attribute has the data type `length` 18.3.18.

20.206 fo:min-width

The `fo:min-width` attribute specifies a default minimum width for new frames that are created using a graphics style. See 19.241.

The `fo:min-width` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `fo:min-width` attribute are a value of type `length` 18.3.18 or a value of type `percent` 18.3.23.

20.207 fo:orphans

See §7.19.6 of [XSL].

The `fo:orphans` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The `fo:orphans` attribute has the data type `nonNegativeInteger` 18.2.

20.208 fo:page-height

See §7.25.13 of [XSL].

The `fo:page-height` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `fo:page-height` attribute has the data type `length` 18.3.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.209 fo:page-width

See §7.25.15 of [XSL].

The `fo:page-width` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `fo:page-width` attribute has the data type `length` 18.3.18.

20.210 fo:padding

See §7.29.15 of [XSL].

The `fo:padding` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-cell-properties>` 17.18.

The `fo:padding` attribute has the data type `nonNegativeLength` 18.3.20.

20.211 fo:padding-bottom

See §7.7.36 of [XSL].

The `fo:padding-bottom` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-cell-properties>` 17.18.

The `fo:padding-bottom` attribute has the data type `nonNegativeLength` 18.3.20.

20.212 fo:padding-left

See §7.7.37 of [XSL].

The `fo:padding-left` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-cell-properties>` 17.18.

The `fo:padding-left` attribute has the data type `nonNegativeLength` 18.3.20.

20.213 fo:padding-right

See §7.7.38 of [XSL].

The `fo:padding-right` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-cell-properties>` 17.18.

The `fo:padding-right` attribute has the data type `nonNegativeLength` 18.3.20.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.214 fo:padding-top

See §7.7.35 of [XSL].

The `fo:padding-top` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-cell-properties>` 17.18.

The `fo:padding-top` attribute has the data type `nonNegativeLength` 18.3.20.

20.215 fo:script

See §7.9.3 of [XSL]. The attribute should be used only if necessary according to the rules of §2.2.3 of [RFC5646], or its successors.

The attribute is evaluated for any [UNICODE] character whose script type is `latin`. 20.348

It may be ignored if is not specified together with a `fo:language` attribute.

In the OpenDocument XSL compatible namespace, the `fo:script` attribute does not support the `inherit` or `none` values.

The `fo:script` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `fo:script` attribute has the data type `scriptCode` 18.3.29.

20.216 fo:text-align

See §7.15.9 of [XSL].

If there are no values specified for the `fo:text-align` and `style:justify-single-word` attributes within the same formatting properties element, the values of those attributes is set to `start` and `false` respectively.

In the OpenDocument XSL compatible namespace, the `fo:text-align` attribute does not support the `inherit`, `inside`, `outside`, or `string` values.

20.216.1 <style:paragraph-properties>

The `fo:text-align` attribute when used with the `<style:paragraph-properties>` element specifies the alignment of paragraphs in a text.

The values of `start` and `end` are interpreted according to the writing direction of the text.

The `fo:text-align` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The values of the `fo:text-align` attribute are `start`, `end`, `left`, `right`, `center` or `justify`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.216.2 <style:list-level-properties>

The `fo:text-align` attribute when used with the `<style:list-level-properties>` elements specifies the alignment of list labels.

If the `text:list-level-position-and-space-mode` attribute on the same `<style:list-level-properties>` element has the value `label-width-and-position`, the `fo:text-align` attribute specifies the horizontal alignment of the list label within the width specified by the `text:min-label-width` attribute. If the the actual width of the list label is greater than the specified minimum width no alignment takes place.

If the `text:list-level-position-and-space-mode` attribute on the same `<style:list-level-properties>` element has the value `label-alignment`, the value of the `text:min-label-width` attribute is treated as 0 and the `fo:text-align` attribute specifies the horizontal alignment of the list label at the alignment position. The alignment position is specified by the `fo:margin-left` and `fo:text-indent` attributes of it child element `<style:list-level-label-alignment>` 17.20.

The defined values for the `fo:text-align` attribute are:

- `center`: center of the list label is positioned at the alignment position.
- `end`: interpreted as `fo:text-align="right"`
- `justify`: label is justified.
- `left`: list label starts at the alignment position.
- `right`: list label ends at the alignment position.
- `start`: interpreted as `fo:text-align="left"`.

The `fo:text-align` attribute is usable with the following element: `<style:list-level-properties>` 17.19.

The values of the `fo:text-align` attribute are `start`, `end`, `left`, `right`, `center` or `justify`.

20.217 fo:text-align-last

See §7.15.10 of [XSL].

This attribute is ignored if it not accompanied by an `fo:text-align` attribute.

If no value is specified for this attribute, the value is set to start.

The `fo:text-align-last` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The values of the `fo:text-align-last` attribute are `start`, `center` or `justify`.

20.218 fo:text-indent

The `fo:text-indent` attribute specifies a positive or negative indent for the first line of a paragraph. See §7.15.11 of [XSL]. The attribute value is a length. If the attribute is contained in a common style, the attribute value may be also a percentage that refers to the corresponding text indent of a parent style.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The fo:text-indent attribute is usable with the following element: <style:paragraph-properties> 17.6.

The values of the fo:text-indent attribute are a value of type length 18.3.18 or a value of type percent 18.3.23.

20.219 fo:text-shadow

The fo:text-shadow attribute specifies the text shadow style to use.

The defined values for this attribute are those defined in §7.16.5 of [XSL], except the value inherit.

The fo:text-shadow attribute is usable with the following element: <style:text-properties> 16.27.28.

The values of the fo:text-shadow attribute are none or a value of type string 18.2.

20.220 fo:text-transform

See §7.16.6 of [XSL].

If fo:text-transform and fo:font-variant attributes are used simultaneously and have different values than normal and none, the result is undefined.

Note: In consumers, the fo:text-transform and fo:font-variant attributes are mutually exclusive.

The fo:text-transform attribute is usable with the following element: <style:text-properties> 16.27.28.

The values of the fo:text-transform attribute are none, lowercase, uppercase or capitalize.

20.221 fo:widows

See §7.19.7 of [XSL].

The fo:widows attribute specifies the minimum number of lines that shall be displayed at the top of a page to avoid paragraph widows.

In the OpenDocument XSL compatible namespace, the fo:widows attribute does not support the inherit value.

The fo:widows attribute is usable with the following element: <style:paragraph-properties> 17.6.

The fo:widows attribute has the data type nonNegativeInteger 18.2.

20.222 fo:width

See §7.14.12 of [XSL].

The fo:width attribute is used with fo:height to set the size of a bullet image.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

In the OpenDocument XSL compatible namespace, the `fo:width` attribute does not support the `auto` or `inherit` values.

The `fo:width` attribute is usable with the following element: `<style:list-level-properties>` 17.19.

The `fo:width` attribute has the data type `positiveLength` 18.3.26.

20.223 fo:wrap-option

See §7.15.13 of [XSL].

If wrapping is disabled, it is implementation-defined whether the overflow text is visible or hidden. If the text is hidden consumers may support a scrolling to access the text.

The `fo:wrap-option` attribute is usable with the following elements: `<style:graphic-properties>` 17.21 and `<style:table-cell-properties>` 17.18.

The values of the `fo:wrap-option` attribute are `no-wrap` or `wrap`.

20.224 presentation:background-objects-visible

The `presentation:background-objects-visible` attribute specifies whether to display objects in the background of a master page when displaying a presentation page.

The defined values for the `presentation:background-objects-visible` attribute are:

- `false`: objects in background of a master page should not be displayed when displaying a presentation page.
- `true`: objects in background of a master page should be displayed when displaying a presentation page.

The `presentation:background-objects-visible` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The `presentation:background-objects-visible` attribute has the data type `boolean` 18.3.3.

20.225 presentation:background-visible

The `presentation:background-visible` attribute specifies whether to display the background of a master page when displaying a presentation page.

The defined values for the `presentation:background-visible` attribute are:

- `false`: background of a master page should not be displayed when displaying a presentation page.
- `true`: background of a master page should be displayed when displaying a presentation page.

The `presentation:background-visible` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The `presentation:background-visible` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.226 presentation:display-date-time

The `presentation:display-date-time` attribute specifies the visibility of from the `<style:master-page>` element with the presentation class `date-time`.

The defined values for the `presentation:display-date-time` attribute are:

- `false`: drawing shape from a `<style:master-page>` element with the presentation class `date-time` should not be visible.
- `true`: drawing shape from a `<style:master-page>` element with the presentation class `date-time` should be visible.

The `presentation:display-date-time` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The `presentation:display-date-time` attribute has the data type `boolean` 18.3.3.

20.227 presentation:display-footer

The `presentation:display-footer` attribute specifies the visibility of a drawing shape used as a footer in a `<style:master-page>` element.

The defined values for the `presentation:display-footer` attribute are:

- `false`: drawing shape used as a footer of a `<style:master-page>` element should not be visible.
- `true`: drawing shape used as a footer of a `<style:master-page>` element should be visible.

The `presentation:display-footer` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The `presentation:display-footer` attribute has the data type `boolean` 18.3.3.

20.228 presentation:display-header

The `presentation:display-header` attribute specifies the visibility of a drawing shape used as a header in a `<style:master-page>` element.

The defined values for the `presentation:display-header` attribute are:

- `false`: drawing shape used as a header of a `<style:master-page>` element should not be visible.
- `true`: drawing shape used as a header of a `<style:master-page>` element should be visible.

The `presentation:display-header` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The `presentation:display-header` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.229 presentation:display-page-number

The `presentation:display-page-number` attribute specifies the visibility of a drawing shape used as a page number in a `<style:master-page>` element.

The defined values for the `presentation:display-page-number` attribute are:

- `false`: drawing shape used as a page number of a `<style:master-page>` element should not be visible.
- `true`: drawing shape used as a page number of a `<style:master-page>` element should be visible.

The `presentation:display-page-number` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The `presentation:display-page-number` attribute has the data type `boolean` 18.3.3.

20.230 presentation:duration

The `presentation:duration` attribute specifies the amount of time that the presentation page is displayed.

The `presentation:duration` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The `presentation:duration` attribute has the data type `duration` 18.2.

20.231 presentation:transition-speed

The `presentation:transition-speed` attribute specifies the speed at which a presentation page is removed from display, and replaced by a new presentation page.

The defined values for the `presentation:transition-speed` attribute are:

- `fast`: An implementation-defined speed. The `fast` speed should be faster than the speed the consumer chooses for the values `medium` and `slow`.
- `medium`:An implementation-defined speed. The `medium` speed should be faster than the speed the consumer chooses for the value `slow`, and slower than the speed the consumer chooses for the value `fast`.
- `slow`: An implementation-defined speed. The `slow` speed should be slower than the speed the consumer chooses for the values `medium` and `fast`.

The `presentation:transition-speed` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The values of the `presentation:transition-speed` attribute are `slow`, `medium` or `fast`.

20.232 presentation:transition-style

The `presentation:transition-style` attribute specifies the way that each presentation page replaces the previous presentation page.

The defined values for the `presentation:transition-style` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `clockwise`: page is uncovered by the hand of a watch, moving clockwise.
- `close`: Combination of close-horizontal and close-vertical.
- `close-horizontal`: page is uncovered by drawing it line by line horizontally starting at the edge of the page.
- `close-vertical`: page is uncovered by drawing it line by line vertically starting at the edge of the page.
- `counterclockwise`: page is uncovered by the hand of a watch, moving counterclockwise.
- `dissolve`: page is faded in by drawing small blocks in a random fashion.
- `fade-from-bottom`: page fades from a visible or hidden state to a hidden or visible state to the bottom of the screen.
- `fade-from-left`: page fades from a visible or hidden state to a hidden or visible state to the left of the screen.
- `fade-from-right`: pages fade from a visible or hidden state to a hidden or visible state to the right of the screen.
- `fade-from-top`: page fades from a visible or hidden state to a hidden or visible state to the top of the screen.
- `fade-from-lowerleft`: page fades from a visible or hidden state to a hidden or visible state to the lower left of the screen.
- `fade-from-lowerright`: page fades from a visible or hidden state to a hidden or visible state to the lower right of the screen.
- `fade-from-upperleft`: page fades from a visible or hidden state to a hidden or visible state to the upper left of the screen.
- `fade-from-upperright`: page fades from a visible or hidden state to a hidden or visible state to the upper right of the screen.
- `fade-from-center`: page fades from a visible or hidden state to a hidden or visible state from the center of the screen.
- `fade-to-center`: page fades from a visible or hidden state to a hidden or visible state to the center of the screen.
- `fly-away`: page first reduces itself to a smaller size (while remaining centered in the screen), and then "flies away" (turns around and moves to the bottom-right corner of the screen). The next slide appears under it meanwhile.
- `horizontal-checkerboard`: page is uncovered by drawing checkerboard like blocks that increase in size horizontally.
- `horizontal-lines`: page is uncovered by drawing it line by line horizontally in a random fashion.
- `horizontal-stripes`: page is uncovered by drawing horizontal stripes that change their size during this effect.
- `interlocking-horizontal-left`: page appears in 4 horizontal stripes (the height is divided in 4, like in the horizontal-stripes effect) but those stripes come from left, right, left, and right, and cross each other in the middle of the screen.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `interlocking-horizontal-right`: page appears in 4 horizontal stripes (the height is divided in 4, like in the horizontal-stripes effect) but those stripes come from right, left, right, and left, and cross each other in the middle of the screen.
- `interlocking-vertical-bottom`: same effect as `interlocking-horizontal-*` but with vertical stripes crossing each other.
- `interlocking-vertical-top`: same effect as `interlocking-horizontal-*` but with vertical stripes crossing each other.
- `melt`: Small vertical stripes move down at random speed, which gives the effect of the current page "melting down".
- `move-from-bottom`: page moves from the bottom of the screen to its final position.
- `move-from-left`: page moves from the left of the screen to its final position.
- `move-from-right`: page moves from the right of the screen to its final position.
- `move-from-top`: page moves from the top of the screen to its final position.
- `move-from-lowerleft`: page from towards the lower left of the screen to its final position.
- `move-from-lowerright`: page from towards the lower right of the screen to its final position.
- `move-from-upperleft`: page from towards the upper left of the screen to its final position.
- `move-from-upperright`: page from towards the upper right of the screen to its final position.
- `none`: no effect is used.
- `open`: Combination of open-horizontal and open-vertical.
- `open-horizontal`: page is uncovered by drawing it line by line horizontally, starting at the center of the page.
- `open-vertical`: page is uncovered by drawing it line by line vertically, starting at the center of the page.
- `random`: an effect is chosen at random to uncover a page.
- `roll-from-bottom`: page moves towards the bottom of the screen to its final position, pushing the previous page out.
- `roll-from-left`: pages move towards the left of the screen to its final position, pushing the previous page out.
- `roll-from-right`: page moves towards the right of the screen to its final position, pushing the previous page out.
- `roll-from-top`: page moves towards the top of the screen to its final position, pushing the previous page out.
- `spiralin-left`: page is uncovered by drawing blocks in a spiral fashion, starting from the left edge of the screen.
- `spiralin-right`: page is uncovered by drawing blocks in a spiral fashion, starting from the right edge of the screen.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `spiralout-left`: page is uncovered by drawing blocks in a spiral fashion, starting from the center of the page.
- `spiralout-right`: page is uncovered by drawing blocks in a spiral fashion, starting from the center of the page.
- `stretch-from-bottom`: page is uncovered by changing its size from the bottom of the screen during this effect.
- `stretch-from-left`: page is uncovered by changing its size from the left of the screen during this effect.
- `stretch-from-right`: page is uncovered by changing its size from the right of the screen during this effect.
- `stretch-from-top`: page is uncovered by changing its size from the left of the screen during this effect.
- `uncover-to-bottom`: page is uncovered from the bottom of the screen.
- `uncover-to-left`: page is uncovered from the left of the screen.
- `uncover-to-right`: page is uncovered from the right of the screen.
- `uncover-to-top`: page is uncovered from the top of the screen.
- `uncover-to-lowerleft`: page is uncovered from the lower left of the screen.
- `uncover-to-lowerright`: page is uncovered from the lower right of the screen.
- `uncover-to-upperleft`: page is uncovered from the upper left of the screen.
- `uncover-to-upperright`: page is uncovered from the upper right of the screen.
- `vertical-checkerboard`: page is uncovered by drawing checkerboard like blocks that increase in size vertically.
- `vertical-lines`: page is uncovered by drawing it line by line vertically in a random fashion.
- `vertical-stripes`: page is uncovered by drawing vertical stripes that change their size during this effect.
- `wavyline-from-bottom`: page is uncovered by drawing small blocks in a snake like fashion from the bottom of the screen.
- `wavyline-from-left`: page is uncovered by drawing small blocks in a snake like fashion from the left of the screen.
- `wavyline-from-right`: page is uncovered by drawing small blocks in a snake like fashion from the right of the screen.
- `wavyline-from-top`: page is uncovered by drawing small blocks in a snake like fashion from the top of the screen.

The `presentation:transition-style` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The values of the `presentation:transition-style` attribute are `none`, `fade-from-left`, `fade-from-top`, `fade-from-right`, `fade-from-bottom`, `fade-from-upperleft`, `fade-from-upperright`, `fade-from-lowerleft`, `fade-from-lowerright`, `move-`

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

from-left, move-from-top, move-from-right, move-from-bottom, move-from-upperleft, move-from-upperright, move-from-lowerleft, move-from-lowerright, uncover-to-left, uncover-to-top, uncover-to-right, uncover-to-bottom, uncover-to-upperleft, uncover-to-upperright, uncover-to-lowerleft, uncover-to-lowerright, fade-to-center, fade-from-center, vertical-stripes, horizontal-stripes, clockwise, counterclockwise, open-vertical, open-horizontal, close-vertical, close-horizontal, wavyline-from-left, wavyline-from-top, wavyline-from-right, wavyline-from-bottom, spiralin-left, spiralin-right, spiralout-left, spiralout-right, roll-from-top, roll-from-left, roll-from-right, roll-from-bottom, stretch-from-left, stretch-from-top, stretch-from-right, stretch-from-bottom, vertical-lines, horizontal-lines, dissolve, random, vertical-checkerboard, horizontal-checkerboard, interlocking-horizontal-left, interlocking-horizontal-right, interlocking-vertical-top, interlocking-vertical-bottom, fly-away, open, close or melt.

20.233 presentation:transition-type

The presentation:transition-type attribute specifies the mode of a transition.

The defined values for the presentation:transition-type attribute are:

- automatic: slide transition and shape effects start automatically.
- manual: slide transition and shape effects are started separately by the user.
- semi-automatic: slide transition starts automatically, shape effects are started by the user.

The smil:type attribute should be used for presentations. The presentation:transition-type and presentation:transition-style attributes are retained for legacy compatibility only.

The presentation:transition-type attribute is usable with the following element: <style:drawing-page-properties> 17.25.

The values of the presentation:transition-type attribute are manual, automatic or semi-automatic.

20.234 presentation:visibility

The presentation:visibility attribute specifies if the content of a <draw:page> element is visible during a presentation.

The defined values for the presentation:transition-speed attribute are:

- hidden: content is hidden during a presentation.
- visible: content is visible during a presentation.

The presentation:visibility attribute is usable with the following element: <style:drawing-page-properties> 17.25.

The values of the presentation:visibility attribute are visible or hidden.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.235 smil:direction

See §12.4.1 of [SMIL20].

The `smil:direction` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The values of the `smil:direction` attribute are `forward` or `reverse`.

20.236 smil:fadeColor

See §12.4.1 of [SMIL20].

The `smil:fadeColor` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The `smil:fadeColor` attribute has the data type `color` 18.3.9.

20.237 smil:subtype

See §12.4.1 of [SMIL20].

Note: See §12.8 of [SMIL20] for a list of supported subtypes.

The `smil:subtype` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The `smil:subtype` attribute has the data type `string` 18.2.

20.238 smil:type

The [SMIL20] `smil:type` attribute specifies a transition type or family.

See §12.8 of [SMIL20] for a list of supported types.

If this attribute is present, the attributes `presentation:transition-type` and `presentation:transition-style` attributes should be ignored.

The `smil:type` attribute is usable with the following element: `<style:drawing-page-properties>` 17.25.

The `smil:type` attribute has the data type `string` 18.2.

20.239 style:auto-text-indent

The `style:auto-text-indent` attribute specifies that the first line of a paragraph is indented by a value that is based on the current font size.

If this attribute has a value of `true` and is used together with a `fo:text-indent` attribute the `fo:text-indent` attribute is ignored.

The `style:auto-text-indent` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The `style:auto-text-indent` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.240 style:background-transparency

The `style:background-transparency` attribute specifies the transparency of a paragraph's background color.

The `style:background-transparency` attribute is usable with the following elements: `<style:graphic-properties>` 17.21 and `<style:paragraph-properties>` 17.6.

The `style:background-transparency` attribute has the data type `zeroToHundredPercent` 18.3.41.

20.241 style:border-line-width

The `style:border-line-width` attribute specifies the widths of borders defined by the FO border properties (see 20.176) for borders where the value of these properties is `double`.

The value of the `style:border-line-width` attribute is a list of three white space-separated lengths, as follows:

- The first value specifies the width of the inner line
- The second value specified the distance between the two lines
- The third value specifies the width of the outer line

The `style:border-line-width` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-cell-properties>` 17.18.

The values of the `style:border-line-width` attribute are three white space separated values of type `positiveLength` 18.3.26.

20.242 style:border-line-width-bottom

The `style:border-line-width-bottom` attribute specifies the widths of the bottom border for borders defined by the FO border properties (see 20.176) if the property for the bottom border has the value `double`.

The value of the `style:border-line-width-bottom` attribute is a list of three white space-separated lengths, as follows:

- The first value specifies the width of the inner line
- The second value specified the distance between the two lines
- The third value specifies the width of the outer line

The `style:border-line-width-bottom` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-cell-properties>` 17.18.

The values of the `style:border-line-width-bottom` attribute are three white space separated values of type `positiveLength` 18.3.26.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.243 style:border-line-width-left

The `style:border-line-width-left` attribute specifies the widths of the left border for borders defined by the FO border properties (see 20.176) if the property for the left border has the value `double`.

The value of the `style:border-line-width-left` attribute is a list of three white space-separated lengths, as follows:

- The first value specifies the width of the inner line
- The second value specified the distance between the two lines
- The third value specifies the width of the outer line

The `style:border-line-width-left` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-cell-properties>` 17.18.

The values of the `style:border-line-width-left` attribute are three white space separated values of type `positiveLength` 18.3.26.

20.244 style:border-line-width-right

The `style:border-line-width-right` attribute specifies the widths of the right border for borders defined by the FO border properties (see 20.176) if the property for the right border has the value `double`.

The value of the `style:border-line-width-right` attribute is a list of three white space-separated lengths, as follows:

- The first value specifies the width of the inner line
- The second value specified the distance between the two lines
- The third value specifies the width of the outer line

The `style:border-line-width-right` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-cell-properties>` 17.18.

The values of the `style:border-line-width-right` attribute are three white space separated values of type `positiveLength` 18.3.26.

20.245 style:border-line-width-top

The `style:border-line-width-top` attribute specifies the widths of the top border for borders defined by the FO border properties (see 20.176) if the property for the top border has the value `double`.

The value of the `style:border-line-width-top` attribute is a list of three white space-separated lengths, as follows:

- The first value specifies the width of the inner line

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- The second value specified the distance between the two lines
- The third value specifies the width of the outer line

The `style:border-line-width-top` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6 and `<style:table-cell-properties>` 17.18.

The values of the `style:border-line-width-top` attribute are three white space separated values of type `positiveLength` 18.3.26.

20.246 style:cell-protect

The `style:cell-protect` attribute specifies how a cell is protected.

This attribute is only evaluated if the current table is protected.

The defined values for the `style:cell-protect` attribute are:

- `formula-hidden`: if cell content is a formula, it is not displayed. It can be replaced by changing the cell content.

Note: Replacement of cell content includes replacement with another formula or other cell content.

- `hidden-and-protected`: cell content is not displayed and cannot be edited. If content is a formula, the formula result is not displayed.
- `none`: formula responsible for cell content is neither hidden nor protected.
- `protected`: cell content can not be edited.
- protected formula-hidden: cell content can not be edited. If content is a formula, it is not displayed. A formula result is displayed.

The `style:cell-protect` attribute is usable with the following element: `<style:table-cell-properties>` 17.18.

The values of the `style:cell-protect` attribute are `none`, `hidden-and-protected`, or white space separated non-empty lists of one of these values: `protected`, or `formula-hidden`..

20.247 style:column-width

The `style:column-width` attribute specifies a fixed width for a column.

The `style:column-width` attribute is usable with the following element: `<style:table-column-properties>` 17.16.

The `style:column-width` attribute has the data type `positiveLength` 18.3.26.

20.248 style:country-asian

The `style:country-asian` attribute specifies the country of a text.

It is evaluated for [UNICODE] characters whose script type is `asian`. 20.348

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

It may be ignored if it is not specified together with a `style:language-asian` attribute.

The `style:country-asian` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:country-asian` attribute has the data type `countryCode` 18.3.11.

20.249 style:country-complex

The `style:country-complex` attribute specifies the country of a text. See §7.9.1 of [XSL].

It is evaluated for [UNICODE] characters whose script type is `complex`. 20.348

It may be ignored if it is not specified together with a `style:language-complex` attribute.

The `style:country-complex` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:country-complex` attribute has the data type `countryCode` 18.3.11.

20.250 style:decimal-places

The `style:decimal-places` attribute specifies the maximum number of decimal places that are displayed if numbers are formatted by a data style that has no setting for number of decimal places itself.

This attribute is only evaluated if it is contained in a default style.

The `style:decimal-places` attribute is usable with the following element: `<style:table-cell-properties>` 17.18.

The `style:decimal-places` attribute has the data type `nonNegativeInteger` 18.2.

20.251 style:diagonal-bl-tr

The `style:diagonal-bl-tr` attribute specifies the style of border to use for a bottom-left to top-right diagonal in a spreadsheet cell.

The `style:diagonal-bl-tr` attribute is usable with the following element: `<style:table-cell-properties>` 17.18.

The `style:diagonal-bl-tr` attribute has the data type `string` 18.2.

20.252 style:diagonal-bl-tr-widths

The `style:diagonal-bl-tr-widths` attribute specifies the width between a double line border to use for a bottom-left to top-right diagonal in a spreadsheet cell.

The `style:diagonal-bl-tr-widths` attribute is usable with the following element: `<style:table-cell-properties>` 17.18.

The values of the `style:diagonal-bl-tr-widths` attribute are three white space separated values of type `positiveLength` 18.3.26.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.253 style:diagonal-tl-br

The `style:diagonal-tl-br` attribute specifies the style of border to use for a left-top to bottom-right diagonal in a spreadsheet cell.

The `style:diagonal-tl-br` attribute is usable with the following element: `<style:table-cell-properties>` 17.18.

The `style:diagonal-tl-br` attribute has the data type `string` 18.2.

20.254 style:diagonal-tl-br-widths

The `style:diagonal-tl-br-widths` attribute specifies the width between a double line border to use for a top-left to bottom-right diagonal in a spreadsheet cell.

The `style:diagonal-tl-br-widths` attribute is usable with the following element: `<style:table-cell-properties>` 17.18.

The values of the `style:diagonal-tl-br-widths` attribute are three white space separated values of type `positiveLength` 18.3.26.

20.255 style:direction

The `style:direction` attribute specifies the direction of characters.

The `style:direction` attribute modifies the direction of text rendering as specified by a `style:writing-mode` attribute. 20.394

The defined values for the `style:direction` attribute are:

- `ltr` – left to right, text is rendered in the direction specified by the `style:writing-mode` attribute
- `ttb` – top to bottom, characters are vertically stacked but not rotated

The `style:direction` attribute is usable with the following elements: `<style:chart-properties>` 17.22 and `<style:table-cell-properties>` 17.18.

The values of the `style:direction` attribute are `ltr` or `ttb`.

20.256 style:dynamic-spacing

The `style:dynamic-spacing` attribute specifies whether the header or footer grows into the space between the page body and the header or footer before the height of the page body becomes smaller.

The defined values for the `style:dynamic-spacing` attribute are:

- `false`: header or footers do not grow into the space between the header and footer and the page body.
- `true`: header or footers first grow into the space between the header and footer and the page body.

The `style:dynamic-spacing` attribute is usable with the following element: `<style:header-footer-properties>` 17.5.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `style:dynamic-spacing` attribute has the data type `boolean` 18.3.3.

20.257 style:editable

The `style:editable` attribute specifies if a text section or box can be edited within a read-only document.

The defined values for the `style:editable` attribute are:

- `false`: text section or box in read-only document should not be editable.
- `true`: text section or box in read-only document should be editable.

The `style:editable` attribute is usable with the following elements: `<style:graphic-properties>` 17.21 and `<style:section-properties>` 17.11.

The `style:editable` attribute has the data type `boolean` 18.3.3.

20.258 style:first-page-number

The `style:first-page-number` attribute specifies the number of a document.

The value of this attribute can be an integer or `continue`. If the value is `continue`, the page number is the preceding page number incremented by 1. The default first page number is 1.

The `style:first-page-number` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The values of the `style:first-page-number` attribute are a value of type `positiveInteger` 18.2 or `continue`.

20.259 style:flow-with-text

The `style:flow-with-text` attribute specifies whether a drawing shape flows with the text of its layout environment or not. The layout environment of a drawing shape is determined by the location of its anchor. The following layout environments are defined:

- endnote area - anchor is inside a endnote.
- footnote area - anchor is inside a footnote.
- frame area - anchor is inside a frame or is a frame.
- page footer area - anchor is inside the page footer.
- page header area - anchor is inside the page header.
- page text area - anchor is inside body text.
- table cell area - anchor is inside a table cell.

The innermost enclosing area of the anchor defines the layout environment of the drawing shape.

If the value of the attribute is `true`, the following conditions shall hold:

- The drawing shape flows with the text of its layout environment.
- The drawing shape does not leave its layout environment in the either text flow direction.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

When a drawing shape leaves its layout environment due to its position and/or size in the forward text flow direction, it flows with the text flow to the next layout environment. If there is no next layout environment, the position of the layout environment is adjusted. If the drawing shape is larger than its layout environment, the size of the layout environment is adjusted.

If due to its position a drawing shape would leave its layout environment in the backward text flow direction, the position is adjusted to the beginning of its layout environment.

A drawing object may leave its layout environment in the other (non text flow) directions. Exceptions from this rule are the layout environments table cell area and frame area. For these layout environments it shall be ensured that the drawing shape is laid out inside its layout environment by adjusting the position and (if necessary) the size.

If the value of the attribute is `false`, the drawing shape does not have to flow with the text of its layout environment. It can be laid out anywhere on the page its anchor is on.

This attribute is not applicable to drawing shapes that are anchored with `text:anchor-type="as-char"`, because such drawing shapes are treated as characters. For drawing shapes, which are anchored to a specific page with `text:anchor-type="page"`, the attribute is also not applicable, because such drawing shapes are to be laid out on the page they are anchored to.

The `style:flow-with-text` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `style:flow-with-text` attribute has the data type `boolean` 18.3.3.

20.260 style:font-charset

The `style:font-charset` attribute specifies whether a font defines glyphs according to the semantics of [UNICODE] or not.

The value of this attributes can be `x-symbol` or a character encoding in the notation described in the §4.3.3 of [XML1.0]. If the value is `x-symbol`, the font does not defines glyphs according to the semantics of [UNICODE]. If the value is one of the encodings or transformations of [UNICODE], the font does define glyphs according to the semantics of [UNICODE]. The use of other values is deprecated.

Note: Fonts for which the attribute has the value `x-symbol` may define glyphs for code points in the private use area of [UNICODE]

This attribute is evaluated for any [UNICODE] character whose script type is `latin`. 20.348

This attribute is ignored if there is no `fo:font-family` attribute attached to the same formatting property element.

Instead of this attribute, the `style:font-name` attribute should be used to specify the properties of a font.

The `style:font-charset` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:font-charset` attribute has the data type `textEncoding` 18.3.35.

20.261 style:font-charset-asian

The `style:font-charset-asian` attribute specifies whether a font defines glyphs according to the semantics of [UNICODE] or not.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The value of this attributes can be `x-symbol` or a character encoding in the notation described in the §4.3.3 of [XML1.0]. If the value is `x-symbol`, the font does not defines glyphs according to the semantics of [UNICODE]. If the value is one of the encodings or transformations of [UNICODE], the font does define glyphs according to the semantics of [UNICODE]. The use of other values is deprecated.

Note: Fonts for which the attribute has the value `x-symbol` may define glyphs for code points in the private use area of [UNICODE]

This attribute is evaluated for [UNICODE] characters whose script type is `asian`. 20.34820.348

This attribute is ignored if there is no `style:font-family-asian` attribute attached to the same formatting property element.

Instead of this attribute, the `style:font-name-asian` attribute should be used to specify the properties of a font.

The `style:font-charset-asian` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:font-charset-asian` attribute has the data type `textEncoding` 18.3.35.

20.262 style:font-charset-complex

The `style:font-charset-complex` attribute specifies whether a font defines glyphs according to the semantics of [UNICODE] or not.

The value of this attributes can be `x-symbol` or a character encoding in the notation described in the §4.3.3 of [XML1.0]. If the value is `x-symbol`, the font does not defines glyphs according to the semantics of [UNICODE]. If the value is one of the encodings or transformations of [UNICODE], the font does define glyphs according to the semantics of [UNICODE]. The use of other values is deprecated.

Note: Fonts for which the attribute has the value `x-symbol` may define glyphs for code points in the private use area of [UNICODE]

The `style:font-charset-complex` attribute is evaluated for [UNICODE] characters whose script type is `complex`. 20.348

This attribute is ignored if there is no `style:font-family-complex` attribute attached to the same formatting properties element.

Instead of this attribute, the `style:font-name-complex` attribute should be used to specify the properties of a font.

The `style:font-charset-complex` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:font-charset-complex` attribute has the data type `textEncoding` 18.3.35.

20.263 style:font-family-asian

The `style:font-family-asian` attribute specifies the font family for a text. See §7.8.2 of [XSL].

This is evaluated for [UNICODE] characters whose script type is `asian`. 20.277

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Instead of this attribute, the `style:font-name-asian` attribute should be used to specify the properties of a font.

The `style:font-family-asian` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:font-family-asian` attribute has the data type `string` 18.2.

20.264 style:font-family-complex

The `style:font-family-complex` attribute specifies the font family for a text. See §7.8.2 of [XSL].

This attribute is evaluated for [UNICODE] characters whose script type is `complex`. 20.348

Instead of this attribute, the `style:font-name-complex` attribute should be used to specify the properties of a font.

The `style:font-family-complex` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:font-family-complex` attribute has the data type `string` 18.2.

20.265 style:font-family-generic

The `style:font-family-generic` attribute specifies a generic font family name.

This attribute is evaluated for any [UNICODE] character whose script type is `latin`. 20.348

This attribute is ignored if there is no corresponding `fo:font-family` attribute attached to the same formatting property element.

Instead of this attribute, the `style:font-name` attribute should be used to specify the properties of a font.

The defined values for the `style:font-family-generic` attribute are:

- `decorative`: the family of decorative fonts.
- `modern`: the family of modern fonts.
- `roman`: the family roman fonts (with serifs).
- `script`: the family of script fonts.
- `swiss`: the family roman fonts (without serifs).
- `system`: the family system fonts.

The `style:font-family-generic` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:font-family-generic` attribute are `roman`, `swiss`, `modern`, `decorative`, `script` or `system`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.266 style:font-family-generic-asian

The `style:font-family-generic-asian` attribute specifies a generic Asian font family name.

The `style:font-family-generic-asian` attribute is evaluated for [UNICODE] characters whose script type is `asian`. 20.277

This attribute is ignored if there is no corresponding `fo:font-family` attribute attached to the same formatting property element.

Instead of this attribute, the `style:font-name-asian` attribute should be used to specify the properties of a font.

The defined values for the `style:font-family-generic-asian` attribute are:

- `decorative`: the family of decorative fonts.
- `modern`: the family of modern fonts.
- `roman`: the family roman fonts (with serifs).
- `script`: the family of script fonts.
- `swiss`: the family roman fonts (without serifs).
- `system`: the family system fonts.

The `style:font-family-generic-asian` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:font-family-generic-asian` attribute are `roman`, `swiss`, `modern`, `decorative`, `script` or `system`.

20.267 style:font-family-generic-complex

The `style:font-family-generic-complex` attribute specifies a generic font family name.

This attribute is ignored if there is no corresponding `fo:font-family` attribute attached to the same formatting property element.

Instead of this attribute, the `style:font-name-complex` attribute should be used to specify the properties of a font.

The defined values for the `style:font-family-generic-complex` attribute are:

- `decorative`: the family of decorative fonts.
- `modern`: the family of modern fonts.
- `roman`: the family roman fonts (with serifs).
- `script`: the family of script fonts.
- `swiss`: the family roman fonts (without serifs).
- `system`: the family system fonts.

The `style:font-family-generic-complex` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The values of the style:font-family-generic-complex attribute are roman, swiss, modern, decorative, script or system.

20.268 style:font-independent-line-spacing

The style:font-independent-line-spacing attribute specifies if font independent line spacing is used.

The defined values for the style:font-independent-line-spacing attribute are:

- false: font metric of the font is taken into account.
- true: line height is calculated only from the font height as specified by the font size attributes fo:font-size, style:font-size-asian and style:font-size-complex.

The style:font-independent-line-spacing attribute is usable with the following element: <style:paragraph-properties> 17.6.

The style:font-independent-line-spacing attribute has the data type boolean 18.3.3.

20.269 style:font-name

The style:font-name attribute specifies a font that is declared by a <style:font-face> element with a style:name attribute whose name is the same as that of the style:font-name attribute value.

This attribute is evaluated for any [UNICODE] character whose script type is latin. 20.348

The style:font-name attribute is usable with the following elements: <style:list-level-properties> 17.19 and <style:text-properties> 16.27.28.

The style:font-name attribute has the data type string 18.2.

20.270 style:font-name-asian

The style:font-name-asian attribute specifies a font that is declared by a <style:font-face> element with a style:name attribute whose name is the same as that of the style:font-name-asian attribute value.

This attribute is evaluated for [UNICODE] characters whose script type is asian. 20.277

The style:font-name-asian attribute is usable with the following element: <style:text-properties> 16.27.28.

The style:font-name-asian attribute has the data type string 18.2.

20.271 style:font-name-complex

The style:font-name-complex attribute specifies a font that is declared by a <style:font-face> element with a style:name attribute whose name is the same as that of the style:font-name-complex attribute value.

The style:font-name-complex attribute is evaluated for [UNICODE] characters whose script type is complex. 20.348

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The style:font-name-complex attribute is usable with the following element: <style:text-properties> 16.27.28.

The style:font-name-complex attribute has the data type string 18.2.

20.272 style:font-pitch

The style:font-pitch attribute specifies whether a font has a fixed or variable width.

This attribute is evaluated for any [UNICODE] character whose script type is latin. 20.348

This attribute is ignored if there is no corresponding fo:font-family attribute attached to the same formatting property element.

Instead of this attribute, the style:font-name attribute should be used to specify the properties of a font.

The defined values for the style:font-pitch attribute are:

- fixed: font pitch is fixed.
- variable: font pitch is variable.

The style:font-pitch attribute is usable with the following element: <style:text-properties> 16.27.28.

The values of the style:font-pitch attribute are fixed or variable.

20.273 style:font-pitch-asian

The style:font-pitch-asian attribute specifies whether a font has a fixed or variable width.

This attribute is evaluated for [UNICODE] characters whose script type is asian. 20.348

This attribute is ignored if there is no corresponding fo:font-family attribute attached to the same formatting property element.

Instead of this attribute, the style:font-name-asian attribute should be used to specify the properties of a font.

The defined values for the style:font-pitch-asian attribute are:

- fixed: font width is fixed.
- variable: font width is variable.

The style:font-pitch-asian attribute is usable with the following element: <style:text-properties> 16.27.28.

The values of the style:font-pitch-asian attribute are fixed or variable.

20.274 style:font-pitch-complex

The style:font-pitch-complex attribute specifies whether a font has a fixed or variable width.

This attribute is evaluated for [UNICODE] characters whose script type is complex. 20.348

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

This attribute is ignored if there is no corresponding `fo:font-family` attribute attached to the same formatting property element.

Instead of this attribute, the `style:font-name-complex` attribute should be used to specify the properties of a font.

The defined values for the `style:font-pitch-complex` attribute are:

- `fixed`: font width is fixed.
- `variable`: font width is variable.

The `style:font-pitch-complex` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:font-pitch-complex` attribute are `fixed` or `variable`.

20.275 style:font-relief

The `style:font-relief` attribute specifies whether a font should be embossed, engraved, or neither.

The defined values for the `style:font-relief` attribute are:

- `embossed`: characters are embossed.
- `engraved`: characters are engraved.
- `none`: characters are neither embossed or engraved.

The `style:font-relief` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:font-relief` attribute are `none`, `embossed` or `engraved`.

20.276 style:font-size-asian

The `style:font-size-asian` attribute specifies the size of a font.

This attribute is evaluated for [UNICODE] characters whose script type is `asian`. 20.348

The value of this attribute is either an absolute length or a percentage as described in §7.8.4 of [XSL]. In contrast to XSL, percentage values can be used within common styles only and are based on the font height of the parent style rather than to the font height of the attributes neighborhood. Absolute font heights and relative font heights are not supported.

The `style:font-size-asian` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:font-size-asian` attribute are a value of type `positiveLength` 18.3.26 or a value of type `percent` 18.3.23.

20.277 style:font-size-complex

The `fo:font-size`, `style:font-size-asian` and `style:font-size-complex` attributes specify the size of a font.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

This attribute is evaluated for [UNICODE] characters whose script type is `complex`. 20.348

The value of this attribute is either an absolute length or a percentage as described in §7.8.4 of [XSL]. In contrast to XSL, percentage values can be used within common styles only and are based on the font height of the parent style rather than to the font height of the attributes neighborhood. Absolute font heights and relative font heights are not supported.

The `style:font-size-complex` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:font-size-complex` attribute are a value of type `positiveLength` 18.3.26 or a value of type `percent` 18.3.23.

20.278 style:font-size-rel

The `style:font-size-rel` attribute specifies a relative font size change.

This attribute is evaluated for any [UNICODE] character whose script type is `latin`. 20.348

This attribute specifies a relative font size change as a length. It cannot be used within automatic styles. This attribute changes the font size based on the font size of the parent style.

The `style:font-size-rel` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:font-size-rel` attribute has the data type `length` 18.3.18.

20.279 style:font-size-rel-asian

The `style:font-size-rel-asian` attributes specifies a relative font size change.

This attribute is evaluated for [UNICODE] characters whose script type is `asian`. 20.348

This attribute specifies a relative font size change as a length. It cannot be used within automatic styles. This attribute changes the font size based on the font size of the parent style.

The `style:font-size-rel-asian` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:font-size-rel-asian` attribute has the data type `length` 18.3.18.

20.280 style:font-size-rel-complex

The `style:font-size-rel`, `style:font-size-rel-asian` and `style:font-size-rel-complex` attributes specify a relative font size change.

The `style:font-size-rel-complex` attribute is evaluated for [UNICODE] characters whose script type is `complex`. 20.348

This attribute specifies a relative font size change as a length. It cannot be used within automatic styles. This attribute changes the font size based on the font size of the parent style.

The `style:font-size-rel-complex` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:font-size-rel-complex` attribute has the data type `length` 18.3.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.281 style:font-style-asian

The `style:font-style-asian` attribute specifies whether to use normal or italic font face. See §7.8.7 of [XSL].

This attribute is evaluated for [UNICODE] characters whose script type is `asian`. 20.348

The defined values for the `style:font-style-asian` attribute are:

- `italic`: characters displayed in an italic font face.
- `normal`: characters displayed in normal font face.
- `oblique`: characters displayed in an oblique font face.

The `style:font-style-asian` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:font-style-asian` attribute are `normal`, `italic` or `oblique`.

20.282 style:font-style-complex

The `style:font-style-complex` attribute specifies whether to use normal or italic font face. See §7.8.7 of [XSL].

This attribute is evaluated for [UNICODE] characters whose script type is `complex`. 20.348

The `fo:font-style` attribute is evaluated for any other [UNICODE] character.

The defined values for the `style:font-style-complex` attribute are:

- `italic`: characters displayed in an italic font face.
- `normal`: characters displayed in normal font face.
- `oblique`: characters displayed in an oblique font face.

The `style:font-style-complex` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:font-style-complex` attribute are `normal`, `italic` or `oblique`.

20.283 style:font-style-name

The `style:font-style-name` attribute specifies a font style name.

This attribute is evaluated for any [UNICODE] character whose script type is `latin`. 20.348

This attribute is ignored if there is no corresponding `fo:font-family` attribute attached to the same formatting property element.

Instead of this attribute, the `style:font-name` attribute should be used to specify the properties of a font.

The `style:font-style-name` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:font-style-name` attribute has the data type `string` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.284 style:font-style-name-asian

The `style:font-style-name-asian` attribute specifies a font style name.

The `style:font-style-name-asian` attribute is evaluated for [UNICODE] characters whose script type is `asian`. 20.348

This attribute is ignored if there is no corresponding `fo:font-family` attribute attached to the same formatting property element.

Instead of this attribute, the `style:font-name-asian` attribute should be used to specify the properties of a font.

The `style:font-style-name-asian` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:font-style-name-asian` attribute has the data type `string` 18.2.

20.285 style:font-style-name-complex

The `style:font-style-name-complex` attribute specifies a font style name.

The `style:font-style-name-complex` attribute is evaluated for [UNICODE] characters whose script type is `complex`. 20.348

This attribute is ignored if there is no corresponding `fo:font-family` attribute attached to the same formatting property element.

Instead of this attribute, the `style:font-name-complex` attribute should be used to specify the properties of a font.

The `style:font-style-name-complex` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:font-style-name-complex` attribute has the data type `string` 18.2.

20.286 style:font-weight-asian

The `style:font-weight-asian` attribute specifies the weight of a font. See §7.8.9 of [XSL].

This attribute is evaluated for [UNICODE] characters whose script type is `asian`. 20.348

The `style:font-weight-asian` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:font-weight-asian` attribute are `normal`, `bold`, `100`, `200`, `300`, `400`, `500`, `600`, `700`, `800` or `900`.

20.287 style:font-weight-complex

The `style:font-weight-complex` attributes specify the weight of a font. See §7.8.9 of [XSL].

This attribute is evaluated for [UNICODE] characters whose script type is `complex`. 20.348

The `fo:font-weight` attribute is evaluated for any other [UNICODE] character.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `style:font-weight-complex` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:font-weight-complex` attribute are `normal`, `bold`, `100`, `200`, `300`, `400`, `500`, `600`, `700`, `800` or `900`.

20.288 style:footnote-max-height

The `style:footnote-max-height` attribute specifies the maximum amount of space on a page that a footnote can occupy. The value of the attribute is a length, which determines the maximum height of a footnote area.

If the value of this attribute is set to `0cm`, there is no limit to the amount of space that the footnote can occupy.

The `style:footnote-max-height` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:footnote-max-height` attribute has the data type `length` 18.3.18.

20.289 style:glyph-orientation-vertical

The `style:glyph-orientation-vertical` attribute specifies a vertical glyph orientation. See §10.7.3 of [SVG]. The attribute specifies an angle or automatic mode. The only defined angle is 0 degrees, which disables this feature.

Note: OpenDocument v1.1 did not support angle specifications that contain an angle unit identifier. Angle unit identifiers should be omitted for compatibility with OpenDocument v1.1.

The `style:glyph-orientation-vertical` attribute is usable with the following element: `<style:table-cell-properties>` 17.18.

The values of the `style:glyph-orientation-vertical` attribute are `auto`, `0`, `0deg`, `0rad` or `0grad`.

20.290 style:horizontal-pos

The `style:horizontal-pos` attribute specifies the horizontal alignment of a frame in relation to a specific area for documents with an `<office:text>` element.

This attribute can have one of the following values: `from-left`, `left`, `center`, `right`, `from-inside`, `inside`, or `outside`.

The defined values for the `style:horizontal-pos` attribute are:

- `center`: horizontal alignment of a frame should be centered in relation to a specific area for documents within an `<office:text>` element.
- `from-inside`: horizontal alignment of a frame should be centered in relation to a specific area for documents, on pages with an even page number within an `<office:text>` element.
- `from-left`: horizontal alignment of a frame should be centered in relation to a specific area for documents, on pages with an odd page number within an `<office:text>` element.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `inside`: horizontal alignment of a frame should be centered in relation to a specific area for documents, on pages with an even page number within an `<office:text>` element.
- `left`: horizontal alignment of a frame should be centered in relation to a specific area for documents, on pages with an odd page number within an `<office:text>` element.
- `outside`: horizontal alignment of a frame should be centered in relation to a specific area for documents, on pages with an even page number within an `<office:text>` element.
- `right`: horizontal alignment of a frame should be centered in relation to a specific area for documents, on pages with an odd page number within an `<office:text>` element.

The area where a position appears to is specified by the `style:horizontal-rel` attribute.

If the attribute value is `from-left` or `from-inside`, the `svg:x` attribute associated with the frame element specifies the horizontal position of the frame. Otherwise the `svg:x` attribute is ignored for text documents.

Tables 17 and 18 display the defined combinations of values of the attributes `style:horizontal-pos` and `style:horizontal-rel`. The values of these alignment attributes are listed in the first column on the left, and an alignment attribute value/anchor type value match is indicated by an X.

Table 17 - Horizontal position values

Value of style:horizontal-pos	***Value of text:anchor-type***				
	page	***frame***	***paragraph***	***char***	***as-char***
any	X	X	X	X	

Table 18 - Horizontal relation values

Value of style:horizontal-rel	***Value of text:anchor-type***				
	page	***frame***	***paragraph***	***char***	***as-char***
`char`				X	
`frame`		X			
`frame-content`		X			
`frame-end-margin`		X			
`frame-start-margin`		X			
`page`	X		X	X	
`page-content`	X		X	X	
`page-end-margin`	X		X	X	

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Value of style:horizontal-rel	Value of text:anchor-type				
	page	frame	paragraph	char	as-char
page-start-margin	X		X	X	
paragraph			X	X	
paragraph-content			X	X	
paragraph-end-margin			X	X	
paragraph-start-margin			X	X	

The style:horizontal-pos attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the style:horizontal-pos attribute are left, center, right, from-left, inside, outside or from-inside.

20.291 style:horizontal-rel

The style:horizontal-rel attribute specifies the area against which the horizontal position of a frame is positioned.

The value start-margin determines the left margin, except when the horizontal position is from-inside, inside or outside and the anchor for the frame is on a page with an even page number, in which case it determines the right margin. The value end-margin determines the opposite margin to the start-margin values.

The defined values for the style:horizontal-rel attribute are:

- char: horizontal position of a frame is positioned relative to a character.
- page: horizontal position of a frame is positioned relative to a page.
- page-content: horizontal position of a frame is positioned relative to page-content.
- page-start-margin: horizontal position of a frame is positioned relative to a page start margin.
- page-end-margin: horizontal position of a frame is positioned relative to a page end margin.
- frame: horizontal position of a frame is positioned relative to another frame.
- frame-content: horizontal position of a frame is positioned relative to frame content.
- frame-end-margin: horizontal position of a frame is positioned relative to a frame end margin.
- frame-start-margin: horizontal position of a frame is positioned relative to a frame start margin
- paragraph: horizontal position of a frame is positioned relative to a paragraph.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `paragraph-content`: horizontal position of a frame is positioned relative to paragraph content.
- `paragraph-end-margin`: horizontal position of a frame is positioned relative to a paragraph end margin.
- `paragraph-start-margin`:horizontal position of a frame is positioned relative to a paragraph start margin.

The `style:horizontal-rel` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `style:horizontal-rel` attribute are `page`, `page-content`, `page-start-margin`, `page-end-margin`, `frame`, `frame-content`, `frame-start-margin`, `frame-end-margin`, `paragraph`, `paragraph-content`, `paragraph-start-margin`, `paragraph-end-margin` or `char`.

20.292 style:join-border

The `style:join-border` property specifies whether a border for one paragraph is to be extended around the following paragraph.

In addition to the value of this attribute, joining of borders requires meeting these conditions:

1) Values of attributes `fo:border-top`, `fo:border-bottom`, `fo:border-left` and `fo:border-right` are the same. These values can also be given by the `fo:border` attribute.
2) Values of attributes `style:border-line-width-top`, `style:border-line-width-bottom`, `style:border-line-width-left` and `style:border-line-width-right` are the same. These values can also be given by the `style:border-line-width` attribute.
3) Values of attributes `fo:padding-left` and `fo:padding-right` are the same. These values can also be given by the `fo:padding` attribute.
4) Values of the `fo:margin-right` attributes are the same. These values can also be given by the `fo:margin` attribute.
5) Values of the `fo:margin-left` attribute, which can also be given by the `fo:margin`, and `fo:text-indent` attributes, that meet one of these conditions:
    1. All values are the same.
    2. Values of the `fo:margin-left` attributes are the same and values of the `fo:text-indent` attributes are non-negative.
    3. Value of the `fo:margin-left` attribute of one paragraph whose value of the `fo:text-indent` attribute is non-negative is the same as the sum of values of the `fo:margin-left` and `fo:text-indent` attributes of the other paragraph whose value of the `fo:text-indent` attribute is negative.
    4. Both values of the `fo:text-indent` attributes are negative and the sums of values of the `fo:margin-left` and `fo:text-indent` attributes are equal.

The default value of this attribute is true.

The defined values for the `style:join-border` attribute are:

- `false`: borders should not be joined.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `true`: borders should be joined.

The `style:join-border` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The `style:join-border` attribute has the data type `boolean` 18.3.3.

20.293 style:justify-single-word

The `style:justify-single-word` attribute specifies whether a single word should be justified when the last line in a paragraph is justified.

Specifying a `style:justify-single-word` attribute without specifying a `fo:text-align` and `fo:text-align-last` attribute has no effect. Unspecified, both `fo:text-align` and `fo:text-align-last` have the value `start`.

The defined values for the `style:justify-single-word` attribute are:

- `false`: single word should not be justified when the last line in a paragraph is justified.
- `true`: single word should be justified when last line in a paragraph is justified.

The `style:justify-single-word` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The `style:justify-single-word` attribute has the data type `boolean` 18.3.3.

20.294 style:language-asian

The `style:language-asian` attribute specifies the language of a text.

This attribute is evaluated for [UNICODE] characters whose script type is `asian`. 20.348

This attribute may be ignored if it is not specified together with a `style:country-asian` attribute.

The `style:language-asian` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:language-asian` attribute has the data type `languageCode` 18.3.17.

20.295 style:language-complex

The `style:language-complex` attribute specifies the language of a text.

The `style:language-asian` attribute is evaluated for [UNICODE] characters whose script type is `asian`. 20.348

This attribute is evaluated for [UNICODE] characters whose script type is `complex`. 20.348

This attribute may be ignored if it is not specified together with a `style:country-complex` attribute.

The `style:language-complex` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:language-complex` attribute has the data type `languageCode` 18.3.17.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.296 style:layout-grid-base-height

The `style:layout-grid-base-height` attribute specifies the height reserved in layout grid lines for non-ruby text.

The `style:layout-grid-base-height` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:layout-grid-base-height` attribute has the data type `length` 18.3.18.

20.297 style:layout-grid-base-width

The `style:layout-grid-base-width` attribute specifies a grid's base width. This attribute is only evaluated if `style:layout-grid-standard-mode` attribute has the value `true`.

The `style:layout-grid-base-width` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:layout-grid-base-width` attribute has the data type `length` 18.3.18.

20.298 style:layout-grid-color

The `style:layout-grid-color` attribute specifies the color of layout grid border lines.

The `style:layout-grid-color` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:layout-grid-color` attribute has the data type `color` 18.3.9.

20.299 style:layout-grid-display

The `style:layout-grid-display` attribute specifies whether layout grid border lines are displayed.

The defined values for the `style:layout-grid-display` attribute are:

- `false`: layout grid border lines should not be displayed.
- `true`: layout grid border lines should be displayed.

The `style:layout-grid-display` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:layout-grid-display` attribute has the data type `boolean` 18.3.3.

20.300 style:layout-grid-lines

The `style:layout-grid-lines` attribute specifies the number of layout grid lines per page. The number of lines displayed may be smaller than specified if the page does not have space to display the specified number of lines with the specified line height.

The `style:layout-grid-lines` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:layout-grid-lines` attribute has the data type `positiveInteger` 18.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.301 style:layout-grid-mode

The `style:layout-grid-mode` attribute enables Asian layout grids.

The defined values for the `style:layout-grid-mode` attribute are:

- `both`: like lines, except that the lines are divided into rectangular layout cells. The calculation of layout cells depends on the `style:layout-grid-standard-mode` attribute. Within a layout cell, no more than one Asian [UNICODE] character is displayed. An Asian character that does not fit into a single layout cell is displayed centered into as many layout cells as required. Non Asian text is centered within as many cells as required.
- `lines`: enables a line layout, this is, the page is divided in a fixed number of lines. The exact number of lines depends on the other layout grid formatting properties. There is no space between the layout grid lines. The layout grid itself is centered on the page.
- `none`: disables the layout grid.

The `style:layout-grid-mode` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The values of the `style:layout-grid-mode` attribute are `none`, `line` or `both`.

20.302 style:layout-grid-print

The `style:layout-grid-print` attribute specifies whether layout grid border lines are printed.

The defined values for the `style:layout-grid-print` attribute are:

- `false`: layout grid border lines should not be printed.
- `true`: layout grid border lines should be printed.

The `style:layout-grid-print` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:layout-grid-print` attribute has the data type `boolean` 18.3.3.

20.303 style:layout-grid-ruby-below

The `style:layout-grid-ruby-below` attribute specifies whether ruby text is displayed above or below the base text.

The defined values for the `style:layout-grid-ruby-below` attribute are:

- `false`: ruby text should be displayed above the base text.
- `true`: ruby text should be displayed below the base text.

The `style:layout-grid-ruby-below` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:layout-grid-ruby-below` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.304 style:layout-grid-ruby-height

The `style:layout-grid-ruby-height` attribute specifies the height reserved in layout grid lines for ruby text.

The `style:layout-grid-ruby-height` attribute appears on a `<style:page-layout-properties>` element only if a `style:layout-grid-standard-mode` attribute, with the value `false`, appears on the same `<style:page-layout-properties>` element.

The `style:layout-grid-ruby-height` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:layout-grid-ruby-height` attribute has the data type `length` 18.3.18.

20.305 style:layout-grid-snap-to

The `style:layout-grid-snap-to` attribute specifies whether the text is snapped to the grid or not. It is evaluated only if the `style:layout-grid-mode` attribute has the value `both` and the `style:layout-grid-standard-mode` attribute has the value `true`.

The defined values for the `style:layout-grid-snap-to` attribute are:

- `false`: text should not be snapped to grid.
- `true`: text should be snapped to grid.

The `style:layout-grid-snap-to` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:layout-grid-snap-to` attribute has the data type `boolean` 18.3.3.

20.306 style:layout-grid-standard-mode

The `style:layout-grid-standard-mode` attribute specifies how the rectangular grid cells are calculated if the `style:layout-grid-mode` attribute has the value `both`.

The `style:layout-grid-standard-mode` attribute can only be used in the default page layout. If the `style:layout-grid-standard-mode` attribute appears inside a `<style:page-layout>` element it shall be ignored.

The defined values for the `style:layout-grid-standard-mode` attribute are:

- `false`: the page is divided in a fixed number of lines, and the lines are divided into square cells. The number of cells per grid line depends on the line height, where the line height is the sum of the base height and the ruby height as specified by the `style:layout-grid-base-height` and `style:layout-grid-ruby-height` attributes.
- `true`: the page is divided into a fixed numbers of lines, and the lines are divided into rectangular cells. The line height is specified by the `style:layout-grid-base-height` attribute, and the cell width is specified by `style:layout-grid-base-width` attribute. The number of cells per line depends on the grid base width. This mode is also called *standard paper mode*. The `style:layout-grid-ruby-height` attribute is ignored in this mode.

The `style:layout-grid-standard-mode` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `style:layout-grid-standard-mode` attribute has the data type `boolean` 18.3.3.

20.307 style:line-break

The `style:line-break` attribute specifies line breaking rules.

The defined values for the `style:line-break` attribute are:

- `normal`: line breaks may occur between any characters.
- `strict`: line breaks shall not occur before or after implementation-defined characters.

The `style:line-break` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The values of the `style:line-break` attribute are `normal` or `strict`.

20.308 style:letter-kerning

The `style:letter-kerning` attribute specifies whether kerning between characters is enabled or disabled.

The defined values for the `style:letter-kerning` attribute are:

- `false`: kerning between letters should be disabled.
- `true`: kerning between letters should be enabled.

The `style:letter-kerning` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:letter-kerning` attribute has the data type `boolean` 18.3.3.

20.309 style:line-height-at-least

The `style:line-height-at-least` attribute specifies a minimum line height. The value of this attribute is a length.

The effect of this attribute is disabled when `fo:line-height` has the value of `normal`.

The `style:line-height-at-least` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The `style:line-height-at-least` attribute has the data type `nonNegativeLength` 18.3.20.

20.310 style:line-spacing

The `style:line-spacing` attribute specifies a fixed distance between two lines.

The effect of this attribute is disabled when `fo:line-height` has the value of `normal`.

The `style:line-spacing` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The `style:line-spacing` attribute has the data type `length` 18.3.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.311 style:may-break-between-rows

The `style:may-break-between-rows` attribute specifies that a page break may occur inside a table.

The defined values for the `style:may-break-between-rows` attribute are:

- `false`: page break may not occur inside a table.
- `true`: page break may occur inside a table.

The `style:may-break-between-rows` attribute is usable with the following element: `<style:table-properties>` 17.15.

The `style:may-break-between-rows` attribute has the data type `boolean` 18.3.3.

20.312 style:min-row-height

The `style:min-row-height` attribute specifies a fixed minimum height for a row.

The `style:min-row-height` attribute is usable with the following element: `<style:table-row-properties>` 17.17.

The `style:min-row-height` attribute has the data type `nonNegativeLength` 18.3.20.

20.313 style:mirror

The `style:mirror` attribute specifies whether an image is mirrored before it is displayed. The mirroring can be vertical or horizontal or both.

The defined values for the `style:mirror` attribute are:

- `none`: image should not be mirrored before being displayed.
- `horizontal`: image should be mirrored horizontally before being displayed.
- `horizontal-on-even`: image should be mirrored horizontally on even numbered pages before being displayed.
- `horizontal-on-odd`: image should be mirrored horizontally on odd numbered pages before being displayed.
- `vertical`: image should be mirrored vertically before being displayed.

The value `vertical` and the horizontal values can be specified together, separated by a white space.

The `style:mirror` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `style:mirror` attribute are `none`, `vertical`, or two white space separated values, that may appear in any order. One of these values is always `vertical`. The other value is one of: `horizontal`, `horizontal-on-odd` or `horizontal-on-even`.

20.314 style:num-format

The `style:num-format` attribute specifies a numbering sequence.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If no value is given, no number sequence is displayed.

The defined values for the `style:num-format` attribute are:

- `1`: number sequence starts with “1”.
- `a`: number sequence starts with “a”.
- `A`: number sequence starts with “A”.
- empty string: no number sequence displayed.
- `i`: number sequence starts with “i”.
- `I`: number sequence start with “I”.
- a value of type `string` 18.2

The `style:num-format` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The values of the `style:num-format` attribute are `1`, `i`, `I`, a value of type `string` 18.2, an empty string, `a` or `A`.

20.315 style:num-letter-sync

The `style:num-letter-sync` attribute specifies whether letter synchronization shall take place. If letters are used in alphabetical order for numbering, there are two ways to process overflows within a digit, as follows:

- `false`: A new digit is inserted that always has the same value as the following digit. The numbering sequence (for lower case numberings) in that case is a, b, c, ..., z, aa, bb, cc, ..., zz, aaa, ..., and so on.
- `true`: A new digit is inserted. Its start value is ”a” or ”A”, and it is incremented every time an overflow occurs in the following digit. The numbering sequence (for lower case numberings) in that case is a,b,c, ..., z, aa, ab, ac, ...,az, ba, ..., and so on.

The `style:num-letter-sync` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:num-letter-sync` attribute has the data type `boolean` 18.3.3.

20.316 style:num-prefix

The `style:num-prefix` attribute specifies what to display before a number.

If the `style:num-prefix` and `style:num-suffix` values do not contain any character that has a Unicode category of Nd, Nl, No, Lu, Ll, Lt, Lm or Lo, an [XSLT] `format` attribute can be created from the OpenDocument attributes by concatenating the values of the `style:num-prefix`, `style:num-format`, and `style:num-suffix` attributes.

The `style:num-prefix` attribute can also specify a character before the value of a `text:bullet-char` attribute.

The `style:num-prefix` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The style:num-prefix attribute has the data type string 18.2.

20.317 style:num-suffix

The style:num-prefix and style:num-suffix attributes specify what to display before and after a number.

If the style:num-prefix and style:num-suffix values do not contain any character that has a Unicode category of Nd, Nl, No, Lu, Ll, Lt, Lm or Lo, an [XSLT] format attribute can be created from the OpenDocument attributes by concatenating the values of the style:num-prefix, style:num-format, and style:num-suffix attributes.

The style:num-suffix attribute can also specify a character after the value of a text:bullet-char attribute.

The style:num-suffix attribute is usable with the following element: <style:page-layout-properties> 17.2.

The style:num-suffix attribute has the data type string 18.2.

20.318 style:number-wrapped-paragraphs

The style:number-wrapped-paragraphs attribute specifies the number of paragraphs that can wrap around a frame if the anchor position of a frame or drawing shape is a paragraph or a character, and the wrap mode specified by the style:wrap attribute is left, right, parallel, or dynamic.

This attribute is only recognized in frames or styles that have a style:wrap attribute attached with a value of left, right, parallel, or dynamic.

The defined values for the style:number-wrapped-paragraphs attribute are:

- no-limit: there is no limit on the number of paragraphs that may wrap around a frame.
- a value of type positiveInteger

The style:number-wrapped-paragraphs attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the style:number-wrapped-paragraphs attribute are no-limit or a value of type positiveInteger 18.2.

20.319 style:overflow-behavior

The style:overflow-behavior attribute specifies the behavior of text boxes where the containing text does not fit into a text box.

If the style:overflow-behavior attribute value is auto-create-new-frame and the text box has a minimum width or height specified the text box will grow as long as there is space left on the page. If no space is left, a new frame will be created on the next page, with the same position and dimensions of the original frame.

The defined values for the style:overflow-behavior attribute are:

- clip: text that does not fit into a text box is not displayed.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `auto-create-new-frame`: a new frame will be created on the next page, with the same position and dimensions of the original frame.

The `style:overflow-behavior` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `style:overflow-behavior` attribute are `clip` or `auto-create-new-frame`.

20.320 style:page-number

The `style:page-number` attribute specifies the page number that should be used for a new page when either a paragraph or table style specifies a master page that should be applied beginning from the start of a paragraph or table.

The defined values for the `style:page-number` attribute are:

- `auto`: a page has the page number of the previous page, incremented by one.
- a value of type `positiveInteger` 18.2: specifies a page number.

The `style:page-number` attribute is usable with the following elements: `<style:paragraph-properties>` 17.6 and `<style:table-properties>` 17.15.

The values of the `style:page-number` attribute are a value of type `positiveInteger` 18.2 or `auto`.

20.321 style:paper-tray-name

The `style:paper-tray-name` attribute specifies the paper tray to use when printing a document. The names assigned to the paper trays depends upon the printer.

The defined values for the `style:paper-tray-name` attribute are:

- `default`: the default tray specified by printer configuration settings.
- a value of type string 18.2

The `style:paper-tray-name` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The values of the `style:paper-tray-name` attribute are `default` or a value of type `string` 18.2.

20.322 style:print

The `style:print` attribute specifies the components in a spreadsheet document to print.

The value of the `style:print` attribute is a white space separated list of one or more of these values: `headers`, `grid`, `annotations`, `objects`, `charts`, `drawings`, `formulas`, `zero-values`, or the empty list.

The defined values for the `style:print` attribute are:

- `annotations`: annotations should be printed.
- `charts`: charts should be printed.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `drawings`: drawings should be printed.
- `formulas`: formulas should be printed.
- `headers`: headers should be printed.
- `grid`: grid lines should be printed.
- `objects`: (including graphics): objects should be printed.
- `zero-values`: zero-values should be printed.

The `style:print` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The value of the `style:print` attribute is a white space separated lists of one of these values: `headers`, `grid`, `annotations`, `objects`, `charts`, `drawings`, `formulas`, or `zero-values`, including the empty list.

20.323 style:print-content

20.323.1 General

The `style:print-content` attribute specifies if content is printed.

20.323.2 <style:graphic-properties>

The `style:print-content` attribute specifies if frame content is printed.

The `style:print-content` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `style:print-content` attribute has the data type `boolean` 18.3.3.

20.323.3 <style:table-cell-properties>

The `style:print-content` attribute specifies if cell content is printed.

The `style:print-content` attribute is usable with the following element: `<style:table-cell-properties>` 17.18.

The `style:print-content` attribute has the data type `boolean` 18.3.3.

20.324 style:print-page-order

The `style:print-page-order` attribute specifies the order in which data in a spreadsheet is numbered and printed when the data does not fit on one printed page.

The defined values for the `style:print-page-order` attribute are:

- `ltr`: create pages from the first column to the last column before continuing with the next set of rows.
- `ttb`: create pages from the top row to the bottom row before continuing with the next set of columns.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The style:print-page-order attribute is usable with the following element: <style:page-layout-properties> 17.2.

The values of the style:print-page-order attribute are ttb or ltr.

20.325 style:print-orientation

The style:print-orientation attribute specifies the orientation of the printed page. The value of this attribute can be portrait or landscape.

The defined values for the style:print-orientation attribute are:

- landscape: a page is printed in landscape orientation.
- portrait: a page is printed in portrait orientation.

The style:print-orientation attribute is usable with the following element: <style:page-layout-properties> 17.2.

The values of the style:print-orientation attribute are portrait or landscape.

20.326 style:protect

20.326.1 General

The style:protect attribute specifies the protection of content.

20.326.2 <style:graphic-properties>

The style:protect attribute specifies whether the content, size, or position of a frame is protected. The value of this attribute can be either none or a white space separated list that consists of any of the values content, position, or size.

The defined values for the style:protect attribute are:

- content: content of a frame should be protected from editing.
- none: the content, size and position of a frame should be subject to editing.
- position: the position of a frame should be protected from editing.
- size: the size of a frame should be protected from editing.

The style:protect attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the style:protect attribute are none, or white space separated non-empty lists of one of these values: content, position, or size..

20.326.3 <style:section-properties>

The style:protect attribute specifies that sections should not be changed. The user interface should prevent the user from manually making any changes. The style:protect attribute should be set to true by default for linked sections or indexes. Removing the protection from

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

linked sections or indexes leaves them unprotected from editing, but any edits will be over-written by updates to those sections.

The defined values for the `style:protect` attribute are:

- `false`: sections should not be protected from editing.
- `true`: sections should be protected from editing.

The `style:protect` attribute is usable with the following element: `<style:section-properties>` 17.11.

The `style:protect` attribute has the data type `boolean` 18.3.3.

20.327 style:punctuation-wrap

The `style:punctuation-wrap` attribute specifies whether a punctuation mark, if one is present, can be hanging, that is, whether it can placed in the margin area at the end of a full line of text.

The defined values for the `style:punctuation-wrap` attribute are:

- `hanging`: a punctuation mark can be placed in the margin area at the end of a full line of text.
- `simple`: a punctuation mark can not be placed in the margin area at the end of a full line of text.

The `style:punctuation-wrap` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The values of the `style:punctuation-wrap` attribute are `simple` or `hanging`.

20.328 style:register-true

The `style:register-true` attribute specifies whether the lines on both sides of a printed page align. The text baselines of text in page columns or text box columns also align.

The defined values for the `style:register-true` attribute are:

- `false`: lines on both sides of a printed text may not align.
- `true`: lines on both sides of a printed text should align.

The `style:register-true` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The `style:register-true` attribute has the data type `boolean` 18.3.3.

20.329 style:register-truth-ref-style-name

The `style:register-truth-ref-style-name` attribute specifies a paragraph style. The line distance specified of the paragraph style is used as the reference line distance for all paragraphs that have the register-truth feature enabled.

The `style:register-truth-ref-style-name` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `style:register-truth-ref-style-name` attribute has the data type `styleNameRef` 18.3.32.

20.330 style:rel-column-width

The `style:rel-column-width` attribute specifies a relative width of a column with a number value, followed by a "*" (U+002A, ASTERISK) character. If r_c is the relative with of the column, r_s the sum of all relative columns widths, and w_s the absolute width that is available for these columns the absolute width w_c of the column is $w_c=r_c w_s/r_s$.

The `style:rel-column-width` attribute is usable with the following element: `<style:table-column-properties>` 17.16.

The `style:rel-column-width` attribute has the data type `relativeLength` 18.3.27.

20.331 style:rel-height

The `style:rel-height` attribute specifies the height of a drawing object as a relative value within a frame. The relative value either is a percentage value, the value `scale`, or the value `scale-min`.

The defined values for the `style:rel-width` attribute are:

- `scale`: the height should be calculated depending on the width, so that the ratio of width and height of the original image or object size is preserved.
- `scale-min`:the height should be calculated as for value `scale`, but the calculated height is a minimum height rather than an absolute one.
- a value of type `percent` 18.3.23.

The interpretation of relative values depends on the anchor of the drawing object. If the anchor for the drawing object is in a table cell, the percentage value is relative to the surrounding table box. If the anchor for the drawing object is in a text box, the percentage value is relative to the surrounding text box. In other cases, the percentage values is relative to the width of the page or window.

To support consumers that do not support relative width and heights, producers should also provide the height in `svg:height` and `fo:min-height` attributes.

The `style:rel-height` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `style:rel-height` attribute are a value of type `percent` 18.3.23, `scale` or `scale-min`.

20.332 style:rel-width

20.332.1 <style:graphic-properties>

The `style:rel-width` attribute specifies the relative width of a drawing object. The relative value either is a percentage value, the value `scale`, or the value `scale-min`.

The defined values for the `style:rel-width` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `scale`: the width should be calculated depending on the height, so that the ratio of width and height of the original image or object size is preserved.
- `scale-min`: the width should be calculated as for value `scale`, but the calculated width is a minimum width rather than an absolute one.
- a value of type `percent` 18.3.23.

The interpretation of the percent value depends on the anchor of the drawing object. If the anchor for the drawing object is in a table cell, the percent value of the surrounding table box. If the anchor for the drawing object is in a text box, the percentage value of the surrounding text box. In all other cases, the percent value of the containing page or window

To support consumers that do not support relative width, producers should also provide the width in a `svg:width` attribute.

The `style:rel-width` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `style:rel-width` attribute are a value of type `percent` 18.3.23, `scale` or `scale-min`.

20.332.2 <style:table-properties>

The `style:rel-width` attribute specifies the width of a table relative to the width of the area that the table is in.

The `style:rel-width` attribute is usable with the following element: `<style:table-properties>` 17.15.

The `style:rel-width` attribute has the data type `percent` 18.3.23.

20.333 style:repeat

The `style:repeat` attribute specifies if an image can be repeated or stretched over an area. The value of the attribute can be `no-repeat`, `repeat`, or `stretch`.

The defined values for the `style:repeat` attribute are:

- `no-repeat`: image should not be repeated.
- `repeat`: image should be repeated.
- `stretch`: image should be stretched over an area.

The `style:repeat` attribute is usable with the following elements: `<style:drawing-page-properties>` 17.25 and `<style:graphic-properties>` 17.21.

The values of the `style:repeat` attribute are `no-repeat`, `repeat` or `stretch`.

20.334 style:repeat-content

The `style:repeat-content` attribute specifies whether text content of a cell is displayed as many times as there is space left in the cell's writing direction. The attribute has no effect for cell content that contains a line break.

The defined values for the `style:repeat-content` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `false`: text content of a cell should not be displayed as many times as there is space left in the cell's writing direction.
- `true`: text content of a cell should be displayed as many times as there is space left in the cell's writing direction.

The `style:repeat-content` attribute is usable with the following element: `<style:table-cell-properties>` 17.18.

The `style:repeat-content` attribute has the data type `boolean` 18.3.3.

20.335 style:rfc-language-tag

The `style:rfc-language-tag` attribute specifies a language identifier according to the rules of [RFC5646], or its successors.

It shall only be used if its value can not be expressed as a valid combination of the `fo:language`, `fo:script` and `fo:country` attributes.

Producers may add support for consumers that don't support the `style:rfc-language-tag` attribute by specifying `fo:language`, `fo:script` and `fo:country` attributes with values that are implementation-dependent.

The attribute is evaluated for any [UNICODE] characters that are not of type asian or complex. 20.348

The `style:rfc-language-tag` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:rfc-language-tag` attribute has the data type `language` 18.3.16.

20.336 style:rfc-language-tag-asian

The `style:rfc-language-tag-asian` attribute specifies a language identifier according to the rules of [RFC5646], or its successors.

It shall only be used if its value can not be expressed as a valid combination of the `style:language-asian`, `style:script-asian` and `style:country-asian` attributes.

Producers may add support for consumers that don't support the `style:rfc-language-tag-asian` attribute by specifying `style:language-asian`, `style:script-asian` and `style:country-asian` attributes with values that are implementation-dependent.

This attribute is evaluated for [UNICODE] characters that are of type asian. 20.348.

The `style:rfc-language-tag-asian` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:rfc-language-tag-asian` attribute has the data type `language` 18.3.16.

20.337 style:rfc-language-tag-complex

The `style:rfc-language-tag-complex` attribute specifies a language identifier according to the rules of [RFC5646], or its successors.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

It shall only be used if its value can not be expressed as a valid combination of the style:language-complex, style:script-complex and style:country-complex attributes.

Producers may add support for consumers that don't support the style:rfc-language-tag-complex attribute by specifying style:language-complex, style:script-complex and style:country-complex attributes with values that are implementation-dependent.

This attribute is evaluated for [UNICODE] characters that are of type complex..

The style:rfc-language-tag-complex attribute is usable with the following element: <style:text-properties> 16.27.28.

The style:rfc-language-tag-complex attribute has the data type language 18.3.16.

20.338 style:rotation-align

The style:rotation-align attribute specifies how the edge of the text in a cell is aligned after a rotation.

The defined values for the style:rotation-align attribute are shown in Table 19:

Table 19 - Rotation align values

Alignment	***Text is...***	***Borders and background are...***
None.	Rotated and aligned within the cell.	Unchanged.
Bottom	Rotated and may overlap with other cells if the text is longer than the length of the cell.	Positioned parallel to the text, whereby the edge that is named by the attribute value aligns with the corresponding edge of the cell's original position.
Center		
Top		

The style:rotation-align attribute is usable with the following element: <style:table-cell-properties> 17.18.

The values of the style:rotation-align attribute are none, bottom, top or center.

20.339 style:rotation-angle

The style:rotation-angle attribute specifies the rotation angle of content. The attribute value is an angle.

If used with a chart style applied to a <chart:axis> element the attribute specifies the rotation of the axis labels, each tick label is rotated, the axis title is not affected in this case.

If used with a chart style applied to a <chart:data-label>, <chart:data-point>, <chart:series> or <chart:plot-area> element the attribute specifies the rotation angle of the according data labels.

If used with a chart style applied to a <chart:title> element the attribute specifies the rotation angle of the title.

The style:rotation-angle attribute is usable with the following elements: <style:chart-properties> 17.22 and <style:table-cell-properties> 17.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `style:rotation-angle` attribute has the data type `angle` 18.3.1.

20.340 style:row-height

The `style:row-height` attribute specifies a fixed row height.

The `style:row-height` attribute is usable with the following element: `<style:table-row-properties>` 17.17.

The `style:row-height` attribute has the data type `positiveLength` 18.3.26.

20.341 style:ruby-align

The `style:ruby-align` attribute specifies the horizontal alignment of the ruby text in relationship to the ruby base.

The defined values for the `style:ruby-align` attribute are:

- `center`: ruby text centered on ruby base text.
- `distribute-letter`: If the width of the ruby text is smaller than that of the ruby base text, then the ruby text contents are evenly distributed across the width of the ruby base text, with the first and last ruby text glyphs lining up with the corresponding first and last base glyphs. If the width of the ruby text is at least the width of the ruby base text, then the letters of the ruby base text are evenly distributed across the width of the ruby text.
- `distribute-space`: If the width of the ruby text is smaller than that of the ruby base text, then the ruby text contents are evenly distributed across the width of the ruby base text, with a amount of white space preceding the first and following the last character in the ruby text. That amount of white space is normally equal to half the amount of inter-character space of the ruby text. If the width of the ruby text is at least the width of the ruby base text, then the same type of space distribution applies to the ruby base text. If the base is shorter than the ruby text, the base is `distribute-space` aligned.
- `left`: ruby text to the left of ruby base text.
- `right`: ruby text to the right of ruby base text.

The `style:ruby-align` attribute is usable with the following element: `<style:ruby-properties>` 17.10.

The values of the `style:ruby-align` attribute are `left`, `center`, `right`, `distribute-letter` or `distribute-space`.

20.342 style:ruby-position

The `style:ruby-position` attribute specifies the vertical position of the ruby text in relationship to the ruby base.

The defined values for the `style:ruby-position` attribute are:

- `above`: ruby text should be above ruby base text.
- `below`: ruby text should be below ruby base text.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `style:ruby-position` attribute is usable with the following element: `<style:ruby-properties>` 17.10.

The values of the `style:ruby-position` attribute are `above` or `below`.

20.343 style:run-through

The `style:run-through` attribute specifies whether content of a frame is displayed in the background or foreground.

The value of this attribute can be `foreground` or `background`.

The defined values for the `style:run-through` attribute are:

- `background`: frame content is displayed behind a text.
- `foreground`: frame content is displayed in front of a text.

Use of this attribute depends upon the presence of a `style:wrap` attribute with the value `run-through`.

The `style:run-through` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `style:run-through` attribute are `foreground` or `background`.

20.344 style:scale-to

The `style:scale-to` attribute specifies that a document is to be scaled to a percentage value. A value of 100% means no scaling.

If this attribute and `style:scale-to-pages` are absent, a document is not scaled.

The `style:scale-to` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:scale-to` attribute has the data type `percent` 18.3.23.

20.345 style:scale-to-pages

The `style:scale-to-pages` attribute specifies the number of pages on which a document should be printed. The document is scaled to fit a specified number of pages.

If this attribute and `style:scale-to` are absent, a document is not scaled.

The `style:scale-to-pages` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The `style:scale-to-pages` attribute has the data type `positiveInteger` 18.2.

20.346 style:script-asian

The `style:script-asian` attribute specifies the script code of a text. The attribute should be used only if necessary according to the rules of §2.2.3 of [RFC5646], or its successors.

This attribute is evaluated for [UNICODE] characters whose script type is `asian`. 20.348

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

It may be ignored if is not specified together with a `style:language-asian` attribute.

The `style:script-asian` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:script-asian` attribute has the data type `scriptCode` 18.3.29.

20.347 style:script-complex

The `style:script-complex` attribute specifies the script code of a text. The attribute should be used only if necessary according to the rules of §2.2.3 of [RFC5646], or its successors.

This attribute is evaluated for [UNICODE] characters whose script type is `complex`. 20.348

It may be ignored if is not specified together with a `style:language-complex` attribute.

The `style:script-complex` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:script-complex` attribute has the data type `scriptCode` 18.3.29.

20.348 style:script-type

The `style:script-type` attribute specifies which script type dependent attributes (`fo:font-family`, `style:font-family-asian`, `style:font-family-complex`) are currently active for a portion of text. The attribute may be evaluated by consumers that cannot determine the script types of Unicode characters to select the correct script type dependent formatting properties. Consumers that can determine script types of Unicode characters may also evaluate the attribute and overwrite the script type they determine for certain character with the value of the attribute.

Note: The usage of this attribute simplifies transformations from and to [CSS2]/[XSL] and other formats that do not have script-dependent attributes, and also can be used to assign script-types to weak [UNICODE] characters, where consumers may choose different script types.

The value `ignore` can be used only within default styles. If it is set, all script-dependent attributes are applied to all script types. This would mean that a `fo:font-family` would be applied to all script types as well as a `style:font-family-asian` or `style:font-family-complex`.

Note: Use of the `ignore` value simplifies saving documents with producers that do not support a script type.

The defined values for the `style:script-type` attribute are:

- `asian`: all asian script type dependent attributes are active.
- `complex`: all complex script type dependent attributes are active.
- `ignore`: all script type dependent attributes are applied to all script types. This is available on default styles only.
- `latin`: all latin script type dependent attributes are active.

The mapping of Unicode code points to script types is defined by table 20. Consumers should apply this mapping. For Unicode code points for which no mapping is defined, the mapping is implementation dependent.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Table 20 - Unicode Code Point to Script Type Mapping

Unicode Code Point Ranges	*Script Type*
U+0003..U+001F, U+0021..U+009F, U+00A1..U+04FF, U+0530..U+058F, U+10A0..U+10FF, U+13A0..U+16FF, U+1E00..U+1FFF, U+2C60..U+2C7F, U+2C80..U+2CE3, U+A720..U+A7FF	`latin`
U+0590..U+074F, U+0780..U+07BF, U+0900..U+109F, U+1200..U+137F, U+1780..U+18AF, U+FB50..U+FDFF, U+FE70..U+FEFF	`complex`
U+1100..U+11FF, U+2E80..U+31BF, U+31C0..U+31EF, U+3200..U+4DBF, U+4E00..U+A4CF, U+AC00..U+D7AF, U+F900..U+FAFF, U+FE30..U+FE4F, U+FF00..U+FFEF, U+20000..U+2A6DF, U+2F800..U+2FA1F	`asian`

The `style:script-type` attribute specifies which script type dependent attributes are currently active for a portion of text. The attribute may be evaluated by consumers that do not support script types to select the correct script dependent formatting properties. Consumers that support script types may also evaluate the attribute and overwrite the script type they would evaluate for a specific character.

The `style:script-type` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:script-type` attribute are `latin`, `asian`, `complex` or `ignore`.

20.349 style:shadow

The `style:shadow` attribute specifies a shadow effect.

The defined values for this attribute are those defined in §7.16.5 of [XSL], except the value `inherit`.

The `style:shadow` attribute is usable with the following elements: `<style:graphic-properties>` 17.21, `<style:header-footer-properties>` 17.5, `<style:page-layout-properties>` 17.2, `<style:paragraph-properties>` 17.6, `<style:table-cell-properties>` 17.18 and `<style:table-properties>` 17.15.

The values of the `style:shadow` attribute are `none` or a value of type `string` 18.2.

20.350 style:shrink-to-fit

The `style:shrink-to-fit` attribute specifies whether content is reduced in size to fit within a cell or drawing object. Shrinking means that the font size of the content is decreased to fit the content into a cell or drawing object. The attribute has no effect on cells where the cell content already fits into the cell.

The defined values for the `style:shrink-to-fit` attribute are:

- `false`: content should not be reduced in size to fit within a cell or drawing object.
- `true`: content should be reduced in size to fit within a cell or drawing object.

The `style:shrink-to-fit` attribute is usable with the following elements: `<style:graphic-properties>` 17.21 and `<style:table-cell-properties>` 17.18.

The `style:shrink-to-fit` attribute has the data type `boolean` 18.3.3.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.351 style:snap-to-layout-grid

The `style:snap-to-layout-grid` attribute specifies whether the layout of a paragraph should consider the layout grid settings of the page where it appears.

The defined values for the `style:snap-to-layout-grid` attribute are:

- `false`: layout of a paragraph should not consider the layout grid settings of the page where it appears.
- `true`: layout of a paragraph should consider the layout grid settings of the page where it appears.

The `style:snap-to-layout-grid` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The `style:snap-to-layout-grid` attribute has the data type `boolean` 18.3.3.

20.352 style:tab-stop-distance

The `style:tab-stop-distance` attribute specifies the distance between default tab stops. A default tab stop is repeated automatically after the specified distance. Default tab stops are only evaluated if they are specified within a default style.

The `style:tab-stop-distance` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The `style:tab-stop-distance` attribute has the data type `nonNegativeLength` 18.3.20.

20.353 style:table-centering

The `style:table-centering` attribute specifies whether tables are centered horizontally and/or vertically on the page. This attribute only applies to spreadsheet documents.

The default is to align the table to the top-left or top-right corner of the page, depending of its writing direction.

The defined values for the `style:table-centering` attribute are:

- `both`: tables should be centered both horizontally and vertically on the pages where they appear.
- `horizontal`: tables should be centered horizontally on the pages where they appear.
- `none`: tables should not be centered both horizontally or vertically on the pages where they appear.
- `vertical`: tables should be centered vertically on the pages where they appear.

The `style:table-centering` attribute is usable with the following element: `<style:page-layout-properties>` 17.2.

The values of the `style:table-centering` attribute are `horizontal`, `vertical`, `both` or `none`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.354 style:text-align-source

The `style:text-align-source` attribute specifies the source of a text-align attribute.

The defined values for the `style:text-align-source` attribute are:

- `fix`: content alignment uses the value of the `fo:text-align` attribute.
- `value-type`: content alignment uses the value-type of the cell.

The default alignment for a cell value-type `string` is left, for other value-types it is right.

The `style:text-align-source` attribute is usable with the following element: `<style:table-cell-properties>` 17.18.

The values of the `style:text-align-source` attribute are `fix` or `value-type`.

20.355 style:text-autospace

The `style:text-autospace` attribute specifies whether to add space between portions of Asian, Western, and complex texts.

The defined values for the `style:text-autospace` attribute are:

- `ideograph-alpha`: space should be added between portions of Asian, Western and complex texts.
- `none`: space should not be added between portions of Asian, Western and complex texts.

The `style:text-autospace` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The values of the `style:text-autospace` attribute are `none` or `ideograph-alpha`.

20.356 style:text-blinking

The `style:text-blinking` attribute specifies whether text blinks.

The defined values for the `style:text-blinking` attribute are:

- `false`: text should not blink.
- `true`: text should blink.

The `style:text-blinking` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:text-blinking` attribute has the data type `boolean` 18.3.3.

20.357 style:text-combine

The `style:text-combine` attribute specifies whether to combine characters so that they are displayed within two lines.

The defined values for the `style:text-combine` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `letters`: Display text in Kumimoji. Up to five (5) characters are combined within two lines and are displayed with a reduced size in a single wide-cell character. Additional characters are displayed as normal text.
- `lines`: Displays text in Warichu. All characters with the `style:text-combine` attribute that immediately follow each other are displayed within two lines of approximately the same length. A line break may occur between any two characters to meet this constraint.
- `none`: characters should not be combined.

The `style:text-combine` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-combine` attribute are `none`, `letters` or `lines`.

20.358 style:text-combine-start-char

The `style:text-combine-start-char` attribute specifies the start character that is displayed before a portion of text whose `style:text-combine` attribute has a value of `lines`.

The `style:text-combine-start-char` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:text-combine-start-char` attribute has the data type `character` 18.3.7.

20.359 style:text-combine-end-char

The `style:text-combine-end-char` attribute specifies the end character that is displayed after a portion of text whose `style:text-combine` attribute has a value of `lines`.

The `style:text-combine-end-char` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:text-combine-end-char` attribute has the data type `character` 18.3.7.

20.360 style:text-emphasize

The `style:text-emphasize` attribute specifies emphasis in a text composed of [UNICODE] characters whose script type is `asian`. 20.348

The value of this attribute consists of two white space-separated values.

The first value represents the style to use for emphasis and it can be `accent`, `circle`, `dot`, `disc` or `none`.

The second value represents the position of the emphasis and it can be `above` or `below`. If the first value is `none`, the second value can be omitted.

The defined values for the `style:text-emphasize` attribute are:

- `accent`: calligraphic accent strokes.
- `circle`: hollow circles.
- `disc`: filled circles.
- `dot`: calligraphic dot.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `none`: no emphasis marks.

The `style:text-emphasize` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-emphasize` attribute are `none`, or two white space separated values. The first of these values is one of: `none`, `accent`, `dot`, `circle` or `disc`. The second of these values is one of: `above` or `below`.

20.361 style:text-line-through-color

The `style:text-line-through-color` attribute specifies the color that is used for line-through text.

The defined values for the `style:text-line-through-color` attribute are:

- `font-color`: current text color is used for underlining.
- a value of type `color` 18.3.9

The `style:text-line-through-color` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-line-through-color` attribute are `font-color` or a value of type `color` 18.3.9.

20.362 style:text-line-through-mode

The `style:text-line-through-mode` attribute specifies whether lining through is applied to words only or to portions of text.

The defined values for the `style:text-line-through-mode` attribute are:

- `continuous`: lining is applied to words and separating spaces.
- `skip-white-space`: lining is not applied to spaces between words.

The `style:text-line-through-mode` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-line-through-mode` attribute are `continuous` or `skip-white-space`.

20.363 style:text-line-through-style

The `style:text-line-through-style` attribute specifies a style for rendering a line-through text.

The defined values for the `style:text-line-through-style` attribute are:

- `none`: text has no line through it.
- `dash`: text has a dashed line through it.
- `dot-dash`: text has a line whose repeating pattern is a dot followed by a dash through it.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `dot-dot-dash`: text has a line whose repeating pattern is two dots followed by a dash through it.
- `dotted`: text has a dotted line through it.
- `long-dash`: text has a dashed line whose dashes are longer than the ones from the dashed line for value dash through it.
- `solid`: text has a solid line through it.
- `wave`: text has a wavy line through it.

Note: The definitions of the values of the `style:text-line-through-style` attribute are based on the text decoration style 'text-line-through-style' from [CSS3Text], §9.2.

The `style:text-line-through-style` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-line-through-style` attribute are `none`, `solid`, `dotted`, `dash`, `long-dash`, `dot-dash`, `dot-dot-dash` or `wave`.

20.364 style:text-line-through-text

The `style:text-line-through-text` attribute specifies a text that is used for line-through. The attribute will be evaluated only if the value of `style:text-line-through-style` attribute is different than `none`.

If the attribute value is not empty, the attribute value string is used for line-through instead of the line style that has been specified by the `style:text-line-through-style` attribute. Consumers that do not support line-through with text should ignore the attribute, i and should use the line style specified by the `style:text-line-through-style` attribute.

Consumers that support line-through with single characters only, should use the first character of the value for line-through, if the `style:text-line-through-text` attribute value as more than one character. Consumers that support line-through with specific characters only (like ”x” or ”/” (U+002F, SOLIDUS) should use one of these characters if the attribute specifies characters that are not supported.

The `style:text-line-through-text` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:text-line-through-text` attribute has the data type `string` 18.2.

20.365 style:text-line-through-text-style

The `style:text-line-through-text-style` specifies a text style that is applied to text-line-through characters. It is not applied to line-through lines. If the attribute appears in an automatic style, it may reference either an automatic text style or a common style. If the attribute appears in a common style, it may reference a common style only.

The `style:text-line-through-text-style` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:text-line-through-text-style` attribute has the data type `styleNameRef` 18.3.32.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.366 style:text-line-through-type

The `style:text-line-through-type` attribute specifies whether text is lined through, and if so, whether a single or double line will be used.

The defined values for the `style:text-line-through-type` attribute are:

- `double`: a double line should be used for a line-through text.
- `none`: deprecated.
- `single`: a single line should be used for a line-through text.

Every occurrence of the `style:text-line-through-type` attribute should be accompanied by an occurrence of the `style:text-line-through-style` attribute on the same element. There should not be an occurrence of the `style:text-line-through-type` attribute if the value of the `style:text-line-through-style` attribute is `none`.

The `style:text-line-through-type` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-line-through-type` attribute are `none`, `single` or `double`.

20.367 style:text-line-through-width

The `style:text-line-through-width` attribute specifies the width of a line-through line. The value `bold` specifies a line width that is calculated from the font sizes like an `auto` width, but is wider than an `auto` width.

The defined values for the `style:text-line-through-width` attribute are:

- `auto`: the width of a line-through should be calculated from the font size of the text where the line-through will appear.
- `bold`: the width of a line-through should be calculated from the font size of the text where the line-through will appear but is wider than for the value of `auto`.
- a value of type `percent` 18.3.23
- a value of type `positiveInteger` 18.2
- a value of type `positiveLength` 18.3.26

The line-through text styles referenced by the values `dash`, `medium`, `thick` and `thin`, are implementation-defined. Thin shall be smaller width than medium and medium shall be a smaller width than thick.

The `style:text-line-through-width` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-line-through-width` attribute are `auto`, `normal`, `bold`, `thin`, `medium`, `thick`, a value of type `positiveInteger` 18.2, a value of type `percent` 18.3.23 or a value of type `positiveLength` 18.3.26.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.368 style:text-outline

The `style:text-outline` attribute specifies whether to display an outline of text or the text itself.

The defined values for the `style:text-outline` attribute are:

- `false`: text itself should be displayed.
- `true`: outline of text should be displayed.

The `style:text-outline` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:text-outline` attribute has the data type `boolean` 18.3.3.

20.369 style:text-overline-color

The `style:text-overline-color` attribute specifies a color that is used to overline text.

The defined values for the `style:text-overline-color` attribute are:

- `font-color`: the current text color is used for overlining.
- a value of type `color`

The `style:text-overline-color` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-overline-color` attribute are `font-color` or a value of type `color` 18.3.9.

20.370 style:text-overline-mode

The `style:text-overline-mode` attribute specifies whether overlining is applied to words only or to portions of text.

The defined values for the `style:text-line-through-mode` attribute are:

- `continuous`: overlining is applied to words and separating spaces.
- `skip-white-space`: overlining is not applied to spaces between words.

The `style:text-overline-mode` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-overline-mode` attribute are `continuous` or `skip-white-space`.

20.371 style:text-overline-style

The `style:text-overline-style` attribute specifies a style for rendering a line over text.

The defined values for the `style:text-overline-style` attribute are:

- `none`: text has no overlining.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `dash`: text has a dashed line overlining it.
- `dot-dash`: text has a line whose repeating pattern is a dot followed by a dash overlining it.
- `dot-dot-dash`: text has a line whose repeating pattern is two dots followed by a dash overlining it.
- `dotted`: text has a dotted line overlining it.
- `long-dash`: text has a dashed line whose dashes are longer than the ones from the dashed line for value dash overlining it.
- `solid`: text has a solid line overlining it.
- `wave`: text has a wavy line overlining it.

Note: The definitions of the values of the `style:text-overline-style` attribute are based on the text decoration style 'text-overline-style' from [CSS3Text], §9.2.

The `style:text-overline-style` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-overline-style` attribute are `none`, `solid`, `dotted`, `dash`, `long-dash`, `dot-dash`, `dot-dot-dash` or `wave`.

20.372 style:text-overline-type

The `style:text-overline-type` attribute specifies the type of overlining applied to a text.

The defined values for the `style:text-overline-type` attribute are:

- `double`: a double line should be used for overlining text.
- `none`: deprecated.
- `single`: a single line should be used for overlining text.

Every occurrence of the `style:text-overline-type` attribute should be accompanied by an occurrence of the `style:text-overline-style` attribute on the same element. There should not be an occurrence of the `style:text-overline-type` attribute if the value of the `style:text-overline-style` attribute is `none`.

The `style:text-overline-type` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-overline-type` attribute are `none`, `single` or `double`.

20.373 style:text-overline-width

The `style:text-overline-width` attribute specifies the width of an overline. The value `bold` specifies a line width that is calculated from the font sizes like an `auto` width, but is wider than an `auto` width.

The defined values for the `style:text-overline-width` attribute are:

- `auto`: the width of an overline should be calculated from the font size of the text where the overline will appear.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `bold`: the width of an overline should be calculated from the font size of the text where the overline will appear but is wider than for the value of `auto`.
- a value of type `percent` 18.3.23
- a value of type `positiveInteger` 18.2
- a value of type `positiveLength` 18.3.26

The overline text styles referenced by the values `dash`, `medium`, `thick` and `thin`, are implementation-defined. Thin shall be smaller width than medium and medium shall be a smaller width than thick.

The `style:text-overline-width` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-overline-width` attribute are `auto`, `normal`, `bold`, `thin`, `medium`, `thick`, a value of type `positiveInteger` 18.2, a value of type `percent` 18.3.23 or a value of type `positiveLength` 18.3.26.

20.374 style:text-position

The `style:text-position` attribute specifies whether text is positioned above or below the baseline and to specify the relative font height that is used for this text.

This attribute can have one or two values.

The first value shall be present and specifies the vertical text position as a percentage of the current font height or it takes one of the values `sub` or `super`. Negative percentages or the `sub` value place the text below the baseline. Positive percentages or the `super` value place the text above the baseline. If `sub` or `super` is specified, the consumer chooses an appropriate text position.

The second value may be present and specifies the font height as a percentage of the current font-height. If this value is not specified, an appropriate font height is used.

The `style:text-position` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:text-position` attribute has one or two white space separated values. The first values is of type `percent` 18.3.23, or is one of: `super` or `sub`. The second value is of type `percent` 18.3.23.

20.375 style:text-rotation-angle

The `style:text-rotation-angle` attribute specifies an angle to which text is rotated. The value of this attribute can be any integer, which specifies the rotation angle in degrees, or an angle as specified in `angle`. 18.3.1

If more than one character is selected, the entire selection is rotated as a block.

The `style:text-rotation-angle` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:text-rotation-angle` attribute has the data type `angle` 18.3.1.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.376 style:text-rotation-scale

The `style:text-rotation-scale` attribute specifies whether for rotated text the width of the text should be scaled to fit into the current line height or the width of the text should remain fixed, therefore changing the current line height.

The defined values for the `style:text-rotation-scale` attribute are:

- `fixed`: width of text should remain fixed.
- `line-height`: width of text should be scaled to fit the current line height.

The `style:text-rotation-scale` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-rotation-scale` attribute are `fixed` or `line-height`.

20.377 style:text-scale

The `style:text-scale` attribute specifies whether to decrease or increase the width of text by scaling the font width.

The `style:text-scale` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:text-scale` attribute has the data type `percent` 18.3.23.

20.378 style:text-underline-color

The `style:text-underline-color` attribute specifies a color that is used to underline text. The value of this attribute is either `font-color` or a color.

The defined values for the `style:text-underline-color` attribute are:

- `font-color`: the current text color is used for underlining.
- a value of type `color`: the color to be used for underlining.

The `style:text-underline-color` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-underline-color` attribute are `font-color` or a value of type `color` 18.3.9.

20.379 style:text-underline-mode

The `style:text-underline-mode` attribute specifies whether underlining is applied to words only or to portions of text. If underlining is applied to text portions, the spaces between words and the words are underlined.

The defined values for the `style:text-underline-mode` attribute are:

- `continuous`: underlining is applied to words and separating spaces.
- `skip-white-space`: underlining is not applied to spaces between words.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `style:text-underline-mode` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-underline-mode` attribute are `continuous` or `skip-white-space`.

20.380 style:text-underline-style

The `style:text-underline-style` attribute specifies a style for underlining text.

The defined values for the `style:text-underline-style` attribute are:

- `none`: text has no underlining.
- `dash`: text has a dashed line underlining it.
- `dot-dash`: text has a line whose repeating pattern is a dot followed by a dash underlining it.
- `dot-dot-dash`: text has a line whose repeating pattern is two dots followed by a dash underlining it.
- `dotted`: text has a dotted line underlining it.
- `long-dash`: text has a dashed line whose dashes are longer than the ones from the dashed line for value dash underlining it.
- `solid`: text has a solid line underlining it.
- `wave`: text has a wavy line underlining it.

Note: The definitions of the values of the `style:text-underline-style` attribute are based on the text decoration style 'text-underline-style' from [CSS3Text], §9.2.

The `style:text-underline-style` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `style:text-underline-style` attribute are `none`, `solid`, `dotted`, `dash`, `long-dash`, `dot-dash`, `dot-dot-dash` or `wave`.

20.381 style:text-underline-type

The `style:text-underline-type` attribute specifies the type of underlining applied to a text.

The defined values for the `style:text-underline-type` attribute are:

- `double`: a double line should be used for underlining applied to a text.
- `none`: deprecated.
- `single`: a single line should be used for underlining applied to a text.

Every occurrence of the `style:text-underline-type` attribute should be accompanied by an occurrence of the `style:text-underline-style` attribute on the same element. There should not be an occurrence of the `style:text-underline-type` attribute if the value of the `style:text-underline-style` attribute is `none`.

The `style:text-underline-type` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The values of the style:text-underline-type attribute are none, single or double.

20.382 style:text-underline-width

The style:text-underline-width attribute specifies the width of an underline. The value bold specifies a line width that is calculated from the font sizes like an auto width, but is wider than an auto width.

The defined values for the style:text-underline-width attribute are:

- auto: the width of an underline should be calculated from the font size of the text where the underline will appear.
- bold: the width of an underline should be calculated from the font size of the text where the underline will appear but is wider than for the value of auto.
- a value of type percent 18.3.23.
- a value of type positiveInteger 18.2.
- a value of type positiveLength 18.3.26.

The underline text styles referenced by the values dash, medium, thick and thin, are implementation-defined. Thin shall be smaller width than medium and medium shall be a smaller width than thick.

The style:text-underline-width attribute is usable with the following element: <style:text-properties> 16.27.28.

The values of the style:text-underline-width attribute are auto, normal, bold, thin, medium, thick, a value of type positiveInteger 18.2, a value of type percent 18.3.23 or a value of type positiveLength 18.3.26.

20.383 style:use-optimal-column-width

The style:use-optimal-column-width attribute specifies that a column width should be recalculated automatically if content in the column changes.

The defined values for the style:use-optimal-column-width attribute are:

- false: column width should not be recalculated automatically if content in the column changes.
- true: column width should be recalculated automatically if content in the column changes.

The style:use-optimal-column-width attribute is usable with the following element: <style:table-column-properties> 17.16.

The style:use-optimal-column-width attribute has the data type boolean 18.3.3.

20.384 style:use-optimal-row-height

The style:use-optimal-row-height attribute specifies that a row height should be recalculated automatically if content in the row changes.

The defined values for the style:use-optimal-row-height attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `false`: row height should not be recalculated automatically if content in the row changes.
- `true`: row height should be recalculated automatically if content in the row changes.

The `style:use-optimal-row-height` attribute is usable with the following element: `<style:table-row-properties>` 17.17.

The `style:use-optimal-row-height` attribute has the data type `boolean` 18.3.3.

20.385 style:use-window-font-color

The `style:use-window-font-color` attribute specifies whether the window foreground color should be used as the foreground color for a light background color and white for a dark background color. The determination of light or dark color is implementation-defined.

The defined values for the `style:use-window-font-color` attribute are:

- `false`: the foreground color is specified by the `fo:color` attribute.
- `true`: windows foreground color should be used as the foreground color for a light background color and white for a dark background color.

The `style:use-window-font-color` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The `style:use-window-font-color` attribute has the data type `boolean` 18.3.3.

20.386 style:vertical-align

20.386.1 <style:paragraph-properties>

The `style:vertical-align` attribute specifies the vertical position of a character. By default characters are aligned according to their baseline.

The defined values for the `style:vertical-align` attribute are:

- `auto`: automatically, which sets the vertical alignment to suit the text rotation. Text that is rotated 0 or 90 degrees is aligned to the baseline, while text that is rotated 270 degrees is aligned to the center of the line.
- `baseline`: to the baseline of the character.
- `bottom`: to the bottom of the line.
- `middle`: to the center of the line.
- `top`: to the top of the line.

The `style:vertical-align` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The values of the `style:vertical-align` attribute are `top`, `middle`, `bottom`, `auto` or `baseline`.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.386.2 <style:table-cell-properties>

The `style:vertical-align` attribute specifies the vertical alignment of text in a table cell. The options for the vertical alignment attribute are as follows:

The defined values for the `style:vertical-align` attribute are:

- `automatic`: consumer determines how to align the text.
- `bottom`: aligns text vertically with the bottom of the cell.
- `middle`: aligns text vertically with the middle of the cell.
- `top`: aligns text vertically with the top of the cell.

The `style:vertical-align` attribute is usable with the following element: `<style:table-cell-properties>` 17.18.

The values of the `style:vertical-align` attribute are `top`, `middle`, `bottom` or `automatic`.

20.387 style:vertical-pos

The `style:vertical-pos` attribute specifies the vertical alignment of a frame relative to a specific area.

The defined values for the `style:vertical-pos` attribute are:

- `below`: the top corner of the frame is positioned below the reference area.
- `bottom`: the bottom of the frame is aligned with the reference area.
- `from-top`: the `svg:y` attribute associated with the frame element specifies the vertical position of the frame. Otherwise, the `svg:y` attribute is ignored for text documents.
- `middle`: the middle of the frame is aligned with the reference area.
- `top`: the top of the frame is aligned with the reference area.

The `style:vertical-pos` attribute is usable with the following elements: `<style:graphic-properties>` 17.21 and `<style:list-level-properties>` 17.19.

The values of the `style:vertical-pos` attribute are `top`, `middle`, `bottom`, `from-top` or `below`.

20.388 style:vertical-rel

The `style:vertical-rel` attribute specifies the area against which the vertical position of a frame is positioned.

The defined values for the `style:vertical-rel` attribute are:

`baseline`: vertical position of frame positioned relative to a baseline.

`char`: vertical position of frame positioned relative to a character.

`frame`: vertical position of frame positioned relative to a frame.

`frame-content`: vertical position of frame positioned relative to frame content.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

`line`: vertical position of frame positioned relative to a line.

`page`: vertical position of frame positioned relative to a page.

`page-content`: vertical position of frame positioned relative to page content.

`paragraph`: vertical position of frame positioned relative to a paragraph.

`paragraph-content`: vertical position of frame positioned relative to paragraph content.

`text`: vertical position of frame positioned relative to text.

Table 21 displays the defined values of `style:vertical-rel` and `text:anchor-type` attributes. Value combinations that can appear in a document are marked with an X.

Table 21 - Vertical Relation Values

Value of `style:vertical-rel`	***Value of `text:anchor-type`***				
	`page`	***`frame`***	***`paragraph`***	***`char`***	***`as-char`***
`baseline`					X
`char`				X	X
`frame`		X			
`frame-content`		X			
`line`					X
`page`	X		X	X	
`page-content`	X		X	X	
`paragraph`			X	X	
`paragraph-content`			X	X	
`text`					X

The `style:vertical-rel` attribute is usable with the following elements: `<style:graphic-properties>` 17.21 and `<style:list-level-properties>` 17.19.

The values of the `style:vertical-rel` attribute are `page`, `page-content`, `frame`, `frame-content`, `paragraph`, `paragraph-content`, `char`, `line`, `baseline` or `text`.

20.389 style:width

The `style:width` attribute specifies the fixed width of a table. Every table shall have a fixed width.

The `style:width` attribute is usable with the following element: `<style:table-properties>` 17.15.

The `style:width` attribute has the data type `positiveLength` 18.3.26.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.390 style:wrap

The `style:wrap` attribute specifies how text is displayed around a frame or graphic object.

The defined values for the `style:wrap` attribute are:

- `biggest`: text may wrap around the shape where the difference to the left or right page or column border is largest.
- `dynamic`: text may wrap around both sides of the shape. The space for wrapping is set by the `style:wrap-dynamic-threshold` attribute. 20.393
- `left`: text wraps around the left side of the shape.
- `none`: text does not wrap around the shape.
- `parallel`: text wraps around both sides of the shape.
- `right`: text wraps around the right side of the shape.
- `run-through`: text runs through the shape.

The `style:wrap` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `style:wrap` attribute are `none`, `left`, `right`, `parallel`, `dynamic`, `run-through` or `biggest`.

20.391 style:wrap-contour

The `style:wrap-contour` attribute specifies whether text wraps around an object or the bounding box of the object.

The defined values for the `style:wrap-contour` attribute are:

- `false`: text wraps around the bounding box.
- `true`: text wraps around the object.

This is called contour wrapping.

The `style:wrap-contour` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `style:wrap-contour` attribute has the data type `boolean` 18.3.3.

20.392 style:wrap-contour-mode

The `style:wrap-contour-mode` attribute specifies the nature of the wrapping of text around the contour of a shape.

This attribute shall be evaluated only by frames/drawing shapes or styles with non-empty `style:wrap` and `style:wrap-contour` attributes.

The defined values for the `style:wrap-contour-mode` attribute are:

- `full`: text wraps around the shape and fills any spaces and indentations in the shape.
- `outside`: text wraps around the general area to the left and right of the shape.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The style:wrap-contour-mode attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the style:wrap-contour-mode attribute are full or outside.

20.393 style:wrap-dynamic-threshold

The style:wrap-dynamic-threshold attribute specifies the minimum distance between the page or column border and the object for which wrapping will be enabled. It is evaluated only if a style:wrap attribute, with the value dynamic, appears on the same <style:graphic-properties> element.

The style:wrap-dynamic-threshold attribute is usable with the following element: <style:graphic-properties> 17.21.

The style:wrap-dynamic-threshold attribute has the data type nonNegativeLength 18.3.20.

20.394 style:writing-mode

20.394.1 General

The style:writing-mode attribute specifies a writing mode for an element.

20.394.2 <style:graphic-properties>

See §7.27.7 of [XSL] with the additional value of page.

The defined value of style:writing-mode attribute is page: writing mode is inherited from the page that contains the element where this attribute appears.

The style:writing-mode attribute is usable with the following element: <style:graphic-properties> 17.21.

The values of the style:writing-mode attribute are lr-tb, rl-tb, tb-rl, tb-lr, lr, rl, tb or page.

20.394.3 <style:page-layout-properties>

See §7.27.7 of [XSL].

The defined value for the style:writing-mode attribute is page: writing mode is inherited from the page that contains the element where this attribute appears.

The style:writing-mode attribute is usable with the following element: <style:page-layout-properties> 17.2.

The values of the style:writing-mode attribute are lr-tb, rl-tb, tb-rl, tb-lr, lr, rl, tb or page.

20.394.4 <style:paragraph-properties>

See §7.27.7 of [XSL] with the additional value of page.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined value for the `style:writing-mode` attribute is `page`: writing mode is inherited from the page that contains the element where this attribute appears.

The `style:writing-mode` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The values of the `style:writing-mode` attribute are `lr-tb`, `rl-tb`, `tb-rl`, `tb-lr`, `lr`, `rl`, `tb` or `page`.

20.394.5 <style:section-properties>

See §7.27.7 of [XSL] with the additional value of `page`.

The defined value for the `style:writing-mode` attribute is `page`: writing mode is inherited from the page that contains the element where this attribute appears.

The `style:writing-mode` attribute is usable with the following element: `<style:section-properties>` 17.11.

The values of the `style:writing-mode` attribute are `lr-tb`, `rl-tb`, `tb-rl`, `tb-lr`, `lr`, `rl`, `tb` or `page`.

20.394.6 <style:table-cell-properties>

See §7.27.7 of [XSL] with the additional value of `page`.

The defined value for the `style:writing-mode` attribute is `page`: writing mode is inherited from the page that contains the element where this attribute appears.

The `style:writing-mode` attribute is usable with the following element: `<style:table-cell-properties>` 17.18.

The values of the `style:writing-mode` attribute are `lr-tb`, `rl-tb`, `tb-rl`, `tb-lr`, `lr`, `rl`, `tb` or `page`.

20.394.7 <style:table-properties>

See §7.27.7 of [XSL] with the additional value of `page`.

The defined value for the `style:writing-mode` attribute is `page`: writing mode is inherited from the page that contains the element where this attribute appears.

The `style:writing-mode` attribute is usable with the following element: `<style:table-properties>` 17.15.

The values of the `style:writing-mode` attribute are `lr-tb`, `rl-tb`, `tb-rl`, `tb-lr`, `lr`, `rl`, `tb` or `page`.

20.395 style:writing-mode-automatic

The `style:writing-mode-automatic` attribute specifies whether a consumer may recalculate the writing mode of a paragraph based on its content whenever the content is edited.

The writing-mode should be specified in a `style:writing-mode` attribute.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If the fo:text-align with value start, text alignment can be adapted to the writing mode.

The defined values for the style:writing-mode-automatic attribute are:

- false: consumers should not recalculate writing mode of a paragraph whenever its content is edited.
- true: consumers should recalculate writing mode of a paragraph whenever its content is edited.

The style:writing-mode-automatic attribute is usable with the following element: <style:paragraph-properties> 17.6.

The style:writing-mode-automatic attribute has the data type boolean 18.3.3.

20.396 svg:fill-rule

See §11.3 of [SVG].

OpenDocument does not support the value inherit.

The svg:fill-rule attribute is usable with the following elements: <style:drawing-page-properties> 17.25 and <style:graphic-properties> 17.21.

The values of the svg:fill-rule attribute are nonzero or evenodd.

20.397 svg:height

20.397.1 <style:graphic-properties>

The svg:height attribute specifies a default height for new frames that are created using the graphics style. See 19.539.

The svg:height attribute is usable with the following element: <style:graphic-properties> 17.21.

The svg:height attribute has the data type length 18.3.18.

20.397.2 <style:header-footer-properties>

The svg:height attribute specifies the height of an header or footer.

The svg:height attribute is usable with the following element: <style:header-footer-properties> 17.5.

The svg:height attribute has the data type length 18.3.18.

20.398 svg:stroke-color

The svg:stroke-color attribute specifies the color of a stroke.

The svg:stroke-color attribute is usable with the following element: <style:graphic-properties> 17.21.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `svg:stroke-color` attribute has the data type `color` 18.3.9.

20.399 svg:stroke-opacity

The `svg:stroke-opacity` attribute specifies the opacity of a stroke. The value of this attribute can be a number between 0 (fully transparent) and 1 (fully opaque) or a percentage value in the range 0% to 100%.

The `svg:stroke-opacity` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `svg:stroke-opacity` attribute are a value of type `double` 18.2 in the range [`0`,`1`] or a value of type `zeroToHundredPercent` 18.3.41.

20.400 svg:stroke-width

The `svg:stroke-width` attribute specifies the width of a stroke.

The `svg:stroke-width` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `svg:stroke-width` attribute has the data type `length` 18.3.18.

20.401 svg:x

The `svg:x` attribute specifies a default horizontal position for new frames that are created using the graphics style. See 19.573.

The `svg:x` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `svg:x` attribute has the data type `coordinate` 18.3.10.

20.402 svg:y

20.402.1 <style:graphic-properties>

The `svg:y` attribute specifies a default vertical position for new frames that are created using the graphics style. See 19.577.

The `svg:y` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `svg:y` attribute has the data type `coordinate` 18.3.10.

20.402.2 <style:list-level-properties>

The `svg:y` attribute specifies the vertical position of a bullet image.

The `svg:y` attribute is usable with the following element: `<style:list-level-properties>` 17.19.

The `svg:y` attribute has the data type `coordinate` 18.3.10.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.403 svg:width

The `svg:width` attribute specifies a default width for new frames that are created using the graphics style. See 19.571.

The `svg:width` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `svg:width` attribute has the data type `length` 18.3.18.

20.404 table:align

The `table:align` attribute specifies the horizontal alignment of a table.

The defined values for the `table:align` attribute are:

- `center`: table aligns to the center between left and right margins.
- `left`: table aligns to the left margin.
- `margins`: table fills all the space between the left and right margins.
- `right`: table aligns to the right margin.

Consumers that do not support the `margins` value, may treat this value as left.

The `table:align` attribute is usable with the following element: `<style:table-properties>` 17.15.

The values of the `table:align` attribute are `left`, `center`, `right` or `margins`.

20.405 table:border-model

The `table:border-model` attribute specifies what border model to use when creating a table with a border.

The defined values for the `table:border-model` attribute are:

- `collapsing`: when two adjacent cells have different borders, the wider border appears as the border between the cells. Each cell receives half of the width of the border.
- `separating`: borders appear within the cell that specifies the border.

In OpenDocument, a row height or column width includes any space required to display borders or padding. This means that, while the width and height of the content area is less than the column width and row height, the sum of the widths of all columns is equal to the total width of the table.

The `table:border-model` attribute is usable with the following element: `<style:table-properties>` 17.15.

The values of the `table:border-model` attribute are `collapsing` or `separating`.

20.406 table:display

The `table:display` attribute specifies whether a table is displayed.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The defined values for the `table:display` attribute are:

- `false`: table should not be displayed.
- `true`: table should be displayed.

The `table:display` attribute is usable with the following element: `<style:table-properties>` 17.15.

The `table:display` attribute has the data type `boolean` 18.3.3.

20.407 text:anchor-page-number

The `text:anchor-page-number` attribute specifies the physical page number of an anchor if the drawing object is bound to a page within a text document.

The `text:anchor-page-number` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `text:anchor-page-number` attribute has the data type `positiveInteger` 18.2.

20.408 text:anchor-type

The `text:anchor-type` attribute specifies how a frame is bound to a text document. The anchor position is the point at which a frame is bound to a text document.

The defined values for the `text:anchor-type` attribute are shown in Table 22.

Table 22 - Text anchor positions

If the value of the `text:anchor-type` attribute is ...	***The anchor position is...***	***The drawing shape element appears ...***	***Notes***
`as-char`	There is no anchor position. The drawing shape behaves like a character.	At the position where the character appears in the document.	
`char`	The character after the drawing shape element.	Just before the character.	
`frame`	The parent text box that the current drawing shape element is contained in.	In the element representing the text box to which the drawing object is bound. If an image is bound to a text box, the image element is located in the text box element.	
`page`	The page that has the same physical page number as the value of the `text:anchor-page-`	Either - At the start of the document body,	The physical page number is the number assigned to the page if all

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

If the value of the `text:anchor-type` attribute is ...	*The anchor position is...*	*The drawing shape element appears ...*	*Notes*
	`number` attribute that is attached to the drawing shape element. If no `text:anchor-page-number` attribute is given, the anchor position is the page at which the character behind the drawing object element appears.	outside any paragraph or frame, provided a `text:anchor-page-number` attribute is given. Or ● Inside any paragraph element that is not contained in a header, footer, footnote, or text box, if a `text:anchor-page-number` attribute is not given.	pages in the document are counted starting with page 1.
`paragraph`	The paragraph that the current drawing shape element is contained in.	At the start of the paragraph element.	

The `text:anchor-type` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `text:anchor-type` attribute are `page`, `frame`, `paragraph`, `char` or `as-char`.

20.409 text:animation

The `text:animation` attribute specifies the type of animation that is used for a text.

The defined values for the `text:animation` attribute are:

- `alternate`: scrolls the text from one side to another and back.
- `none`: disables the text animation.
- `scroll`: scrolls the text from one side to another.
- `slide`: scrolls the text from one side to the original text position and stops there.

The `text:animation` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `text:animation` attribute are `none`, `scroll`, `alternate` or `slide`.

20.410 text:animation-delay

The `text:animation-delay` attribute specifies a delay before an animation is started.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:animation-delay` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `text:animation-delay` attribute has the data type `duration` 18.2.

20.411 text:animation-direction

The `text:animation-direction` attribute specifies the scroll direction of animated text.

The defined values for the `text:animation-direction` attribute are:

- `down`: animated text scrolls down.
- `left`: animated text scrolls left.
- `right`: animated text scrolls right.
- `up`: animated text scrolls up.

The `text:animation-direction` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The values of the `text:animation-direction` attribute are `left`, `right`, `up` or `down`.

20.412 text:animation-repeat

The `text:animation-repeat` attribute specifies the number of times an animation is repeated. If the value of the attribute is `0`, the animation is repeated indefinitely.

The `text:animation-repeat` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `text:animation-repeat` attribute has the data type `nonNegativeInteger` 18.2.

20.413 text:animation-start-inside

The `text:animation-start-inside` attribute specifies if a text animation starts inside or outside a shape.

The defined values for the `text:animation-start-inside` attribute are:

- `false`: text starts its animation just outside the shape's bounding rectangle.
- `true`: text starts its animation inside the shape.

The `text:animation-start-inside` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `text:animation-start-inside` attribute has the data type `boolean` 18.3.3.

20.414 text:animation-steps

The `text:animation-steps` attribute specifies the distance by which text is moved within a scrolling step.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The `text:animation-steps` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `text:animation-steps` attribute has the data type `length` 18.3.18.

20.415 text:animation-stop-inside

The `text:animation-stop-inside` attribute specifies if a text animation stops inside or outside a shape.

The defined values for the `text:animation-stop-inside` attribute are:

- `false`: text stops its animation outside the shape's bounding rectangle.
- `true`: text stops its animation when it is inside the shape.

The `text:animation-stop-inside` attribute is usable with the following element: `<style:graphic-properties>` 17.21.

The `text:animation-stop-inside` attribute has the data type `boolean` 18.3.3.

20.416 text:condition

The `text:condition` attribute specifies the display of text.

The defined value of the `text:condition` attribute is `none`, which means text is hidden.

The `text:condition` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The only value of the `text:condition` attribute is `none`.

20.417 text:display

The `text:display` attribute specifies whether text is hidden.

The defined values for the `text:display` attribute are:

- `condition`: text is hidden under the condition specified in the `text:condition` attribute.
- `none`: text is hidden unconditionally.
- `true`: text is displayed. This is the default setting.

The `text:display` attribute is usable with the following element: `<style:text-properties>` 16.27.28.

The values of the `text:display` attribute are `true`, `none` or `condition`.

20.418 text:dont-balance-text-columns

The `text:dont-balance-text-columns` attribute specifies whether the text column content should be evenly distributed over all text columns or not.

The defined values for the `text:dont-balance-text-columns` attribute are:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- `false`: text column content should not be evenly distributed over all text columns in a set of columns.
- `true`: text column content should be evenly distributed over all text columns in a set of columns.

The `text:dont-balance-text-columns` attribute is usable with the following element: `<style:section-properties>` 17.11.

The `text:dont-balance-text-columns` attribute has the data type `boolean` 18.3.3.

20.419 text:line-break

The `text:line-break` attribute specifies whether word wrapping is allowed for axis labels.

This attribute is evaluated for a chart style that is applied to a `<chart:axis>` element.

The defined values for the `text:line-break` attribute are:

- `false`: word wrapping should not be allowed for axis labels.
- `true`: word wrapping should be allowed for axis labels.

The `text:line-break` attribute is usable with the following element: `<style:chart-properties>` 17.22.

The `text:line-break` attribute has the data type `boolean` 18.3.3.

20.420 text:line-number

The `text:line-number` attribute specifies a new start value for line numbering, if a `text:number-lines` attribute, with the value `true`, appears on the same `<style:paragraph-properties>` element. Otherwise, this attribute shall be ignored.

The `text:line-number` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The `text:line-number` attribute has the data type `nonNegativeInteger` 18.2.

20.421 text:list-level-position-and-space-mode

The `text:list-level-position-and-space-mode` attribute specifies how the position and spacing of the list labels (numbers or bullets) is defined.

The defined values for the `text:list-level-position-and-space-mode` attribute are:

- `label-alignment`: The `<style:list-level-label-alignment>` element and the `fo:text-align` attribute are used to define the position and spacing of the list label and the list item. The values of the attributes for `text:space-before`, `text:min-label-width` and `text:min-label-distance` are assumed to be `0`.
- `label-width-and-position`: The `text:space-before`, `text:min-label-width`, `text:min-label-distance` and `fo:text-align` attributes are used to define the position and spacing of the list label and the list item.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

The default value of the text:list-level-position-and-space-mode attribute is label-width-and-position.

The text:list-level-position-and-space-mode attribute is usable with the following element: <style:list-level-properties> 17.19.

The values of the text:list-level-position-and-space-mode attribute are label-width-and-position or label-alignment.

20.422 text:min-label-distance

The text:min-label-distance attribute specifies the minimum distance between a number and a list item.

The content of a list label is rendered inside a specified minimum width - text:min-label-width. 20.423 The text of a list item is rendered following the label width area. If the distance between a list label and the text of a list item is smaller than the value of the text:min-label-distance attribute, the following actions are performed. First, the content of the list label is moved inside the specified minimum label width up to the value of the text:min-label-distance attribute. If that does not result in a value equal to the text:min-label-distance attribute, the text of the list item is moved until the distance between the list label and text of list item equals the value of the text:min-label-distance attribute.

This attribute can be associated with an formatting properties element that is contained in a <text:list-level-style-*> element.

The attribute will be evaluated only if the text:list-level-position-and-space-mode attribute has the value label-width-and-position or is not present.

The text:min-label-distance attribute is usable with the following element: <style:list-level-properties> 17.19.

The text:min-label-distance attribute has the data type nonNegativeLength 18.3.20.

20.423 text:min-label-width

The text:min-label-width attribute specifies the minimum width of a list label.

This attribute can be associated with an formatting properties element that is contained in a <text:list-level-style-*> element.

The list label can be aligned horizontally within the specified minimum width using the fo:text-align attribute. If the the actual width of the list label is greater than the specified minimum width no alignment takes place.

The attribute will be evaluated only if the text:list-level-position-and-space-mode attribute has the value label-width-and-position or is not present.

The text:min-label-width attribute is usable with the following element: <style:list-level-properties> 17.19.

The text:min-label-width attribute has the data type nonNegativeLength 18.3.20.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

20.424 text:number-lines

The `text:number-lines` attribute specifies whether lines are numbered.

The defined values for the `text:number-lines` attribute are:

- `false`: lines should not be numbered.
- `true`: lines should be numbered.

The `text:number-lines` attribute is usable with the following element: `<style:paragraph-properties>` 17.6.

The `text:number-lines` attribute has the data type `boolean` 18.3.3.

20.425 text:space-before

The `text:space-before` attribute specifies the space to include before a number for all paragraphs at a specified level. If a paragraph has a left margin greater than 0, the position of the list label box is the left margin width plus the start indent value.

This attribute can be associated with a formatting properties element that is contained in a `<text:list-level-style-*>` element.

This attribute is evaluated only if the `text:list-level-position-and-space-mode` attribute has the value `label-width-and-position` or is not present.

The `text:space-before` attribute is usable with the following element: `<style:list-level-properties>` 17.19.

The `text:space-before` attribute has the data type `length` 18.3.18.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Appendix A. OpenDocument Relax NG Schema

The OpenDocument Relax-NG (see [RNG]) schema is defined by a separate document, whose location can be found in the Related Work section on the introductory pages.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Appendix B. OpenDocument Metadata Manifest Ontology

The OpenDocument metadata manifest ontology is defined by a separate document, whose location can be found in the Related Work section on the introductory pages.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Appendix C. MIME Types and File Name Extensions (Non Normative)

The following table contains a list of MIME types and file name extensions for OpenDocument documents, that, at the time this specification is published, have been registered according to [RFC4288]. Please see [MIMETYPES] for a current list of registered MIME types.

Registered MIME types are for use with documents contained in OpenDocument packages.

Table 23 - Registered MIME types

MIME type	***Ext.***	***Description***
`application/vnd.oasis.opendocument.text`	`odt`	Text document
`application/` `vnd.oasis.opendocument.text-template`	`ott`	Text document used as template
`application/vnd.oasis.opendocument.graphics`	`odg`	Graphics document (Drawing)
`application/` `vnd.oasis.opendocument.graphics-template`	`otg`	Drawing document used as template
`application/vnd.oasis.opendocument` `.presentation`	`odp`	Presentation document
`application/` `vnd.oasis.opendocument.presentation-template`	`otp`	Presentation document used as template
`application/vnd.oasis.opendocument.spreadsheet`	`ods`	Spreadsheet document
`application/` `vnd.oasis.opendocument.spreadsheet-template`	`ots`	Spreadsheet document used as template
`application/vnd.oasis.opendocument.chart`	`odc`	Chart document
`application/` `vnd.oasis.opendocument.chart-template`	`otc`	Chart document used as template
`application/vnd.oasis.opendocument.image`	`odi`	Image document
`application/` `vnd.oasis.opendocument.image-template`	`oti`	Image document used as template
`application/vnd.oasis.opendocument.formula`	`odf`	Formula document
`application/` `vnd.oasis.opendocument.formula-template`	`otf`	Formula document used as template
`application/vnd.oasis.opendocument.text-master`	`odm`	Global Text document. See section 19.806.
`application/vnd.oasis.opendocument.text-web`	`oth`	Text document used as template for HTML documents

The following table contains a list of MIME types and file name extensions for office documents that conform to this specification where a registration according to [RFC4288] is in progress at the time this specification is published.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Please check [MIMETYPES] before using these MIME types. If a MIME type is not listed there, the MIME type that is the result of inserting "`x-`" behind the "/" (U+002F, SOLIDUS) character (`application/x-vnd.oasis.opendocument.text`) should be used.

Table 24 - Recommended MIME types

MIME type	***Ext.***	***Description***
`application/vnd.oasis.opendocument.base`	`odb`	Database front end document

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Appendix D. Accessibility Guidelines (Non Normative)

D.1. Title, Description and Caption of Graphical Elements

OpenDocument provides conventions to support accessible names, descriptions and captions for graphical elements.

Accessible names, if available, are represented by the `<svg:title>` element. 10.3.17 If the `<svg:title>` element is not available, any text referenced by a `draw:caption-id` attribute is used as the title. 19.115

When transforming from another document format to OpenDocument the short names, like HTML's alt text on the `<img>` elements shall be mapped to the `<svg:title>` element.

User agents shall not manufacture names for the `<svg:title>` element, such as using the drawing object name followed by a cardinal number in a string as it is used for accessibility. Such name assignments provide no semantic meaning to the user.

Accessible descriptions, if available, are represented by the `<svg:desc>` element. 10.3.18

If a user agent supports relationships between graphic elements and their captions, the value of the `draw:caption-id` attribute for a graphical element should be used to for that relationship. 19.115

D.1.1. Guidance for authors

Authors should not assign names to objects having no semantic value. If no name is assigned the caption text will be used in its place. The `<svg:title>` element shall take precedence over the caption text for accessible name assignment by the user agent.

Assignment of the long description should only be necessary when a drawing object is significantly complex and the user needs more information to describe it. Long descriptions would be more applicable to drawing groupings than basic drawing shapes.

D.1.2. Authoring tool responsibility for presenting and prompting for the `<svg:title>` and `<svg:desc>` elements

Authoring tools should provide an option from an objects context menu to allow the user to enter the text for either of these elements as a minimum. More proactive authoring tools should have a facility for prompting the author for this text. Since the `<svg:desc>` element is a long description, a text area vs. a text field should be used to prompt the user accordingly in GUI-based authoring tools like office applications.

Navigation tools used to list the objects in the view should provide the type of object followed by the contents of `<svg:title>` element.

For `<draw:g>` elements the drawing objects which are members of the group should visible only when the group is expanded.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

D.2. Hyperlink Titles

When transforming from another document format to OpenDocument the alt text of hyperlinks, shall be mapped to the `office:title` attribute of `<text:a>` elements (see 6.1.8) or `<draw:a>` elements. 18.3.41 When exporting OpenDocument documents to HTML, the contents of title text should be mapped to title attribute text on HTML anchor tags. As a minimum, authoring tools should provide a mechanism to provide the hint text.

The title text should be made accessible to the assistive technology and user. The user agent should allow for programmatic access through standard accessibility APIs such as the accessible description. Users should experience visible access to the hint text via the keyboard or mouse.

D.3. Tables in Presentations

Users importing non-OpenDocument slides that contain tables need access to the table structure via their assistive technology. Therefore tables imported into an OpenDocument application from another file format must have their structure preserved, and when saved as OpenDocument should be saved as as embedded spreadsheets.

D.4. Further Guidelines

Additional, non-normative Accessibility Guidelines are available at: http://docs.oasis-open.org/office/office-accessibility/guidelines. That more comprehensive document will be the up-to-date set of recommendations for what all OpenDocument applications should do in order to fully support accessibility.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Appendix E. Bidirectional (BiDi) Scripts,Numeric Digits Presentation and Calendars (Non Normative)

This appendix specifies how bidirectional (BiDi) scripts and related information are represented in OpenDocument.

E.1. Paragraph and Layout Direction

In OpenDocument, the direction of text runs inside a paragraph is calculated using the Unicode BiDi Algorithm. See [UAX9]. The paragraph direction, as required by the BiDi Algorithm (see BD5 of [UAX9]), and the display direction of layout objects like table or page columns (in the following called layout direction) is controlled by a writing mode attribute (`style:writing-mode`) that can be used within styles.

The writing mode attribute can be applied individually to paragraph styles, page styles, section styles, table styles, table cell styles, graphic styles and chart styles. If present within a paragraph style, it controls the paragraph direction of those paragraphs, to which the style is applied. If present within a page style, section style, table style, table cell style, graphic style or chart style, it controls the layout direction of those pages, text sections, tables, table cells, text-boxes and chart objects to which the styles is applied.

Section 20.394 specifies the `style:writing-mode` attribute for page styles. It may, among other values, take the values `lr-tb` (left-to-right, top-to-bottom) and `rl-tb` (right-to-left, top-to-bottom). The writing-mode attribute of a page style specifies the layout direction of page columns (left-to-right or right-to-left) for pages that are formatted using the page style.

Section 20.394 specifies the `style:writing-mode` attribute for paragraph styles. It specifies the paragraph direction as defined in BD5 of [UAX9] for all paragraphs that have the paragraph style assigned. For paragraphs that are contained in lists, it further specifies whether the list numbers and bullets are displayed on the left or on the right of the paragraph.

The writing mode attribute for paragraph styles takes the same values as the writing mode attribute for page styles, but may also take the value `page`. This value specifies that the paragraph direction is inherited from the layout direction of the closest layout object (section, table or text-box) in which the paragraph is contained, and which has a layout direction other than `page`. If the paragraph is not contained in any of these layout objects, the paragraph direction is inherited from the page on which the paragraph appears.

The paragraph direction specifies the default bidirectional orientation of the text in that paragraph. The result of the BiDi Algorithm can be manually changed by inserting BiDi embedding control characters (U+202A ... U+202E) and implicit directional marks (U+200E ...U+200F) into the text. See [UTR20].

OpenDocument further has a `style:writing-mode-automatic` attribute (described in section 20.395) that specifies that an consumer is allowed to recalculate the value of the paragraph's writing-mode attribute based on its content whenever the content changes.

Section 20.394 specifies the `style:writing-mode` attribute for section styles. It may take the same values as the writing mode attribute for paragraph styles.

The writing-mode attribute of a section style specifies the layout direction of section columns (left-to-right or right-to-left) for text sections that have the section style assigned. If the attribute value

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

is `page` the layout direction is inherited from the layout direction of the closest layout object (section, table, table-cell or text-box) in which the section is contained, and which has a layout direction other than `page`.

Section 20.394 specifies the `style:writing-mode` attribute for table styles. It may take the same values as the writing mode attribute for paragraph styles.

The writing-mode attribute of a table style specifies the layout direction of table cells (left-to-right or right-to-left) for tables that have the table style assigned. If the attribute value is `page` the layout direction is inherited from the layout direction of the closest layout object (section, table, table-cell or text-box) in which the table is contained, and which has a layout direction other than `page`.

Section 20.394 specifies the `style:writing-mode` attribute for table cell styles. It may take the same values as the writing mode attribute for paragraph styles.

The writing-mode attribute of a table cell style specifies the layout direction of table cells (left-to-right or right-to-left) that have the table style assigned. If the attribute value is `page` the layout direction is inherited from the layout direction of the closest layout object (table, section or text-box) in which the table is contained, and which has a layout direction other than `page`.

Section 20.394 specifies the `style:writing-mode` attribute for graphic styles. It may take the same values as the writing mode attribute for paragraph styles.

The writing-mode attribute of a graphic style specifies the layout direction of columns (left-to-right or right-to-left) for text-boxes that have the graphic style assigned. If the attribute value is `page` the layout direction for text-boxes that are anchored to a page is inherited from the layout direction of the page on which the text-box is displayed. For text-boxes that have a different anchor type, the layout direction is inherited from the paragraph direction of the paragraph that contains the text-box.

The writing mode for chart styles is described by the same attribute as for paragraph styles. See 20.394.

E.2. Numeric Digits Presentation and Calendars

All digits that have a Unicode code point can be included in an OpenDocument document.

Note 1: office application have a feature that allows the user to specify whether the ASCII digits U+0030 ... U+0039 should be displayed as Latin-Indic digits or as Arabic-Indic digits (U+0660 ... U+0669). Since this feature effects only what digits are displayed and does not influence the representation of digits in the document itself, OpenDocument only allows storing this setting as an implementation-dependent setting, not as document or style content.

For list numbers, that are calculated automatically, OpenDocument provides a generic mechanism to specify the applicable numbering systems. See 19.500.

Note 2: The specification currently mentions only "1, 2, 3...", "I, II, III...", and "i, ii, iii" explicitly, but the schema also allows a generic string value.

OpenDocument further supports data styles, which describe how different types of data are displayed, for example, a number or a date. Data styles are described in section 16.27. The presentation of numeric digits can be controlled by the transliteration attributes described in sections 19.361-19.364. The presentation of date information can be controlled by the `number:calendar` attribute specified in section 19.347.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Appendix F. Recommended Usage of SMIL

The following sections describe the usage of SMIL animation elements that enables an office application to present the animation elements in a simple and easy to use UI to the user. This UI may contain a single main sequence of effects, and in addition to this, multiple sequences of effects that are started as interactions on drawing shapes. An *effect* is a combination of one or more animation elements that animate a single shape and or a shape's paragraphs.

In user interfaces, effects should be creatable by using presets that have localized and meaningful names. This way, the user will not work on a hierarchy of SMIL animation elements, but on one dimensional lists of effects, which are much easier to handle for the office application users.

F.1. Slide Animation

Each `<draw:page>` element may have an `<anim:par>` element that defines the animation of that page during a running slideshow. This `<anim:par>` element should contain one `<anim:seq>` element which is the main sequence for shape effects and zero or more `<anim:seq>` elements that define interactive sequences for shapes that contain animation interactions. The animation elements are executed after the slide has executed its initial transition.

The `<anim:par>` element may further contain an `<anim:par>` element that defines the slide transition. Its `smil:begin` attribute shall have the value *`<id>`*`.begin`, where *`<id>`* is the id of the slide's `<draw:page>` element itself. This `<anim:par>` element can contain basic animation elements as defined in chapter 15. These elements shall specify the `<draw:page>` element itself as target. If such an `<anim:par>` element for slide transitions is present, it overrides the following presentation page formatting properties:

- `<presentation:sound>`. See 10.8.2.
- `presentation:transition-speed`. See 20.231.
- `presentation:transition-style`. See 20.232.
- `presentation:transition-type`. See 20.233.

For backward compatibility reasons, producers that use an `<anim:par>` element to define the slide transition should also add the above presentation page formatting properties. This also enables consumers without SMIL support to display the slide transitions.

Example: The following example defines a slide wipe transition.

```
<draw:page draw:id="id1">
    <anim:par presentation:node-type="timing-root">
        <anim:par smil:begin="id1.begin">
            <anim:transitionFilter smil:dur="2s" smil:targetElement="id1"
                smil:type="slideWipe" smil:subtype="fromBottom"
                smil:direction="reverse"/>
        </anim:par>
    </anim:par>
</draw:page>
```


Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

F.2. Main Sequence

The main sequence is a `<anim:seq>` element which contains the effects that should start after the slide has executed its initial transition. Since this is a sequential container, its child nodes are executed one after each other. If a child node's `smil:begin` attribute has the value `indefinite` execution is stalled until the user advances the slideshow by a mouse or key interaction.

The first level of child nodes in the main sequence should be `<anim:par>` elements that group animation elements that are started with the same user interaction. The second level of child nodes should be `<anim:par>` elements that group animations elements that start at the same time. The third level of child nodes should be `<anim:par>` elements that group the animation elements for a single effect.

Example: The following example shows a main sequence with the effects A, B, C and D. Effect A is started on user interaction, effect B is started simultaneously with A. Effect C is started 4 seconds after the effects A and B. Effect D is started on the next user interaction:

```
<amin:par> <!-- timing root-->
    <anim:seq> <!-- main sequence-->
        <anim:par smil:begin="indefinite">
            <!-- first user interaction -->
            <anim:par smil:begin="0s" smil:dur="4s">
                <!-- first group of effects to execute -->
                <anim:par> <!-- effect a -->
                    <!-- nodes for effect a-->
                </anim:par>
                <anim:par> <!-- effect b -->
                    <!-- nodes for effect b-->
                </anim:par>
            </anim:par>
            <anim:par smil:begin="4s">
                <!-- second group of effects to execute -->
                <anim:par> <!-- effect c -->
                    <!-- nodes for effect c-->
                </anim:par>
            </anim:par>
        </anim:par>
        <anim:par>
            <!-- second user interaction-->
            <anim:par smil:begin="indefinite">
                <!-- first group of effects to execute -->
                <anim:par> <!-- effect d -->
                    <!--- nodes for effect d-->
                </anim:par>
            </anim:par>
        </anim:par>
    </anim:seq>
</anim:par>
```

F.3. Interactive Sequence

An interactive sequence is a `<anim:seq>` element that should have the same structure as a main sequence. The only difference is that the `<anim:par>` element in the first level has a `smil:begin` attribute with a value like *`[shape-id]`*`.click`, where *`[shape-id]`* identifies a drawing shapes by its `draw:id` attribute. These animation elements are triggered when the user interacts with the element defined by *`[shape-id]`*.

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

Appendix G. Changes From Previous Specification Versions (Non Normative)

G.1. Changes from “Open Document Format for Office Applications (OpenDocument) v1.1”

The OpenDocument specification has been divided into three parts and has been restructured.

This appendix describes changes that are related to part 1 of this specification.

The following is a list of major features that have been added. For minor features please see the lists of new and changed elements and attributes.

- New conformance clauses and levels (21)
- Digital signatures (3.16)
- Enhanced charts, including a new chart type 'filled-radar' (19.15.1)
- Protection keys (19.697 and 19.850)
- Encyption algorithms for protection keys (19.698 and 19.851)
- Tables in presentations (9.1.2)
- New formatting options for lists (17.20)
- New formatting options for text grids (20.297, 20.305 and 20.306)
- Database front end documents (12.1)
- RDF based metadata (4.2)

The following elements are new:

- `<chart:data-label>` 11.14
- `<chart:equation>` 11.18
- `<chart:label-separator>` 17.24
- `<db:application-connection-settings>` 12.15
- `<db:auto-increment>` 12.10
- `<db:character-set>` 12.12
- `<db:column>` 12.35
- `<db:column-definition>` 12.40
- `<db:column-definitions>` 12.39
- `<db:columns>` 12.34
- `<db:component>` 12.25.5

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- <db:component-collection> 12.25.4
- <db:connection-data> 12.3
- <db:connection-resource> 12.7
- <db:database-description> 12.4
- <db:data-source> 12.2
- <db:data-source-setting> 12.23
- <db:data-source-settings> 12.22
- <db:data-source-setting-value> 12.24
- <db:delimiter> 12.11
- <db:driver-settings> 12.9
- <db:file-based-database> 12.5
- <db:filter-statement> 12.30
- <db:forms> 12.25.2
- <db:index> 12.46
- <db:index-column> 12.48
- <db:index-columns> 12.47
- <db:indices> 12.45
- <db:key> 12.42
- <db:key-column> 12.44
- <db:key-columns> 12.43
- <db:keys> 12.41
- <db:login> 12.8
- <db:order-statement> 12.29
- <db:queries> 12.26
- <db:query> 12.28
- <db:query-collection> 12.27
- <db:reports> 12.25.3
- <db:schema-definition> 12.36
- <db:server-database> 12.6
- <db:table-definition> 12.38
- <db:table-definitions> 12.37
- <db:table-exclude-filter> 12.18

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- <db:table-filter> 12.16
- <db:table-filter-pattern> 12.19
- <db:table-include-filter> 12.17
- <db:table-representation> 12.33
- <db:table-representations> 12.32
- <db:table-setting> 12.14
- <db:table-settings> 12.13
- <db:table-type> 12.21
- <db:table-type-filter> 12.20
- <db:update-table> 12.31
- <office:annotation-end> 14.2
- <office:database> 12.1
- <style:default-page-layout> 16.8
- <style:list-level-label-alignment> 17.20
- <table:background> 16.20
- <table:desc> 9.1.14
- <table:filter-set-item> 9.5.6
- <table:title> 9.1.13
- <text:meta> 6.1.9
- <text:meta-field> 7.5.19

The following attributes are new:

- chart:angle-offset 20.2
- chart:automatic-content 19.14
- chart:auto-position 20.3
- chart:auto-size 20.4
- chart:axis-label-position 20.5
- chart:axis-position 20.6
- chart:display-equation 19.19
- chart:display-r-square 19.20
- chart:error-lower-range 20.16
- chart:error-upper-range 20.21
- chart:group-bars-per-axis 20.23

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- chart:hole-size 20.24
- chart:include-hidden-cells 20.25
- chart:label-position 20.31
- chart:label-position-negative 20.32
- chart:reverse-direction 20.44
- chart:right-angled-axes 20.45
- chart:sort-by-x-values 20.48
- chart:tick-mark-position 20.63
- chart:treat-empty-cells 20.64
- db:additional-column-statement 19.31
- db:append-table-alias-name 19.32
- db:apply-command 19.33
- db:as-template 19.34
- db:base-dn 19.35
- db:boolean-comparison-mode 19.36
- db:catalog-name 19.37
- db:command 19.38
- db:database-name 19.43
- db:data-source-setting-is-list 19.39
- db:data-source-setting-name 19.40
- db:data-source-setting-type 19.41
- db:data-type 19.42
- db:decimal 19.44
- db:default-cell-style-name 19.45
- db:default-row-style-name 19.46
- db:delete-rule 19.47
- db:description 19.48
- db:enable-sql92-check 19.49
- db:encoding 19.50
- db:escape-processing 19.51
- db:extension 19.52
- db:field 19.53

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- db:hostname 19.54
- db:ignore-driver-privileges 19.55
- db:is-ascending 19.56
- db:is-autoincrement 19.57
- db:is-clustered 19.58
- db:is-empty-allowed 19.59
- db:is-first-row-header-line 19.60
- db:is-nullable 19.62
- db:is-password-required 19.63
- db:is-table-name-length-limited 19.66
- db:is-unique 19.64
- db:local-socket 19.67
- db:login-timeout 19.61
- db:max-row-count 19.68
- db:media-type 19.69
- db:name 19.70
- db:parameter-name-substitution 19.71
- db:port 19.72
- db:precision 19.65
- db:referenced-table-name 19.73
- db:related-column-name 19.74
- db:row-retrieving-statement 19.75
- db:scale 19.76
- db:schema-name 19.77
- db:show-deleted 19.78
- db:string 19.79
- db:style-name 19.80
- db:suppress-version-columns 19.81
- db:system-driver-settings 19.82
- db:thousand 19.83
- db:title 19.84
- db:type 19.85

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- db:type-name 19.86
- db:update-rule 19.87
- db:use-catalog 19.88
- db:user-name 19.90
- db:use-system-user 19.89
- db:visible 19.91
- draw:draw-aspect 20.107
- draw:escape-direction 19.147
- fo:script 19.24220.215
- form:linked-cell 19.283
- form:list-linkage-type 19.284
- form:repeat 19.302
- form:source-cell-range 19.305
- form:spin-button 19.306
- grddl:transformation 19.320
- number:rfc-language-tag 19.356
- number:script 19.357
- style:join-border 20.292
- style:layout-grid-base-width 20.297
- style:layout-grid-snap-to 20.305
- style:layout-grid-standard-mode 20.306
- style:list-level 19.495
- style:percentage-data-style-name 19.507
- style:rfc-language-tag 19.51220.335
- style:rfc-language-tag-asian 20.336
- style:rfc-language-tag-complex 20.337
- style:script-asian 20.346
- style:script-complex 20.347
- style:text-overline-color 20.369
- style:text-overline-mode 20.370
- style:text-overline-style 20.371
- style:text-overline-type 20.372

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- style:text-overline-width 20.373
- svg:stroke-linecap 20.164
- table:embedded-number-behavior 19.624
- table:first-row-end-column 19.640
- table:first-row-start-column 19.641
- table:last-row-end-column 19.659
- table:last-row-start-column 19.661
- table:paragraph-style-name 19.688
- table:protection-key-digest-algorithm 19.698
- table:rfc-language-tag 19.703
- table:script 19.706
- table:template-name 19.732
- table:use-banding-columns-styles 19.736
- table:use-banding-rows-styles 19.737
- table:use-first-column-styles 19.738
- table:use-first-row-styles 19.739
- table:use-last-column-styles 19.740
- table:use-last-row-styles 19.741
- table:use-wildcards 19.744
- text:continue-list 19.780
- text:label-followed-by 19.827
- text:list-id 19.829
- text:list-level-position-and-space-mode 20.421
- text:list-tab-stop-position 19.830
- text:protection-key-digest-algorithm 19.851
- text:style-override 19.875
- xhtml:about 19.905
- xhtml:content 19.906
- xhtml:datatype 19.907
- xhtml:property 19.908
- xml:id 19.914

The value types of the following attributes changed:

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product

- smil:endsync 19.444 of <anim:iterate> 15.4.4, <anim:par> 15.4.2 and <anim:seq> 15.4.3
- smil:fadeColor 19.445 of <anim:transitionFilter> 15.2.7
- draw:notify-on-update-of-ranges 19.200 of <draw:object> 10.4.6.2
- draw:dots1-length 19.136 of <draw:stroke-dash> 16.40.9
- draw:dots2-length 19.138 of <draw:stroke-dash> 16.40.9
- draw:distance 19.134 of <draw:stroke-dash> 16.40.9
- office:version 19.386 of <office:document> 3.1.2, <office:document-content> 3.1.3.2, <office:document-meta> 3.1.3.4, <office:document-settings> 3.1.3.5 and <office:document-styles> 3.1.3.3
- presentation:action 19.387 of <presentation:event-listener> 10.9.2
- chart:data-label-number 20.8 of <style:chart-properties> 17.22
- chart:error-category 20.13 of <style:chart-properties> 17.22
- draw:stroke-linejoin 20.163 of <style:graphic-properties> 17.21
- fo:clip 20.179 of <style:graphic-properties> 17.21
- style:glyph-orientation-vertical 20.289 of <style:table-cell-properties> 17.18
- style:text-rotation-angle 20.375 of <style:text-properties> 16.27.28
- table:value 19.747 of <table:filter-condition> 9.5.5
- table:value-type 19.748 of <table:null-date> 9.4.2
- text:reference-format 19.854 of <text:bookmark-ref> 7.7.6
- text:display 19.796 of <text:index-entry-chapter> 8.13.1
- style:type 19.515 of <text:index-entry-tab-stop> 8.13.6
- style:type 19.515 of <text:index-entry-tab-stop> 8.13.6
- text:reference-format 19.854 of <text:note-ref> 7.7.7
- text:reference-format 19.854 of <text:reference-ref> 7.7.5
- text:reference-format 19.854 of <text:sequence-ref> 7.7.8

Copyright © OASIS® 2010. All Rights Reserved. Standards Track Work Product